WRITTEN BY: Sylviane ALIE

CHECKED BY: Gerard HOUSIEAUX

APPROVED BY: Jean Claude BODIN

ReVIEWED BY: Jerry SARIK

TITLE: HIGH SPEED SCANNER REMOVAL (FC 4741)

**STATUS:** 

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 1 OF 13

# **BEFORE INSTALLATION (STEPS 1-8)**

#### 1.0 MACHINES AFFECTED:

3745 MODEL 170,130,150.

#### 2.0 PREREQUISITES/CONCURRENT/COMPANION:

#### 2.1 Prerequisite:

NONE

#### 2.2 Concurrent - (Must be installed together)

NONE

#### 2.3 Companion - (May be installed separately)

NONE

## 3.0 B/M(S) TO BE INSTALLED

## 3.1 Install the following B/Ms:

```
B/M 03F5059 - HPTSS Removal (FC4741)
03F5160 - Installation instructions
```

#### 3.2 As required FFB/M

B/M 03F5056 - BPC1 card installation

## 4.0 PREPARATION:

- 1. Familiarize yourself with the purpose and details of the installation instruction prior to obtaining the customer machine time commitment.
- 2. Check all the items and count the parts listed on the B/M to be installed to determine that all the parts were received
- Using the HONE configurator printout determine the adapter card positions to be removed.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 2 OF 13

#### **Notes**

- 1. Up to 2 *HPTSS* can be installed in 3745 170 /130. Only one HPTSS can be installed in 3745 model 150.
- 2. In models 170 and 130 the first HPTSS to be removed, if 2 HPTSS's are installed, is adapter number 4 (card positions A1R2 and A1S2)
- 3. A BPC1 card will be installed in place of removed CSP card.

#### PROGRAMMING: 5.0

#### 5.1 Diagnostic programs.

CDF to reflect this change will be performed in step 11.0. This is essential to allow internal diagnostics to be run properly.

#### 5.2 System programs

The customer has to update the control program to implement this change.

#### PURPOSE AND DESCRIPTION: 6.0

#### 6.1 Purpose

Remove a HPTSS feature. (FC4741)

#### 6.2 Description

Remove Adapter cards, internal cable.

#### **INSTALLATION TIME:** 7.0

FFB/M 03F5059	Machine Hrs. 0.7	System Hrs. 00.0
test	0.8	
total	1.5	

## SPECIAL TOOLS AND/OR MATERIALS REQUIRED:

ESD kit P/N 6428316

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 3 OF 13

# **INSTALLATION** (Steps 9 - 11)

#### 9.0 SAFETY

Remove all electrical power from the machine and associated machines prior to beginning hardware installation.

Review the Safety Procedures located at the beginning of the 3745 Maintenance Information Procedures (MIP) manual, SY33-2070.

Review Safety Notices located at the beginning of the Maintenance Information Procedures manual.

#### 10.0 DETAILS OF INSTALLATION

Before proceeding with installation the following steps must be performed:

- Ask customer to set all lines and channel addresses offline for this controller.
- Ask customer to logoff the console if not already done.
- Ask customer for Maintenance Password.

#### 10.1 Checking, Diagnostics, Power off.

#### 10.1.1 On control panel:

Check that *Power Control* indicator displays 3.

If not, record the value \_\_\_, then press *power control* key until 3 is displayed, press *Validate* key.

#### 10.1.2 On local console:

- From CA interface display screen, record *enabled channel adapters* then *Disable* all channel adapters.
- Wait for interface status disabled for all CA's, Press F4.
- Enter the *Maintenance Password*, Press *SEND*.
- If CCU running, enter RST to reset the CCU. MOSS goes in MOSS Alone state.

## 10.1.3 Display the Configuration Data File (CDF) on local console.

- Enter CDF, Press SEND.
- Select DISPLAY/UPDATE, Enter 1, Press SEND.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 4 OF 13


Select LA, Enter 10, Press SEND.
 Check for the presence of Y under the identified LA number you have to remove according to the HONE Configurator sheet.
 Check the LA type (2 for HPTSS).
 Press F1.

#### 10.1.4 Run Diagnostics.

- Enter ODG, Press SEND.
- Select *IOCB*, Enter 3, Press *SEND*.
  - If any error is reported, go to *Maintenance Information Procedure (MIP)* chapter 1 and follow appropriate procedure.
  - If no error reported, Press F1.

#### 10.1.5 Power off.

- Power off the 3745 from the control panel.
- Open the system cover and switch off CB1.




ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 5 OF 13

## 10.2 Hardware Installation

10.2.1 Follow the existing ESD procedures when handling logic parts.

#### 10.2.2 Cards removal.


- From the front of the machine, remove the basic board cover.



- Identify the position of cards to be removed and remove the 3 top cards crossovers.

**Note:** Adapter 3 cards are plugged in A1T2 and A1U2. Adapter 4 cards are plugged in A1R2 and A1S2.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 6 OF 13



- Unplug the adapter cards and remove the internal HPTSS cable asm from the *FESH* card.
- Insert the cards in envelopes provided by the FFB/M.

#### 10.2.3 DCREG card removal.

A DCREG card must be removed when a HPTSS feature is removed from the machine.


- If you remove the ADPT 3 (Cards in A1T2 and A1U2), you must remove a DCREG from A1ZG.
- If you remove the ADPT 4 (Cards in A1R2 and A1S2), you must remove a DCREG from A1ZE.
  - If removing Adpt 4, unplug the cards from A1J2 thru A1S2 for access to DCREG. If removing Adpt 3, unplug the cards from A1R2 thru A1X2 for access to DCREG.

**Note:** Be sure that cards are labelled according to their positions.

- Unfasten the screw of the bottom 'spring retainer' securing cards in row Z of board. (See next figure)
- Remove the DCREG card from identified position and tighten the retainer screw.
- Re-install all cards in board.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 7 OF 13

10.2.4 Remove the clamp with its screw securing the HPTSS cable for removal from the machine.




10.2.5 Install a filler P/N 2733278 in position A1S2 or A1U2.

Install the BPC1 card mounted on its extender P/N 1953093, received with FFB/M in position A1R4 or A1T4.

Secure the card with intermix bracket P/N 1953110.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 8 OF 13

- 10.2.6 Re-install the base board cover.
- 10.2.7 HPTSS internal cable asm P/N 03F4693 removal.
  - Open the rear system cover.




- Locate the HPTSS tailgate in position Q at the 3745 bottom left, and locate the connector to be removed.

Disconnect the external cable if not already done.

- Remove the GRID over the CA tailgate area.
- Remove two screws securing the cable asm and remove the cable from the machine thru the bottom frame window.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 9 OF 13



- Install a dummy bracket P/N 58X9369 in the same tailgate position with the removed screws.
- Re-install the grid over the CA tailgate.

#### 11.0 TEST PROCEDURES:

#### 11.1 Power on

Switch CB1 in 3745 ON and close the system cover.

On control panel, press *Function* key until a flashing *I* is displayed. Press *Validate* key. Press *power on* key. A *MOSS IML* is performed.

#### 11.2 On local console:

- When CA interface display screen is displayed, press F4.
- Enter Maintenance Password, press Send.
- 11.2.1 Update the Configuration Data File (CDF).
- Enter CDF, Press Send.
- Select *Verify*, Enter 4, press *Send*.

  The values from the disk and the machine should be in

The values from the disk and the machine should be identical except for the adapter you have just removed.

To update the CDF with machine values, enter 2, Press Send.

- When function completed, msg "CDF verify completed" is displayed. . Press F6.
- If adapters are not recognized go to MIP and follow appropriate procedure.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 10 OF 13

- 11.2.2 Display the Configuration Data File (CDF).
- Select DISPLAY/UPDATE, Enter 1 Press SEND.
- Select LA, Enter 10, Press SEND.
   N should appear under the LA number you have just removed.
- Press F1.

#### 11.2.3 Run Diagnostics.

- Enter ODG, Press SEND.
- Select IOCB, Enter 3.
- Press SEND.
  - If any error is reported, go to *Maintenance Information Procedures (MIP)* chapter 1 and follow appropriate procedure.
  - If no error reported, press F1.

**Note:** If all HPTSS features were not removed, run the HPTSS diagnostics to check the DMA bus integrity.

# 11.2.4 Save Configuration Data File (CDF) on BACK UP and NORMAL sets of diskettes.

- Enter DIF, Press SEND.
- Select 2,
- Enter the date and save ID, Press SEND.
- Follow prompts on console. When function complete, press *F1*.

**Note:** Repeat this step for each set of diskettes.

#### 11.2.5 Logoff local console.

Re-enable all channel adapters disabled in step 10.1.2

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 11 OF 13

## 11.3 General IPL.

- 11.3.1 Set the Power control indicator to the value recorded in step 10.1.1
- 11.3.2 On control Panel.
- Set the Function indicator value to 0 (General IPL).
- Press Validate key.
- General IPL starts.

If steady FF4 code is displayed on control panel, ask customer to load Control Program. If Control program is loaded from hard disk, 000 will be displayed when IPL successful.

**Note:** Control program can fail if a mismatch exists between control program and hardware configuration.

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 12 OF 13

# **AFTER INSTALLATION.** (Steps 12 - 15)

#### 12.0 FIELD UPDATING:

NONE

#### 13.0 FIELD SUPPORT PUBLICATIONS:

NONE

## 14.0 PARTS DISPOSITION:

- **Purchased Machines**: Refer to the ownership of parts matrix to determine the correct owner of removed/unused parts.
  - For Domestic Area, return parts to customer.
  - For EMEA/APG/AG Area, refer to H.W. and General Service Code Description.

All parts determined to be the property of IBM should be processed as stated in the rental machine directions below.

• **Rental Machines**: Provide all (or the following) parts to the IBM branch office for potential return in accordance with existing return, recovery, and reclamation programs.

#### 15.0 MACHINE RECORDS:

- Install the new MACHINE HISTORY supplied.
- Report the installation and quality according to the existing procedure.

# 16.0 END OF INSTRUCTIONS

ENG CHANGE NO.	A47495	A73532	A97870	PART NO. 03F5160
DATE OF CHANGE	03MAY89	03AUG89	21NOV89	PAGE 13 OF 13