

Field Feature Bill of Material (FFBM) PN 17G5536 CONVERT an IBM 3745 Model 41A to 61A

Written by: J. Michaut Checked by: J. Combes Approved by: A. Badino Reviewed by: B. Smith


3745 | PN 17G5536 | EC C38405 | FFBM | 1 of 24 | 06APR93

C C38405 | EC C38405A 6APR93 | 17JUN93 EC D55799 16SEP94 EC D55883 EC E27926 11MAY95 14MAR97

Installation Instructions



As instructions are divided in two procedures, 2 CEs may be used for the installation. An additional person may be called to move the enclosure unit.



3745	PN 17G5536	EC C38405	EC C38405A	EC D55799	EC D55883	EC E27926
FFBM	3 of 24	06APR93	17JUN93	16SEP94	11MAY95	14MAR97

Before Installation (steps 1-8)

VERY IMPORTANT -

MES should be installed without delay, after receipt, to avoid multiple MCLs needed for the microcode.

Net Priced Feature

All parts removed from this machine are IBM property and must be returned to IBM.

Machines Affected

IBM 3745 Model 41A.

This feature should only be applied on the machine serial for which it is specified.

Related BMs and ECs

None.

3.0 BMs to be Installed

Install one of the following FFBM.

FFBM 17G5549 - Convert a 3745 41A to 61A (4MB memory size)

or

FFBM 17G5550 - Convert a 3745 41A to 61A (8MB memory size)

or

FFBM 17G5551 - Convert a 3745 41A to 61A (16MB memory size)

and 17G5536 - Installation Instructions.

4.0 Preparation

- 1. Familiarize yourself with the purpose and details of the installation instruction before negotiating machine time with the customer.
- 2. Check all items listed on the BM(s) to determine that all parts have been received.
- 3. The installation must be performed off-line.
- 4. Ensure that RETAIN search has been performed and all prerequisites have been installed.

Perform a search using 3745CCUPGRADE as SAS keyword

5. To check if a new MCLs level is necessary, perform a RETAIN search using 3745UPGRADE CODE LEVEL for the TDR which gives the most recent level of microcode available for this machine (model).

To install the last level of MCLs, the most efficient way is with the LIC upgrade procedure. Use the RETAIN search, 3745ECA134 **COF**, for the TDR which explains the procedure for ordering the latest level microcode from COF.

Third party can get the latest level of code through their normal microcode ordering procedures.

MCLs can be obtained from RETAIN (If if the customer provide an RSF link), or by ordering the 3746 optical disk MCL via CCSS.

- 6. Follow the unpacking instructions attached to the case to unpack the MES material. Do not damage the packing boxes, they will be used for repacking.
- 7. Before starting Model conversion ensure that the complete 3745 is available.

Additional information:

· All parts to be removed should be handled carefully. Returnable parts must be received at the factory in good order.

3745 PN 17G5536 FFBM 4 of 24

EC C38405 06APR93

EC C38405A 17JUN93

EC D55799 16SEP94

EC D55883 EC E27926 14MAR97 11MAY95



- To save installation time and machine down time, some tasks will be performed after the General IPL Section (Step 11.4).
- When hardware installation is complete and before starting Test Procedure section (11.0), each CE should check the other CE's work.

8.0 Tools/Materials Required

- ESD kit (PN 6428316)
- TCM tool kit (PN 69X7667)
- Isopropyl alcohol.

5.0 Programming

5.1 Diagnostic Programs

To reflect this change, CDF will be upgraded in Step 11.0. This is essential to allow internal diagnostics to be run properly.

5.2 System Programs

The customer must update the control program to implement this change.

6.0 Purpose and Description

6.1 Purpose

Convert a 3745 Model 41A to a 3745 Model 61A.

6.2 Description

- Remove the TCM CCU enclosure, PSTY1s, Air Moving Device, and associated cabling.
- Install a new CCU enclosure with Fans, new PSTY1Bs, and associated cabling.
 Logics cards will not be re-used.

7.0 Installation Time

To be reported as MES

FFBM	Machine hours	System Hours	Nbr of CEs
17G5549 or 17G5550 or 17G5551	2.0	0.0	2
Test Time	1.90	0.0	
Total Time	3.90	0.0	

3745	PN 17G5536
FFBM	5 of 24

EC C38405	EC C38405A	EC D55799	EC D55883	EC E27926
06APR93	17JUN93	16SEP94	11MAY95	14MAR97

Installation (steps 9-11)

9.0 Safety

 Review the Safety Notices and the Service Inspection Procedures located at the beginning of the 3745 Maintenance Information Procedure (MIP) manual, SY33-2054.

10.0 Details of Installation

Before the installation, ask the customer:

- · To set all lines and channel addresses offline for this controller and associated machines.
- · To provide the maintenance password.
- To logoff the Service Processor, if not already done.

10.1 Checking, Diagnostics

10.1.1 MOSS IML

From the control panel:

- 1. Check that the Power Control indicator displays 3. If it does not, record the value __. Then, set the Power Control indicator to 3. Press the Validate key.
- 2. Set the **Service Mode** indicator to **1**. Press the Validate key.
- 3. Set the Function indicator to 1. Press the Validate key.

The MOSS IML is completed when FOE is displayed on the control panel.

10.1.2 Logon

From the Service Processor:

- 1. On MOSS-E View window, click on Program.
- 2. Click on LOG ON MOSS-E.

3. Enter the maintenance password, press

Administrator Maintenance Mode is displayed on the lower line of the window.

10.1.3 Open MOSS/MOSS-E Session

___ 1. On the MOSS-E View window, double click on the ICON of the identified 3745. On the 3745 Menu window, double click on MOSS Console.

Wait for Function Selection Rules screen.

10.1.4 Disable Channel Adapters

- 1. Enter CID, press Enter.
- 2. On CA Interface Display screen, record the Enabled Channel Adapters, then Disable all the CAs.

Note: If 3746 A11 is installed, press F8 to display channels 8 to 16.

- 3. Wait for Interface Status Disabled for all channels.
- 4. Press **F1**.
- 5. If CCU running, enter **RST** to reset the

MOSS goes in MOSS ALONE state.

Note: CCU must be selected with CSR function before performing RST function. Perform CSR/RST sequence for each CCU.

10.1.5 Verify the CDF

- Enter CDF, press Enter.
- 2. Enter 4 (VERIFY), press Enter. The value from the CDF DATA and the MACHINE DATA should be identical. If there is a discrepancy, physically, verify the features, and if correct, update the CDF with machine values. Enter 2, press Enter.

3745 PN 17G5536 FFBM 6 of 24

EC C38405 EC C38405A 06APR93 17JUN93

EC D55799 16SEP94

EC D55883 11MAY95

EC E27926 14MAR97




3. When CDF VERIFY COMPLETED is displayed, press F1.

10.1.6 Run the Diagnostics

- 1. Enter ODG, press Enter.
- 2. Enter 3 (IOCB), press Enter.
- If NO ERROR FOUND is displayed, press F1.
- Otherwise, see the MIP, Chapter 1.

10.1.7 Power OFF

- 1. From the control panel, press the Power OFF key.
- 2. Open the front system cover, then switch OFF CB1.



06APR93



10.2 CE 'A' Tasks

Warning: Follow existing ESD procedures when handling logic parts.

10.2.1 Power Supplies

Open the rear system door(s), disconnect the ground wire(s) (if present) from the right door and remove the door.

Note: To provide clearance for easier door removal, you may have to loosen two screws securing the end cover.

- 1. From the rear, remove the shield . 1. over the CCU cards if present.
- 2. Locate the PSTY1 in location 01Q and 01R, then remove the plastic cover from the power TB(s) .2.. Disconnect all FDS cables from the TB(s).


Tape the FDS cables end to the enclosure (use tape provided for repacking).


3. From the top of PSTY1(s), unplug the Power Control Bus cables from connectors J2 and the Power On Reset cables from J1 . 3...

- Warning -

Secure the power bus cable in the raceway to prevent damage during the CCU enclosure exchange.

- 4. Remove the 3 screws .4., and remove the PSTY1(s) from the 3745 (the power cords have been routed back by CE 'B').
- 5. Disconnect the FDS ground cable attached to the frame .5.. Save screws.






10.2.2 Tri Lead Cables, MAC Card Exchange

1. Locate the MOSS board in 01A, and the tri lead cables connected in 01A-Y0D4/D5, E4/E5 and 01A-Y0B4/B5 and C4/C5.


Note

To prevent damage to cables and board, use the tool (PN 71F9877) to unlock the connector as shown in the figure below.

Gently insert the blade, then pull on cable housing to remove the cable.



- 2. Unplug the cables and route them back to the CCU Enclosure. Secure tri lead cables in the right side of CCU cage .2..
- 3. In MOSS board, locate the MAC card in 01A-X0H2, and remove the cable connected to the MAC card .3.. Route the cable back to the CCU enclosure, and secure it in the right side of CCU cage .2..
- __ 4. Remove the spring clips securing the locks of MAC card.
- Remove the MAC card.
- __ 6. Install the new MAC card provided by the FFBM in same position.
- 7. Re-install the spring clips on MAC card, then take 'H' label off the old card and put it on the new card.





10.3 CE 'B' Tasks

Warning: Follow existing ESD procedures when handling logic parts.


10.3.1 AMD, Power Cords

- 1. From the front of the 3745, remove the 4 screws. Remove the shield . 1. (will not be re-used) over the AMD(s) (Air Moving Device).
- 2. Unplug the AMD power cables from primary power box connectors J1 and J2 .2..
- 3. Remove the 4 screws securing each AMD. Then, remove the AMDs from the machine .4..

Note: Swing out the bottom of AMD to disengage the top leg.

4. Unplug the PSTY1 power cables . . from connectors J4 and J9. Then, route them to the rear of 3745.

with 2 screws as shown, on the 2 top holes of AMD asms.



10.3.2 Flat Cables

__ 1. Open the operator panel gate.

– Note –

To prevent damage to cables and board, use the tool (PN 71F9877) to unlock the connector as shown in the figure on previous page.

Gently insert the blade, then pull on the cable.

- 2. Check that all cables from SACU board are correctly identified. Rewrite plug location on cables if not readable.
- ___ 3. Unplug the flat cables from the **SACU** board.


- Warning -

Secure cables in the raceway to prevent damage during CCU enclosure exchange.

4. Refer to figure on next page (View A) and attach the handhold (PN 76F9077). 2.

E0 F0 G0 H0 J0

MØNØPØQØRØ



3745 FFBM

PN 17G5536 10 of 24 EC C38405 06APR93

405 EC C38405A 17JUN93

EC D55799 16SEP94

EC D55883 11MAY95 EC E27926 14MAR97



10.4 CCU Enclosure Exchange

CAUTION:

CCU enclosure can weight up to 45 Kg (100 lb).

An additional person may be needed because of the weight of the enclosure unit.

The first person is placed on the right side of enclosure, the second on the left side, and the third, if needed, at the front of the enclosure using the handhold provided.


Note: Ensure that all flat cables are protected from damage during CCU enclosure exchange.

10.4.1 TCM Enclosure Removal

- __ 1. Remove the 4 screws .1. securing the CCU enclosure.
- ___ 2. Pull the enclosure, approximately 15 cm, out of the 3745.

- __ 3. From the rear of 3745, attach the handhold (PN 76F9076) . . to the enclosure as shown in the figure below. This will allow the third person involvement if needed. The handhold is clipped to the right and left sides of the CCU enclosure (see view B). Secure the handhold with the attached pins.
- 4. Two persons grasp the enclosure asm by the handhold .2. and at the SACL board. The third person, if needed, grasps the front handhold .3..

 Slide the asm out of the 3745.
- __ 5. Put the enclosure in a safe place.
- 6. Install 3 clamps (PN 34F1295) as follows:
 Remove the clamp . . . , and stick a
 clamp 9 cm (3.5 in.) to the left.
 Remove the clamp . . . and stick a clamp
 3 cm (1.1 in.) to the right.
 Remove the clamp . . . and stick a clamp
 1 cm (0.4 in.) to the right.



10.4.2 New CCU Enclosure Installation

- 1. Move the new CCU enclosure, still on its shipping pallet assembly, close to the machine.
- 2. If three persons are needed, remove handhold (PN 76F9076) from the TCM CCU enclosure and attach it to the new CCU enclosure (need to tilt the enclosure on the shipping pallet).
- 3. Lift the enclosure from the shipping pallet (use the enclosure top bar). Put the part of the enclosure marked .A. on the slides .B. in 3745 (refer to figure on previous page). Slide the enclosure partially in 3745.

– Note –

When the enclosure is on its slides, check from the front of the 3745 that there is no risk of damaging flat cables, FDS cables, and FAN power cords.


4. Remove the handhold and slide the enclosure in place.

10.4.3 Card Locking

- 1. Secure the enclosure with the screws provided in the bag attached to the cage
- 2. Remove 4 screws securing the red bracket .4. and remove it.
- 3. Remove brackets (PN 61F4485) .2. (top) and (PN 61F4486) .3. (bottom). Save brackets/screws for re-install.
- 4. On each_card location, carefully move levers . 5. inwards simultaneously.

Note: To improve contact, operate the levers 3 times.

5. Install brackets .2. at the top and .3. at the bottom of the CCU cage. Use screws saved in Step 2. Position brackets to lock the STER cards in position.



3745	PN 17G553
FFBM	12 of 24

۷	17	'G5536
2	of	24



10.5 CE 'A' Tasks

10.5.1 Flat Cables


__ 1. Place the template (PN 76F8595) .1. as shown on figure. The template should be positioned as far up and left as permitted by the frame.


Note: Remove existing cable clamps which interfere with the correct placement of the template.

__ 2. Attach 4 clamps (PN 34F1295) in the windows of the template . 2.

Note: Place the clamps as shown on the template.

- 3. Remove the template.
- 4. Place the pre-folded flat cables (PN 76F8591 and 76F8592) in the clamps (cables are tied all-together).
- 5. Plug the flat cables, one at a time, on MOSS board .3. in the following sequence:
 - Y0E4, Y0D4, Y0E5, Y0D5.
 - Y0C4, Y0B4, Y0C5, Y0B5.
- __ 6. Route the Flat cables through the machine to CE 'B'. .4.








10.5.2 PSTY1B Installation

- 1. Install the PSTY1B support bracket asm (PN 71F9950) . 1. and secure it at the bottom with 2 screws provided in the bag attached to it. Do not tighten the screws.
- 2. Install two PSTY1B (PN 26F1733) .2. with 6 screws (PN 2665528), provided in the bag attached to the support bracket. Place the power supply labelled CCUA in 01Q, and the power supply labelled CCUB in 01R.
- 3. Tighten the two bottom screws of the power supply bracket. Feed the PSTY1B power cords to the front of the machine.




- 4. Loosen the screw securing the bracket .3. and install the filter (PN 58X9295) under the CCU enclosure. Note the arrow direction for air flow. Tighten the screw.
- 5. Connect the FDS ground cable to the frame .4.. Secure it with the screws saved in Step 10.2.1, "Power Supplies" on page 8.
- 6. Connect the FDS cables .5. to the PSTY1B with screws (PN 61F4511), provided in a bag attached to the power supply. Connect cables on TB1/TB2 first.

- 7. Connect the power control bus cable to connector J2 of each power supply .6..
 - 8. Locate the Power On Reset cable (PN 61F4448) . 7. connected in SACL positions 01B-A2Z2-D and 01B-A2Z4-D. Route the cables to PSTY1B and connect them as follows:

from 01B-A2Z2-D to 01Q-J1 from 01B-A2Z4-D to 01R-J1

9. On PSTY1B in 01Q check that switch 1 is set to A (CCUA) .8.. On PSTY1B in 01R check that switch 1 is set to B (CCUB) .8..



3745	PN 17G5536
FFBM	14 of 24


7	G5536	l
f	24	l

10.5.3 Mechanical

- 1. Re-install shield over CCU board if removed in Step 10.2.1, "Power Supplies" on page 8.
- 2. Re-install the rear door removed in Step 10.2.1, "Power Supplies" on page 8.

Note: Tighten end cover screws if they were loosened.

- 3. Re-connect ground wires (if present).
- 4. Affix label (PN 71F9997) over existing label on the door .1.. Close the door.




06APR93




10.6 CE 'B' Tasks

10.6.1 I/O Cables


- 1. Reconnect Flat cables on SACU board Refer to the template on SACU board.
- 2. Route and connect to the SACU board flat cable group (PN 76F8591 and 76F8592) which were prepared by CE 'A' .2..





10.6.2 Diskette Storage Box

• Install the new diskette_storage box supplied on the top of the PS6 .4..



10.6.3 Mechanical Changes

__ 1. Install air filter (PN 58X9296) on the CCU enclosure . . Secure it with the bottom bracket.

Note the arrow direction for air flow.


2. Plug the power cords in primary power box . 2. as follows:


PSTY1 01Q Connector J4
PSTY1 01R Connector J9
FAN CCUA Connector J1
FAN CCUB Connector J2

- ___ 3. Affix label (PN 71F9996) over existing label in front door .3.
- 4. Remove the name plate from the front system cover, and clean any adhesive residue from the recessed area with Isopropyl alcohol.
 Remove the paper from the back of ne

Remove the paper from the back of new name plate (PN 71F9546) and affix the plate.

5. Strike out the model number on the S/N label, only the nameplate will identify the model type from now on.





11.0 Test Procedures

Note: Ensure that each CE has verified the other's work before powering on the 3745.

11.1 Power ON

 Switch the 3745 CB1 ON and close the system cover(s).

3745	F
FFBM	1

PN 17	G5536
17 of	24

36	



From the control panel:	6. Set the Service Mode indicator to 2 .
1. Check that Service Mode indicator display 1.	Press the Validate key. 7. Set the Function indicator to 1 .
2. Set the Function indicator to 1 .	Press the Validate key.
Press the Validate key. Press the Power ON key.	8. Press the Power On Reset key. The MOSS IML is completed when F0E is
The MOSS IML is completed when F0E is dis-	displayed on the control panel.
played on the control panel.	From the Service Processor:
44.0.0	9. Click on OK .
11.2 Open MOSS/MOSS-E Session	The 3745 Model number is being recorded.
From the Service Processor, wait until the ICON of the identified 3745 becomes purple.	10. When the operation is completed, click on OK .
1. On the 3745 Menu window, double click	11. Click on Cancel.
on MOSS Console. Wait for Function Selection Rules screen.	12. On the 3745 Menu window, double click on MOSS Console.
4404 11 14 41 005	Wait for Function Selection Rules screen.
11.2.1 Update the CDF	44.00 0 11 01 11
1. Enter CDF, press Enter.	11.2.3 Run the Diagnostics
2. Enter 4 (VERIFY), press Enter. The value from the CDF DATA and the	1. Enter ODG , press Enter .
The value from the CDI DATA and the	2 Enter 2 (CCII) proce Enter
MACHINE DATA should be identical	2. Enter 2 (CCU), press Enter .
MACHINE DATA should be identical except for the new hardware installed.	• If NO ERROR FOUND is displayed,
except for the new hardware installed. 3. To update the CDF with the machine	 If NO ERROR FOUND is displayed, press F1.
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter.	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed,
 except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter.
 except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is 	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1.
 except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step.
 except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model 	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model From the Service Processor: 1. On the Service Processor menu, double click on Manage 3745/3746-900 Installa-	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and 5-8) with HSS/ELA adapter. If NO ERROR FOUND is displayed, press F1.
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model From the Service Processor: 1. On the Service Processor menu, double click on Manage 3745/3746-900 Installation. 2. Click on the line of the 3745 you have	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and 5-8) with HSS/ELA adapter.
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model From the Service Processor: 1. On the Service Processor menu, double click on Manage 3745/3746-900 Installation. 2. Click on the line of the 3745 you have just converted.	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and 5-8) with HSS/ELA adapter. If NO ERROR FOUND is displayed, press F1.
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model From the Service Processor: 1. On the Service Processor menu, double click on Manage 3745/3746-900 Installation. 2. Click on the line of the 3745 you have just converted. 3. Click on Change. 4. On Controller Model Change message,	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and 5-8) with HSS/ELA adapter. If NO ERROR FOUND is displayed, press F1.
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model From the Service Processor: 1. On the Service Processor menu, double click on Manage 3745/3746-900 Installation. 2. Click on the line of the 3745 you have just converted. 3. Click on Change. 4. On Controller Model Change message, click on Yes.	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and 5-8) with HSS/ELA adapter. If NO ERROR FOUND is displayed, press F1.
except for the new hardware installed. 3. To update the CDF with the machine values, enter 2, press Enter. • When CDF VERIFY COMPLETED is displayed, press F6. 11.2.2 Record the 3745 Model From the Service Processor: 1. On the Service Processor menu, double click on Manage 3745/3746-900 Installation. 2. Click on the line of the 3745 you have just converted. 3. Click on Change. 4. On Controller Model Change message, click on Yes. From the 3745 control panel:	 If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 3. Enter 3 (IOCB), press Enter. If NO ERROR FOUND is displayed, press F1. Otherwise, see the MIP, Chapter 1. 4. If no HSS/ELA feature is installed, press F1 and go to next Step. If HSS/ELA feature is installed in your 3745, run HSS/ELA diags on at least one HSS/ELA on each DMA bus (Adp 1-4 and 5-8) with HSS/ELA adapter. If NO ERROR FOUND is displayed, press F1.

3745

PN 17G5536

18 of 24

EC C38405

06APR93

EC C38405A

17JUN93

EC D55799

16SEP94

EC D55883

11MAY95

EC E27926

14MAR97

11.2.4 Air Filter Ack	knowledge
-----------------------	-----------

- 1. Check all frame filters. replace if needed.
- __ 2. Enter **POS**, press **Enter**.
- 3. Select option A, press Enter.
- __ 4. Select option **F** (Acknowledge Air Filter change), press **Enter**.
- 5. Enter a Y to confirm, press Enter. When completed, press F1.

11.3 Close MOSS/MOSS-E Session

- Enter CID, press Enter.
- 2. Re-enable all channel Adapters disabled in Step 10.1.4, "Disable Channel Adapters" on page 6.
- 3. When CA are enabled, press F1.
- 4. Enter **OFF**, press **Enter**.
- __ 5. On **3745 Menu**, click on **Function**. Then, click on **Exit**.

The MOSS-E View window is displayed.

11.4 General IPL

From the control panel:

- Set the **Power Control** indicator to its original value, recorded in Step 10.1.1, "MOSS IML" on page 6.
- 2. Set the Service Mode indicator to 0. Press the Validate key.
- __ 3. Set the **Function** indicator to **0** (general IPL).

Press the Validate key.

The general IPL starts.

- If FF4 code is displayed on control panel, ask the customer to load the control program.
- If the control program is loaded from hard disk, 000 will be displayed when IPL successful.

Note: The control program load can fail if a mismatch exists between the control program and the hardware configuration.

11.5 Disk Save

When the customer network is restarted, save the contents of the hard disk on the **BACKUP** set of diskettes.

11.5.1 Open MOSS/MOSS-E Session

From the Service Processor:

- On the MOSS-E View window, double click on the ICON of the identified 3745.
- 2. On the 3745 Menu window, double click on MOSS Console.

Wait for Function Selection Rules screen.

11.5.2 Save Disk Contents onto Diskettes

1. If NCP is restarted and MOSS ONLINE, set the MOSS OFF LINE, enter MOF, press Enter.

Note: Select the CCU with CSR function first.

- 2. Select **DIF**, press **Enter**.
- 3. Select 2.
- 4. Enter the save-ID, and press **Enter**.
- Follow prompts on console.
- 6. When function is completed, press **F1**.

11.6 Install Latest MLCs

Prior to returning the 3745 to the customer, you must install the latest MCLs.

1. If you have an RSF link: Refer to the SP Installation and Maintenance Manual. Follow the procedure Reporting problem to retain in Chapter 3 and, when requested enter Converting a Model A and testing the RSF link as short description of the problem. The latest MCLs are automatically dowloaded. Then go to :Handling Microcode Change level in Chapter 3. When the RSF link is completed and the MCLs are installed, go to 11.7, "Close MOSS/MOSS-E Session" on page 20.

2. If you use the LIC Upgrade kit:

3745 PN 17G5536 FFBM 19 of 24

36 | |

EC C38405 06APR93 EC C38405A 17JUN93 EC D55799 16SEP94 EC D55883 11MAY95

EC E27926 14MAR97



Refer to the SP Installation and Maintenance Manual. Follow the procedure Installing a new version of the Licensed Internal Code in Chapter 3. When done go to 11.7, "Close MOSS/MOSS-E Session."

3. If you use the 3746 Optical Disk MCLs: Refer to the SP Installation and Maintenance Manual. Follow the procedure Handling Microcode Change Level in Chapter 3. When done go to 11.7, "Close MOSS/MOSS-E Session."

11.7 Close MOSS/MOSS-E Session

1.	Enter (DFF,	press	Enter
----	---------	------	-------	-------

2. On the 3745 Menu, click on Function. Then, on Exit.

The MOSS-E View window is displayed.

11.8 Logging OFF from SP

- 1. On the MOSS-E View window, click on Program.
- 2. Click on LOG OFF MOSS-E.



11.9 Re-packing

11.9.1 TCM Removal


TCMs will be sent back to IBM in the TCM BOXES provided by the FFBM.

Tools to be used in this section are provided by TCM tool kit.

Repeat this procedure for each TCM.

- 1. Use the torque tool (PN 2360092) to loosen the 9 captives screws securing the TCM heat sink . 1. Carefully remove the heat sink.
- ___ 2. Install the handle provided by FFBM. Tighten the 2 thumbscrews .2..
- __ 3. Use the torque tool (PN 2360092) to loosen completely the four TCM retaining screws (captives screws) .3..
- 4. Use the TCM actuating tool (PN 5665909) to remove the TCM as follows: .4.

- Check that the detent pin in the tool is in the **Removal Position (R)**.
- Set the lever on the handle to drive in a counterclockwise direction.
 On the TCM, slide the cam guard to its left side limit.
- Insert the actuating tool into the module with indicator pin pointing to cammed position (9 o'clock).
 Be sure that the TCM actuation tool is fully inserted (red line not visible).
- Turn the actuating tool counter clockwise, to deactivate the latch.
 Remove the actuating tool.
- ___ 5. Unlatch the 3 spring clip retainers .5., hold the TCM handle firmly and carefully remove the TCM from the enclosure.
 - 6. Install the Clip On TCM Cover .6. (PN 7331541) on the TCM, then put the TCM in the TCM shipping container.



3745	PN 17G5536
FFBM	21 of 24

EC C38405	EC C38405A	EC D55799	EC D55883	EC E27926
06APR93	17JUN93	16SEP94	11MAY95	14MAR97



11.9.2 TCM Enclosure

- 1. Place the TCM enclosure on the shipping pallet assembly provided with the new enclosure.
- 2. Secure it with the screws and nuts.
- 3. Remove the bracket locking the STER cards in the TCM enclosure by removing 2 screws.
- 4. Open carefully the **ZIF connectors** on all cards.

Notes:

- a. In US, remove all cards from the CCU enclosure and put them in ESD envelopes and containers provided by the MES.
- b. In EMEA, remove the storage cards from the CCU enclosure and put them in ESD envelopes and containers provided with the MES.
- 5. Install the **Red Bracket** removed in Step 10.4.3, "Card Locking" on page 12 over the CCU cards and secure it with 4 screws.
- 6. Follow the re-packing instructions to send parts back to IBM.

After Installation (steps 12-15)

12.0 Field Updating

None.

13.0 Publications Update

None.

14.0 Parts Disposition

For parts listed in the RMER

All these parts become the property of IBM. You MUST RETURN these parts following the instructions given on the Returned Material Equipment Report (RMER) provided with this FFBM.

· For parts not listed in the RMER

All these parts should be returned according to your local procedure.

3745 PN 17G5536 FFBM 22 of 24

EC C38405 EC C38405A 06APR93 17JUN93

EC D55799 16SEP94

EC D55883 11MAY95

EC E27926 14MAR97



15.0 Machine Records

- Install the new MACHINE HISTORY supplied.
- Report installation (As MES activity) and quality to existing procedures.

End of instructions.

3745	PN 17G5536	EC C38405	EC C38405A	EC D55799	EC D55883	EC E27926
FFBM	23 of 24	06APR93	17JUN93	16SEP94	11MAY95	14MAR97

Installation Instructions

EC C38405	EC C38405A	EC D55799	EC D55883	EC E27926
06APR93	17JUN93	16SEP94	11MAY95	14MAR97