881/882 Video Test Generator

User Guide



quantumdata

881/882 Video Test Generator, User Guide, Revision A.31 (5/11/09)

Copyright 2009 Quantum Data. All rights reserved.

The information in this document is provided for use by our customers and may not be incorporated into other products or publications without the expressed written consent of Quantum Data. Quantum Data reserves the right to make changes to its products to improve performance, reliability, producibility, and (or) marketability. Information furnished by Quantum Data is believed to be accurate and reliable. However, no responsibility is assumed by Quantum Data for its use.

Updates to this manual are available at http://www.quantumdata.com/support/downloads/.

Contents

Chapter 1 Getting Started

Introduction 2
Standard features 2
Optional features 3
Video interfaces 4
VGA interface 5
DVI-I interface 6
Special Sync interface 6
S-Video interface 7
Composite video BNC 7
Computer interfaces 8
RS-232 interface 8
GPIB interface 9
Front panel interface 10
Status indicators 10
Menu selection keys 11
Selecting menu items 11
Item selection examples 12
About the Settings and Options keys 12
Generator file system and media 14
Generator file system 14
Generator media 14
Generator operational modes 15
Booting up the generator 15
Basic mode 16
Browse mode 16
Browsing other media 17
Setting the generator's path 18

Programming the generator's function keys 20
Switching from Browse mode to Basic mode 20
Web interface 21
Working with the Virtual Front Panel 21
Working with the CMD (Command) Terminal 23
Working with the Generator FTP Browser 24
Copying files from a PC to a generator 24
Copying files from a generator to a PC 26
Copying files between the generator's flash memory and PC card 27
Copying files between generators 28
Command line interface 31
Working with the serial interface 31
Establishing a terminal session with the generator 31
Configuring the generator's serial port 32
Working with the network interface 34
Establishing a Telnet session with the generator 34
Sending commands interactively 35
Common commands 35
Sending command files (serial interface only) 36
Working with user profiles 37

Chapter 2 Testing Video Displays

General video display testing procedures 40
Making physical connection 40
Selecting interface type 41
Selecting video format 43
Setting Source list of formats 43
Selecting a format 45
Understanding the format library 46
Viewing or modifying format parameters 47
Selecting image 47
Rendering images 47
Rendering image versions 50

Testing analog computer (IT) CRTs 52
Testing digital computer (IT) FPDs 55
Testing analog composite video SDTV (CE) CRTs 58
Testing analog component video SDTV (CE) CRTs 61
Testing digital component video HDTV (CE) FPDs 64
Testing SDI and HD-SDI digital component video studio displays 69
Using the Image Caching feature 72
Using the AuxTest image 74
Using the ImageShift utility 76
Using the ImageShift utility through the front panel 76
Using the ImageShift utility through the command line interface 79
Adjust Frequency Function 81
Keypad Utility 82

Chapter 3 Administrative Tasks

Overview 86
Calibrating the generator 87
Calibrating signal level 87
Calibrating frequency 88
Auto Upgrade 91
Auto upgrade - Network Method 91
Auto upgrade - PCMCIA/Compact Flash Method 98
Upgrading the generator locally 110
Manually upgrading using PCMCIA Compact Flash card 110
Manually upgrading the generator without using PC Card 112
Connecting generator directly to a PC 114
Setting the generator's IP address 114
Setting the PC's network settings 116
Reconfiguring and booting a stalled generator 120
Cloning generators 125
Cloning a generator using the PC card 125
Cloning a generator using the Generator FTP Browser 126
Resetting a generator 129
Viewing generator configuration information 130

Chapter 4 Networking Generators

Overview . . . 138
Generator file system . . . 138
Configuring a file server . . . 139
File server specifications . . . 139
Installing an FTP server . . . 139
Copying resource files to the FTP site on the file server . . . 142
Establishing a network environment . . . 144
Connecting generators to the network . . . 144
Setting the generator's IP address . . . 145
Setting the file server IP address in the generator . . . 148
Network operations . . . 151
Booting a generator from the file server . . . 151
Sharing objects on a file server . . . 152
Controlling a generator remotely . . . 154
Using the Virtual Front Panel to operate a generator remotely . . . 154
Maintaining the generator's file system using the Generator FTP Browser . . . 154
Operating the generator remotely through the command line interface . . . 154
Upgrading generators over a network . . . 155
Upgrade options and procedures . . . 155
Overview of upgrade procedures . . . 155
Backing up the current files on the file server . . . 155
Copying files to the PC file server . . . 156
Removing current files from the generators . . . 157
Copying the new files to each generator . . . 157
Reboot the generators . . . 157
Cloning generators using the generator FTP Browser . . . 158

Chapter 5 Using GPIB Interface

Overview . . . 162
Setting the GPIB port address . . . 163
Queries and commands . . . 165
Commands . . . 165
Queries . . . 166

Sending commands and queries 167
Sending multiple commands and queries per line 167
Completion handshake 168
Input buffer 168
Status queries and control 169
Status byte 169
Requesting service 169
Bus commands 171
Remote/local operation 171

Chapter 6 Working with Formats

Overview 174
Format library 175
Composite television format names 175
Component television format names 176
Computer display format names 177
Aperture designators 178
Viewing the source list of formats 180
Configuring format parameters 181
Viewing and modifying format parameters through the front panel 181
Viewing and modifying format parameters via the command line 185
Viewing and modifying format parameters by editing XML files 186
Format Editor Overview 189
Format Editor - Basic Window Configuration and Operation 189
Format Editor - Top Level Menus 190
Format Editor - Menu Buttons 192
Format Editor - New Format 193
New Format - Timing Tab 195
New Format - General Tab 199
New Format - Digital Video Tab 207
New Format - Digital Audio Tab 209
New Format - AFD Tab 212
Format Editor - New Report 214
Format Editor - New Source Menu 218

Format Editor - Open 220
Format Editor - Save. 221
Creating a new format using the Format Editor 222
Creating custom formats using the command line interface 227
Format catalogs 229
Using format catalogs 229
Creating format catalogs. 230
Deleting format catalogs 232

Chapter 7 Working with Images

Overview 236
Viewing the Content list of images 237
Viewing and modifying image options 237
Viewing image versions 237
Creating custom images 240
Command file example 241
Editing images 242
Rendering bitmap images 243
Setting image component values 245
Creating image catalogs 247
Creating an image catalog 247
Deleting an image catalog 251

Chapter 8 Working with Test Sequences

Overview 256
Viewing the test sequence list. 257
Viewing the test sequence list using the front panel. 257
Viewing the test sequence list using the command line interface. 257
Running a test sequence 259
Running a test sequence using the front panel 259
Running a test sequence using the command line interface 260
Creating a test sequence 262
Creating a test sequence using the command line interface 262
Editing a test sequence XML file 266
Deleting a test sequence. 269

Chapter 9 Analyzing Digital Sources and Cables

Getting started. . . . 272
Analyzer connections . . . 273
HDMI 1.1 . . . 273
HDMI 1.3 . . . 274
HDMI interface . . . 274
Monitoring HDMI 1.1 analyzer signal input . . . 275
Monitoring HDMI 1.3 analyzer signal input . . . 275
Measuring timing of video signal. . . . 279
Measuring timing parameters . . . 279
Testing cables and distribution systems . . . 286
Testing video signal quality from a source . . . 290
Running the Pseudo-Random Noise test . . . 290
Running the Pixel Error test . . . 295
Running the ViewPix test . . . 301
Generating Pseudo-random noise . . . 303
Testing InfoFrames (HDMI only) . . . 305
Testing HDMI transmit device InfoFrame capability . . . 305
Testing audio (HDMI only) . . . 310
Testing HDMI transmit device audio capability. . . . 310
Controlling the analyzer using the command line interface. . . . 311
Signal timing analysis commands. . . . 311
Viewing specific timing parameters . . . 311
Pseudo-random noise generation commands . . . 312
Configuring pseudo-random noise output parameters . . . 312
Analyzing pseudo-random noise from an external source . . . 312
Analyzing pixel data (pixel error test) . . . 314
Reading pixel data . . . 315
Controlling the analyzer with Signal Analysis Module . . . 317
Setting up the Signal Analysis Module . . . 317
Running the Signal Analysis Module . . . 317
Measuring Timing with the Signal Analysis Module . . . 318
Generating pseudo-random noise from an external source . . . 326
Implementing pseudo-random noise on an external source . . . 326

lfsr.h 326
lfsl.cpp 327

Chapter 10 Testing HDMI Sink Devices

Overview of HDMI display testing 332
Physical connections 332
Format selection 334
Image selection. 337
Setting up the generator for HDMI testing. 338
Selecting video format 339
Setting Source list of formats 340
Selecting a format 342
Testing HDMI displays 343
Testing HDMI 1.3 displays 345
Testing Deep Color. 345
Image Control Tool. 345
Ramp12 image. 346
RampDif image 349
Checkers image 352
Accessing the Image Control Tool 354
Testing xvYCC 356
Testing HDMI video pixel repetition (882 only) 363
Testing HDMI audio 367
Testing 2-channel HDMI audio output from internal SPDIF source 367
Testing 8-channel HDMI audio output from internal source 370
Testing multi-channel compressed HDMI audio formats 375
Testing HDMI audio using an external audio source 377
Testing HDMI InfoFrames (882 only) 380
Viewing InfoFrame contents (882 only) 380
Testing with Active Format Description (AFD) (882 only). 384

Chapter 11 CEC Interactive Troubleshooting Environment (ITE)

Overview 390
CEC Overview. 391
CEC devices 391

CEC features 392
Testing CEC Devices 393
Testing CEC devices for messaging. 393
Making physical connections 393
Emulating an HDMI CEC device 395
Configure an HDMI CEC device 396
Configure generator to log CEC messages 399
Verifying continuity over the CEC bus 399
Sending CEC messages from an emulated HDMI CEC device 401
Configuring generator to not respond to CEC messages 402
Querying the CEC message log. 403
Stress testing a CEC device 405
Setting up the CEC Controller 405
Bit timing tests 408
Bus arbitration tests 414
Bit corruption tests 420
Message acknowledgement tests 425
End of message tests. 431
CEC Bus Monitor 432
Activating the CEC bus monitor 432
Querying the CEC bus monitor. 432
Query the bus monitor messages 432
Query the bus monitor for bit timing errors and bit values 433

Chapter 12 CEC Compliance Testing

Overview 438
CEC Overview. 439
CEC devices 439
CEC features 440
Setting up CEC compliance testing. 441
Making physical connections 441
Establishing and verifying IP communication with the generator 442
Configuring the generator for HDMI 443
Verifying continuity over the CEC bus 444

Configuring generator to not respond to CEC messages 446
Additional equipment required 447
Running the CEC Compliance Test with the TME Software 450
Installing the TME software 450
Establishing communication between the TME software and the generator . . 451
Completing the Capabilities Declaration Form (CDF). 452
Defining a CDF for a device under test 453
Running the CEC Compliance Test 458
Viewing the results of the CEC compliance test 467

Chapter 13 Testing DisplayPort Sinks

Overview of DisplayPort sink testing. 472
Physical connections 472
Format selection 473
VESA DMT Formats. 473
VESA CVT Formats 475
Image selection. 479
Setting up the generator for DisplayPort testing 481
Selecting video format 482
Setting Source list of formats 482
Selecting a format 484
Testing DisplayPort sinks 485
Testing DisplayPort audio 487
Testing DisplayPort 2-channel LPCM audio output from internal source 487
Testing DisplayPort 8-channel LPCM audio output from internal source 490
Testing DisplayPort multi-channel compressed audio formats. 494
Testing DisplayPort audio using an external audio source. 497

Chapter 14 DisplayPort Link Layer Testing

Overview 500
Running the Link Layer compliance test for DisplayPort sink devices 501
Overview. 501
Setting up the tests 502
Monitoring the link layer transactions during a sink test with the ACA 510
Link Layer sink testing operations 513

Link Layer sink control operations 514
Link Layer sink control operations through command line 514
Link Layer sink control operations through front panel 518
Running the Link Layer compliance test for DisplayPort source devices 520
Monitoring the link layer transactions during a source test with the ACA 529
Link Layer source control operations 532

Chapter 15 MCCS

Overview 536
Accessing the MCCS application 537
Using the MCCS application 540
Connecting to and disconnecting from a generator 540
Adjusting display settings on a tab 541
Image Adjustments 541
Display Control Adjustments 542
Geometry Adjustments 544
Audio Adjustments 546
DPVL Adjustments 548
Creating and executing MCCS command scripts 549
Using the Message Exchange Log 550
Checking the connection status of the display 551
Refreshing the settings on the current tab 552
Checking display capabilities 552

Chapter 16 Auxiliary Channel Analyzer

Auxiliary Channel Analyzer Overview 554
Setting up and using the ACA 555
Running the ACA 555
ACA File menu options 557
ACA Filters 558
ACA search 558
Monitoring the HDMI auxiliary channels 560
Monitoring the DisplayPort auxiliary channel 572
Monitoring the DisplayPort auxiliary channel between the 882E and a DisplayPort device 572

Passive monitoring between a source and a sink. 576

Chapter 17 Testing EDID for HDMI and DisplayPort

Overview 580
Testing with display (sink) devices 581
Viewing EDID from a display (882 only) 581
Generating an EDID Information Report. 584
Modifying EDID in a display 587
Testing with source devices 589
Capturing and storing EDID from display device 589
Creating or editing EDID contents 590
Testing EDID handling of source device. 592
Testing EDID for HDMI compliance in display (sink) devices 593
Testing HDMI sink device for EDID compliance 593
Defining the capabilities of the display device under test. 593
Setting up generator for HDMI sink device EDID compliance testing 597
Running the EDID compliance test through the front panel 598
Running the HDMI EDID Compliance test report. 605
Running the HDMI EDID Compliance using the Compliance Controller 608
Verifying pixel encoding and rate support. 612
Testing EDID for HDMI compliance in source devices 615
Overview of HDMI compliance testing 615
Testing HDMI source devices for EDID compliance 615
EDID emulation for physical layer testing of source devices 618
Using Tektronix Test Instruments 619
Using Agilent Test Instruments 619
Using the EDID Editor tool 620
Loading EDIDs with the EDID Editor 620
Editing an existing EDID. 624
Creating a new EDID 627
Saving an EDID to a file 635
Putting (Writing) EDID to a display 636
Emulating an EDID 637
Running an EDID HDMI compliance test 638

Running an EDID data report 639
Using the EDID Compare tool 640
Comparing EDIDs 640
Testing EDID for DisplayPort verification in display (sink) devices 643
DisplayPort EDID verification test overview 643
Obtaining a “Reference EDID” for the test 643
Running the DisplayPort EDID Verification Test 644
Viewing the DisplayPort EDID Verification test report 645

Chapter 18 Testing Lipsync

Overview 652
Testing display (sink) devices 653
Testing source devices 659
Testing HDMI source device for Lipsync handling 659
Generating an HDMI source Lipsync data report 661

Chapter 19 Testing HDCP on HDMI and DisplayPort

Overview 666
Testing DVI displays with HDCP 667
Testing HDMI displays with HDCP 669
Testing DisplayPort sinks with HDCP 672
Running HDCP test in step mode 674
Running an HDMI HDCP self-test 676
Understanding the HDCP test 677
HDMI HDCP test sequence: 677
DisplayPort HDCP test sequence: 677
Running the HDCP compliance test for HDMI devices 679
Overview 679
Compliance Controller 679
Encryption Status Tester 682
List of Tests 683
Running HDCP compliance test on HDMI transmitters 686
Running HDCP compliance tests on HDMI receivers 696
Running HDCP compliance tests on HDMI repeaters 708
Running the HDCP compliance test for DisplayPort devices 749

Chapter 20 Using Special Sync Output

Overview 760
Operating special sync for probe pulse 761
Probe coordinate numbering 761
Configuring the probe feature 761
Controlling the probe using the command line interface 764
Configuring special sync for FS, LS, or CS 765

Chapter 21 Script SDK

Overview 768
Installation 768
Image programs versus script programs 769
Creating executable program scripts 770
Getting Started 770
Naming the file and the executable script 770
Returning “true” on exit 770
Enabling output to a serial terminal 770
Writing to a log file 771
Halting a script through the front panel during execution 771
About the ScriptSDK main window 771
ScriptSDK menu summary 772
Starting ScriptSDK 774
Creating, compiling, and executing a script 775
ScriptSDK API functions by category 779
Control functions 779
Command functions 779
Response functions 780
Front panel functions 780
Operator functions 780
ScriptSDK API functions by name 781
ScriptSDK commands 809
Sample ScriptSDK programs 816

Appendix A Command Reference

Commands by category 836

System 836
Control 836
Parameters 836
Tools 837
Network 837
User Profile 837
GPIB (IEEE-488.2 standard) 838
Commands 838
Port control 838
Gating Controls 838
Images 839
Control 839
Edit 839
Custom Image Draw 840
ImageShift utility 841
Formats 841
Control 841
Edit 842
Parameters (Video Signal) 842
Parameters (Video Timing) 845
Parameters (Audio Signal and Timing) 845
Test Sequences 846
Control 846
Edit 847
Directories 848
Control 848
Edit 848
EDID and DDC 848
Control 848
Edit 849
Special Sync Probe Pulse 850
Color Look-Up Table (LUT) 850
HDMI 850

Data Island Packet 850
InfoFrame Packet 850
DVI/HDMI HDCP 852
HDCP Compliance 852
DVI/HDMI Signal Analyzer 853
HDMI LipSync Generator/Analyzer 854
Commands by name 855

Appendix B Image Reference
Standard image descriptions 1264

Appendix C Error Messages
Error code descriptions 1368
0000-0099 General errors 1368
2000-2999 Format errors 1368
3000-3999 Image errors 1383
4000-4999 Test sequence errors 1384
5000-5999 Directory errors 1386
6000-6999 Bitmap errors 1386
7000-7999 LUT errors 1387
8000-8999 Font errors 1387
9000-9999 System errors 1388
10000-10999 System errors 1393

Appendix D Format Reference
SDTV Formats 1397
HDTV Formats 1400
VESA DMT Formats 1401
VESA CVT Formats 1402
Game Formats 1406
Medical Formats 1407
Military Formats 1408
TTL Formats 1408
Misc. Formats 1409
Test Formats 1409

Manufacturer Associated Formats 1410

1 Getting Started

Topics in this chapter:

- Introduction
- Video interfaces
- Computer interfaces
- Front panel interface
- Generator file system and media
- Generator operational modes
- Web interface
- Command line interface
- Working with user profiles

Introduction

This User's Guide describes the features, functions and operating procedures for the 881 and 882 Quantum Data video test instruments for testing analog and digital video display devices. The 881 provides features for testing video displays in production environments. The 882 is its complement. It provides extended features to test video displays for development environments and quality assurance applications.

There are three versions of the 882: 1) the 882C (and CA which includes the analyzer) and 2) the 882D and 3) 882E. The 882C provides two HDMI output ports (and two HDMI input ports if the analyzer option is present), a composite video and S-video connector and a VGA connector. The 882D provides a single HDMI output connector, a dual link DVI-I connector and a composite video and S-video connector. The SDI/HD-SDI outputs are an option for either the 882C or the 882D. The 882D does not support the analyzer option. The 882E provides either HDMI outputs and inputs or a DisplayPort output and input.

Standard features

DTV ready — Pre-programmed standard DTV formats are ready for immediate use. Digital outputs support YCbCr color encoding. Analog outputs support tri-level composite sync and YPbPr.

Built-in formats — Over 350 popular video formats are built in, including VESA, ATSC, EIA-770.x, SMPTE 170, 240, 259, 267, 274, 292, 293, 295, 296, Australian, EIA/CEA-861B, NTSC and PAL.

Central administration — Update and configure all networked instruments from a single computer.

Network control — Fully control instrument from any network location with Web browser or Telnet client.

Graphics SDK — Create complex patterns based on your specifications using C++ software development kit.

HDMI and DVI — 882C provides full single-link HDMI 1.1 and DVI (165 MHz) in same connector. DVI requires HDMI-to-DVI adapter cable. 882D provides dual link DVI out of a separate connector.

HDCP — Production keys with HDMI and DVI output.

Easy to use — Access powerful features easily using intuitive user interface.

Multiple configurations — Save and restore different instrument configurations for different applications.

Local pattern storage — Store multiple custom images (.bmp, .jpg, and .png) in instrument.

Self-calibrating — Analog video outputs are automatically adjusted against an internal precision reference. This ensures video levels are precise and reliable. Signal levels are auto-adjusted individually.

250 MHz analog pixel rate for 882C; 400MHz for 882D — Programmable precision RGB, YPbPr.

Probe — Trigger a scope or inspection camera using the probe signal. Position a pulse anywhere in the frame.

PC Card — Clone one generator to another using a standard CompactFlash card.

Optional features


HDMI and DVI analyzer (only available with the 882C) — Full single-link HDMI 1.1 and DVI (150 MHz) analyzer in same instrument. Measures source timing and source pixel errors. Also useful for testing cables. Test results can be issued as formatted reports.

SD/HD-SDI — Single link

- 1.485Gb/s and 1.485/1.001Gb/s
- YCbCr
- 4:2:2 color sub-sampling at 10 bits per component


Video interfaces

This section describes the generator's video interfaces. The video interfaces on the 882C are shown below.



Interface	Description
1	**SDI/HD-SDI** connector outputs a serial digital signal per SMPTE 259M and SMPTE 292M standards.
2	**CVBS** connector outputs an analog composite video baseband signal in accordance with SMPTE 170M standard.
3	**S-VIDEO** connector outputs an S-Video split luminance (Y) and chrominance (C) analog video signal.
4	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse • pixel clock signal
5	**VGA OUT** connector outputs a analog component video or analog RGB signal.
6	**HDMI OUT 1** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
7	**HDMI OUT 2** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
8	**HDMI IN 1** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
9	**HDMI IN 2** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
10	**SPDIF-AV** connector inputs audio from an external source.

This section describes the generator's video interfaces. The video interfaces on the 882D are shown below.



Interface	Description
1	**SDI/HD-SDI** connector outputs a serial digital signal per SMPTE 259M and SMPTE 292M standards.
2	**CVBS** connector outputs an analog composite video baseband signal in accordance with SMPTE 170M standard.
3	**S-VIDEO** connector outputs an S-Video split luminance (Y) and chrominance (C) analog video signal.
4	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse • pixel clock signal
5	**HDMI OUT** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
6	**DVI** connector outputs full dual link HDMI video.
7	**SPDIF** connector inputs audio from an external source.

VGA interface

The VGA interface, available on the model 882C generator, outputs analog video for testing analog video displays. The following table describes the VGA connector pinouts.

Pin	Signal	Pin	Signal	Pin	Signal
1	Analog Red Video	6	Analog Red Video Ground	11	No Connection
2	Analog Green Video	7	Analog Green Video Ground	12	DDC/EDID Serial Data
3	Analog Blue Video	8	Analog Blue Video Ground	13	Horizontal Sync

Pin	Signal	Pin	Signal	Pin	Signal
4	No Connection	9	DDC/EDID +5 Vdc Out	14	Vertical Sync
5	Digital Ground	10	Digital Ground	15	DDC/EDID Data Clock

DVI-I interface

The DVI-I interface, available on the model 882D generator, outputs digital video for testing DVI-compliant video displays. The DVI-I connector also provides an analog output which can be used to test analog formats.

The DVI connector pinouts are shown in the following table.

Pin	Signal	Pin	Signal	Pin	Signal	Pin	Signal
1	TMDS D2-	9	TMDS D1-	17	TMDS D0-	C1	Analog Red
2	TMDS D2+	10	TMDS D1+	18	TMDS D0+	C2	Analog Green
3	D2/4 Shield	11	D1/3 Shield	19	D0/5 Shield	C3	Analog Blue
4	TMDS D4-	12	TMDS D3-	20	TMDS D5-	C4	Horizontal Sync
5	TMDS D4+	13	TMDS D3+	21	TMDS D5+	C5	Analog Ground
6	DDC Clock	14	+5 Vdc	22	Clock Shield		
7	DDC Data	15	Ground	23	TMDS Clock+		
8	No Connection	16	Hot Plug Detect	24	TMDS Clock-		

HDMI interface

The HDMI interface emulates an HDMI-compliant video display. The HDMI connector pinouts are shown in the following table.

HDMI Type A Connector Pinouts

Pin	Signal	Pin	Signal	Pin	Signal
1	TMDS Data 2+	7	TMDS Data0+	13	CEC
2	TMDS Data2 Shield	8	TMDS Data0 Shield	14	Reserved (N.C.)
3	TMDS Data2-	9	TMDS Data0-	15	SCL
4	TMDS Data1+	10	TMDS Clock+	16	SDA
5	TMDS Data1 Shield	11	TMDS Clock Shield	17	DDC/SEC Ground
6	TMDS Data1-	12	TMDS Clock-	18	+5 V Power
				19	Hot Plug Detect

Special Sync interface

Use the Special connector to output frame sync, line sync, composite sync, or a special probe pulse. For more information, see Chapter 20, “Using Special Sync Output.”

S-Video interface


The 882 generator has an S-Video connector labeled “S-VIDEO.” This is a miniDIN connector that emulates an S-Video compliant source for outputting composite TV signal.

Composite video BNC

The 882 generator has a composite TV BNC connector labeled “CVBS.” This interface emulates an analog composite TV source.

Computer interfaces

This section describes the generator's computer interfaces. The computer interfaces are shown below (882C shown).



Connector	Description
1	**SERIAL** connector provides RS-232C serial data communication interface for the generator.
2	**DEBUG** connector is for Quantum Data use only.
3	**ETHERNET** connector is used to connect the generator with a TCP/IP network, for remote administration and control, and for sharing resources from a file server.
4	**GPIB** connector provides IEEE-488 GPIB interface to the generator (882 only; not provided on 881 generators).

RS-232 interface

Each generator has a standard RS-232 serial connector, labeled "SERIAL." This is a 9-pin D-Sub male connector which enables you to connect the generator with a computer. A null modem cable is provided to support this interface. You can communicate with the generator through the command line interface using a terminal emulator such as HyperTerminal. For more information, see "Working with the serial interface" on page 31. The pinouts for the RS-232 connector are shown in the following table.

Pin	Signal	Pin	Signal	Pin	Signal
1	Data Carrier Detect	4	Data Terminal Ready	7	Request to Send
2	Received Data	5	Signal Ground	8	Clear to Send
3	Transmitted Data	6	Data Set Ready	9	Ring Indicator


GPIB interface

The GPIB interface allows you to use the generator as a programmable video signal source in a larger automated test system. The GPIB connector pinouts are listed in the following table.

Pin	Signal	Pin	Signal	Pin	Signal	Pin	Signal
1	DIO1	7	NRFD	13	DIO5	19	Shield
2	DIO2	8	NDAC	14	DIO6	20	Shield
3	DIO3	9	IFC	15	DIO7	21	Shield
4	DIO4	10	SRQ	16	DIO8	22	Shield
5	EOI	11	ATN	17	REN	23	Shield
6	DAV	12	Shield	18	Shield	24	Signal Ground


Front panel interface

This section describes the front panel interface for operating the generator. The front panel keys are shown below.




Status indicators

Status indicators provide feedback about the operational status of the generator. The graphic below shows the location of the status indicators.




Menu selection keys

You can access the generator's menus using the menu selection keys depicted below.



Selecting menu items

When you press a menu selection key, a menu appears on the generator's display. Each menu item corresponds to a key located adjacent to the item. These keys are called "soft keys" because their functions change depending on the items that appear on the generator's display. For example, for the menu shown below, the soft key at the upper left corresponds to the System item on the generator's display.




Pressing a soft key either selects an item, enables or disables the item, or causes additional information about the item to appear on the generator's display. An icon located next to an item provides additional information about the item. Following is a list of icons and their meanings.

Icon	Meaning
	Folder containing related items.
	Recently visited folder.

Icon	Meaning
	Indicates active item in list of mutually exclusive items.
	Item is active, but may be deactivated by pressing soft key.
	Item is not active, but may be activated by pressing soft key.
	Value may be increased by pressing Up (+) key, or decreased by pressing Down (-) key.
	Page down to view more items.
	Scroll left to previous option, or right to next option
	Selecting this item will cause an action.

Item selection examples


The following examples show the different types of menu items.




About the Settings and Options keys

The **Options** key enables you to view or set basic options for the selected item. For items with multiple pages of options, press the **Options** key again to view additional pages. Typically, options are attributes that are either enabled or disabled. For example, the screen below shows the options for a format. On this screen, the asterisk (*) next to DSS

means that DSS is selected, the + sign next to SyncOnG means that this option is enabled, and the - signs next to Pedestal, SyncOnR, and SyncOnB mean that these options are disabled. If you press the soft key adjacent to SyncOnR, the - will change to a +, indicating the option is now enabled.



The **Settings** key enables you to view or set a parameter to a value. For example, the screen below shows the settings for the video signal of a format. To change the value of the XVSI, AVSI, or DVSI setting, press the soft keys next to the arrows on the bottom row of the generator's display until the blinking cursor is on the value you want to change. Increment the value up or down by pressing the + and - keys.



To see other settings for the format, press the soft key adjacent to the arrows. If you press the soft key next to the arrow by Video Signal, you will see the settings for Video Timing. If you press the soft key next to the arrow by Interface, you will see the settings for Synchronization.

Generator file system and media

The generator has a file system comprised of a System folder and a Library folder of resource files that can be stored on multiple media (storage devices or locations). The files in the file system are briefly described below.

Generator file system

The 882 generator file system is comprised of two main directories (folders): 1) System and 2) Library. The System folder contains the realtime operating system and firmware file (vxWorks) and the gateware. The Library folder contains the following resource files:

- Fonts - Object files used to define the font types.
- Formats - XML files defining the format parameter settings.
- FormatLib - XML files for configuring the source list of formats
- Images - C++ object files, executables, bitmaps, and XML files for rendering images.
- ImageLib - XML files for configuring the content list of images
- Sequences - XML files with instructions for test sequences.
- Users - XML files for user configuration profiles

Generator media

The generator provides for two read/write local storage media and one server-based medium (storage locations):

- Flash memory
- PCM CIA card
- Host server

Each of these storage locations contains or can contain all the generator's System and Library files.

Generator operational modes

The generator has two operational modes: 1) Basic mode and 2) Browse mode. The generator boots up in the Basic mode which is the main operating mode you will be using. Both modes are described below along with instructions for booting up the generator.


Booting up the generator

When the generator is powered up it presents a screen enabling you to select the boot device. The generator loads its operating system and firmware from a from the selected boot device or specified medium (storage location). If you do not press a key within 5 seconds the currently specified boot location is used and boot up proceeds. This feature enables you to control where the generator boots from in instances where the default location is either inaccessible or known to have a suspect application file. Follow the procedure below to boot the generator:


To boot the generator:

1. Apply power to the generator. The following display appears.


   If you are sure you want to boot from the current storage location you can let the system boot automatically.



   a. To boot from an alternative device, press any key within five seconds. The following screen appears on the generator's display:



2. Choose the **!BootDev** item by pressing the adjacent soft key.



3. Do one of the following:

   - To boot from the file server, press the soft key adjacent to **Network Boot**.
   - To boot from the generator's flash memory, press the soft key adjacent to **Internal Flash**.

- To boot from the generator's PC card, press the soft key adjacent to **PCMCIA Boot**.

4. Press the **Options** (**Enter**) key to save the configuration.
5. Either restart the generator by cycling the power or press the **Tools** key to return to the boot menu.
6. Scroll down to allow viewing and selection of the BootNow item as shown below.

```
!FileName   !Other
!InetAddr   !TrgtName
!HostAddr    BootNow
!User
```

7. Select **BootNow** by pressing the adjacent item selection key.
8. The following display appears:

```
 Press UP arrow
 to Boot Now
```

9. Press the + key to boot the generator.

Basic mode


The Basic mode is the main operating mode of the generator. Typically, you will use the Basic mode when testing displays and sources. In Basic mode you can select formats and images, create and run test sequences, view and edit object properties, and so on.

In the Basic mode you make selections in the front panel with the item selection keys and the soft keys. The function of the menu selections key is described and depicted in "Menu selection keys" on page 11.

Browse mode

Browse mode is for advanced users who want to load objects from different media and program the generator function keys. This mode is for expert users only.


When in Browse mode, the selection keys shown below are active.



The procedure below describes how to place the generator in Browse mode:

To place the generator in Browse mode:

Press and hold the **Tools** key. The message **Hold to enter Browse Mode** appears on the generator's display. Continue holding the Tools key until the Browser status indicator lights. The following menu appears:



Browsing other media


In Browse mode, you can view and use objects located in the generator's flash memory, a network file server, the generator's PC card, or the generator's cache memory.

To choose the medium to browse:

1. Press the soft key adjacent to the medium you want to browse.

Medium	Description
Flashmem	Non-volatile memory in generator.
NetPlace	File server connected with generator.
PCCard	Compact Flash card in generator.
Cache	Volatile memory in generator. This source contains objects that have been used (loaded into cache) since the generator was started.

A list of folders on that medium appears on the generator's display as shown below.



2. Choose the folder you want to open by pressing the adjacent soft key. The contents of the folder appears on the generator's display. If you need to return to the previous menu list press the back (settings) key.




3. Continue selecting folders to open until you locate the item you need. To use an item, press the adjacent soft key.

Setting the generator's path

The generator can be set to access format, image, and sequence files stored on its flash memory, PC card, or on a file server. To do this, you must set the generator's path to point to the corresponding folders on the desired medium. You can set the path using the command line interface or the front panel.

To set the generator's path using the front panel:

1. Place the generator in Browse mode by holding down the **Tools** key until the media menu appears on the generator's display as shown below.



2. Choose the desired medium by pressing the adjacent soft key. The folders on the selected medium (for example flash memory) appear on the generator's display as shown below.



3. Press the soft key adjacent to the Library folder. The contents of the selected folder appears on the generator's display as shown in the example below.



4. Press the soft key adjacent to the folder you want to use. For example, to set the format path, press the soft key adjacent to Formats. The contents of the Formats folder appears on the generator's display.

5. Select a format by pressing the adjacent soft key. The format path is now set to the selected folder on the selected medium.

To set the generator's path using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. For each file type (format, image, and sequence), set the path parameter to the corresponding folder on the desired medium. In the command syntax, specify the medium as follows:
   - Flash memory: tffs0 (TFFS - Transaction Flash File System)
   - PC card: card0
   - File server: <server name>
3. For each file type (format, image, and sequence), set the path parameter to the corresponding folder on local generator media using the following commands:

   ```
   FMTP /medium/Library/Formats
   IMGP /medium/Library/Images
   SEQP /medium/Library/Sequences
   ```

   For example the medium name for the PC card is /card0. So you would enter the following command to set the image path to the image directory on the PC card:

   ```
   IMGP /card0/Library/Images
   ```

   The generator will now display the images on the PC card when you press the **Contents** key.

   The medium name for the flash memory is /tffs0. So you would enter the following command to set the image path to the format directory on the flash memory:

   ```
   FMTP /tffs0/Library/Formats
   ```

   The generator will now display the formats on the flash memory when you press the **Source** key.

   The medium name for the network is the server (host name) memory. So you would enter the following command to set the image path to the format directory on the flash memory:

   ```
   SEQP /Server030/Library/Sequences
   ```

   The generator will now display the sequences on the server when you press the **Tools** key and then select sequences.

Programming the generator's function keys

The generator is equipped with four function keys (F1 through F4) that can be programmed as shortcuts to folders. The procedure below describes how to program the function keys.


To program a function key as a folder shortcut:

1. Browse to the folder to which you want to create a shortcut.
2. Hold down a function key (F1, F2, F3, or F4) to assign the key to the folder.

Switching from Browse mode to Basic mode

To switch from Browse mode to Basic mode:

Press and hold the **Tools** key. The message **Hold to enter Basic Mode** appears on the generator's display. Continue holding the Tools key until the Browse Mode status indicator turns off and the Tools menu appears.



Web interface

The generator has a built-in Web server that enables you to interact with the generator using a PC and an Ethernet connection. The Web interface includes the following functions:

- Format Editor for creating formats and modifying and viewing format parameters. For more information about the Format Editor, see “Creating custom formats using the Format Editor” on page 186.
- Virtual Front Panel for operating the generator remotely.
- CMD Terminal for operating the generator using the command line interface.
- Generator FTP Browser for copying files between media within the generator, between generators, and between a generator and a PC.
- Calibration reports (Currently not available)

This section describes how to operate the Virtual Front Panel, CMD Terminal, and the Generator FTP Browser.


Working with the Virtual Front Panel

The Virtual Front Panel enables you to perform remotely the same tasks as you would with the generator’s front panel. To use the Virtual Front Panel, you must have a PC connected to a generator either through an Ethernet LAN or locally through an Ethernet crossover cable connected between the Ethernet ports on the generator and the PC. These configurations are described in more detail in “Establishing a network environment” on page 144. You must also have the Java Runtime Environment (JRE) 1.5 or later installed on your PC. You can download the JRE from http://www.java.com/en/download/windows_ie.jsp.

To use the Virtual Front Panel, you must know the IP address of the generator. The following procedures describe how to determine the generator’s IP address and how to access the Virtual Front Panel using a Web browser.

To determine the IP address of the generator:

1. Press the **Tools** key. The Tools menu appears on the generator’s display as shown below.



2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.

```
Clock              Clone*
CalFactor         Server
Network            About
Serial              GPib
```

3. Choose the **Network** item by pressing the adjacent soft key. The generator's IP address appears on the generator's display as shown below.

```
IP Address
192.168.254.001
Subnet Mask
255.255.255.000
```

To use the Virtual Front Panel:


1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://192.168.254.001.

   The generator home page appears in the browser.



Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*

2. Click the **Virtual Front Panel** link. The Virtual Front Panel appears.



3. Use your mouse to click the virtual keys, which function the same as if you pressed the physical keys on the generator.


Working with the CMD (Command) Terminal

The CMD Terminal allows you to send commands to the generator using the command line interface.

To use the CMD Terminal:

1. Access the Virtual Front Panel page. See “To use the Virtual Front Panel:” on page 22.
2. Click the **CMD Terminal** link. The CMD Terminal window appears.

3. In the box at the top of the CMD Terminal window, enter a command, and then press Enter. The command appears in the lower pane.



Working with the Generator FTP Browser


If you create objects on a PC, such as images or formats, you can use the Generator FTP Browser to copy these objects to a generator. You can also use the Generator FTP Browser to copy objects between media in a generator and to copy objects from one generator to another.

Copying files from a PC to a generator

To copy files from a PC to a generator:

1. Access the generator's FTP browser by choosing the **FTP Browser** menu item from the main web page. The Generator FTP Browser appears. The Instrument Files area

2. shows the files stored on the generator. The Host Files area shows the files stored on the PC.




3. In the **Host Files** area, locate and select the file or folder you want to copy.
4. In the **Instrument Files** area, locate the destination folder for the file as follows:
   a. In the **Look in** box, click the down arrow and select the medium where you want to copy the file. Select **tffs0** for the generator's flash memory or **card0** for the generator's PC card.
   b. In the list of files, open the destination folder.
5. In the **Host Files** area, click **Download**. The **Transfer Files** dialog box appears.
6. Verify that the source file or folder and the destination folder are correct, and then click **OK**.
7. The **Copying Files** dialog box appears showing the status of the operation. When the status is 100%, click **Done**.

Copying files from a generator to a PC

To copy files from a generator to a PC:

1. Access the generator's FTP browser by choosing the **FTP Browser** menu item from the main web page. The Generator FTP Browser appears. The Instrument Files area shows the files stored on the generator. The Host Files area shows the files stored on the PC.




2. In the **Instrument Files** area, locate and select the file or folder you want to copy as follows.
   a. In the **Look in** box, click the down arrow and select the medium where the file is located. Select **tffs0** for the generator's flash memory or **card0** for the generator's PC card.
   b. In the list of files, select the file or folder you want to copy.
3. In the **Host Files** area, open the destination folder where you want to copy the files.
4. In the **Instrument Files** area, click **Upload**. The **Transfer Files** dialog box appears.

5. Verify that the source file or folder and the destination folder are correct, and then click **OK**.
6. The **Copying Files** dialog box appears showing the status of the operation. When the status is 100%, click **Done**.

Copying files between the generator's flash memory and PC card

To copy files between media in a generator:

1. Access the generator's FTP browser by choosing the **FTP Browser** menu item from the main web page. The Generator FTP Browser appears. The Instrument Files area shows the files stored on the generator. The Host Files area shows the files stored on the PC.




2. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0**. This is the generator's flash memory.

3. Repeat step 2 to open a second Generator FTP Browser. In the **Instrument Files** area of the second Generator FTP Browser window, click the down arrow by the **Look in** box and select **card0**. This is the generator's PC card.
4. Locate the file or folder you want to copy in the source window.
5. Locate and open the destination folder in the destination window.
6. Drag the file or folder from the Instrument Files area of the source window to the Instrument Files area of the destination window.


Copying files between generators

To copy files between generators:

1. Open a Web browser (such as Internet Explorer) and type the source generator's IP address in the address entry field. The source generator's home page appears in the browser.



2. Access the generator's FTP browser by choosing the **FTP Browser** menu item from the main web page. The Generator FTP Browser appears. The Instrument Files area shows the files stored on the generator. The Host Files area shows the files stored on the PC.



3. Repeat steps 1 and 2 for the target generator.

Note: *You now have two instances of the Generator FTP Browser running: one for the source generator and one for the target generator.*

4. In the Generator FTP Browser window for the source generator, locate the file or folder you want to copy as follows:
   a. In the **Look in** box, click the down arrow and select the medium where the file or folder is located. Select **tffs0** for the generator's flash memory or **card0** for the generator's PC card.
   b. In the list of files, select the file or folder.

5. In the Generator FTP Browser window for the target generator, open the destination folder as follows:
    a. In the **Look in** box, click the down arrow and select the medium to which you want to copy the file or folder. Select **tffs0** for the generator's flash memory or **card0** for the generator's PC card.
    b. In the list of files, open the destination folder.
6. Drag the file or folder from the Instrument Files area to the Host Files area of the source window. A confirmation dialog box appears.
7. Click **OK** to copy the files.
8. Locate the file or folder in the Host Files area in the target window. Drag the file or folder from the Host Files area to the destination folder in the Instrument Files area of the target window. A confirmation dialog box appears.
9. Click **OK** to copy the files.

Command line interface

Common test procedures can be accomplished using the generator's physical controls on the front panel, Virtual Front Panel or through the command line interface. The generator supports an ASCII command and query language that allows you to control the generator interactively or through batch processing of command files. All generator functions are supported through this interface. The command line interface is available through three physical interfaces:

- Serial (RS-232) interface (terminal session, such as HyperTerminal, via the serial port)
- Ethernet network interface (Telnet session or Web browser via the Ethernet port)
- GPIB (IEEE-488) interface (via the GPIB port)

The serial and Ethernet interfaces are described in this section. For information on the GPIB interface, see Chapter 5, "Using GPIB Interface."

Working with the serial interface

This section describes how to connect the generator to the PC via the serial port, how to establish a terminal session with the generator using a terminal emulator such as HyperTerminal, and how to change serial port settings.

To connect the generator to the PC:

To set up the generator to use the serial interface, connect a serial null modem cable from the serial port of the PC to the SERIAL connector on the rear of the generator.

Establishing a terminal session with the generator

The following procedure describes how to establish a terminal session with the generator through the serial port. For information about establishing a Telnet session over an Ethernet LAN, see "Establishing a Telnet session with the generator" on page 34.

To establish a terminal session with the generator:


1. Open a terminal emulator, such as HyperTerminal. Configure the terminal emulator to use the parameters set in the generator. By default, the generator's serial port is set to 9600 baud, 8 data bits, no parity, 1 stop bit, no flow control.
2. Establish a terminal connection with the generator. Press Enter until the C:> prompt appears.

Configuring the generator's serial port

The following procedures describe how to change the generator's default serial port configuration for a terminal session. You can configure the serial port through either the front panel, Virtual Front Panel or through the command line interface.

To configure the generator's serial port through the front panel or Virtual Front Panel:


1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



3. Choose the **Serial** item by pressing the adjacent soft key. The serial port settings appear on the generator's display.



4. Press the **Settings** key. The following information appears on the generator's display:



5. To change the baud rate, do the following:

   a. Position the blinking cursor on the baud rate setting. To do this, press the soft key adjacent to the arrow by the baud rate setting to move the cursor left or right until it appears on the baud rate setting.

   b. Press the + or - keys to adjust the baud rate setting up or down.

6. To change the flow control state, do the following:

   a. Position the blinking cursor on the flow control setting. To do this, press the soft keys adjacent to the arrow by the flow control setting until the cursor appears on the current flow control setting (N, H, or T).

   b. Press the + or - keys to change the setting.

7. To change the number of data bits, do the following:

   a. Press the soft keys adjacent to the third row until **CHAR** appears. The current data bits setting is shown in the bottom row.

```
      Serial Port
       Set Params
<-  CHAR   PRTY   STOP
       8      N      1 ->
```

   b. Position the blinking cursor on the CHAR setting. To do this, press the soft keys adjacent to the arrow by the CHAR setting until the cursor appears on the current data bits setting.

   c. Press the + or - keys to adjust the setting up or down.

8. To change the parity, do the following:

   a. Position the blinking cursor on the PRTY setting. To do this, press the soft keys adjacent to the arrow by the PRTY setting until the cursor appears on the current parity setting.

   b. Press the + or - keys to adjust the setting up or down.

9. To change the stop bits, do the following:

   a. Position the blinking cursor on the STOP setting. To do this, press the soft keys adjacent to the arrow by the STOP setting until the cursor appears on the current stop bits setting.

   b. Press the + or - keys to adjust the setting up or down.

10. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:

```
     Apply Settings?

                      Back
Yes                     No
```

    To save the changes, choose the **Yes** item by pressing the adjacent soft key.

    To exit without saving the changes, choose the **No** item.

    To return to the previous screen without saving the changes, choose the **Back** item.

To configure the generator's serial port through the command line interface:

1. Establish a session with the generator using HyperTerminal over a serial connection or Telnet over an Ethernet LAN. For instructions, see "Establishing a terminal session with the generator" on page 31 and "Establishing a Telnet session with the generator" on page 34.
2. At the session prompt, enter the following command to query the generator for the current serial port settings:

   ```
   MODE?
   ```

   The generator returns the current values:

   ```
   9600,N,8,1,N,N
   ```
3. To change the settings, enter the following command:

   ```
   MODE baud parity data stop handshake protocol
   ```

   For example, to change the baud rate to 38400, enter the following command:

   ```
   MODE 38400 n 8 1 n n
   ```

   Note: *In this example, after you press Enter, the baud rate of the session and baud rate of the generator will no longer match. This will cause the session to lose its connection with the generator. Close the session, change the session baud rate to 38400, and then re-open the session.*

Working with the network interface

This section describes how to connect the generator to a PC via an Ethernet LAN and how to establish a Telnet session with the generator.

To connect the generator to a PC over an Ethernet LAN:

1. Connect the Ethernet cable between the PC's Ethernet port and an active Ethernet jack.
2. Connect an Ethernet cable between the generator's ETHERNET port and an active Ethernet jack.

Establishing a Telnet session with the generator

The following procedure describes how to establish a Telnet session with the generator over an Ethernet LAN. For information about establishing a terminal session over a serial connection, see "Establishing a terminal session with the generator" on page 31.

To establish a Telnet session with the generator:

1. Using a text terminal application, such as DOS Command Prompt, enter the following command:

```
telnet generatorIPaddress
```

Example:

```
telnet 192.168.254.220
```

2. The **/tffs0>** prompt appears. Type commands at the **/tffs0>** prompt, and press Enter after each command.

Sending commands interactively

This section describes how to send commands through an interactive command line interface session. The generator parses command lines one at a time. Command lines must be terminated with a carriage return (<cr>). The generator immediately echoes each character as it is received and places it in a command line buffer. Commands are not case sensitive.

When sending multiple commands at once, separate each command with a semi-colon. For example, to load the 480p59 format with the SMTPEbar image, send the following commands:

```
FMTL 480p59
IMGL SMPTEbar
ALLU
```

Common commands

- To apply an image and format to the generator hardware, enter:

  ```
  ALLU
  ```

- To display the name of the format currently in the format buffer, enter:

  ```
  FMTL?
  ```

- To load a format, enter:

  ```
  FMTL format_name
  ```

- To apply the format to the generator hardware, enter:

  ```
  FMTU
  ```

- To load an image, enter:

  ```
  IMGL image_name
  ```

- To apply the image to the generator hardware, enter:

  ```
  IMGU
  ```

Sending command files (serial interface only)

When developing more complex, custom test sequences or formats, it is easiest to enter commands in a text file, and then send the file to the generator. This approach allows you to modify the file without entering the entire command script.

Note: *Sending command text files can be performed via the serial interface only.*

To send a text file to the generator:

1. Using a text editor, enter commands into a text file, and save the text file using a *.txt extension.
2. Establish a session with the generator using a terminal emulator, such as HyperTerminal over a serial connection.
3. At the C:> prompt, transfer the text file to the generator. For example, to transfer a file using HyperTerminal, do the following:
   a. On the **Transfer** menu, click **Send Text File**. The **Send Text File** dialog box appears.
   b. Select the text file you want to send, and then click **Open**. HyperTerminal displays the commands as they are sent.
   c. Press **Enter** once to ensure that the last command is sent.

Working with user profiles

The generator provides user profiles that enable you to quickly load pre-defined configurations. This can be done either through the front panel, virtual front panel or the command line. For example, you can create different profiles for each operator, production line, display type under test, and so on.

A user profile is always active on the generator (“User1” is the default profile). While active, the generator tracks subsequent format and format options, format catalogs, interface, and content selections made by the user. These configuration settings are saved to the active profile when a different user profile is chosen on the generator.

To choose a user profile:

1. Press the **Source** and **Content** keys simultaneously (or press USER on the Virtual Front Panel) to access the list of user profiles.

   The following is an example of a set of user profiles that might appear on the generator’s display. Note that User1 is active, which is indicated by the = sign.

   ```
   =User1              User2
    User3              User4
    User5              User6
    User7              User8
   ```

2. Choose another user by pressing the adjacent soft key. For example, to change to User5, press the soft key adjacent to User5. This will save the configuration settings for User1 and select the profile for User5. Any subsequent configuration changes will apply to User5.

   Alternatively, to switch users using the command line interface, enter the following command:

   ```
   USRU username.xml
   ```

   For example, to select User5, enter

   ```
   USRU User5.xml
   ```

   To query the current user, enter

   ```
   USRU?
   ```

   The generator returns the current user name.

   ```
   /tffs0/Library/Users/User5.xml
   ```

To create a new user profile:

The procedure for setting up a new user profile is accomplished using the command line interface.

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with

the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

2. Enter the following command:

```
USRA username.xml
USRU username.xml
```

Note: *A user name is 8 alphanumeric characters.*

For example, to set up a user profile called "User3," enter:

```
USRA User3.xml
USRU User3.xml
```

A new user profile is created with default configuration settings and becomes the active profile on the generator. While active, the generator tracks subsequent format and format options, format catalogs, interface, and content selections made by the user. These configuration settings are saved to the active profile when a different user profile is chosen on the generator.

To delete a user profile:

1. Enter the following command:

```
USRK username.xml
```

For example to delete User5, enter:

```
USRK User5.xml
```

2 Testing Video Displays

Topics in this chapter:

- General video display testing procedures
- Testing analog computer (IT) CRTs
- Testing digital computer (IT) FPDs
- Testing analog composite video SDTV (CE) CRTs
- Testing analog component video SDTV (CE) CRTs
- Testing digital component video HDTV (CE) FPDs
- Using the Image Caching feature
- Using the AuxTest image
- Using the ImageShift utility
- Adjust Frequency Function
- Keypad Utility

General video display testing procedures

This section provides an overview of basic steps performed to test your video display using your 882C(A) or 881 generator. Testing your video display involves four basic steps:

1. Connecting generator to display under test.
2. Selecting interface type for display under test.
3. Selecting a video format appropriate for display under test.
4. Selecting an image suitable for testing the display under test.

Making physical connection

The first step is to make a physical cable connection between the generator and display under test. The following table provides guidelines for connecting the 882C(A) or 881 generator to the display under test.

Display type		**Signal type**	**Port (Interface)**	**Cable**
Information Technology (IT)	Computer - VESA (DMT, CVT)	Analog component RGB	VGA	VGA to VGA
	Computer - VESA DDWG	Digital component RGB	HDMI OUT (HDMI-D)	HDMI to DVI
Consumer Equipment (CE)	SDTV - ITU-470-6 baseband	Analog composite CVBS	CVBS	BNC to RCA 75 Ohm
	SDTV - ITU-470-6 baseband	Analog composite S-Video	SVIDEO	S-Video (miniDin)
	SDTV - CEA-861B	Analog component YPbPr	VGA	VGA to RCA[1]
	HDTV - CEA-861C	Digital component DVI RGB	HDMI OUT (HDMI-D)	HDMI to DVI
	HDTV - CEA-861C	Digital component HDMI RGB and YCbCr	HDMI OUT (HDMI-H)	HDMI to HDMI
Profes-sional AV	SDI (SMPTE-259M) and HD-SDI (SMPTE-292M-C)	Digital component YCbCr	SDI/HD-SDI	BNC Coax

1. Optional cable available from Quantum Data.

Use the following table to connect the 882D generator to the display under test.

Display type		Signal type	Port (Interface)	Cable
Information Technology (IT)	Computer - VESA (DMT, CVT)	Analog component RGB	DVI-A with DVI to VGA adapter	VGA to VGA
	Computer - VESA DDWG	Digital component RGB	DVI for single and dual link or HDMI OUT (HDMI-D) for single link only	DVI to DVI cable for DVI connector or HDMI to DVI for HDMI-D connector
Consumer Equipment (CE)	SDTV - ITU-470-6 baseband	Analog composite CVBS	CVBS	BNC to RCA 75 Ohm
	SDTV - ITU-470-6 baseband	Analog composite S-Video	SVIDEO	S-Video (miniDin)
	SDTV - CEA-861B	Analog component YPbPr	DVI with DVI to VGA adapter	VGA to RCA[1]
	HDTV - CEA-861C	DVI for single and dual link or HDMI OUT (HDMI-D) for single link only	HDMI OUT (HDMI-D)	DVI to DVI cable for DVI connector or HDMI to DVI for HDMI-D connector
	HDTV - CEA-861C	Digital component HDMI RGB and YCbCr	HDMI OUT (HDMI-H)	HDMI to HDMI
Professional AV	SDI (SMPTE-259M) and HD-SDI (SMPTE-292M-C)	Digital component YCbCr	SDI/HD-SDI	BNC Coax

1. Optional cable available from Quantum Data.

Selecting interface type

After making the physical connection, you are ready to select the interface type for your display under test.

You can select the interface using either the front panel keys or the command line interface. The interface is one of the following:

- VGA - For testing analog VESA displays on the 882C.
- DVI-A - For testing analog VESA displays on the 882D.
- CVBS - For testing composite analog consumer electronic displays.
- S-Video - For testing composite (separate luma and chroma) consumer electronic displays.
- DVI-D - For testing digital VESA displays (dual link) on the 882D.

- HDMI-D - For testing DVI displays through an HDMI interface.
- HDMI-H - For testing HDMI consumer electronic displays.
- SDI/HD-SDI - For testing SDI and HD-SDI professional AV displays.

To select an interface:

1. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



2. Choose the interface by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format. An asterisk is shown beside the selected interface.


   Alternatively, to select the interface through the command line interface, enter commands like shown below:

```
XVSI 9          // Selects the VGA interface
ALLU            // Applies the interface setting to the generator
```

To define the display size:

Once you have selected the interface, you can change the parameters specifying the physical size of the display (if your application calls for that).

1. After selecting the interface, press the **Sink** key and then the **Settings** key. The following information appears on the generator's display.




2. Navigate to the other parameters for physical size (VSIZ and USIZ) to set the display size for your test application.

To gate off the output:

You can gate off and on the interface output as follows:

1. Press the **Interface** key, then press the **Options** key. The following information appears on the generator's display.



2. Enable or disable the interface output by pressing the adjacent soft key.

Selecting video format

Once you have selected the interface type for the display under test, you need to select a video output format. A format defines a set of video, timing, and sync parameters for a specific device or standard. This section explains how to configure the generator to output video formats that are supported by the display under test.

Important: *If the display under test has not implemented hot plug correctly, you will have to bypass hot plug detection in the generator to enable video output. See below for procedure on bypassing hot plug detection.*

Note: *For more information about formats, see Chapter 6, "Working with Formats."*


Setting Source list of formats

The generator provides a Source list of standard (pre-defined) formats. The Source list can be set automatically when connecting to a EDID-compatible display. Otherwise, you can manually set which formats are listed.


To automatically set Source list of formats for EDID-compatible display:

When testing EDID-compatible displays, the generator can automatically update the Source list to include only formats supported by the display under test. To do this:

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.



3. Press the **Options** key. The following information appears on the generator's display.



4. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats indicating enabled.

   The generator loads the Source list with formats supported by the connected display (hot-plug formats read via EDID structure of attached display).

5. To redisplay all formats, press the soft key adjacent to EDID Formats. A '-' (minus sign) next to EDID Formats indicates it is disabled.

To bypass hot plug detection:

If the display under test has not implemented hot plug correctly, you will have to bypass hot plug detection in the generator to enable video output.

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats       CDF↖
+HP Bypass
-Emulate
```

4. Choose the **HP Bypass** (hot plug bypass) item by pressing the adjacent soft key. A + appears next to HP Bypass indicating enabled.

To manually set Source list of formats for non-EDID-compatible display:

When testing a display that is not EDID-compliant, the Source list is filtered to display only those formats suitable for a particular interface type. For example, if you select CVBS, the Source list does not include the VESA formats.

The generator's format library is comprised of a set of format catalogs. You can set up the generator to show only the formats you want, in the order you want, when you browse through the Source list. See "Format catalogs" on page 229 for details.

To use Emulate mode:

Emulate mode automatically sets color space, synchronization type, and other settings based on the interface and format selected:

- For VGA interface, synchronization type and color space are automatically set and are not changeable.
- For HDMI interface, synchronization type and color space are automatically set, but color space can be changed.

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

3. Press the **Options** key. The following information appears on the generator's display.



4. Choose the **Emulate** item by pressing the adjacent soft key. A + appears next to Emulate indicating enabled.

   Alternatively, to select the emulate mode through the command line interface, enter the command shown below:

```
EMUG 1        // Enables emulate mode
```

   To disable the emulate mode through the command line interface, enter the command shown below:

```
EMUG 0        // Disables emulate mode
```

Selecting a format

From the Source list of formats, you select the video format output for your display under test.


To select a format:

1. Identify the type of display (composite television, component standard definition television, component high definition television, computer equipment, or other specialty display).

   Note: *The generator has a library of standard formats. For a description of how the library is organized, see "Understanding the format library" on page 46.*

2. For non-EDID compliant displays, check the specifications of your display for supported formats.

3. Press the **Source** key to access the list of formats. A list of formats appears on the generator's display as shown below. To see all of the formats, press the + and - keys.



   Note: *The list of formats displays when pressing the* ***Source*** *key may be a filtered or abbreviated list. Formats not suitable for the selected interface type will not appear by default on the* ***Source*** *list. Also, you can disable format catalogs to prevent certain formats from appearing on the Source list. For more information about format catalogs, see "Format catalogs" on page 229.*

4. Choose a format by pressing the adjacent soft key.

Upon selecting a format, you can modify the format options and settings if necessary. For instructions on this, see “Configuring format parameters” on page 181.

Understanding the format library

The generator has several built-in formats to test a broad range of display types. These formats are grouped in the following categories:

- Composite television formats
- Component standard definition television formats
- Component high definition television formats
- Computer display formats
- Military and medical display formats
- Miscellaneous formats

Note: *A summary of the format naming conventions is provided in this section. For a detailed description of the naming conventions, see “Format library” on page 175.*

Composite television formats

Composite television formats are named by the standards defining them. The first three to five characters of the format name indicate the color coding scheme. The first set of characters refers to the standard. The next characters are optional and indicate adjustments to the format. Examples of these formats are:

- NTSC (North American TV)
- PAL (European TV)
- NTSC-J (where J refers to a Japan standard per NTSC without 7.5 IRE setup)
- PAL-N (where N indicates 3.58205625 MHz color sub-carrier)
- PAL# (where # indicates that the sampling rate is reduced to achieve square pixels)

Component standard definition television formats

Component SDTV formats are applicable in the case of RGB and YPbPr. These formats are named by their vertical resolution, scanning method, and frame rate. The initial characters indicating the resolution are followed by the scanning method. The two characters following the scanning method indicate the frame rate. A typical example of a component standard definition TV video format is:

- 480i2x30 (for a vertical resolution of 480 pixels with interlaced scanning and a 30 Hz frame refresh rate; 2x indicates that the pixels are double-clocked for DVI compatibility).

Component high definition television formats

Component high definition television formats, like the standard definition television formats, are named by their vertical resolution, scanning method, and frame rate. These formats are applicable in the case of RGB, YPbPr, and YCbCr. These initial characters indicating the resolution are followed by the scanning method. The two characters following the scanning method indicate the frame rate. A typical example of a component high definition TV video format is:

- 1080i30 (for a vertical resolution of 1080 active vertical lines with interlaced scanning and a 30 Hz frame refresh rate).

Computer display formats

Computer display formats are assumed to use progressive scanning. Computer display format names consist of four blocks. The initial three characters indicate the vendor ID using the EISA ID (for example, IBM, SUN, and VSC) or the standard body or acronym (for example, SMT, DMT, GTF, CEA, and EIA). The next two characters provide the first two digits of the horizontal resolution in pixels. Following the horizontal resolution are two characters which indicate the frame rate. The final character indicates the aperture, which is used only if the aperture is not 1.33 (A). The following are examples of computer display formats:

- VSC1275 for Viewsonic 1280 by 1024 at 75 Hz
- DMT0685 for Discrete Monitor Timing with 680 by 480 at 85 Hz

Viewing or modifying format parameters

You can use the Format image to view detailed information about formats in the generator.

You can also modify format parameters through the front panel, through the command line interface, or through the Format Editor. These procedures are provided in “Configuring format parameters” on page 181.

Selecting image

Once you have determined the format or formats appropriate for testing the display, you will apply a series of images suitable for evaluating the display. Of primary importance is determining what type of display you are testing (for example, CRT or digital flat panel display). You must also determine if you are testing composite TV and use images appropriate for these formats and video types.

Each image in the generator’s library is intended to test one or more attributes of a particular display type and video type.

Rendering images

Use the following procedures to view primary images.

Once you have selected an image you can modify the image options if necessary. For instructions on this refer to “Viewing and modifying image options” on page 237.

To select an image:

1. Identify the type of display (CRT or FPD) and the images that are used for testing this type of display (see the table below).
2. Press the **Content** key. A list of images appears on the generator’s display as shown below. Press the + and - keys to see all of the images.

Acer1	Acer2
Acer3	Acer4
Acer5	Acer6
Acer7	Acer8

Note: *The list of images that appears when you press the* ***Content*** *key may be a filtered or abbreviated list. You may have disabled certain image catalogs, preventing the images in those catalogs from appearing on the Content list. For more information about image catalogs, see “Creating image catalogs” on page 247.*

3. Choose an image by pressing the adjacent soft key.

The table below provides a summary of display characteristics and the images used to evaluate them. For details on the images and display attributes, see Appendix B, "Image Reference."

Display type	Display test	Recommended images
Analog CRT	Geometry (pin and barrel, linearity)	Static images Hatch (TVHatch, Hatch_16, Hatch_20), CirclesL, Geom_1 - Geom_5, SMPTE133
	Focus	Focus_@6, Focus_@7, Focus_@8, Focus_@9, Text_9, Text_9T, Text_11, Text_12T, Text_16
	Photometry (chrominance, contrast, levels)	Flat, Flat07, Flat13, Flat20, Flat27, Flat33, Flat40, Flat47, Flat53, Flat60, Flat67, Flat73, Flat80, Flat87, Flat93, FlatGray, Flat_01, Flat_02, Flat_03, Flat_04, Flat_05, Flat_06, Flat_07, Flat_08, Flat_09, Flat_10, Flat_11, Flat_12, Flat_13, Flat_14, Flat_15, Flat_16, Ramp_B, Ramp_G, and Ramp_R, ColorBar, SMPTEbar, TVBar100 & TVBar_75 (TV formats only)
	Luminance	SMPTE133 (grayscale), Grays5, Grays9, Grays11, Grays16, Grays32, Grays64
	Gamma correction	SMPTE133 (checkerbox)
	Resolution	BurstTCE, Burst (TV formats only), Grill_11, Grill_15, Grill_22, Grill_33, Grill_44
	Pulse (CE SDTV)	PulseBar
	Centering	Outline0, Outline1, Outline2, Outline3
	Voltage Regulation	Regulate
	Electromagnetic Interference	EMITest1, EMITest2, EMITest3, EMITest4, EMITest5

Display type	Display test	Recommended images
Digital flat panel (fixed pixel display)	Pixel anomalies (stuck pixels, misc sampling)	Flat, Raster, Ramp_B, Ramp_G, and Ramp_R, Focus_@6, Focus_@7, Focus_@8, Focus_@9, Text_9, Text_9T, Text_11, Text_12T, Text_16
	Photometry (chrominance, contrast, levels)	Flat, Flat07, Flat13, Flat20, Flat27, Flat33, Flat40, Flat47, Flat53, Flat60, Flat67, Flat73, Flat80, Flat87, Flat93, FlatGray, Flat_01, Flat_02, Flat_03, Flat_04, Flat_05, Flat_06, Flat_07, Flat_08, Flat_09, Flat_10, Flat_11, Flat_12, Flat_13, Flat_14, Flat_15, Flat_16, Ramp_B, Ramp_G, and Ramp_R, ColorBar, SMPTEbar, SMPTE133
	Luminance	SMPTE133 (Grayscale), Grays5, Grays9, Grays11, Grays16, Grays32, Grays64
	Centering	Outline0, Outline1, Outline2, Outline3
	Resolution	BurstTCE, Grill_11, Grill_15, Grill_22, Grill_33, Grill_44
	Persistence	Animated images: Persist, Cubes, SlideBox

Rendering image versions

Many images have secondary or alternate versions and some images have many versions. Use the procedures below to view the alternate and multiple image versions.

To view alternate image versions in the Content list:

1. Select an image by pressing the **Contents** key and selecting an image with the adjacent soft key until a * appears next to image name.
2. Enable and view image versions as follows:
   a. Press the **Options** key. The following menu will appear on the generator's display for images with a single secondary image:

```
-Alternate
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

   b. Choose the **Alternate** item by pressing the adjacent soft key until a + appears next to the item.

```
+Alternate
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

3. Toggle back and forth between the images using the adjacent soft key.

To view multiple image versions in the Content list:

1. Select an image by pressing the **Contents** key and selecting an image with the adjacent soft key until a * appears next to image name.
2. Enable and view image versions as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

   ```
   -More
                          Red+
   -NoGamma             Green+
   -Noise                Blue+
   ```

   b. Choose the **More** item by pressing the adjacent soft key until a + appears next to **More** and **Rendition** appears on the other side of the menu.

   ```
   +More     Rendition: 000
                          Red+
   -NoGamma             Green+
   -Noise                Blue+
   ```

   c. Press the + and - keys to advance through the image versions. Each version shows the format parameters for a different format in the Source list.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

   ```
   ISUB 1       // Enables sub images
   IVER 1       // Specifies the first image version
   IMGU         // Activates the image version
   IVER 2       // Specifies the second image version
   IMGU         // Activates the image version
   ```

3. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

   ```
   ISUB 0       // Disables sub images
   ```

Testing analog computer (IT) CRTs

This section describes how to test analog computer (IT) displays. The display responses shown as examples in the procedures use the 882C. However you can also test analog composite with the 882D using the same format and image selections. The interface selection is different and is noted.

To set up the generator to test an analog computer CRT:

1. Connect a standard VGA cable between the VGA connector on the generator and the VGA connector on the display under test.
2. Calibrate the generator in accordance with the procedures described in “Calibrating signal level” on page 87.
3. Determine the formats to test (see “Setting Source list of formats” on page 43).
4. Determine additional formats to test based on the resolution of the display. The VESA formats are shown below:

Standard	Quantum Data format name
VGA	DMT06xx
SVGA	DMT08xx
XGA	DMT10xx
SXGA	DMT12xx
UXGA	DMT16xx
QXGA	DMT20xx
QSXBA	DMT25xx

5. Determine the images to test. For analog CRTs, you typically want to select images to test for geometry, focusing, photometry, resolution, cross talk, EMI, and regulation characteristics. For more details on what images test these specific display attributes, see “Selecting image” on page 47 or Appendix B, “Image Reference.”

To activate the VGA interface on the output port:

1. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator’s display as shown below.



2. Choose the **VGA** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format. An asterisk is shown beside the selected interface.

   Alternatively, to select the interface through the command line interface, enter the following commands:

```
XVSI 9          // Selects the VGA interface
ALLU            // Applies the interface setting to the generator
```

   If you are using the 882D you select the DVI-A interface.

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL DMT0660
FMTU
```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, ColorBar) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

```
IMGL ColorBar
IMGU
```

5. Verify that the image appears on the display under test.

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

```
FMTL format_name
FMTU
```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

```
IMGL image_name
IMGU
```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing geometry with the Hatch images (for example, Hatch20) look for distortion with concave or convex lines near the periphery of the display. Look for irregular spacing on the cross hatch patterns.
   - When testing photometry such as chrominance, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or

unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.

- To test luminance, you can use the SMPTE133 (grayscale portion) image. To test gamma correction, you can use the SMPTE133 (checkerbox portion) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, "Image Reference."
- When testing focus with the Focus or Text images, the characters in all areas of the display should be well-formed and in focus.
- When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.
- When testing for centering use the Outline images. For detailed methods for verifying centering with the Outline images, see Appendix B, "Image Reference."
- When testing for high voltage regulation with the Regulate image, observe the outline at the edges of the image. It should stay in place and not pull away from the area of the large white blinking patch (when it appears).

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, "Working with Test Sequences." for details.*

Testing digital computer (IT) FPDs

This section describes how to test digital computer (IT) displays. You can test DVI on digital computer displays using the 882C up to single link through the HDMI connector. However you can test DVI digital computer displays up to full dual link on the 882D through the dual link DVI connector. The procedures below describe how to test DVI computer digital displays using the 882D.

To set up the generator to test a digital FPD:

1. Connect a single or dual link DVI cable between the DVI connector on the generator and the DVI connector on the display under test.
2. Determine the formats to test. See “Setting Source list of formats” on page 43 for instructions.
3. Determine the images to test. For digital flat panel displays, you typically want to select images to test for pixel anomalies, persistence, photometry, and resolution-related problems. For more information, see “Selecting image” on page 47 or Appendix B, “Image Reference.”

To activate the HDMI-D interface on the output port:

1. Press the **Interface** key. A listing of signal interfaces appears on the generator’s display as shown below.



2. Choose the **DVI-D** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format that is compatible with the interface. An asterisk is shown beside the selected interface.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 2          // Selects the HDMI-D interface
ALLU            // Applies the interface setting to the generator
```

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL DMT0660
FMTU
```

3. Press the **Content** key to access the list of images.

4. Choose a suitable image (for example, SMPTE133) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

   ```
   IMGL SMPTE133
   IMGU
   ```

5. Verify that the image appears on the display under test.

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

   ```
   IMGL image_name
   IMGU
   ```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing photometry such as chrominance, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - To test luminance, you can use the SMPTE133 (grayscale portion) image. To test gamma correction, you can use the SMPTE133 (checkerbox portion) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”
   - When testing for centering use the Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
   - When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.
   - When testing for pixel anomalies use the Flat, Raster, and Ramp images. Use the Raster and Flat images to look for pixels that may be stuck on or off, respectively. The luminance should increase uniformly for the Ramp image. Also, look for sparkles indicating problems with sampling.
   - When testing for persistence with the animated images (for example, Cubes and Persist), look for bleeding or trails in the wake of the moving object.

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, "Working with Test Sequences." for details.*

Testing analog composite video SDTV (CE) CRTs

This section describes how to test CRT composite televisions with analog composite video inputs. The display responses shown as examples in the procedures use the 882C. However you can also test analog composite with the 882D using the same interface, format and image selections.

To set up the generator to test analog composite video SDTV:

1. Connect a standard coax cable between the CVBS connector on the generator and the display under test.

   Or, connect an S-video cable between the S-VIDEO connector on the generator and the S-Video input on the display under test.

2. Determine which composite television standard you need, such as NTSC or PAL, and then select the formats compatible with the standard. Typically, you would test all the formats in the family of formats for a standard.

3. Determine the images to test. For analog CRTs you typically want to select images to test for geometry, focusing, photometry, resolution, cross talk, EMI, and regulation characteristics. For more details on what images test these specific display attributes, see “Selecting image” on page 47 or Appendix B, “Image Reference.”

To activate the CVBS or S-Video interface on the output port:

1. Press the **Interface** key. A listing of signal interfaces appears on the generator’s display as shown below.



2. Choose either the **CVBS** or **S-VIDEO** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format. An asterisk is shown beside the selected interface **CVBS** or **S-VIDEO.**

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 6          // Selects the CVBS interface
  or
XVSI 5          // Selects the S-VIDEO interface
ALLU            // Applies the interface setting to the generator
```

To verify the test set-up:

1. Press the **Source** key to access the list of formats.

2. Choose a typical composite format (for example, NTSC) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

   ```
   FMTL NTSC
   FMTU
   ```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, SmpteBar) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

   ```
   IMGL SmpteBar
   IMGU
   ```

5. Verify that the image appears on the display under test.

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

   ```
   IMGL image_name
   IMGU
   ```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing geometry with the Hatch images (for example, TVHatch and Hatch20) look for distortion with concave or convex lines near the periphery of the display. Look for irregular spacing on the cross hatch patterns.
   - When testing photometry such as chrominance, use the TVBar100 & TVBar_75 (TV formats only), TVSplBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - When testing luminance, you can use the Pluge image.
   - When testing focus with the Focus images, the characters in all areas of the display should be well-formed and in focus.
   - When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions. When testing for resolution with the Burst image, the peak intensities of all of the bursts should match the white reference level. The darkest portions between the peaks should match the black reference level.

- When testing for centering, use the Outline and TVoutLin images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
- When testing for high voltage regulation with the Regulate image, observe the outline at the edges of the image. It should stay in place and not pull away from the area of the large, white blinking patch (when it appears).

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, “Working with Test Sequences.” for details.*

Testing analog component video SDTV (CE) CRTs

This section describes how to test CRT televisions with standard definition component video inputs. The examples show the 882C. However there are notes that describe the differences related to the 882D.

To set up the generator to test an analog component video SDTV display:

1. Connect a VGA-to-RCA cable between the VGA connector on the generator and the YPbPr inputs on the display under test.
2. Identify the component television formats to test. These formats are listed after the composite television formats in the generator's default Source list. Begin with the first format in the range of standard definition component television formats (480i).
3. Determine additional formats to test based on the resolution of the television display. The television specification sheet will provide information on what resolutions to test. It is necessary to test only those resolutions with the supported scanning type (typically, interlaced for a standard definition television).
4. Determine the images to test. For analog CRTs you typically want to select images to test for geometry, focusing, photometry, resolution, cross talk, centering, EMI, and regulation characteristics. For more details on what images test these specific display attributes, see "Selecting image" on page 47 or Appendix B, "Image Reference."

To activate the VGA interface on the output port:

1. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below on the 882C).



2. Choose the **VGA** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format. An asterisk is shown beside the selected interface.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 9          // Selects the VGA interface
ALLU            // Applies the interface setting to the generator
```

   If you are using the 882D generator use the DVI-A interface selection.

To verify the test set-up:

1. Press the **Source** key to access the list of formats.

2. Choose a standard component format (for example, 480i) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

   ```
   FMTL 480i
   FMTU
   ```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, SMPTE133) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

   ```
   IMGL SMPTE133
   IMGU
   ```

5. Verify that the image appears on the display under test.

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

   ```
   IMGL image_name
   IMGU
   ```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing geometry with the Hatch images (for example, TVHatch and Hatch20), look for distortion with concave or convex lines near the periphery of the display. Look for irregular spacing on the cross hatch patterns.
   - When testing photometry such as chrominence, use the TVBar100 & TVBar_75 (TV formats only), ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - When testing luminance you can use the SMPTE133 (grayscale portion) image. To test gamma correction you can use the SMPTE133 (checkerbox portion) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”
   - When testing focus with the Focus or Text images, the characters in all areas of the display should be well-formed and in focus.
   - When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.

- When testing for centering use the TVOutline and Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
- When testing for high voltage regulation with the Regulate image, observe the outline at the edges of the image. It should stay in place and not pull away from the area of the large white blinking patch (when it appears).

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, “Working with Test Sequences.” for details.*

Testing digital component video HDTV (CE) FPDs

This section describes how to test digital DVI and HDMI component video for HDTV flat panel displays. The display responses shown as examples in the procedures use the 882C. However, you can also test dual-link digital component video with DVI using the 882D. The different selection options are provided for the 882D throughout the procedure.

DVI interface testing

To set up the generator to test a digital DVI component video HDTV display:

1. Connect an HDMI to DVI cable between the HDMI OUT (1 or 2) connector on the generator and the DVI connector on the television display under test.

   Note: *If the display under test has a DVI-D connector, you will need a DVI-I to DVI-D adapter.*

2. Identify the high-definition component television formats to test. These formats are listed after the composite television formats in the generator's default Source list. Begin with the first format (720p) in the range of high definition component television formats. See "Setting Source list of formats" on page 43.

3. Determine additional formats to test based on the resolution of the television display. The television product specification sheet will provide information on what resolutions to test. It is necessary to test only those resolutions with the supported scanning type (typically interlaced for a high definition television).

4. Determine the images to test. For digital television flat panel displays, you would typically want to select images to test for pixel anomalies, persistence, photometry, and resolution-related problems. For more details on which images test these specific display attributes, see "Selecting image" on page 47 or Appendix B, "Image Reference."

To activate the HDMI-D interface on the output port:

1. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



2. Choose the **HDMI-D** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3          // Selects the HDMI-D interface
ALLU            // Applies the interface setting to the generator
```

If you are using the 882D you can select either HDMI-D or DVI-D interface. The DVI-D option provide dual link, the HDMI-D offers signal link only.

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a high definition component format (for example, 720p50) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

   ```
   FMTL 720p50
   FMTU
   ```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, SMPTE133) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

   ```
   IMGL SMPTE133
   IMGU
   ```

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

   ```
   IMGL image_name
   IMGU
   ```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing photometry such as chrominence, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - When testing luminance, you can use the SMPTE133 (grayscale) images. To test gamma correction, you can use the SMPTE133 (checkerbox) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”

- When testing for centering, use the Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, "Image Reference."
- When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.
- When testing for pixel anomalies, use the Flat, Raster, and Ramp images. Use the Raster and Flat images to look for pixels that may be stuck on or off, respectively. The luminance should increase uniformly for the Ramp image. Also look for sparkles indicating problems with sampling.
- When testing for persistence with the animated images (Cubes and Persist), look for bleeding or trails in the wake of the moving object.

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, "Working with Test Sequences." for details.*

HDMI interface testing

To set up the generator to test a digital HDMI component video HDTV display:

1. Connect an HDMI to HDMI cable between the HDMI OUT (1 or 2) connector on the generator and the HDMI connector on the television display under test.
2. Identify the high-definition component television formats to test. These formats are listed after the composite television formats in the generator's default Source list. Begin with the first format (720p) in the range of high definition component television formats. See "To select a format:" on page 45.
3. Determine additional formats to test based on the resolution of the television display. The television product specification sheet will provide information on what resolutions to test. It is necessary to test only those resolutions with the supported scanning type (typically interlaced for a high definition television).
4. Determine the images to test. For digital television flat panel displays, you would typically want to select images to test for pixel anomalies, persistence, photometry, and resolution-related problems. For more details on which images test these specific display attributes, see "Selecting image" on page 47 or Appendix B, "Image Reference."

To activate the HDMI-H interface on the output port:

1. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



2. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a high definition component format (for example, 720p50) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL 720p50
FMTU
```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, SMPTE133) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

```
IMGL SMPTE133
IMGU
```

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

```
FMTL format_name
FMTU
```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

```
IMGL image_name
IMGU
```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing photometry such as chrominence, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - When testing luminance, you can use the SMPTE133 (grayscale) images. To test gamma correction, you can use the SMPTE133 (checkerbox) image. The detailed

methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”

- When testing for centering, use the Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
- When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.
- When testing for pixel anomalies, use the Flat, Raster, and Ramp images. Use the Raster and Flat images to look for pixels that may be stuck on or off, respectively. The luminance should increase uniformly for the Ramp image. Also look for sparkles indicating problems with sampling.
- When testing for persistence with the animated images (Cubes and Persist), look for bleeding or trails in the wake of the moving object.

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, “Working with Test Sequences.” for details.*

Testing SDI and HD-SDI digital component video studio displays

This section describes how to test SDI and HD-SDI digital component video for HDTV flat panel displays.

To set up the generator to test a digital (SDI/HD-SDI) component video HDTV display:

1. Connect a coaxial cable between the SDI/HD-SDI BNC connector on the generator and the SDI/HD-SDI BNC connector on the studio display under test.
2. Identify the component studio formats to test. These formats are listed after the composite studio formats in the generator's default Source list. See "Setting Source list of formats" on page 43.
3. Determine additional formats to test based on the resolution of the studio display. The studio monitor product specification sheet will provide information on what resolutions to test. It is necessary to test only those resolutions with the supported scanning type.
4. Determine the images to test. For digital studio displays, you would typically want to select images to test for pixel anomalies, persistence, photometry, and resolution-related problems. For more details on which images test these specific display attributes, see "Selecting image" on page 47 or Appendix B, "Image Reference."

To activate the SDI/HD-SDI interface on the output port:

1. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



2. Choose the **SDI** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 8          // Selects the SDI interface
ALLU            // Applies the interface setting to the generator
```

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a component studio format (for example, 720p50) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL 720p50
FMTU
```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, SMPTE133) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

```
IMGL SMPTE133
IMGU
```

To test the display:

1. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

```
FMTL format_name
FMTU
```

2. Press the **Content** key and select the first test image.

   Alternatively, you can load the image with the following command:

```
IMGL image_name
IMGU
```

3. Repeat steps 1 and 2 for all formats and test images. Use the following guidelines to verify proper operation:

   - When testing photometry such as chrominence, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - When testing luminance, you can use the SMPTE133 (grayscale) images. To test gamma correction, you can use the SMPTE133 (checkerbox) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”
   - When testing for centering, use the Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
   - When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.
   - When testing for pixel anomalies, use the Flat, Raster, and Ramp images. Use the Raster and Flat images to look for pixels that may be stuck on or off, respectively. The luminance should increase uniformly for the Ramp image. Also look for sparkles indicating problems with sampling.
   - When testing for persistence with the animated images (Cubes and Persist), look for bleeding or trails in the wake of the moving object.

Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See Chapter 8, "Working with Test Sequences." for details.*

Using the Image Caching feature

The Image Cache feature enables you to render images quickly. This feature is ideal for applications, such as production line testing, which require rapid image rendering.

The Image Cache features renders a number of images in advance and stores them in memory for immediate recall. The number of images that can be stored in cache depends on the resolution and bit depth of the chosen format. The cached images are stored in video RAM, and are lost on power cycle, reboot, or issuance of the ICHC command.

Usage of cached images can be divided into two sets of operations. First, the desired formats and images are loaded in the conventional non-cached manner. As each image is displayed, it can be saved in the cache to be later recalled in the same format. When all images have been saved with the proper video formats, they can be quickly recalled from the cache and displayed.

Use the procedure below to render images quickly with the Image Cache feature.

To test an HDMI sink with the Image Caching feature:

1. Load the cache with some images in 2 different formats.

```
IMGX:SRC Render   // specify normal render mode
ICHC              // clear the cache
FMTL DMT0660      // select first format
FMTU              // use this format
IMGL SmpteBar     // load image SmpteBar
IMGU              // use this image
ICHA IMG1         // save this image to cache as IMG1 for DMT0660
IMGL Master       // load image Master
IMGU              // use this image
ICHA IMG2         // save this image to cache as IMG2 for DMT0660
IMGL TVBarH       // load image TVBarH
IMGU              // use this image
ICHA IMG3         // save this image to cache as IMG3 for DMT0660
FMTL 720p60       // load 720p60 format
FMTU              // use this format
IMGL SmpteBar     // load image SmpteBar
IMGU              // use this image
ICHA IMG4         // save this image to cache as IMG4 for 720p60
IMGL Ramp_B       // load image Ramp_B
IMGU              // use this image
ICHA IMG5         // save this image to cache as IMG5 for 720p60
IMG:SRC Cache     // enable image caching
```

2. Display these images from cache.

```
FMTL DMT0660      // load format DMT0660
FMTU              // use this format without redrawing
ICHL IMG3         // load cached TVBarH for DMT0660
ICHU              // fast display of TVBarH from cache
ICHL IMG1         // load cached SmpteBar for DMT0660
ICHU              // fast display of SmpteBar from cache
```

```
FMTL 720p60       // load format 720p60
FMTU 0            // use format without redrawing
ICHL IMG4         // load cached SmpteBar for 720p60
ICHU              // fast display of SmpteBar from cache
ICHL IMG5         // load cached Ramp_B for 720p60
ICHU              // fast display of Ramp_B
FMTL DMT0660      // load format DMT0660
FMTU 0            // use format without redrawing
ICHL IMG2         // load cached Master for DMT0660
ICHU              // fast display of Master
FMTU              // revert to normal rendering, reset cache
```

3. Return to normal rendering mode.

```
IMGX:SRC Render   // specify normal render mode
```

Using the AuxTest image

This section describes the AuxTest composite test image used in production. This image tests an HDMI sink for CEC, EDID and HDCP at the same time. The CEC test is a simple ping test. The HDCP test is an authentication test. The EDID test is a checksum test.

Use the procedure below to test a sink for CEC, EDID and HDCP.

To test an HDMI sink for CEC, EDID and HDCP:

1. Physically connect a monitor to the HDMI Tx port.

   There are two AuxTest images. AuxTest1 tests out the HDMI Tx port1 and AuxTest2 tests out the HDMI Tx port2:

2. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



3. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```


4. Press the **Content** key and select the first AuxTest image.

   Alternatively, you can load the image with the following command:

```
IMGL AuxTest1
IMGU
```

   The test image is shown below. The upper left section shows the results of the EDID test which verifies the checksum. The upper right section shows the result of the CEC test which does a basic ping test and also reads the physical address of a connected

device. The section in the center shows the step by step results (11 steps) of the first phase of the HDCP authentication. Below that is the ongoing test results of the third phase of authentication, i.e. exchanging the Ri values.



Using the ImageShift utility

This section describes the ImageShift utility and how to use it. The ImageShift utility allows you to set in motion any of the built-in or bitmap static images stored in the generator. Image shifting can be controlled at both the pixel level in horizontal and vertical directions, and on a per frame basis. The shift pattern can be set to either a repeated pattern or back and forth (reversed).

You can create your own imageshift files in order to specify particular image shifting configurations to invoke. This enables you to quickly invoke an image shifting set of parameters to apply.


The ImageShift function can be configured and run either through the front panel or the command line. Procedures for both are provided.

Using the ImageShift utility through the front panel

The procedure for configuring and running the ImageShift utility is provided below.

To use the ImageShift utility through the front panel:

1. Physically connect a monitor to the generator at any of the interfaces using a suitable cable.
2. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



3. Choose **ImgShift** by pressing the adjacent soft key. The following menu appears on the generator's display.




This display enables you to browse for a bitmap image or a built-in image stored in cache.

4. Choose **Cache** to browse for a built-in image. The following menu appears on the generator's display.



5. Choose **Images**, and then select the image you want to use.

   The image appears and begins shifting in accordance with default settings for both speed and method of shifting (either repeat or reversed). The following settings appear on the generator's display as shown below.




   a. Configure image shifting parameters by selecting a parameter using its adjacent soft key, then adjusting the value by pressing the + or - keys.

   Refer to the following table for a description of the parameters used to control image shifting.

Parameter	**Action**
Line	Selects image shifting pattern. This can be either Reverse or Repeat. • Reverse moves the image in both directions in accordance with the shift parameters. • Repeat moves the image in only one direction.
HInc	Specifies number of pixels the image travels in a horizontal direction per time period.
VInc	Specifies number of lines the image travels in a vertical direction per time period.
TInc	Specifies movement to occur per N number of frames.

6. To set the starting point of the image shift, press the **Settings** key. The following settings appear on the generator's display.




You can set the starting coordinates of the image shift as follows:

a. To specify the X Start Point, position the blinking cursor on the digits of the X coordinate you wish to change. To do this, press the soft key adjacent to the arrow by the coordinates to move the cursor left or right until it appears on the digit in the X coordinate. Adjust the value of the setting up or down by pressing the + or - keys.

b. To specify the Y Start Point, position the blinking cursor on the digits of the Y coordinate you wish to change. To do this, press the soft key adjacent to the arrow by the coordinates to move the cursor left or right until it appears on the digit in the Y coordinate. Adjust the value of the setting up or down by pressing the + or - keys.

7. To set the ending point of the image shift, press the soft key to the right of Start Point. The following settings appear on the generator's display.




You can set the ending coordinates of the image travel as follows:

a. To specify the X End Point, position the blinking cursor on the digits of the X coordinate you wish to change. To do this, press the soft key adjacent to the arrow by the coordinates to move the cursor left or right until it appears on the digit in the X coordinate. Adjust the value of the setting up or down by pressing the + or - keys.

b. To specify the Y End Point, position the blinking cursor on the digits of the Y coordinate you wish to change. To do this, press the soft key adjacent to the arrow by the coordinates to move the cursor left or right until it appears on the digit in the Y coordinate. Adjust the value of the setting up or down by pressing the + or - keys.

Note: *The movement that you see may not always correspond to the settings for HInc and VInc. The reason is that the number of shifts from start point to end point is determined by the quotient of the total travel in the horizontal (pixels) and vertical (lines) directions and the total increment defined. The lowest quotient of the two (horizontal vs. vertical) will determine how many shifts the utility will make from start point to end point. For example, if the start point is 0,0 and the end point is 100,100. An HInc setting of 10 and a VInc setting of 20 will result in 5 shift movements (100/20 = 5). The generator will not produce shifts of 10 horizontal pixels per increment because it cannot move from 0 to 100 in 5 shifts by only moving 10 horizontal increments.*

8. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   - To save the changes, choose the **Yes** item by pressing the adjacent soft key.
   - To exit without saving the changes, choose the **No** item.
   - To return to the previous screen without saving the changes, choose the **Back** item.

Using the ImageShift utility through the command line interface

The procedures for configuring and running the ImageShift utility from the command line interface are given below. To run the ImageShift utility from the command line interface, you must utilize an imageshift file. An imageshift file specifies both the image and parameters necessary to run the ImageShift utility.

To create an imageshift file:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Configuring the generator's serial port" on page 32 or "Establishing a Telnet session with the generator" on page 34.
2. Set the path to the imageshift files using the ISHP command. For example:

```
ISHP tffs0/library/imageshifts
```

3. Create a new imageshift file using the ISHN command. For example:

```
ISHN Newshift
```

4. Define the imageshift file settings as shown in the example below:

```
ISHB          //begins an imageshift editing session
XISH:SRCN /cache0/images/SMPTEBar  //selects the SMPTEBar image
XISH:PATH 0,0 150,20  //sets the imageshift path x,y coordinates
XISH:TTYP 1  //sets the trace type to Repeat (1)
XISH:HINC 4  //sets the horizontal shift increment to 4
XISH:VINC 2  //sets the vertical shift increment to 2
XISH:TINC 5  //sets the time shift value to 5
ISHE         //ends the imageshift editing session
```

5. Save the settings to the same imageshift file using the ISHS command, For example:

```
ISHS         //saves the settings to the Newshift file
```

To run the ImageShift utility through the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Configuring the generator’s serial port” on page 32 or “Establishing a Telnet session with the generator” on page 34.
2. Set the path to the imageshift files using the ISHP command. For example:

```
ISHP tffs0/library/imageshifts
```

3. Enter the following commands to display the list of imageshift files.

```
ISHQ?   //Displays the first 5 imageshift filenames
ISHQ?   //Displays 5 more imageshift filenames
```

4. Load an imageshift file and apply the image to hardware. For example:

```
ISHL Newshift   //Loads the values from the imageshift file named
                //Newshift
ISHG 1          //Initiates (gates on) the imageshift function
ISHU            //Applies the values to the hardware
```

5. Apply the imageshift file to the hardware using the ISHU command. For example:

```
ISHU         //applies the imageshift file to the hardware
```

To stop the ImageShift utility through the command line interface:

1. To stop the Imageshift enter the following command.

```
ISHG 0          //Stops (gates off) the imageshift function
```

Adjust Frequency Function


This section describes the adjust frequency control (AFC) function.

The AFC function provides you with the ability to increase or decrease the horizontal frequency (HRAT parameter) of the active video format in increments of 2%.


Use the following procedures to increase or decrease the frequency of the active format.

To utilize the AFC function:

1. Physically connect a monitor to the generator at any of the interfaces using a suitable cable.
2. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



3. Choose **AFC** by pressing the adjacent item selection key. The following display appears on the generator's display.



This display enables you to increase or decrease the horizontal frequency parameter in increments of 2% using the +/- keys.

Keypad Utility

This section describes the Keypad utility and how to use it.


The keypad provides you with a quick and convenient way of changing between formats and images. The interface from the Keypad to the generator is through the serial interface. Once connected you can change between formats and image with a single key stroke. You can also control test sequences using the Keypad.

Use the following procedures to install and operate the remote keypad.

To install and enable the keypad:

1. Shut off the generator.
2. Connect the keypad to the serial port on the generator.


   The serial port is on the back of the generator on the lower panel. It is labeled **Serial**.
3. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



4. Choose **System** pressing the adjacent item selection key. The following display appears on the generator's display.



5. Choose **Serial** to access the menu for enabling the Keypad. The following display appears on the generator's display.



6. Press the **Options** key. The following information appears on the generator's display:




7. Press the softkey adjacent to the **Keypad** item to enable the keypad function.

   A + appears next to the **Keypad** item indicating that the functionality is enabled.

To monitor the status of the keypad:


1. Press the **Tools** key. The Tools menu appears on the generator's display.

   When the keypad has been enabled there is an additional item in the Tools menu. This is indicated by an arrow key. If you scroll down using the - key the following menu appears:



2. Select the **Keypad** item to view the keypad status. The screen shown below appears.


   This display shows the Mode which is either normal or Sequence and the current format and image. The Exit enables you to exit from the menu without disabling the keypad function.



To operate the keypad


1. Use the figure below to operate the keypad. The keypad has two basic modes: 1) Normal which enables you to change the formats, images and colorimetry and 2) Sequence mode which enables you to control a running test sequence.

Normal mode key functions



Task	Procedure
Select image from current list	Press * key, use numeric keys to specify the image number, and then press Enter.
Select next image	Press Enter.
Select previous image	Press + key.
Select alternate version of image (if available)	Press Del key.
Change R-B-G video gating	Press – key to cycle through gating combinations.
Select any format from current list	Press / key, use numeric keys to specify format number, and then press Enter.
Select next format	Press 2.
Select previous format	Press 8.
Switch to Sequence Mode	Press Num Loc key.

Sequence mode key functions



Task	Procedure
Select sequence from current list	Press – key, use numeric keys to specify sequence number, and then press Enter.
Select any step in sequence	Press Del key, use numeric keys to specify step number, and then press Enter.
Select next step	Press Enter.
Select previous step	Press + key.
Change sequence step method (step, wrap, auto, and so on)	Press * key to cycle through options.
Change DNUM settings	Press / key to cycle through options.
Switch to Normal Mode	Press Num Loc key.

3 Administrative Tasks

Topics in this chapter:

- Overview
- Calibrating the generator
- Auto Upgrade
- Upgrading the generator locally
- Reconfiguring and booting a stalled generator
- Cloning generators
- Resetting a generator
- Viewing generator configuration information

Overview

This section describes how to accomplish administrative tasks, including calibrating the generator, upgrading a generator, cloning a generator and maintaining the generator's file system.

Calibrating the generator

The 882 generator can calibrate itself. Once calibrated, the generator does not require periodic calibration. There are no physical controls to adjust. All calibration is electronic. Calibration factors are saved in non-volatile memory.

Calibrating signal level


The calibration accuracy of the generator for analog video voltage swing is specified to be ±14 mV (or ±2% for a nominal 700 mV signal). Using a typical oscilloscope such as a Tektronix VM700T, which might have a swing measurement accuracy of ±14 mV, readings should be between 674 mV to 726 mV.

You can set the analog output calibration factors to values other than those set by the generator's own self-calibration function. Each channel is calibrated using two independent, zero calibration points, and two independent, slope calibration points. Interpolation equations for the different video types are used to set the caldac values that control the output sync and voltage levels to the correct values.

You can calibrate the generator using the front panel keys or the command line interface. Follow the procedures below to calibrate the generator.

To self-calibrate the generator using the front panel:


1. (Optional) Load the outputs of the generator. Although it is not necessary to load the outputs during self-calibration, attaching a nominal load may yield a slight increase in accuracy.
2. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



3. Choose the **System** item by pressing the adjacent soft key. The System menu appears. Press the - key to scroll down until the CalFactor item appears.



4. Choose the **CalFactor** item by pressing the adjacent soft key. The following items appear on the generator's display:



5. Choose the **Self-Calibrate** item by pressing the adjacent soft key.

   During calibration, calibration factors and other information appear on the generator's display. Observe the generator's display for error messages. If an error message appears, make a note of it and call your technical support representative for further assistance.

To self-calibrate the generator using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. At the prompt, enter the following command:

   ```
   SCAL
   ```

   The generator begins the calibration procedure.

To view analog calibration factors:

Enter the following command to view the analog video red, green, blue calibration factors:

```
CALF?
```

The generator presents the following in response:

```
1089, 2589, 1993, 3223, 1148, 2633, 2059, 3279, 1000, 2505, 1990, 3219,
793, 787, 3382, 3509
```

For an explanation of the calibration factors, see the `CALF?` command in the Appendix A, "Command Reference."

Calibrating frequency

All frequencies associated with the generator are derived from a common frequency reference, which can be calibrated using the rate calibration command `RATC`.

To calibrate all frequencies:


1. Load a standard format and set the horizontal rate to 100 kHz.

   For example, enter the following command:

   ```
   FMTL DMT0660
   ```

```
HRAT 100E3
ALLU
```


2. Measure the TTL horizontal sync frequency with the frequency counter.
3. Divide the frequency that you expect by the frequency that you measure on the frequency counter. For example, if you measure 99.9955782499875 kHz, when you expect 100.000000000KHz, then divide 100.000000000 kHz by 99.9950002499875 kHz; the result is 1.0000442194553987.
4. Enter the result into the generator. This will raise all frequencies output by the generator and make them exact. To enter the results through the front panel using the following procedures:
5. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




6. Choose the **System** item by pressing the adjacent soft key. The System menu appears. Press the - key to scroll down until the CalFactor item appears.



7. Choose the **CalFactor** item by pressing the adjacent soft key. The following items appear on the generator's display:



8. Choose the **Edit Factors** item by pressing the adjacent soft key. The following items appear on the generator's display:



   a. Edit the RATC factor by pressing the soft keys adjacent to the bottom row until the cursor appears on the digit you want to change. Press the + or - keys to adjust the setting up or down.

   b. Press the **Enter** (**Options**) key to save the new setting.

   Alternatively, to enter the result using the command line interface, use the RATC command. For example:

```
RATC 1.0000442194553987
```

Auto Upgrade

This section provides procedures on how to upgrade your generator using the auto upgrade feature. Note that there are also procedures for manually upgrading your 880 series generator, refer to “Manually upgrading using PCMCIA Compact Flash card” on page 110 or “Manually upgrading the generator without using PC Card” on page 112.


Quantum Data periodically makes available new firmware releases for the 880 series generators. The Auto Update utility automates the process of upgrading firmware. It guides the user through the upgrade process, checking the Quantum Data website for the latest version and installing all files in the correct location on the generator.


The Auto Update utility provides for two methods of copying the firmware files into the generator: 1) The network method and 2) the PCMCIA/Compact Flash method. These are provided below.

Auto upgrade - Network Method

The first method is the Network Upgrade. This is the recommended upgrade method. This method requires that the generator and your computer be connected by Ethernet, either via a direct crossover cable, or by being accessible to each other on a common network. The generator must possess a valid IP address, either through manual setting or via a

DHCP server on the network. The PC has to be connected to the Internet. Refer to the 880 Series User Guide, Chapter 4, “Networking Generators.” for full information on configuring a generator for network use. Refer to the diagrams below.





Downloading and installing the Auto Update utility:


The Auto Update utility is java-based, and requires the Java Virtual Machine (Java runtime) to be installed on the computer. This can be obtained from http://www.java.com.

The Auto Update utility can be downloaded from the downloads section of the Quantum Data website, at http://www.quantumdata.com/downloads/index.asp.


After downloading the Auto Update ZIP file, installation is simply a matter of unzipping it into a folder on your hard disk.

Running the Auto Update utility: Network Upgrade

1. Run the utility by double-clicking on **AutoUpdate.jar**. You will be presented with the following screen:




2. Select **Network Upgrade**, then **Next**. The Network Upgrade screen will appear:




3. Make sure you have network access to the generator, then select **Next**.


   Next you will have the opportunity to back up the files in the generator. If you have any custom images, formats, reports, or other files stored on the /tffs0 flash drive within the generator, they will be lost unless you choose to back up the files.




4. Optionally browse to a new backup directory, then click **Next** to begin the backup. If you don't want to back up any files from the generator, click on **Skip Backup**.
5. Next, enter the IP address for the generator:




6. Click **Next** to continue.
7. If you see this screen, click **Continue With Upgrade**:




8. Next you must confirm that you are connected to the correct generator:



Click **Yes** to continue. Next the utility will connect to the Quantum Data website to download the current firmware version for this generator, then display the version number and wait for your confirmation.



9. Click **Yes** to continue. The utility will extract the downloaded files, back up the generator's current files to the PC, and finally transfer the new files to the generator. Please don't disconnect or turn off the generator or PC until you see the final screen:



10. Now you must power cycle the generator to boot from the new firmware.

Auto upgrade - PCMCIA/Compact Flash Method


The second method of upgrading the generator using the auto upgrade feature is the PCMCIA/Compact Flash upgrade. This method is used when you connect the generator to the network and you cannot connect the PC to the generator but requires that you have a PC that is connected to the network (Internet). This method uses the PCMCIA/Compact Flash card (or compact flash with the PCMCIA/Compact Flash adapter) to transport the

upgrade files from the computer to the generator. The Auto Upgrade utility prompts the user when the PCMCIA/Compact Flash card must be moved between the computer and the generator.




Running the Auto Update utility: PCMCIA Upgrade


1. Run the utility by double-clicking on **AutoUpdate.jar.** You will be presented with the following screen:


Upgrade Selection Type
quantumdata
88X Upgrade Utility
Version 1.1.1
This application will assist you in upgrading your 88X by obtaining information from your 88X Generator, and downloading the appropriate upgrade from the Quantum Data website for this particular model.
Select your method of Upgrade:
Network Upgrade
PCMCIA Upgrade
Cancel
Next >>


2. Select **PCMCIA Upgrade**; then click **Next**. Prepare the PCMCIA/Compact Flash card per the following screen:




3. Click **Next**, then enter generator information (genstats) on the following screen. The button **How To Get Genstats Manually** will show you the method for reading genstats on an attached display. You can also generate an HTML genstats report by pressing **TOOLS -> Reports -> Misc -> Genstats**. You can view this report by selecting the Generated Reports link from the generator's home page; then select GenStats.
4. Enter the information exactly as presented in the genstats report. Following is an example:




5. When this information is correct, click on **Next**.
6. The utility will download the new firmware files from the Quantum Data website, and report the version number of the release:





7. Click on **Yes**, and the utility will extract the individual files from the downloaded release archive. Then you will be prompted to insert a blank PCMCIA/Compact Flash card into the generator.



Insert Card Into 88X
quantumdata
Please insert a BLANK PCMCIA card into the 88X Generator's PCMCIA card slot.
Then hit the Next Button Below
Cancel
Next


Clone Capture
quantumdata
Please Hit the Clone Capture Button...This may take several minutes.
When the Clone Capture is complete, remove the PCMCIA card from the
88X Generator and insert the PCMCIA card back into this PC,
then Hit the Next Button Below.
Note: The contents of the PCMCIA card will be replaced by the contents in flash.
How To Find The Clone Capture Button
Cancel
Next

8. Next you will be prompted to hit the **Clone Capture button** (**Tools -> System -> Clone -> Capture**.) This will cause the generator to back up the internal files to the PCMCIA/Compact Flash card. When this process is complete, insert the card into the computer and click on **Next**.
9. Then you will be asked to specify the location of the PCMCIA/Compact Flash drive on the computer. You can type the drive letter into the space provided (such as G:\) or you can browse to the location. In either case, you must specify the root of the PCMCIA/Compact Flash card.









10. When the drive address is selected, click **Next**, and the backup files will be copied from the card onto the PC. When the backup is completed, the new release files will be


copied onto the card. Then you will be prompted to insert the card back into the generator.




11. Click Next, and you will see the following screen instructing you to initiate the clone restore process by pressing **Tools -> System -> Clone -> Restore.**



12. After the clone restore is complete, you will again see the menu on the generator's screen. Then click on **Next**.


Upgrade Complete
quantumdata
88X Generator Upgraded Complete.
Please Power Cycle your 88X Generator
Finished



13. Power cycle the generator, and it will boot the upgraded firmware.

Upgrading the generator locally

This section provides procedures for upgrading a generator locally. Procedures for upgrading multiple generators over a network are provided in “Upgrading generators over a network” on page 155.

There are two methods for upgrading a generator locally:

- Upgrading using PC card
- Upgrading without using PC card

Upgrading using the PC card is the recommended approach to upgrade the generator locally. However, you may prefer to leave the current files on the PC card so you can return to a known operational state should the upgrade fail. In this case, you can upgrade by transferring the new release files directly to flash memory in the generator.

Manually upgrading using PCMCIA Compact Flash card

This procedure requires that you put the new release files (System and Library directories) on the PC card, then use the Restore function to transfer the files from PCMCIA Compact Flash card (PC Card) to flash memory on the generator.

Important: *If you have custom files stored in flash memory or PC card, you must back them up to your PC before upgrading your generator. These files will be deleted during this upgrade procedure. See “Copying files from a generator to a PC” on page 26 for details on using the FTP Browser to back up generator files. Once your generator is upgraded, you will need to restore these files.*

Follow this procedure to upgrade a generator using the PC card.


To upgrade a generator using the PC card:

1. Download the new release zip file from the Quantum Data download page (http://www.quantumdata.com/downloads/index.asp) and extract into a folder on your PC.
2. If you have a PCMCIA slot accessible with your PC, perform the following steps. Otherwise, proceed to Step 3.
   a. Insert the PC card into the PC’s PCMCIA slot.
   b. Transfer the new release files (System and Library directories) to the PC card.
   c. Remove the PC card from your PC and insert into the generator’s PC card slot.

3. If your PC does not have access to a PCMCIA slot or device, use the following procedure. You can skip this step if you performed Step 2 above.

   a. Access the generator's main web page. For details on this, see "To connect directly to the generator:" on page 116.

   b. Access the generator's FTP browser by choosing the **FTP Browser** menu item from the generator's main web page. The Generator FTP Browser appears. The **Instrument Files** area shows the files stored on the generator. The **Host Files** area shows the files stored on the PC.



   c. In the **Instrument Files** area, set the destination folder to the PC card. To do this, select **card0** for the generator's PC card.

   d. In the **Instrument Files** area, upload (copy) any custom generator files on the PC card you want to save to a backup folder on the PC.

   e. In the **Instrument Files** area, delete all files stored on the PC card.

f. In the **Host Files** area, locate and select the new release files (System and Library directories) to transfer to the PC card.

g. In the **Host Files** area, click **Download**. The **Transfer Files** dialog box appears.

h. Verify that the source file or folder and the destination folder are correct, and then click **OK**. The **Copying Files** dialog box appears showing the status of the operation.

i. When transfer is complete, click **Done.**


4. On the generator front panel, press the **Tools** key. The Tools menu appears on the generator's display as shown below.



5. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



6. Choose the **Clone** item by pressing the adjacent soft key. The Clone menu appears on the generator's display as shown below.




7. Choose the **Restore** item by pressing the adjacent soft key. The current files on the generator's flash memory are replaced by the new release files from the PC card. You are prompted to confirm the restore.
8. Choose **Yes** to proceed with the upgrade by pressing the adjacent soft key. When restore operation is complete, the Tools menu is displayed.
9. Restart the generator while booting from flash memory.
10. Restore any custom files to flash memory or PC card.

Manually upgrading the generator without using PC Card

This procedure allows you to transfer (copy) the new release files (System and Library directories) directly to flash memory without using a PC Card.

Follow this procedure to upgrade a generator without using a PC Card.

1. Download the new release zip file from the Quantum Data download page (http://www.quantumdata.com/downloads/index.asp) and extract into a folder on your PC.
2. Access the generator's main web page. For details on this, see "To connect directly to the generator:" on page 116.
3. Access the generator's FTP browser by choosing the **FTP Browser** menu item from the generator's main web page. The Generator FTP Browser appears. The **Instrument Files** area shows the files stored on the generator. The **Host Files** area shows the files stored on the PC.



4. In the **Host Files** area, create a backup folder.
5. In the **Host Files** area, open the backup folder.
6. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0**. This is the generator's flash memory.

7. In the **Instrument Files** area, select all of the folders (or only the specific files in the lower pane that you want to backup).
8. Click **Upload**. A **Transfer Files** dialog box appears.
9. Verify that the source file or folder and the destination folder are correct, and then click **OK**. The **Copying Files** dialog box appears showing the status of the operation.
10. When transfer is complete, click **Done.**
11. In the **Instrument Files** area, select all of the folders (System and Library) in the lower pane.
12. Click **Delete**. A **Deleting Files** dialog box appears.
13. Verify that the selected folders on the generator's flash memory (**tffs0)** are correct, and then click **OK**. The **Deleting Files** dialog box appears showing the status of the operation.
14. When delete is complete, click **Done.**
15. In the **Host Files** area, locate and select the new release files (System and Library directories).
16. In the **Host Files** area, click **Download**. A **Transfer Files** dialog box appears.
17. Verify that the source file or folder and the destination folder are correct, and then click **OK**. The **Copying Files** dialog box appears showing the status of the operation.
18. When transfer is complete, click **Done.**
19. Restart the generator while booting from flash memory.
20. Restore any custom files to flash memory from backup.

Connecting generator directly to a PC

This section describes how to connect your generator directly to a PC using a crossover cable. For instructions on connecting to an Ethernet LAN, see "Connecting generators to the network" on page 144.

Use the procedures below to set the IP addresses in your generator and PC, and connect directly to the generator through an Ethernet crossover cable.


1. "Setting the generator's IP address"
2. "Setting the PC's network settings"

Setting the generator's IP address

To establish communication between the PC and the generator, the generator must have an IP address. You can view and set the IP address through the front panel using the following procedures.

To set the generator's IP address:


1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



3. Choose the **Network** item by pressing the adjacent soft key. The generator's IP address and subnet mask appear on the generator's display as shown below.



4. Press the **Settings** key. The Network Connection screen appears on the generator's display as shown below.




   If the IP Address configuration option is not visible, press the soft key adjacent to the arrow symbol by SubnetMask until IP Address appears.

5. Change the IP address as follows:

   a. Position the blinking cursor on the address digit you want to change. To do this, press the soft key adjacent to the arrow by the address to move the cursor left or right until it appears on the digit you want to change.

   b. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each IP address digit you want to change.

6. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   To save the changes, choose the **Yes** item by pressing the adjacent soft key.

   To exit without saving the changes, choose the **No** item.

   To return to the previous screen without saving the changes, choose the **Back** item.

7. Reboot the generator.


Setting the PC's network settings

To establish a local ethernet connection between PC and generator, follow these steps to configure a static IP address on your PC and connect using a crossover cable.


To connect directly to the generator:

1. Determine the IP address of the generator by pressing the **Tools** key, choosing the **System** item, and then choosing the **Network** item. The IP address of the generator appears on the generator's display. Refer to the procedures above "Setting the generator's IP address" on page 145 for more details on accessing this display.
2. Configure the IP address of your PC. To enter the IP address, open Windows Control Panel, and then open the Network Connections window.
3. In the Network Connections window, right click the connection that represents your Ethernet card and select **Properties**. Select the **Internet Protocol TCP/IP** connection, and then click **Properties**.

Note: *If you have more than one Ethernet card make sure you configure the select the correct one.*



4. In the Internet Protocol (TCP/IP) Properties dialog box, select **Use the following IP address** and type the IP address in the box.



Note: *IP addresses consist of a network component and a host component. The network component is represented by the first 3, 6, or 9 digits of the address, depending on the network class. The host component is the last 3 digits. The network component of the IP address you enter for the PC must match the network component of the generator's IP address. The host component of both IP addresses must be different. You do not have to specify the DNS server.*

5. Enter the subnet mask such that the network portion of the address is masked to a value of 255 for each.
6. Connect the crossover cable between the ETHERNET jack on the generator and the Ethernet jack on the PC.

7. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator web page appears in the browser.



Reconfiguring and booting a stalled generator

If a generator fails to boot as expected, it may be set to boot from a location with a corrupt system file or without the necessary system files. The symptom of this problem could be that the generator just fails to boot. In other cases you could see an error such as “tffs0 failed to load.” Starting in Release 2.6 (vxWorks file 20.1883600) the generator has a feature which reformats a corrupt file system. Follow the procedures below to boot the generator in these instances.

To boot a generator that is in a stalled state:

1. Apply power to the generator. The following display appears.

```
 Quantum Data
  Windriver
  vxWorks System Boot
Press any key for setup
```

   To boot from an alternative device, press any key within three seconds. The following display appears. Note that you can also obtain this screen by powering up the generator and holding down any key, e.g. **Tools** key.

```
!BootDev    !Passwd
!HostName   !Flags
!FileName   !Other
!InetAddr   !TrgtName
```

2. Choose the **!BootDev** item by pressing the adjacent soft key.

```
 Network Boot
*Internal Flash
 PCMCIA Boot
```

3. Do one of the following:
   - To boot from the file server, press the soft key adjacent to **Network Boot**.
   - To boot from the generator’s flash memory, press the soft key adjacent to **Internal Flash**.
   - To boot from the generator’s PC card, press the soft key adjacent to **PCMCIA Boot**.
4. Press the **Options** (**Enter**) key to save the configuration.
5. Either restart the generator by cycling the power or press the **Tools** key to return to the boot menu.

6. Scroll down to the allow viewing and selection of the BootNow item as shown below.

```
!FileName   !Other
!InetAddr   !TrgtName
!HostAddr    BootNow
!User
```

7. Select **BootNow** by pressing the adjacent item selection key.
8. The following display appears:

```
 Press UP arrow
 to Boot Now
```

9. Press the + key to boot the generator.

To boot a generator that has a corrupt file system:

1. Configure a PCcard with Release 2.6 (vxWorks file: 20.1883600) or later including all the System and Library files.
2. Insert the PCcard in the generator's card slot.
3. Power down the generator, hold down the **Tools** key and then re-apply power to the generator. The following screen appears on the generator's display:

```
!BootDev    !Passwd
!HostName   !Flags
!FileName   !Other
!InetAddr   !TrgtName
```


4. Choose the **!BootDev** item, and then choose the **PCMCIA Boot** item from the menu below:

```
 Network Boot
*Internal Flash
 PCMCIA Boot
```

5. Press the **Options** (**Enter**) key to save the configuration.
6. Either restart the generator by cycling the power or press the **Tools** key to return to the boot menu.
7. Scroll down to the allow viewing and selection of the BootNow item as shown below.


```
!FileName   !Other
!InetAddr   !TrgtName
!HostAddr    BootNow
!User
```

8. Select **BootNow** by pressing the adjacent item selection key.
9. The following display appears:



10. Press the + key to boot the generator.

    The following display appears and the generator boots up.




11. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



12. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



13. Choose the **Clone** item by pressing the adjacent soft key. The Clone menu appears on the generator's display as shown below.



14. Choose the **Restore** item by pressing the adjacent soft key.

    A progress indicator appears. This will take some time.


15. Reconfigure the generator to boot from the Flashmem using the procedures described in "To boot a generator that is in a stalled state:" on page 120.
16. Restart the generator.
17. If the problem persists you may have to unseat the video board from the main board:

    http://www.quantumdata.com/support/videos/video.asp


18. Repeat the procedure.

To boot a stalled generator from a different host:


1. Power down the generator, hold down the **Tools** key and then re-apply power to the generator. The following screen appears on the generator's display:



2. Choose the **!BootDev** item, and then choose the **Network Boot** item.
3. Press the **Tools** key and choose the **!HostName** item by pressing the adjacent soft key. The following appears on the generator's display:




4. Change the host name as follows:
   a. Position the blinking cursor on the character you want to change. To do this, press the soft key adjacent to the arrow by the host name to move the cursor left or right until it appears on the character you want to change.
   b. Select the desired character by pressing the + or - keys to scroll through uppercase letters, lowercase letters, and numbers. Repeat for each character you want to change.
5. Press the **Options** (**Enter**) key to save the configuration.
6. Return to the **Tools** menu and choose the **!HostAddr** item by pressing the adjacent soft key. The following appears on the generator's display:




7. Change the host IP address as follows:
   a. Position the blinking cursor on the digit of the IP address you want to change. To do this, press the soft key adjacent to the arrow by the address to move the cursor left or right until it appears on the digit you want to change.
   b. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each digit you want to change.
8. Press the **Options** (**Enter**) key to save the configuration.
9. Restart the generator by cycling the power.

To change the IP address of the generator:

1. From the Boot Menu select **!InetAddr**.



2. Choose the **!InetAddr** by pressing the adjacent item selection key. The generator's IP address and subnet mask appear on the generator's display as shown below.



   If the IP Address configuration option is not visible, press the soft key adjacent to the arrow symbol by SubnetMask until IP Address appears.

3. Change the host IP address as follows:

   a. Position the blinking cursor on the digit of the IP address you want to change. To do this, press the soft key adjacent to the arrow by the address to move the cursor left or right until it appears on the digit you want to change.

   b. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each digit you want to change.

Cloning generators


You can clone generators using either the generator's PC card or the Generator FTP Browser over an Ethernet connection. To clone a generator, the firmware revision of the source and target generators must match.

Cloning a generator using the PC card

Follow this procedure to clone a generator using the PC card.

To clone a generator using the PC card:


1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Insert the PC card into the source generator.
3. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



4. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



5. Choose the **Clone** item by pressing the adjacent soft key. The Clone menu appears on the generator's display as shown below.




6. Choose the **Capture** item by pressing the adjacent soft key.

   Note: *The contents on the PC card are replaced by the contents on the flash memory.*

   A progress indicator appears.
7. Remove the PC card from the source generator and insert it into the target generator.

8. On the target generator, press the **Tools** key. The Tools menu appears on the generator's display as shown below.



9. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



10. Choose the **Clone** item by pressing the adjacent soft key. The Clone menu appears on the generator's display as shown below.



11. Choose the **Restore** item by pressing the adjacent soft key.

    A progress indicator appears.

12. Restart the generator from flash memory.

Cloning a generator using the Generator FTP Browser


This section provides procedures for cloning a generator with a PC directly connected to a generator. You will find this cloning method procedure useful if you do not have a PC Card. To complete this procedure you connect the Ethernet crossover cable to the Ethernet ports of both the PC and the generator. If your generators are networked over an Ethernet LAN, see "Cloning generators using the generator FTP Browser" on page 158.

During this procedure, you will copy the files from the source generator to the PC, disconnect the source generator and connect the target generator, and then copy the files from the PC to the target generator. You must know the IP address of both generators.

To clone a generator using the Generator FTP Browser:

1. Connect the source generator to the PC using an Ethernet crossover cable between the Ethernet ports on the PC and the generator.

2. Access the source generator's Generator FTP Browser. See "Working with the Generator FTP Browser" on page 24.



3. Copy all of the files in the source generator's flash memory to the PC as follows:
   a. In the **Instrument Files** area of the Generator FTP Browser window, click the down arrow by the **Look in** box and select **tffs0 (FlashMem)**.
   b. Select the system and library folders in the lower pane.
   c. In the **Host Files** area, open the folder where you want to copy the files. To create a new folder, click **New**.
   d. In the **Instrument Files** area, click **Upload**. A confirmation dialog box appears.
   e. Click **OK** to copy the files.
4. Close the Generator FTP Browser.

   Note: *If both generators on the Ethernet/IP network you do not have to close the source generator FTP Browser.*

5. Disconnect the source generator from the Ethernet cable and connect the target generator.

   Note: *If both generators on the Ethernet/IP network you do not have to disconnect the generator.*

6. Access the target generator's FTP Browser.
7. Delete the current system and library resource folders from the target generator's flash memory as follows:
   a. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0 (FlashMem)**.
   b. Select all of the files in the lower pane.
   c. Click the **Delete** button. A confirmation dialog box appears.
   d. Click **OK** to delete the files.
8. Copy the source system and library folders from the PC to the target generator's flash memory as follows:
   a. In the **Host Files** area, open the folder containing the system and library folder.
   b. Select the system and library folders in the lower pane.
   c. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0 (FlashMem)**.
   d. In the **Host Files** area, click **Download**. A confirmation dialog box appears. Click OK to download the source files to the generator.
9. Reboot the generator by cycling the power.

Resetting a generator

You can reset a generator to a known good condition.

Note: *Resetting does not restore the generator to factory default condition. Thus, it should not be used to restore proper operation of the generator.*

Follow this procedure to reset a generator.

To reset the generator using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.
2. Enter one of the following commands:
   - To reset the generator, enter:

     ```
     *RST
     ```

   - To reset and calibrate the generator, enter:

     ```
     *RST          // Resets the generator
     SCAL          // Calibrates the generator
     ```

Viewing generator configuration information

You can view information about a generator's configuration, including the firmware and gateware revisions, installed options, board serial numbers, and so on. The procedure for accessing this information depends on the type of information you want.

- For information about the main board and video board memory, use the front panel.
- For complete generator statistics, view the GenStats image.
- For firmware and gateware versions, use the command line interface.

This section describes the procedures for accomplishing these methods of accessing generator configuration information.

To view generator configuration information using the front panel:


1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display.




3. Choose the **About** item by pressing the adjacent soft key. A following message appears on the generator's display as shown below.



4. Press the **Settings** key. The main board information appears. Press the soft key adjacent to the arrow by Serial Number to see other information about the main board.



5. To view the video board information, pressing the soft key adjacent to the arrow by Main Board. The video board build date appears as shown below. Press the soft key adjacent to the arrow by Build Date to see other information about the video board.



To view generator configuration information using the GenStats image:

1. Press the **Source** key and select a standard format such as DMT0660.

   Alternatively, enter the following commands to load the format:


   ```
   FMTL DMT0660.xml; FMTU
   ```

2. Press the **Content** key and select the GenStats image.

   Alternatively, enter the following commands to load the GenStats image:

   ```
   IMGL GenStats.img; IMGU
   ```

   The GenStats image appears as shown below.



3. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with

the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

4. Enter the following command to view the generator firmware version (runtime and boot code versions):

```
VERF?
20.0882002,01.04.11
```


5. Enter the following command to view the generator gateware information for each programmable device:

```
VERG?
253C,36,1272005:253F,73,8292005:253A,5,4252005
```


The information provided for each gateware is the Product Code, Revision Code and Date Code. There are three sets of gatewares listed. The first listing is for an CPLD which does not have an associated file in the System directory. The second listing is for the transmitter and the third listing is for the receiver if the analyzer option is present.

To get a report of the genstats image (or any active image):

1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



2. Choose the **Reports** item by pressing the adjacent soft key. The Report menu appears on the generator's display.



3. Choose the **Misc** item by pressing the adjacent soft key. The following menu appears on the generator's display.



4. Choose the **!GenStats** item by pressing the adjacent soft key. The generator display will briefly indicate that the report is being generated.


5. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.




Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*

6. Choose the **Generated Reports** item. The Generator the provides a list of reports currently available as shown below.



7. Select the GenStats report. The GenStats report then appears in the browser window as shown below. You can then save the report as an web page file for distribution.


HOME

quantumdata

Generator Information Report

Generator Information

Model = 882D
Unit PN = 0-00191
Unit Revision = A
Unit SN = 6110023
Date = 11132006
Firmware = 20.1883405
BootROM = 01.04.11

Memory Status (bytes)

Free flash = 2678784
Free RAM = 5548808

Main Board

Part Num = 99-00505
Serial Num = 86961
Board Rev = E

Video Board

Part Num = 99-00552
Serial Num = 87218
Board Rev = C
Date = 11132006
Options =
GW 1 = 400C,4,6062006

4 Networking Generators

Topics in this chapter:

- Overview
- Configuring a file server
- Establishing a network environment
- Network operations
- Controlling a generator remotely
- Upgrading generators over a network
- Cloning generators using the generator FTP Browser

Overview

This chapter describes how to use the generator in a networked environment.

Quantum 882 generators can operate and be administered over an Ethernet LAN connection. By networking multiple generators together, you can centralize control in production environments.

When networking generators, a file server containing a set of system and resource files is installed on the network. This arrangement allows you to:

- Set up generators to automatically retrieve and use a centrally-stored set of system and firmware files upon startup. This ensures that each generator on the network is running the same firmware.
- Set up generators to access a common set of objects, such as images and formats, from a file server. This allows each generator on the network to access the same set of standard and custom library files.
- Easily upgrade a generator's local system and library files from the file server. This ensures that each generator on the network is using the most current system and library files when booting and accessing files locally.
- Control and maintain your network of generators remotely from a single host PC. You can manage the generators through the command line interface, through the Virtual Front Panel in a Web browser, or by transferring files using the Generator FTP Browser.

Generator file system

The 882 generator file system is comprised of two main directories (folders): 1) System and 2) Library. The System folder contains the realtime operating system and firmware file (vxWorks) and the gateware. The Library folder contains the following resource files:

- Fonts - Object files used to define the font types.
- Formats - XML files defining the format parameter settings.
- FormatLib - XML files for configuring the source list of formats
- Images - C++ object files, executables, bitmaps, and XML files for rendering images.
- ImageLib - XML files for configuring the content list of images
- Sequences - XML files with instructions for test sequences.
- Users - XML files for user configuration profiles

Configuring a file server

This section describes how to set up a file server. The file server is a PC used to host the generator system and resource files to be shared by networked generators. To configure the file server, you must install FTP server software on it, create an FTP directory (site), and copy the 882 system and resource files into the FTP directory.

File server specifications

The minimum configuration for the file server should be as follows:

- Windows NT, Windows 2000, or Windows XP operating system
- Pentium-based processor (for example, Pentium 4)
- 256 MB SDRAM
- 20 MB of free disk space

  Note: *If you will be using the Software Development Kit and gcc compiler to create custom images, an additional 100 MB of free disk space is required.*

- Ethernet card and a connection to the corporate LAN
- CD-ROM drive (for loading the 882 system and resource files and documentation from the ResourceCD)
- Java Runtime Environment 1.5 or later


Installing an FTP server

Setting up an FTP server on the file server is necessary if you want the generators to boot from the file server or if you want to store files on the server that you can access from the generator in the Browse mode. Any standard FTP server program, such as Microsoft FTP Server, can be used. Microsoft FTP Server operates with Microsoft Internet Information Services; therefore, both must be installed on the server PC.

To set up the FTP server:

1. Install the FTP server software on the file server PC and create the FTP site directory.

   You can use Microsoft Internet Information Services shown below.




2. Configure the FTP site properties.


   a. On the **Home Directory** tab, enter the name of the **Local Path** (your default directory for the FTP server). By default, Microsoft Internet Information Services

uses C:\Inetpub\ftproot as the local path as shown below. You can use this path or click **Browse** to select a different path.

b. On the **Home Directory** tab, specify read/write access.



c. On the **Security Accounts** tab, select **Allow only anonymous connections**, and then click **OK**.




Copying resource files to the FTP site on the file server

After installing the FTP server, you can download the generator system and resource files from the Quantum Data Web site and copy them to the FTP site on the file server.

To copy generator system and resource files to the file server:

1. Create a download folder in a convenient location on your PC.
2. Access the download page of the Quantum Data Web site at: http://www.quantumdata.com/support/downloads/
3. Copy the contents of the 882 folder from the download folder to the root folder on the FTP server. The resulting folder structure on the file server PC is shown below.

4. Move the vxWorks file out of the System folder and into the ftproot folder.




Establishing a network environment

To create a network environment for your generators, you must physically connect the generators to the network, and then configure their IP addresses and the IP address of the file server. Procedures for these tasks are described in this section.


Connecting generators to the network

In a typical networked environment, you will connect the generators to the corporate, IP-based Ethernet LAN. In this scenario, you connect a standard Ethernet patch cable between the Ethernet port on the generator and a LAN access jack. The file server is also connected to the LAN in the same manner.



Another type of network scenario is to directly connect a single generator to a file server. For a direct connection, you must use a crossover Ethernet cable and connect it from the Ethernet port on the file server to the generator Ethernet port as shown below.

Note: *If you are using a PC that is connected to a network that automatically assigns an IP address, and you will be disconnecting from that network to connect to the crossover cable and generator, you must manually enter an IP address into the PC so it can communicate with the generator. The network portions of the IP addresses of the generator and the PC must match.*



When the network connection on the generator is active, the **Network** LED lights on the front panel.

Setting the generator's IP address

You can either set the IP address of the generator manually with an address you select or automatically by using the built in DHCP support. The default state of the generator is that DHCP is off. So you have to enable it if you want the IP address to be set automatically from a DHCP server. The procedures for setting the IP address manually and enabling DHCP for auto configuration are provided below.

Each generator on the network must have a unique IP address if you want to control the generator over a network, or want the generator to share resources located on a file server. Typically, your site's LAN administrator will provide you with IP addresses for each generator. Depending on how your site's LAN is configured, your LAN adminstrator may also provide you with a subnet mask.

To set the IP address of the generator:


1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



3. Choose the **Network** item by pressing the adjacent soft key. The generator's IP address and subnet mask appear on the generator's display as shown below.



4. Press the **Settings** key. The Network Connection screen appears on the generator's display as shown below.



   If the IP Address configuration option is not visible, press the soft key adjacent to the arrow symbol by SubnetMask until IP Address appears.

5. Change the IP address as follows:

   a. Position the blinking cursor on the address digit you want to change. To do this, press the soft key adjacent to the arrow by the address to move the cursor left or right until it appears on the digit you want to change.


   b. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each IP address digit you want to change.

6. If necessary, change the subnet mask as follows:


   a. If the SubnetMask configuration option is not visible, press the soft key adjacent to the arrow symbol by IP Address until SubnetMask appears.

   b. Position the blinking cursor on the subnet mask digit you want to change. To do this, press the soft key adjacent to the arrow by the subnet mask to move the cursor left or right until it appears on the digit you want to change.

   c. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each subnet mask digit you want to change.



7. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   To save the changes, choose the **Yes** item by pressing the adjacent soft key.


   To exit without saving the changes, choose the **No** item.

   To return to the Network Connection screen without saving the changes, choose the **Back** item.

8. Power cycle the generator to invoke the new IP address.

To enable DHCP for auto IP address configuration of the generator:


1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.




3. Choose the **Network** item by pressing the adjacent soft key. The generator's IP address and subnet mask appear on the generator's display as shown below.




4. Press the **Settings** key. The Network Connection screen appears on the generator's display as shown below.




   If the DHCP configuration option is not visible, press the soft key adjacent to the arrow symbol by SubnetMask or IP Address until the DHCP configuration screen appears.



5. Change the setting to YES by pressing the + key.



6. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   To save the changes, choose the **Yes** item by pressing the adjacent soft key.

   To exit without saving the changes, choose the **No** item.

   To return to the Network Connection screen without saving the changes, choose the **Back** item.


7. Power cycle the generator to set the IP address of the generator.

Setting the file server IP address in the generator

You must enter the IP address of the file server in each generator so the generator can communicate with the file server. In addition, you can also enter a name (called the Host Name) for the file server.

To specify the IP address and host name of the file server:


1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



3. Choose the **Server** item by pressing the adjacent soft key. The server name and IP address appear on the generator's display.



4. Press the **Settings** key. The Network Host screen appears on the generator's display as shown below.



   If the Host Address configuration option is not visible, press the soft key adjacent to the arrow symbol by Host Name until Host Address appears.

5. Change the host address as follows:

   a. Position the blinking cursor on the address digit you want to change. To do this, press the soft key adjacent to the arrow by the address to move the cursor left or right until it appears on the digit you want to change.


   b. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each address digit you want to change.

6. (Optional) Change the host name as follows:


   a. If the Host Name configuration option is not visible, press the soft key adjacent to the arrow symbol by Host Address until Host Name appears.

   b. Position the blinking cursor on the character you want to change. To do this, press the soft key adjacent to the arrow by the name to move the cursor left or right until it appears on the character you want to change.

   c. Select the desired character by pressing the + or - keys to scroll through uppercase letters, lowercase letters, and numbers. Repeat for each character you want to change.



7. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   To save the changes, choose the **Yes** item by pressing the adjacent soft key.

   To exit without saving the changes, choose the **No** item.

   To return to the Network Host screen without saving the changes, choose the **Back** item.

8. Power cycle the generator to set the server IP address.

Network operations

This section provides common networking tasks, such as booting generators from the file server, accessing files stored on the file server, transfering files from the file server to the generator, and controlling the generator remotely.


Booting a generator from the file server

A generator can be set up to boot from an operating system (vxWorks) file stored on the file server. To do this, you must set the IP address of the file server in the generator, and then configure the generator to use the file server as a boot device. For instructions on setting the IP address of the file server in the generator, see “To enable DHCP for auto IP address configuration of the generator:” on page 147.

Procedures for booting the generator from the file server are provided below. For procedures to boot a stalled generator refer to “Reconfiguring and booting a stalled generator” on page 120.

To configure the generator to boot from the file server:


1. Copy the vxWorks folder into the ftproot folder using the procedures described in “Copying resource files to the FTP site on the file server” on page 142.
2. Press the **Tools** key. The Tools menu appears on the generator’s display as shown below.



3. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator’s display as shown below.
4. Scroll down to the end of the System menu by pressing the - key until the following menu items appear on the generator’s display:



5. Choose the **BootFrom** item by pressing the adjacent soft key. The BootFrom menu appears on the generator’s display as shown below.



6. Choose the **NetPlace** item by pressing the adjacent soft key.

Sharing objects on a file server

The generator can be set up to access shared format, image, and sequence files stored on a file server. To do this, you must set the generator's path to point to the corresponding folders on the file server. You can set the path using the command line interface or the front panel.

To set the generator's path using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. For each file type (format, image, and sequence), set the path parameter to the corresponding folder on the file server using the following commands:

   ```
   FMTP hostname:/Library/Formats
   IMGP hostname:/Library/Images
   SEQP hostname:/Library/Sequences
   ```

   For example if your file server host name is Host01, you would enter the following command to set the format path to the Formats directory on the file server:


   ```
   FMTP Host01:/Library/Formats
   ```

   Note: *The hostname portion of the path is case sensitive.*

   The generator will now display the formats on the file server when you press the **Source** key.

To set the generator's path using the front panel:


1. Place the generator in Browse mode by holding down the **Tools** key until the media menu appears on the generator's display as shown below.

2. Choose the **NetPlace** item by pressing the adjacent soft key. The folders on the file server appear on the generator's display as shown below.

3. Choose the **Library** item by pressing the adjacent soft key. A list of folders in the library folder appear on the generator's display as shown below.



4. Press the soft key adjacent to the folder you want to use. For example, to use the Formats folder, press the soft key adjacent to Formats. The contents of the selected folder appears on the generator's display.
5. Choose an item by pressing the adjacent soft key. The path is now set to the selected folder on the file server.

Controlling a generator remotely

In addition to controlling the generator using the front panel keys, you can also control the generator from a remote PC either through the Virtual Front Panel Web-based interface or the command line interface.

Using the Virtual Front Panel to operate a generator remotely

The 882 generator has a built-in Web server that provides a graphical interface called the Virtual Front Panel to control the generator. With the Virtual Front Panel, you can perform the same tasks as you would with the generator's front panel. To use the Virtual Front Panel on your PC you must have the Java Runtime Environment (JRE) 1.5 or later installed on your PC. You can download the JRE from http://www.java.com/en/download/windows_ie.jsp. For more information about using the Virtual Front Panel, see "Working with the Virtual Front Panel" on page 21.

Maintaining the generator's file system using the Generator FTP Browser

If you create objects on a PC, such as images or formats, you can copy these objects to a generator if you want the generator to load them locally. For example, you may want to create a new image on the file server PC, and then copy the image to certain generators in your production environment. The Generator FTP Browser enables you to copy files between the file server PC and the generators.

You can also use the Generator FTP Browser to copy files between media in the generator. For example, you can update the generator's PC card with the generator's flash memory or update the flash memory with files on the PC card. You can also update the media of one generator with the contents of another generator's media.

For more information about using the Generator FTP Browser, see "Working with the Generator FTP Browser" on page 24.

Operating the generator remotely through the command line interface

You can operate the generator remotely using the command line interface through either a Telnet session over an Ethernet LAN or the command terminal on the Virtual Front Panel Web page. For instructions on connecting to the generator using Telnet, see "Establishing a Telnet session with the generator" on page 34. For instructions on using the command terminal through the Virtual Front Panel, see "Working with the CMD (Command) Terminal" on page 23.

Upgrading generators over a network

An upgrade to a network of generators can involve a new system and firmware file ("vxWorks"), a new gateware file, and new library resource files. In some cases you may be upgrading only the firmware or only the gateware, but not both. In other cases, the upgrade may involve only new images or formats. The procedures you follow for an upgrade will therefore depend on what you are upgrading.

This section provides procedures for upgrading generators over a LAN. The procedures for upgrading a single generator that is not connected to a LAN are provided in "Upgrading the generator locally" on page 110.

Upgrade options and procedures

The recommended procedure for upgrading is to upgrade the file server and the flash memory of each generator. Upgrading the PC card is optional, depending on how your site uses the PC card. For example, you may decide to leave the current files on the PC card so you can return to a known operational state should the upgrade fail.

To begin an upgrade, you must either have a CD-ROM containing the new files, or download the files from the Quantum Data Web site. You will copy the new files to your file server PC which must be connected to the LAN through the Ethernet cable.

Overview of upgrade procedures

The following are the high-level steps for performing a complete upgrade (system and firmware file, gateware, and library resource files) to generators over a network. Detailed instructions for each step are provided in the sections that follow.


1. Back up the current file server system and firmware file, gateware, and library files.
2. Copy the new generator system and firmware file, gateware, and resource files onto the file server PC.
3. Remove the system and firmware file, gateware, and library resource files from each generator's flash memory.
4. Copy the new system and firmware file, gateware, and library resource files from the file server PC to each generator's flash memory.
5. Reboot all generators.

Backing up the current files on the file server

Backing up the current files ensures that you can return to a known operational state should the upgrade fail.

To back up the current files on the file server:

1. Create a separate, backup folder on your file server PC (not in the FTP folder) to house the files currently used by the network of generators.
2. Open the FTP site folder and copy the contents of the folder to your backup folder. These should include the 882 directory and the System and Library folders as shown below.



3. If any of the generators have custom format, image, sequence, or font files that do not also reside on the file server, you must back them up to the backup folder on the file server independently to preserve them. See “Backing up the current files on the file server” on page 155 for instructions.

   You might want to back up only the custom files on the generator to a custom folder on the file server you create. Alternatively if you are sure you want to restore a generator with its current set of library files you can simply backup its entire library folder to a custom folder on the file server.


Copying files to the PC file server

After you have backed up your existing files, you must delete the current files from the FTP folder on the file server, and then copy the new, updated files to the FTP folder. Before you begin, you must either have a CD-ROM containing the new system, gateware, and library files, or download the files from the Quantum Data Web site.

To copy the new files to the file server:

1. Open the FTP site folder and delete the contents.
2. Open the 882 folder from the location where you downloaded the files from the Quantum Data Web site.

3. Copy the contents of the 882 folder to the FTP site folder. The resulting folder structure is shown below.



Removing current files from the generators

Prior to upgrading the generators, you must remove the existing system and firmware file, gateware, and resource files from the flash memory of each generator. For instructions on removing files from the generator, see “Upgrading the generator locally” on page 110. If you are also installing the new files on the generator’s PC card, you must also remove the current files from the PC card.

Copying the new files to each generator

Now you are ready to copy the new, updated system and firmware, gateware, and library resource files to the generators to complete the upgrade. See “Working with the Generator FTP Browser” on page 24 for instructions.

Reboot the generators

The upgrade is now complete and you are ready to reboot the generators from the updated system files you just copied to each generator’s flash memory. Reboot each generator by cycling the power.


Cloning generators using the generator FTP Browser

You can clone generators either through the front panel or through the Generator FTP Browser on the Virtual Front Panel Web page. Procedures for cloning generators through the front panel are provided in “Cloning generators” on page 125.

This section describes how to clone generators by copying system and library files over the network using the Generator FTP Browser.

To clone a generator:

1. Access the generator’s FTP browser by choosing the **FTP Browser** menu item from the main web page. The Generator FTP Browser appears. The Instrument Files area shows the files stored on the generator. The Host Files area shows the files stored on the PC.



2. Open a second Web browser. You now have two instances of the Generator FTP Browser running: one for the source generator and one for the target generator.
3. In the Generator FTP Browser window for the target generator, delete all of the files in the target generator's flash memory as follows:
    a. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0**. This is the target generator's flash memory.
    b. Select all of the System and Library folders in the lower pane.
    c. Click the **Delete** button. A confirmation dialog box appears.
    d. Click **OK** to delete the files.
4. Copy all of the files in the source generator's flash memory to the target generator's flash memory as follows:
    a. In the **Instrument Files** area of source generator's Generator FTP Browser window, click the down arrow by the **Look in** box and select **tffs0**. This is the source generator's flash memory.
    b. Select the System and Library folders in the lower pane.
    c. Hold down the SHIFT key and drag the selected folders to the **Instrument Files** area of the target generator's Generator FTP Browser window. A confirmation dialog box appears.
    d. Click **OK** to copy the files.

5 Using GPIB Interface

Topics in this chapter:

- Overview
- Setting the GPIB port address
- Queries and commands
- Status queries and control

Overview

You can operate and program the generator from an external computer or terminal using the optional IEEE-488 (GPIB) interface. The GPIB interface enables the generator to be used as a programmable video signal source for integration into automated test systems that use IEEE-488 or GPIB communications between instruments.

Setting the GPIB port address


The default GPIB address is 15. You can specify a different address as described in the procedure below.

To set the address of the GPIB port using the front panel:

1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.



2. Choose the **System** item, and then choose the **GPIB** item. The GPIB address appears on the generator's display as shown below.
3. To change the address, do the following:
   a. Press the **Settings** key.
   b. Position the blinking cursor on the address digit you want to change. To do this, press the soft key adjacent to the arrow by the address to move the cursor left or right until it appears on the digit you want to change.
   c. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each address digit you want to change.
4. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   To save the changes, choose the **Exit, Save Change** item by pressing the adjacent soft key.

   To exit without saving the changes, choose the **Exit, No Change** item.

   To return to the previous screen without saving the changes, choose the **Go Back** item.

To set the address of the GPIB port using the command line:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. (Optional) Enter the following command to check the current address:

```
GPIB?
```

3. Enter the following command to set the address:


   ```
   GPIB address
   ```

   When the address is changed with the GPIB command, the change takes place as soon at the command is issued.


Queries and commands

The GPIB interface is an ASCII command line interface like the RS-232 command line interface. The communications protocol is per IEEE-488.2 specification. Queries and commands consist of four ASCII upper/lower case characters. Commands do not require a response from the generator, while queries cause the generator to respond with the required data.

You can send multiple commands on the same line by separating the commands with a semicolon (;) followed by a terminator. A terminator is defined as the NL character (ASCII 10), or EOI sent with the last byte of the command. The generator will not parse any commands received until a terminator is received. All commands are executed sequentially; that is, when a command is parsed it is allowed to finish execution before the next command is parsed, as illustrated in the following figure.



Program Message Syntax



Message Unit Syntax

Commands

Commands instruct the generator to set a parameter to the value given or perform some function not requiring any additional data. Commands which have an asterisk (*) as their first character are common commands as defined by the IEEE-488.2 standard and generally operate the same in all instruments. All commands are listed and described in Appendix A, “Command Reference.”

Commands which do not require any additional data from the controller are self-contained and should be followed by either a message separator (;) or message terminator. Any other characters (except whitespace characters) will cause a command error.

Commands which require numeric data must be followed by at least one separator character (whitespace), and then the data. Numeric data sent with a command is in decimal format. Numeric data can be represented in one of three methods: integer, floating point, or scaled floating point.

For example, the following number can be represented in three ways:

- Integer (42)
- Floating point (42.00)
- Scaled floating point (4.200E+01)

Queries

Queries are comprised of a header followed immediately by a question mark (?). If there are any characters between the query header and the question mark character (including whitespace), a command error will result. Queries return a response message upon completion of execution. A response message is comprised of the requested data terminated with an NL (ASCII 10) character. For example, the following text would be returned in response to the HRAT? (horizontal rate query) message:

```
3.1500E+04<NL>
```

Note that the HRAT? query returns its parameter in exponential form. Possible returned parameter forms are:

- Integer (3965)
- Exponential (+3.965E+03)
- String ("text string")

Output queue

When a query is executed, the resulting response message is placed in an output queue where it can be read by the controller. The generator has an output queue that is 255 bytes long. When a message is present in the output buffer, the MAV (message available) bit in the Status Byte register is set. This varies slightly from the 488.2 standard in that the MAV bit will be set only when at least one complete response message is present in the output queue. A complete response message consists of response message text and a message terminator (NL).

Buffer deadlock

Buffer deadlock occurs when the generator tries to put a response message in the output queue when the output queue is full and the controller is held off while sending a new message because the input buffer is full. If deadlock occurs, the generator will clear its output queue, set the query error (QYE) bit in the Event Status register and proceed to parse incoming messages. If any additional queries are requested while in deadlock, those response messages will be discarded.

The generator will clear the buffer deadlock when it finishes parsing the current command/query. The QYE bit will remain set until read with the *ESR? query or cleared with the *CLS command.

Sending commands and queries

The generator parses command lines one at a time. Command lines must be terminated with a carriage return (<cr>).The generator immediately echoes each character as it is received and places it in a command line buffer. This buffer currently has room for a total of 256 characters. If more than 256 characters are sent before sending a <cr>, then the following response will be given:

```
Buffer overflow<cr><lf><cr><lf>R:\>
```

Upon receiving a carriage return, the generator immediately echoes the <cr> and follows it with a line feed (<lf>). The generator then parses the command line and initiates whatever processing is implied. The generator then responds with one of the following four responses depending on the condition:

```
Command invalid<cr><lf><cr><lf>R:\>

<message1><cr><lf><message2><cr><lf>...<messageN><cr><lf><cr><lf>R:\>

Execution error: <nnnn><cr><lf><cr><lf>R:\>

R:\>
```

Where <cr> and <lf> are the carriage return and line feed characters, respectively.

Note: *Handshaking routines should only look for > and not R:\>. In the future, the R:\ part of the prompt may change (for example, may be expanded to indicate the current path).*

Bench-top generators output the following prompt on their serial port after finishing the power-on procedure.

```
R:\>
```

This feature allows ATE systems to know when the generator is ready.

Sending multiple commands and queries per line

You can send multiple commands and queries per line by separating each command or query with a semi-colon (;) character. For example:

```
HRES 900; ALLU
```

The response to multiple queries will be a series of data elements separated by semi-colons (;). For example, with the VGA_m3 format loaded, the following command string will produce the response shown.

```
HRES?; VRES?; VTOT?
640;480;525
```

Normally, all of the commands on a command line associated with a single command terminator are read as a single command message without regard for execution or completion order. However, by inserting the *WAI command, you can force the generator

to wait for all preceding commands to be completed before the commands that follow *WAI are processed. For example, sending the following command line causes a red rectangle to be drawn and then overwritten by the ColorBar image.

```
IMGL COLORBAR; IMGU; IMGE; RECT RED 200 200 0 0 GRAYPAT100
```

Note that the IMGU command merely requests that the current image be rendered eventually, not necessarily right away nor in a single attempt. By inserting a *WAI command after the IMGU, the generator is instructed to render the ColorBar image first, before rendering the red rectangle. This command ensures that the generator draws the red rectangle on top of the ColorBar image.

```
IMGL COLORBAR; IMGU; *WAI; IMGE; RECT RED 200 200 0 0 GRAYPAT100
```

The generator will wait until the ColorBar image has been completely rendered before it reads and executes the RECT command.

The *WAI command is required by the IEEE-488.2-1992 standard, but also works with GPIB and RS-232 protocols as well.

Completion handshake

The generator returns a > prompt immediately after an FMTU, IMGU, ALLU, BOOT, INIT, or SCAL command is received, even if these commands have not finished executing. If the system controlling the generator must know when the process started by one of these commands has been completed, then append *OPC? to the command string.

For example, the following command causes the generator to wait until all processes have been completed before responding with the number 1 and sending the > prompt.

```
FMTL VGA_M3; IMGL FLAT; ALLU; *OPC?
```

The *OPC? command is required by the IEEE-488.2-1992 standard, but also works with GPIB and RS-232 protocols as well.

Input buffer

Since some commands may take longer to execute, the generator has an input buffer. This input buffer is 255 characters long and can be written to by the host controller while the generator is busy executing or parsing previous messages. If the input buffer becomes full, the generator will hold off the controller until there is room in the buffer. For this reason, a program message cannot be longer than 255 characters including terminator.

Status queries and control

To create applications that control the generator using the GPIB port, it is sometimes necessary to query the status of the generator and set or reset the status bits and bytes. There are two sets of status registers: 1) the Event Status Register and Event Status Enable Register and 2) the Status Byte Register and Service Request Enable Register. These are described in the following paragraphs.

Status byte


The status byte used by the generator is the same as that defined by the IEEE-488.2 standard and does not use any other bits of the status byte. The status byte is one part of a complete status reporting system shown in the figure on page 170. The status byte is read by using the serial poll feature of your controller.

Requesting service

The GPIB provides a method for any device to interrupt the controller-in-charge and request servicing of a condition. This service request function is handled with the status byte. When the RQS bit of the status byte is true, the generator is requesting service from the controller. There are many conditions which may cause the generator to request service. For more information about these conditions, see the *SRE command description (page 472). The table below lists the status commands and queries.

Status commands and queries	Definition
*ESE	Sets the Event Status Enable register to the given mask value. When a bit in the Event Status register goes high and the corresponding bit in the Event Status Enable register is a 1, it is enabled and will cause the ESB bit in the Status Byte register to go high.
*ESR??	Returns the current value of the Event Status register. After this command is executed, the Event Status register is cleared. This is the only way of clearing any bit in the Event Status register except by the *CLS command.
*SRE	Sets the Service Request Enable register to the mask value given. When a bit in the Status Byte register goes true and the corresponding bit in the Service Request Enable register is also true, the generator will request service using the GPIB.
*SRE?	Returns the current value of the Service Request Enable register.
*STB?	Returns the current value of the Status Byte register. The value stored in the Status Byte register is not affected by reading it.
*CLS	Clears the Event Status register, the Status Byte, and the output buffer.

The following figure illustrates IEEE-488 status reporting.



Status byte bit	Definition
MAV	Message available. Indicates that at least one complete response is present in the output buffer.
ESB	Event status bit. Indicates that one of the enabled conditions in the Standard Event Status register is set.
MSS	Master summary status. Indicates that the generator has a reason for requesting service.
RQS	Request service. This bit is read only by executing a serial poll of the generator.

Event Status bit	Definition
OPC	Operation complete. Indicates that all operations have been completed.
RQC	Request control. Indicates that a device is requesting control. The generator will never request control, so this bit will always be 0.
QYE	Query error. Indicates that a query request was made while the generator was in deadlock.
DDE	Device dependent error. Indicates that the generator encountered an error executing a command.
EXE	Execution error. Indicates that there was an error parsing a parameter.
CME	Command error. Indicates that there was an unrecognizable command.
URQ	User request. Indicates that a front panel key has been pressed or that the front panel knob has been turned.
PON	Power on. Indicates that power has been turned off and on. This bit will always be 0 in the generator.

Bus commands

The IEEE-488.1 standard defines bus commands, which are sent to the generator with ATN true. The following table lists bus commands supported by the generator. For more detailed descriptions of these commands, see the IEEE-488.1 and 488.2 standards.

Command	Description
DCL	Device clear. Clears the input buffer and output queue, and stops parsing any commands.
SDC	Selected device clear. Same as DCL.
GTL	Go to local. Enters the local state. See “Remote/local operation” on page 171.
LLO	Local lockout. Enters the lockout state. See “Remote/local operation” on page 171.
SPE	Serial poll enable. Enables transmission of the Status Byte.
SPD	Serial poll disable. Exits the serial poll state.

Remote/local operation

The generator has complete remote/local operation as defined by the IEEE-488.1 standard. All four remote/local states (REMS, LOCS, RWLS and LWLS) are supported.

In the remote state (REMS), the generator is under remote control and messages are processed as received. The generator enters the remote with lockout state (RWLS) if the controller issues the local lockout (LLO) message to the generator. The generator enters the local state (LOCS) when the REN line goes false or the controller issues the go to local (GTL) message to the generator, or a front panel control is actuated.

In the remote with lockout state (RWLS), the generator is under complete remote control and front panel controls are disabled. The generator enters the RWLS state when the controller issues the local lockout (LLO) message to the generator. Front panel access is re-enabled when the controller issues the go to local (GTL) message to the generator.

In the local state (LOCS), the generator is under local control and all front panel controls are enabled. Any remote messages received are stored for processing when the generator enters the remote state again. The generator enters the remote state (REMS) if the REN line is true and the generator is addressed to listen.

In the local with lockout state (LWLS), the generator is under local control, and all front panel controls are enabled. Any remote messages received are stored for processing when the generator enters the remote state again. The generator enters the remote with lockout state (RWLS) if it is addressed to listen.

6 Working with Formats

Topics in this chapter:

- Overview
- Format library
- Viewing the source list of formats
- Configuring format parameters
- Format Editor Overview
- Creating a new format using the Format Editor
- Creating custom formats using the command line interface
- Format catalogs

Overview

The generator contains a library of standard formats. You can create your own formats, however, either by using the Format Editor or by entering format commands through the command line interface. You can also create format catalogs which allow you to control the formats that appear on the generator's display when you press the **Source** key.

This chapter describes the format library and provides procedures for using the generator's front panel keys, the command line interface, and the format editor to view formats, create and customize formats, and create format catalogs.

The following functions are described in this chapter:

- **Viewing the Source list of formats.** You can view the Source list of formats using the front panel or the command line interface.
- **Creating formats.** You can create new formats through the format editor or the command line interface.
- **Viewing and modifying format parameters.** You can view and edit format parameter values either through the format editor, the front panel, the command line interface, or by editing the format XML file.
- **Configuring the Source list.** You can edit the **Source** list of formats to include only those formats you use.


Format library

The generator has a built-in library of formats which are stored as XML files in any of the generator's media. This section describes three sets of naming conventions for identifying formats: 1) Composite television formats, 2) Component television formats, and 3) Computer display formats. In addition, several miscellaneous naming conventions are also described.

Composite television format names

Composite television formats apply to RF, D2, CVBS, and S-VIDEO signal interfaces. Composite television format names consist of a three to five character color coding scheme indicator followed by optional characters that indicate format adjustments.

Example



Color coding schemes

- NTSC
- PAL

Adjustments to the format

- 4x == sampling rate is four times the color sub-carrier frequency
- 44 == NTSC with color sub-carrier frequency of 4.43361875 MHz (as opposed to 3.58)
- # == sampling rate is reduced in order to make pixels square
- jp == NTSC-Japan (NTSC without 7.5 IRE setup)
- -M == PAL with 3.57561149 MHz color sub-carrier and M timing (M/PAL Brazil)
- -N == PAL with 3.58205625 MHz color sub-carrier (N/PAL Argentina, Paraguay, Uruguay)
- -N == NTSC color encoding with N timing (NTSC-N)
- -60 == PAL format that allows NTSC tape playback on PAL TV (PAL-60)
- plusKKKK == Enhanced wide-screen PALplus TV transmission system
- p == progressive video game signal (for example, NTSCp or PALp)


Common composite TV formats with sub-carriers and their respective standards:

- NTSC - ITU-R BT.470-6
- NTSC# - SMPTE 170M
- NTSC#KA - SMPTE 170M
- PAL - ITU-R BT.470-6
- PAL# - ITU-R BT.470-6
- PAL#KA - ITU-R BT.470-6

Component television format names

Component television formats are named by their vertical resolution and scanning method. These formats apply to RGB, YPbPr, YcbCr and HD-SDI video. In component television format naming, the first three or four characters indicate the active vertical lines in the format, the next characters indicate the frame tracing method, and the last two optional characters indicate the frame rate.

Example



Active vertical lines

- 480 (active lines with 525 total lines)
- 1035 (active lines with 1125 total lines)

Frame tracing methods

- p = progressive
- i = interlaced
- s = segmented frame interlace (e.g., 1080s24, where a 24p frame is segmented into two interlaced fields occurring at twice the frame rate - scene changes only between field pairs – also known as “48sF”)
- x = any – progressive, interlace, or segmented

Double clocking

- i2x = double-clocked interlace (scene may change between fields) pixels are double-clocked for DVI compatibility)

Frame rate

Frame rate is optional. If no frame rate is given, then the frame rates are assumed.

- 24 = 24 Hz
- 60 = 60 Hz


Common component TV formats

- 480pLH Component SDTV signal containing letterboxed 16x9 high-definition content
- 480pSH Component SDTV signal containing anamorphically under-sampled 16x9 content

Computer display format names

Computer display formats are assumed to use progressive scanning. In computer format naming, the first three characters indicate the vendor ID using the EISA ID (for example, IBM, SUN, VSC) or the display type, the next two characters indicate the approximate horizontal resolution, the next two digits indicate the frame rate (which will be half the field rate with interlace scanning), and the final character designates the aperture (used only when the aperture is not A).

Example



Vendor ID (EISA)

- SMT for VESA (digital) Safe Mode Timing
- DMT for VESA Standard Discrete Monitor Timing
- GTF for VESA Generalized Timing Format standard
- CEA for Consumer Electronics Association
- EIA for Electronics Industries Association (CEA)

Approximate horizontal resolution examples

- 02 for 256 pixels
- 09 for 960 pixels
- 12 for 1200 pixels
- 30 for 3072 pixels

Frame rate examples (half the field rate with interlace scanning)

- 48 for 48 Hz
- 60 for 60 Hz
- 75 for 75 Hz

Aperture (used only when the aperture is not A)

See “Aperture designators” on page 178.

Common computer display formats

- VSC1275 for Viewsonic 1280 by 1024 at 75 Hz
- DMT0685 for Discrete Monitor Timing with 680 by 480 at 85 Hz

Aperture designators

Format names may include one or two characters that describe the aperture of the display. These are listed below.

Aspect ratio

- Q = 1.00:1 Quadrate - MIL, Radiology (square, 512x512, 1024x1024)
- G = 1.25:1 Graphics workstation (5x4, 1280x1024, 1600x1280)
- A = 1.33:1 Academy (4x3, 640x480, 800x600, 1024x768, 1280x960, 1600x1200)
- B = 1.44:1 Big (13x9, IMAX™)
- T = 1.50:1 Three halves (3x2, 1152x768 Apple Computer)
- V = 1.56:1 PALplus WWS case #2 (14x9, see ITU-R BT.1119)
- D = 1.60:1 VESA CVT proposed (16x10, 1728x1080, 1280x800)
- E = 1.67:1 European film (15x9 or 5x3, 1200x720, 1280x768, 1800x1080, a.k.a. “1.66”)
- H = 1.78:1 High-definition image (16x9, 1280x720,1920x1080)
- F = 1.85:1 US film (320x173, 1280x692, 1920x1038)
- U = 2.00:1 Univisum™ (2x1, 1280x640, 1920x960)
- C = 2.39:1 CinemaScope™ (160x67, 1280x536, 1920x804, a.k.a. “2.35”, was 2.35 before 1971)

Content fitting operators

- N = Natural (do nothing)
- L = Letterbox (linear scale to fit one axis, center w/black bars in other)
- Z = Zoom (blow- up to fill destination aperture with cropping, or LI)

- S = Scope (under-sample content horizontally)
- W = Widescreen (over-sample content horizontally)
- J = Justify (non- linear horizontal expand – more near edges)
- K = Keep safe (shrink to avoid cropping – provide safe title)
- P = Pan & Scan (truncate)
- M = Mirror (horizontally – rear projection)

Other modifiers

- I = Inverse (undo operator; for example, S = Scope and SI = Inverse Scope)
- O = Orthogonally (rotate operator effect or aperture 90 degrees)
- X = Wildcard or special

Viewing the source list of formats

You can view the list of formats available in the generator using the front panel or the command line interface. Use the following procedures to view the Source (format) list.

Note: *The Source list of formats that appears on the generator's display is determined by the format path. In addition, the list may be filtered based on the interface selected and the format catalogs that are enabled. For more information about setting the path, see "Setting the generator's path" on page 18. For more information about format catalogs, see "Format catalogs" on page 229.*

To view the formats in the Source list using the front panel:

Press the **Source** key. The list of formats appears on the generator's display as shown below. To see all of the formats, press the + and - keys to scroll through the list.



To view the formats in the Source list using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Set the path to the format folder on the medium you want to view using the following command:

   ```
   FMTP /tffs0/Library/Formats // sets format path to flashmen directory
   ```

3. List the contents of the format folder by entering the following command:

   ```
   FMTQ? 1 200                 // lists the formats from 1 through 200
   ```

Configuring format parameters

Each standard and custom format is defined by a set of parameters. These parameters are categorized in the generator as either Options or Settings. You can view and modify the parameters of a format in the following ways:

- On the generator's front panel display
- On a display connected to the generator (view only)
- Through the command line interface
- In the format's XML file
- Through the Format Editor

Viewing and modifying format parameters through the front panel

Procedures for viewing and modifying the format parameters and format options through the front panel are provided below. Format options are selections that are of a binary nature, i.e. either on or off. Settings are attributes of a format that can take on a wider range of values.

Note that format setting and option changes made through the front panel do not persist through power cycles or changes in formats. If you make a change to a format parameter, then choose another format, and then go back to the format you changed, you will find that the parameter has been reset to the default value for that format.

To view and modify a format's options using the front panel:

1. Press the **Source** key and choose a format by pressing the adjacent soft key.
2. Press the **Options** key. The format options appear on the generator's display as shown below.



3. To set an option, do one of the following:
   a. To choose an option, press the soft key adjacent to the option. An asterisk (*) appears next to the option, indicating it is selected.
   b. To enable or disable an option, press the soft key adjacent to the option. A + sign indicates the option is enabled; a - sign indicates it is disabled.
   c. To set an option to a value (for example, AFD), increment the value by pressing the + key.

4. To see more options, press the **Options** key again. The following appears on the generator's display as shown below.

```
 MaxRange
 MaxRangeTV
 NomRange
```

5. To see more options, press the **Options** key again. The following appears on the generator's display as shown below.

```
*ACS              SyncOnR+
 DCS              SyncOnG+
 DSS              SyncOnB+
-Pedestal        TriLevel+
```

6. Press the **Options** key again to see additional options for testing digital displays. The following appears on the generator's display as shown below.

```
+ShotProtect    AFD:  0
*Production
 SafeAction     Action-
 SafeTitle       Title-
```


To view and modify a format's settings using the front panel:

1. Press the **Source** key and choose a format by pressing the adjacent soft key.
2. Press the **Settings** key. The format settings appear on the generator's display as shown below. Press the soft keys adjacent to the arrows to see all of the format settings. Refer to the table below to locate the setting you want to change.

```
     Video Signal    ->
      Interface      ->
  XVSI   AVSI   DVSI
<-   1      3      0 ->
```

3. To change a setting value:
   a. Position the blinking cursor on the value you want to change. To do this, press the soft key adjacent to the arrow by the setting value to move the cursor left or right until it appears on the digit you want to change.
   b. Adjust the value of the setting up or down by pressing the + or - keys.

4. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



   To save the changes, choose the **Yes** item by pressing the adjacent soft key.

   To exit without saving the changes, choose the **No** item.

   To return to the parameters screen without saving the changes, choose the **Back** item.


The following table shows the layout of the format Settings menu.

Parameter Class	Parameter Type	Parameters
Video Signal	Interface	XVSI, AVSI, DVSI
	Synchronization	SSST
	Gamma Correction	GAMA, GAMC
	Active Format	CXAR, EXAR, SXAR, EXCX, SXEX, SXCX, XAFD
	Manual Border	XLBW, XRBW, XTBH, XBBH
	Canvas	PELD, NPPP
	Analog Video	AVST, AVSS, AVSB, AVPS, AVPG, AVCS
	Analog Sync	ASSS, ASCT, EQUF
	Analog Sync Gates	ASRG, ASGG, ASBG, TSPG
	Digital Video	DVST, DVQM, NCPP, NBPC, NLNK, CTLM, BALG, PREG, DVSP, DVPT, DVSM, DVSS
	Digital Sync	DSST, DSCT
	Digital Sync Polarity	HSPP, VSPP, CSPP, FSPP, PSPP
	Digital Sync Gates	HSPG, VSPG, CSPG, PSPG, LSPG, FSPG, PCPG
Video Timing	Rates	PRAT, HRAT, VRAT, FRAT, TUNE
	Horizontal	HTOT, HRES, HBNK
	Vertical	VTOT, VRES, VBNK, SCAN, RFLD
	Horizontal Sync	HSPD, HSPW, HSPB, HVPD
	Vertical Sync	VSPD, VSPW, VSPB
	Composite Sync	HBPD, HBPW, HEPW, EQUB, EQUA, HVSA
	Frame Sync	FSPD, FSPW
	Probe Sync	PSHD, PSVD, PSPW, PSPM
Audio Signal	Interface	DASI

Parameter Class	Parameter Type	Parameters
	Encoding	DAST, NDAS, NDAC, NBPA
	Components	DAXG, DAXA
	Mix	SDMG, DADG, DALS
	Channels	DACA, DACG
Audio Timing	Sampling Rate	ARAT, BRAT

To view a format's parameters on a display connected to the generator:

1. Press the **Source** key and choose a format by pressing the adjacent soft key.
2. Press the **Content** key and choose the **Format** image. The format parameters appear on the connected display.



To view format parameters for all formats in the Source list:

1. Display the Format image as described above.

2. Enable and view image versions as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions. Each version shows the format parameters for a different format in the Source list.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

3. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0      // Disables sub images
```

Viewing and modifying format parameters via the command line

Procedures for viewing and modifying the format parameters through the command line are provided below.

To view and modify a format's options using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

2. Load the format whose parameters you want to view by entering the following command:

```
FMTL format  // Specify a valid format name
FMTU
```

3. To view options, enter the commands for the format options you want to view. For example, to view the sync configuration, enter the following command:

   ```
   ASSG?
   ```

   The generator responds with the information as shown below:

   ```
   0, 1, 0    // Indicates no sync on red, sync on green, no sync on blue
   ```

4. To modify options, enter the format commands with the new values. For example, to enable sync on red and disable sync on green, enter the following commands:

   ```
   FMTL DMT0660      // Load DMT0660 for editing
   ASSG 1, 0, 1      // Enable sync on red, disable sync on green
   FMTU              // Apply the changes to the generator
   ```

To view and modify a format's parameter settings using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

2. Load the format whose parameters you want to view by entering the following command:

   ```
   FMTL format  // Specify a valid format name
   FMTU
   ```

3. To view parameters, enter the commands for the format settings you want to view. For example, to view the horizontal resolution, vertical resolution, horizontal period, and analog video sync type, enter the following command:

   ```
   HRES?; VRES?; HTOT?; AVST?
   ```

   The generator responds with the information in sequence as shown below:

   ```
   640;480;800;2
   ```

4. To modify settings, enter the format commands with the new values. For example to modify the horizontal resolution and the horizontal sync pulse delay for DMT0660, enter the following commands:

   ```
   FMTL DMT0660       // Load DMT0660 for editing
   HRES 660           // Change horizontal res. from 640 to 660 pixels
   HSPD 10            // Change pulse delay from 16 to 10 pixels
   FMTU               // Apply the changes to the generator
   ```

Viewing and modifying format parameters by editing XML files

Procedures for viewing and modifying the format parameters by editing the format XML files are provided below.

To view and modify a format's parameter values in the format's XML file:

1. Using the Generator FTP Browser, copy the format's XML file from the generator to a PC. See "Copying files from a generator to a PC" on page 26 for instructions.
2. Open the XML file in a standard text editor.
3. To modify parameters in the XML file, do the following:
   a. Make your changes in the XML file, and then save the file under a new file name, including the .xml extension.
   b. Using the Generator FTP Browser, download the format XML file from your PC to the generator. See "Copying files from a PC to a generator" on page 24 for instructions.

   A sample format XML is shown below.

```
<?xml version="1.0" encoding="UTF-8" ?>
<DATAOBJ>
  <HEADER TYPE="FMT" VERSION="1.0" ></HEADER>
  <DATA>
    <AVPS>+7.5000000E+00</AVPS>
    <GAMA>+2.2000000E+00</GAMA>
    <AVSS>+0.7000000E+00</AVSS>
    <ASSS>+0.3000000E+00</ASSS>
    <HSIZ>+1.1200000E+01</HSIZ>
    <VSIZ>+8.3999996E+00</VSIZ>
    <HRAT>+3.1500000E+04</HRAT>
    <TUNE>+1.0000000E+00</TUNE>
    <HRAT0>+3.1500000E+04</HRAT0>
    <HRES>640</HRES>
    <HTOT>800</HTOT>
    <VRES>480</VRES>
    <VTOT>525</VTOT>
    <HSPD>16</HSPD>
    <HBPD>0</HBPD>
    <HSPW>96</HSPW>
    <VSPD>10</VSPD>
    <VSPW>2</VSPW>
    <EQUB>0</EQUB>
      .
      .    // other parameters omitted
      .
    <SXAR>+1.3333334E+00</SXAR>
    <EXAR>+1.3333334E+00</EXAR>
    <NPPP>0</NPPP>
    <EXCX>0</EXCX>
    <XLBW>0</XLBW>
    <XRBW>0</XRBW>
    <XTBH>0</XTBH>
    <XBBH>0</XBBH>
    <DVSS>+1.0000000E+00</DVSS>
    <DVPT>0</DVPT>
  </DATA>
```


```
</DATAOBJ>
```

Format Editor Overview

The Format Editor provides a graphical user interface for modifying existing formats, creating custom formats and viewing format parameters. The Format Editor is part of the generator's Web server and is accessed over an Ethernet LAN connection using a Web browser, such as Microsoft Internet Explorer. You can also test formats on the generator directly from the Format Editor.

Note: *The Format Editor has been updated with release 2.18. Releases prior to that will have the original version of the application. The information below pertains to the new Format Editor. This Format Editor requires Internet Browser version 6.x or newer. If you have Internet Browser version 5.x you will need to upgrade.*

The main screen of the Format Editor is shown below.



Format Editor - Basic Window Configuration and Operation

The Format Editor is a windowing application. You can open up many windows at one time. They can be floating or docked in the main window. The activation buttons appear in the upper right corner of a window. They are shown in the figure below.

In this figure, clicking on the left most activation button will cause the window to become an icon in the lower left corner of the Format Editor main window.

Clicking on the activation button in the center of the figure below will dock the window into the main Format Editor window such that it will occupy the entire window opening of the Format Editor.


Clicking on the right most activation button in the figure below will close the window.



Format Editor - Top Level Menus

The top level menus of the Format Editor are shown below.








The following table describes the top level menus in the Format Editor.

Menu	Description	
File		
	New Format	Opens up the New Format - Timing window. Enables you to create new formats (equivalent to clicking on the New Format activation button).
	New Report	Opens up the Report Format window (equivalent to clicking on the New Report activation button). Enables you to view list of formats and their primary parameters.

Menu	Description	
	New Source Menu	Opens up the Source Menu (equivalent to clicking on the New Source Menu activation button).
	Open	Enables you to browse to and open an xml format file on your PC. This is equivalent to clicking on the **Open** activation button.
	Save	Enables you to save an xml format file on your PC. This is equivalent to clicking on the **Save** activation button.
	Quit	Closes out the Format Editor.
Instrument		
	Connect	Enables you to establish a connection between the Format Editor and the 882E. A dialog pops up to enable you to enter the IP address of the 882E you wish to connect to.
	FTP Browser	Opens up the FTP browser application which enables you to transfer files between your host PC and the 882E generator that you are connected to.
	CMD Terminal	Opens up the CMD Terminal application which enables you to enter commands to the 882E generator that you are connected to.
Window		
	Message Log	Check box enables or disables message logging.

Format Editor - Menu Buttons

The activation buttons of the Format Editor are shown in the window below.



The following table describes the Format Editor menu buttons.

Button	Description
Connect	Clicking on this button enables you to establish a connection between the Format Editor and the 882E. A dialog pops up to enable you to enter the IP address of the 882E you wish to connect to. This is equivalent to selecting the **Instrument Connect** pull down menu.
New Format	Opens up the New Format at the Timing tab. Enables you to create new formats. This is equivalent to selecting the **New Format** from the **File** menu.
New Report	Opens up the Report Format window. This is equivalent to selecting **New Report** from the **File** menu. Enables you to view list of formats and their primary parameters.
New Source Menu	Opens up the **Source** Menu. This is equivalent to selecting **New Source** from the **File** menu.
Open	Enables you to browse to and open an xml format file on your PC. This is equivalent to selecting **Open** from the **File** menu.
Save	Enables you to save an xml format file on your PC. This is equivalent to selecting **Save** from the **File** menu.

Format Editor - New Format

This subsection defines the tabs and status panels available with the New Format screen shown below.



The table below describes the tabs available for the New Format window.

Tab	Description / Function
Timing	Selecting the Timing tab opens up an application screen that enables you to define the timing parameters for a custom format or modify the timing parameters of an existing format. (See “New Format - Timing Tab” on page 195 below for details on each of the parameters.)
General	Selecting the General tab opens up an application screen that enables you to define the sync, level, pixel depth, gamma and pedestal parameters for a custom format or modify these parameters of an existing format. (See “New Format - General Tab” on page 199 below for details on each of the parameters.)
Digital Video	Selecting the General tab opens up an application screen that enables you to define the digital video parameters for a custom format or modify these parameters of an existing format. (See “New Format - Digital Video Tab” on page 207 below for details on each of the parameters.)

Tab	Description / Function
Digital Audio	Selecting the General tab opens up an application screen that enables you to define the digital audio parameters for a custom format or modify these parameters of an existing format. (See “New Format - Digital Audio Tab” on page 209 below for details on each of the parameters.)
AFD	Selecting the General tab opens up an application screen that enables you to define the AFD parameters for a custom format or modify these parameters of an existing format. (See “New Format - AFD Tab” on page 212 below for details on each of the parameters.)

The table below describes the Problem List status panels for the New Format window.


Entity	Type	Description / Function
Unit	Pull-down menu	Enables you to select the type of 882 unit that you are viewing problems for. Options are: • C/CA - 882C or 882CA • D - 882D • E - 882E • EA/DP - 882E (HDMI), 882EA (HDMI), 882E (DisplayPort) •
Interface	Pull-down menu	Enables you to select the type of interface you are defining a format for. Options are: • Analog - Component analog (RGB or YPbPr) • CVBS - Composite Video Baseband Signal • S-Video - Y/C • DVI - DVI from the DVI output • HDMI-D - DVI from the HDMI output • HDMI-H - HDMI • SDI - SDI and HDSDI
Instrument (Connection Status)	Status text field	Shows the current connection status.
Error log		
	Red Dot	Indicates that an error has occurred. In the future warnings will be supported which will be yellow.
	# (Number)	An integer assigned to the error in the log list. This is a number assigned in sequence as the errors occur.
	Error #	The 882 error number for a particular error type. The error list can be found in “Error code descriptions”.
	Description	A text description of the error.

New Format - Timing Tab

The Timing window of the Format Editor Timing is shown below. This window is activated by pressing the Timing tab.



The main panel of the Timing tab is shown below.




The table that follows describes each of the fields in the main panel of the Timing tab.

Entity	Field	Description / Function
Pixel Rate		Sets the pixel rate in pixels (Machine) or microseconds (Time) of the format.
Horizontal		
	Rate	The horizontal line rate of the format. The HRAT is the fundamental frequency in the 882. Parameter: HRAT.
	Tune	The tunning value of the base frame rate (base/tune) for NTSC color broadcast compatibility. The tuning value is base/1.001.
	Base	The base frame rate.
	Active	The number of active pixels (machine) or microseconds (Time) of the horizontal video. Parameter: HRES.
	Blank	The number of active pixels (Machine) or microseconds (Time) of the horizontal video. This parameter is calculated.
	Total	The total number of active pixels (Machine) or microseconds (Time) of the horizontal video. The total is the sum of the Active and Blanking. Parameter: HTOT.
	Pulse Delay	The number of pixels (Machine) or microseconds (Time) in the blanking preceding the horizontal sync pulse. Parameter: HSPD.
	Pulse Width	The number of pixels (Machine) or microseconds (Time) of the horizontal sync pulse. Parameter: HSPW.
Vertical		
	Rate	The vertical frame rate of the format. Parameter: VRAT.
	Active	The number of active lines (machine) or milliseconds (Time) of the vertical video. Parameter: VRES
	Blank	The number of active lines (Machine) or milliseconds (Time) of the vertical video. This parameter is calculated.
	Total	The total number of active lines (Machine) or milliseconds (Time) of the vertical video. The total is the sum of the Active and Blanking. Parameter: VTOT.
	Pulse Delay	The number of lines (Machine) or milliseconds (Time) in the blanking preceding the vertical sync pulse. Parameter: VSPD.
	Pulse Width	The number of lines (Machine) or milliseconds (Time) of the vertical sync pulse. Parameter: VSPW.
 (green calculator)		Indicates that the value in the field is calculated by the Format Editor.
 (red calculator)		Indicates that the value in the field is calculated by the Format Editor, and that the new value has replaced the value previously in the field.

Entity	Field	Description / Function
		Indicates that the values in this field are settable in the current configuration.
Red Field		Indicates that the fields are in the read only mode. These fields will show a change in value when the value in a field affecting these fields is modified.
Green Field		Indicates that the fields are in the read/write mode. When you make a change and hit the enter key new values will be calculated.
Black Field		Indicates that the fields can be modified directly and are calculated when other related fields are modified.
Gray Field		Indicates that the fields are disabled because the Entry Units are selected such that the fields are not used. However these fields will show a change in value when the value in a field affecting these fields is modified.

New Format - Timing Tab (Bottom Panel)

The bottom panel of the Timing tab in the Format Editor is shown below.



The table that follows describes each of the fields in the panel.

Field	Description
Serration with Adjustment	Sets the length of the serration period on composite video to a given number of pixels from the format's nominal default value as required by some military STANAG video formats. Valid range is in pixels with integer values from 0 to less than HSPW in pixels. Parameter: HVSA
H to V Delay	Displays the current value for the pixel delay between horizontal and vertical sync pulses. Parameter: HVPD?
Horizontal Broad Pulse Delay	
Equalization Before	Establishes the width of the equalization interval before the vertical sync pulse in each field whenever a serrated and equalized sync type is selected via either ACST or DSCT command and the SSST command. Valid values are 0 and number of lines after vertical sync before video. Parameter: EQUB
Equalization After	Establishes the width of the equalization interval after the vertical sync pulse in each field whenever a serrated and equalized sync type is selected via either ACST or DSCT command and the SSST command. Valid values are 0 and number of lines after vertical sync before video. Parameter: EQUA.

New Format - Timing Tab (Right Side Panel)

The right side panel of the Timing tab in the Format Editor is shown below. The table that follows describes each of the fields in the panel.




New Format - Timing (Right Side Panel)

Entity	Parameter	Description / Function
Entry Field		
	Machine	Activates the fields in the timing tab window such that the timing parameter values are expressed and settable in terms of pixels and lines.
	Time	Activates the fields in the timing tab window such that the timing parameter values are expressed and settable in terms of time increments such as milliseconds and microseconds.
Scan Type		
	Progressive	Sets the format scan type to Progressive. Parameter: SCAN = 2
	Interlace	Sets the format scan type to Interlaced. Parameter: SCAN = 1
check boxes		
	Back Porch	Toggles the Pulse Delay field so that the value is provided for the back porch rather than the front porch.
	Clock Pulse	Enables and disables the pixel clock pulse output on generators that have a pixel clock output available. The pixel clock output appears on the special sync BNC connector. Parameter: PCPG.

Entity	Parameter	Description / Function
	PreEmphasis	Enables and disables adding pre-emphasis to the Open LVDI digital outputs on generators that support LVDI outputs.
	DC Balance	Not used
	Flat Front Porch	Determines if composite sync will have all equalization pulses removed in the vertical sync front porch (delay) period as required by certain military HOBO and Maverik video formats. Parameter: EQUF.
	Tri-Level Sync	Enables or disables Tri-Level sync. Parameter: TSPG
	Repeat Field	Determines if identical video information is output for each field of an interlaced (SCAN = 2) format. Parameter: RFLD.

New Format - General Tab

The Format Editor General tab is shown below. The table that follows describes each of the fields in the tab.



New Format - General Tab (Top Left Panel)

The top left panel of the General tab in the Format Editor is shown below.



The table that follows describes each of the fields in the top left panel of the General tab.

Field / Entity	Type	Description / Function
Horizontal	Entry field	The horizontal aperture of the display under test.
Vertical	Entry field	The vertical aperture of the display under test.
Unit Size	Radio Buttons:	
	inches	Selects the unit size of the Horizontal and Vertical Size entities to be expressed in inches.
	mm	Selects the unit size of the Horizontal and Vertical Size entities to be expressed in millimeters.

New Format - General Tab (Top Right Panel)

The top right panel of the General tab in the Format Editor is shown below.




The table that follows describes each of the fields in the top right panel of the General tab.

Field / Entity	Type	Description / Function
Pixel Depth	Pull-down menu	Establishes the number of data bits that represent each active pixel in video memory (frame buffer). Parameter: PELD. There are three settings: Default - uses the generator default 8 - 8 bits-per-pixel (256 colors) 24 - 24 bits-per-pixel (16,777,216 colors)

New Format - General Tab (Center Panel)

The center panel of the General tab in the Format Editor is shown below.



The table below describes the pull-down menus in the center panel of the General tab.


Field / Entity	Description / Function
Color Encoding	Sets the colorimetry of the format. The parameter is AVST or DVST. The following are the selections: • Default • Analog Grayscale YYY • Analog Component RGB • Analog Composite with Color Kill • Analog Composite with Subcarrier • Analog Component YPbPr SDTV • Analog Component YPbPr HDTV Legacy • Analog Component YPbPr HDTV Modern • Analog Component YPbPr Betacam • Analog Component Monochrome • Digital Direct VI MDA • Digital Direct RGB • Digital Direct RGBI CGA • Digital Direct RrGgBb EGA • Digital Component YYY • Digital Component RGB • Digital Component YCbCr SDTV (ITU-R BT.601-5) • Digital Component YCbCr HDTV Legacy (SMPTE 240M) • Digital Component YCbCr HDTV Modern (ITU-R BT.709-5) • Digital BT.601 xvYCC • Digital BT.709 xvYCC
Sync Type	Sets the sync type of the format. The parameter is SSST. The following are the selections: • (0) None • (1) DSS - Digital Separate Sync • (2) DCS - Digital Composite Sync • (3) ACS **-** Analog Composite Sync • (4) ACS, DSS - Analog Composite Sync, Digital Separate Sync • (5) ACS, DCS - Analog Composite Sync, Digital Composite Sync • (6) ACS, DCS, DSS - Analog Composite Sync, Digital Composite Sync and Digital Separate Sync • (7) DPMS OFF • (8) DPMS Suspend • (9) DPMS Standby • (10) DPMS ON

Field / Entity	Description / Function
ACS Type	Sets the analog composite sync type of the format. The parameter is ASCT. The following are the selections: • None • American ORed • American Single Serrated • American Double Serrated (ref SMPTE 170M NTSC) • Australian AS 493.1-200X CS Serrated • European ORed • European Double Serrated (ref ITU-R BT.470-6 PAL) • SMPTE 296M-EIA/CEA • HDTV Double Serrated (ref SMPTE 296M) • SMPTE 295M-EIA/CA • HDTV Double Serrated (ref SMPTE 295M) • SMPTE 274M-EIA/CA • HDTV Double Serrated (ref SMPTE 240M, 260M, 274M)
DCS Type	Sets the digital composite sync type of the format. The parameter is DSCT. The following are the selections: • None • American ORed • American Single Serrated • American Double Serrated (ref SMPTE 170M NTSC) • Australian AS 493.1-200X CS Serrated • European ORed • European Double Serrated (ref ITU-R BT.470-6 PAL)

Field / Entity	Description / Function
DSS Type	Sets the digital composite sync type of the format. The parameter is DSST. The following are the selections: • None • American Separate • European Separate • American Separate HDTV • European Separate HDTV • Japanese Separate HDTV • Australian AS 493.1-200X HS & VS • IEC 62315-1 Australian AS 493.1-200X HS & VS
SubCarrier	Sets the composite video subcarrier type. Only valid when the color encoding parameter (AVST) is set to Analog Composite with Subcarrier. The parameter is AVSC. The following are the selections: • None • NTSC M • NTSC 443 • PAL BDGHI • PAL NC • PAL N • PAL M • PAL 60

New Format - General Tab (Right Panel)

The right panel of the General tab in the Format Editor is shown below.




The table below describes the entities and fields of the right-side panel of the General tab.

Field / Entity	Entity Type	Description / Function
Analog Video Swing	Entry field	Sets the analog video swing.
Analog Sync Swing	Entry field	Sets the analog sync swing.

Field / Entity	Entity Type	Description / Function
Gamma	Check box	Enables or disables Gamma. Used with the entry field below. Parameter: GAMC.
	Entry field	Enables you to set the Gamma once the Gamma check box above is enabled (checked). The allowable ranges of values is 0.1 to 10.0. Parameter: GAMA.
Pedestal	Check box	Enables or disables the Pedestal. Used with the entry field below. Pedestal is only supported on NTSC format types. Parameter: AVPG.
	Entry field	Enables you to set the Pedestal once the Pedestal check box above is enabled (checked). The allowable ranges of values is 0 IRE to 100 IRE. Parameter: AVPS.
Analog Cal. Mode	Pull-down select	Sets the analog calibration mode. Determines how the generator tests and calibrates its analog video outputs Parameter: AVCM. The following are the selections: • Interpolate • Measure Interpolate • Measure Set Absolute • Test Levels
Analog Color Order	Pull-down select	Sets the mapping of the analog video colors to the video output connections. Parameter: AVCO. The following are the selections: • RGB - R to R, G to G, B to B (default) • RBG - R to R, B to G, G to B • GRB - G to R, R to G, B to B • GBR - G to R, B to G, G to B • BRG - B to R, R to G, G to B • BGR - B to R, G to G, R to B

New Format - General Tab (Bottom Panel)

The bottom panel of the General tab in the Format Editor is shown below.




The table below describes the gating functions of the right-side panel of the General tab.

Field / Entity	Entity Type	Description / Function
Analog Sync Gate	Select buttons	Enables you to put the analog composite sync on one of the components when analog composite sync is selected as the sync type using the SSST command. Multiple selections can be made.
		R Puts the analog composite sync on the Red component. Parameter: ASSG.
		G Puts the analog composite sync on the Green component. Parameter: ASSG.
		B Puts the analog composite sync on the Blue component. Parameter: ASSG.
Digital Sync Gate	Select buttons	
		H Enables and disables the digital horizontal sync output. To use digital horizontal sync, the digital separate H and V sync must be selected with the SSST command. Parameter: HSPG.
		V Enables and disables the digital vertical sync output. To use digital vertical sync, the digital separate H and V sync must be selected with the SSST command. Parameter: VSPG.
		C Enables and disables the digital vertical sync output. To use digital composite sync, the digital composite sync must be selected with the SSST command. Parameter: CSPG.
Digital Sync Polarity	Select buttons	
		H Determines whether the digital horizontal sync pulse polarity is positive going or negative going. To set the digital horizontal sync polarity, digital horizontal sync must be gated on with the HSPG command. Parameter: HSPP.
		V Determines whether the digital vertical sync pulse polarity is positive going or negative going. To set the digital vertical sync polarity, digital vertical sync must be gated on with the VSPG command. Parameter: VSPP.
		C Determines whether the digital composite sync pulse polarity is positive going or negative going. To set the digital composite sync polarity, digital composite sync must be gated on with the CSPG command. Parameter: CSPP.
Video Gate	Select buttons	Enables you to gate ON or OFF any of the video components. More than one can be selected.
		R Gates ON or OFF the Red component/
		G Gates ON or OFF the Green component/
		B Gates ON or OFF the Blue component/

New Format - Digital Video Tab

The Format Editor Digital Video tab is shown below.




The table that follows describes each of the fields in the Digital Video tab.

Entity / Field	Type	Description / Function
Range	Entry field	
Clocks per Pixel	Entry field	Specifies the number of clocks per pixel (double clocking factor for whole line. This parameter is used to boost the clock rate to the minimum supported by TMDS interface. Allowable values are: • 1 - one clock per pixel • 2 - two clocks per pixel Parameter: NCPP.
Pixels per Pixel	Entry field	Specifies the number of pixels per pixel. This parameter specifies the pixel repetition factor for the active portion of the line. Allowable values are: • 0 - disables repetition mode • 1 to 10 - enables pixel repetition (inserts extra left and right pixel repetition bars) Parameter: NPPP.

Entity / Field	Type	Description / Function
AVI Video Identification Code	Entry field	The digital video code corresponding to the EIA/CEA-861 standard. Parameter: DVIC.
Number of Links	Radio button	
		1 Sets the number of links to 1 by the DVI output.
		2 Sets the number of links to 2 for the DVI output
		Parameter: NLNK
Protocol Type	Pull-down select	Specifies which digital output is active through the HDMI interface. Allowable values are: • DVI - Enables DVI mode out the DVI output or the HDMI output. • HDMI - Enables HDMI mode out the HDMI output. Parameter: XVSI
Sampling Mode	Pull-down select	Specifies the digital sampling mode. Allowable values are: • Default - RGB 4:4:4. • 4:2:2 - Color difference components are sampled at half the pixel rate. Luminance is sampled at the full pixel rate. Requires that the YCbCr color mode be selected with the DVST command. • 4:4:4 - Color difference components and luminance component is sampled at the full pixel rate. Requires that the YCbCr color mode be selected with the DVST command. Parameter: DVSM
Bits per Color Component	Pull-down select	Specifies the number of bits per component. Allowable values are: • Default - Use the default setting in the generator. • 6 - Six bits per component. • 8 - Eight bits per component. • 10 - Ten bits per component. • 12 - Twelve bits per component. Parameter: NBPC
Video Swing 1	Entry field	Sets the digital video voltage swing for the HDMI output 1. The range of values is: 0.150 to 1.560 Parameter is: DVSS
Video Swing 2	Entry field	Sets the digital video voltage swing for the HDMI output 2. The range of values is: 0.150 to 1.560 Parameter is: DVSS

New Format - Digital Audio Tab

The Format Editor Digital Audio tab is shown below. The table that follows describes each of the fields in the tab.




The table below describes each of the fields in the Digital Audio tab.

Field	Type	Description / Function
Signal Interface	Pull-down select	Sets the digital audio signal interface. The valid values are: • None - Use HDMI. • SPDIF. • AES3 (not used). • AESid (not used). • TOSlink optical (not used). • MiniPlug (not used). Parameter is: DASI.
Signal Type	Pull-down select	Sets the digital audio signal type. The valid values are: • None • IEC 60958-3 Consumer LPCM. • IEC 60958-4 Professional LPCM. • IEC 61937 w/AC-3 (Dolby Digital). • MP2 (Video CD) (not used). • MP3 (MPEG1 Layer 3) (not used). • MPEG2 5.1 channels Advanced Audio Coding (AAC) • MPEG2 7.1 channel CBR or VBR • IEC 61937 w/'DTS • ATRAC Parameter is: DAST.
Level Shift	Entry field	Sets the digital audio level shift value. The valid values are: 0 - 15 dBFS. Parameter is: DALS.
Sampling Rate	Entry field	Sets the digital audio sampling rate. The valid values are: • 32.0kHz • 44.1kHz • 48.0kHz • 88.2kHz • 96.0kHz • 176.4kHz • 192.0kHz Parameter is: ARAT.
Number of Streams	Entry field	Sets the digital audio streams. The valid value is: 1. Parameter is: NDAS.
Number of Channels	Entry field	Sets the digital audio sampling rate. The valid values are: 2 through 8 Parameter is: NDAC.

Field	Type	Description / Function
Bits per Sample	Pull-down select	Sets the digital audio sampling rate. The valid values are: • 16 • 20 • 24 Parameter is: NBPA.
Contents Gated	Entry field	Sets the digital audio content gate. The valid values are: 0 through 4095. Refer to EIA/CEA-861-x. Parameter is: DAXG.
Contents Available	Entry field	Sets the digital audio content available. The valid values are: 0 through 4095. Refer to EIA/CEA-861-x. Parameter is: DAXA.
Mix Down Gate	Check box	Sets the digital audio down-mix gate. The valid values are: enabled or disabled. Parameter is: DADG.
Channels Available	Entry field	Sets the digital audio channels available. The valid values are: 0 through 255. Refer to EIA/CEA-861-x. Parameter is: DACA.
Channels Gated	Entry field	Sets the digital audio channel gate. The valid values are: 0 through 255. Refer to EIA/CEA-861-x. Parameter is: DACG.

New Format - AFD Tab

The Format Editor AFD tab is shown below. The table that follows describes each of the fields in the tab.




The table that follows describes each of the text entry fields in the AFD tab.

Heading	Field	Description / Function
Active Format		
	Content Aspect Ratio	Sets the aspect ratio of the source image content. The valid parameter range is: 0.75 to 2.39. Parameter: CXAR.
	Embedded Aspect Ratio	Sets the aspect ratio of the extended image content. The valid parameter range is: 0.75 to 2.39. Parameter: EXAR.
	Signal Aspect Ratio	Sets the aspect ratio of the video signal image content. The valid parameter range is: 0.75 to 2.39. Parameter: SXAR.

Heading	Field	Description / Function
	Extended From Content Apert. Map	Enables you to set the mapping type for mapping CXAR-shaped image content into the extended EXAR-shaped aperture. Parameter: EXCX
	Signal from Extended Apert. Map	Enables you to set the mapping type for mapping EXAR-shaped image content into the SXAR-shaped signal interface. Parameter: SXEX
Bars		
	Left	Sets the left side letterbox bars in pixels.
	Right	Sets the right side letterbox bars in pixels.
	Top	Sets the top letterbox bars in pixels.
	Bottom	Sets the bottom letterbox bars in pixels.

Format Editor - New Report

This subsection defines the New Report screen. The contents of the New Report tab is shown below.





The table below describes the top selection panels for the New Report activation button

Entity	Type	Description / Function
Instrument (Connection Status)	Status text field	Shows the current connection status.
Connect	Activation Button	Enables you to connect to an 882 generator. When clicked a dialog box will pop up enabling you to specify an IP address to connect to.
Type	Pull-down menu	Always set to Format.
Path	Entry Field	The path to the directory where the list of formats used to configure a format list.
Edit Path	Activation Button	Enables you to change the path to a list of formats.

The table below describes the activation buttons available for the New Report screen.

Button	Description / Function
Configure	Clicking on the Configure button will open up a dialog box that enables you to configure which format parameters appear in the report and in what order.
Fill / Cancel	Clicking on the Fill activation button will cause the Format Editor application to begin loading the formats from the list that the Path is set to. The completion status is shown below the list. The Cancel button on the lower right enables you to halt the filling (reading) of the formats from the list in the directory that the path parameter is set to.
Generate HTML Report	Clicking on this button will cause the Format Editor application to generate an HTML report of the list of formats. A dialog box pops up to allow you to specify a location and name on your PC.
Edit Format	This activation button is only enabled when you select a format from the list. Clicking on this button will open up the Format Editor window at the Timing tab.
Use Format	This activation button is only enabled when you select a format from the list. Clicking on this button activate this format in the connected 882 generator.

The table below describes the report fields available for the New Report screen.

Report Parameter	Parameter Description
Name	The format name.
Digital Video Identification Code	Writes the specified Video Identification Code (VIC) into the AVI InfoFrame.
Horizontal Total	The total number of active pixels (Machine) or microseconds (Time) of the horizontal video. The total is the sum of the Active and Blanking. Parameter: HTOT.
Horizontal Active	The number of active pixels (machine) or microseconds (Time) of the horizontal video. Parameter: HRES.
Horizontal Sync Pulse Polarity	Indicates whether the digital horizontal sync pulse polarity is positive going or negative going. Parameter: HSPP.
Horizontal Rate (kHz)	The horizontal line rate of the format. The HRAT is the fundamental frequency in the 882. Parameter: HRAT.
Vertical Total	The total number of active lines (Machine) or milliseconds (Time) of the vertical video. The total is the sum of the Active and Blanking. Parameter: VTOT.
Vertical Active	The number of active lines (machine) or milliseconds (Time) of the vertical video. Parameter: VRES.
Vertical Sync Pulse Polarity	Indicates whether the vertical sync pulse polarity is positive or negative going. Parameter: VSPP.
Vertical Rate	The vertical frame rate of the format. Parameter: VRAT.
Sync Type	Indicates the sync type of the format. The parameter is SSST.

The screen below shows the Format Table Configuration Screen. This screen enables you to configure the fields for the format report.




The table below describes the fields and buttons for the Table Configuration Screen.

Entity	Description / Function	
Column Choices	Configuration Field	Provides a list of format parameters to select and move to the report.
Column in the Table	Configuration Field	Shows the current list of format parameters that will appear in the report. The format parameters will appear in the order (top to bottom / left to right) in the report.
Add	Activation Button	Enables you to move format parameters from the Column Choices to the Columns in the Table (that will appear in the reports).
Remove	Activation Button	Enables you to remove format parameters from the Columns that will appear in the table.
Remove All	Activation Button	Enables you to remove all the format parameters currently shown in the Column in the Table field.
Move Up	Activation Button	Enables you to change the order (move up) the selected format parameters in the Columns in Table that will appear in the format report. The top most parameters will appear in the left most side of the report.
Move Down	Activation Button	Enables you to change the order (move down) the selected format parameters in the Columns in Table that will appear in the format report. The top most parameters will appear in the left most side of the report.

Format Editor - New Source Menu

This subsection defines the New Source Menu dialog box. The New Source Menu dialog box is shown below:



The table below describes the top panels fields, activation buttons and pull down menus.


Entity	Type	Description / Function
Instrument (Connection Status)	Status text field	Shows the current connection status.
Connect	Activation Button	Enables you to connect to an 882 generator. When clicked a dialog box will pop up enabling you to specify an IP address to connect to.
Save and Use	Activation Button	Enables you to save the format source list to the generator you are connected to and then apply this list to the current generator configuration.
Reset Source Menu	Activation Button	
Type	Pull-down menu	Always set to Format.
Path	Entry Field	The path to the directory where the list of formats used to configure a source list.
Edit Path	Activation Button	Enables you to change the path to a list of formats.

The table below describes the main panels fields, of the New Source Menu.

Entity	Type	Description / Function
Directory Listing	Configuration Field	Provides a list of formats to select and move to a particular (set by the Path entry field) directory on the 882 generator.
Source Menu Listing	Configuration Field	Shows the current list of formats that will appear in a particular directory (set by the Path entry field) on the 882 generator.
Add	Activation Button	Enables you to move formats from the Directory Listings to the Source Menu Listing fields (formats that will appear a particular format directory i.e. set by the Path entry field).
Remove	Activation Button	Enables you to remove formats from the Source Menu Listing fields so that they will not appear in a particular format directory (set by the Path entry field).
Remove All	Activation Button	Enables you to remove all the formats currently shown in the Source Menu Listing field.
Move Up	Activation Button	Enables you to change the order (move up) the selected formats in the Source Menu Listing field that will appear in a particular format directory (set by the Path entry field). The top most formats will appear first in the list.
Move Down	Activation Button	Enables you to change the order (move down) the selected formats in the Source Menu Listing field that will appear in a particular format directory (set by the Path entry field). The top most formats will appear first in the list.


Format Editor - Open

This subsection defines the Open [File] dialog box. The Open dialog box is shown below. This enables you to open an existing format file either from your PC (**Local** tab) or from the 882 instrument (**Remote** tab).



Format Editor - Save

This subsection defines the Save [File] dialog box. The Save dialog box is shown below. You use the Save function to store a format that you have defined. You can either save it to your PC (**Local** tab) or the 882 instrument (**Remote** tab).




Creating a new format using the Format Editor

The procedure below describes how to create a new format using the Format Editor.

To create a new format using the Format Editor:

1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.



   Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*


2. Select **Format Editor**. The Format Editor appears.

3. Click **New Format**. The Timing tab of the format definition page appears as shown below.



4. Open an existing file to work from by clicking on the **Open** activation button near the top of the window.

   The open file dialog box appears as shown below.



   You can either load a file from your PC or from the 882 test instrument by selecting the appropriate tab: 1) **Local** (host PC) or 2) **Remote** (882).

   If you are loading a format from the 882 instrument, you will need to make sure that the path is pointing to the directory where the format you wish to use as a base format is stored at. If it is not you will have to edit the path by clicking on the **Edit Path** activation button on the right side of the **Path** field.

5. Navigate and select a format file to use as a starting point for defining your new format or to make simple modifications on an existing format.

6. The format parameters of the selected format will appear in the new format **Timing** window as shown below.

7. Modify the parameters as required for the new format. You can reference the parameter definitions in the subsections above "Format Editor Overview" on page 189. The following guidelines will help you modify the format parameters.

   - There are parameter values that you may want to change on multiple tabs: 1) Timing "New Format - Timing Tab" on page 195, 2) General "New Format - General

Tab" on page 199, 3) Digital Video "New Format - Digital Video Tab" on page 207, 4) Digital Audio "New Format - Digital Audio Tab" on page 209.

- When selecting a parameter to modify on the **Timing** tab, ensure that the value is editable. To be editable, the field either needs to have a pencil icon next to it or a black field background. Gray fields are disabled for editing. Fields in red (with the calculator icon) cannot be modified. However you can change whether a field can be modified by clicking on the calculator icon which will cause it to change to a pencil icon allowing you to change its value.
- Upon modifying a format value hit the enter key to invoke the change. The Format Editor applies the new value to the timing algorithm and updates any values dependent on the value you entered (or changed).

  For example, to change the horizontal resolution to 660, enter the value in the **Active** field under Pixels in the Horizontal area.

  You will notice that the Format Editor has calculated and written values to the **Blank** and **Period** fields as indicated by the red calculator () symbol. Although the Period value has not changed, the Format Editor still indicates it is a calculated value by displaying the red calculator.
- To apply the format settings on the generator, click the **Use** activation button on the lower right side.


8. Save new format.

   a. Click the **Save** activation button or the select **Save** from the **File** pulldown menu to save the format. The save dialog box appears as shown below.

   a. Enter new format name in **File Path** field.

   You can either save it to your PC (**Local** tab) or the 882 instrument (**Remote** tab).

Note: *It is recommended that you save custom formats in a directory on the PCcard because of file storage limitations in the flash memory.*



Creating custom formats using the command line interface

There are two methods for creating formats through the command line interface. The first method is to use the FMTN command to set all format parameters in the format buffer to their default values, and then modify each value. The second method is to select an existing format to use as a template for the new format, and then modify only the values needed to create the new format. When using this method, you can save the new format under a new name or the existing name.

Independent of the method you choose, you can enter each command interactively or create a text file containing all the commands you want to issue, and then download the text file to the generator. See “Configuring the generator’s serial port” on page 32 for more information about sending commands to a generator.

The FMTN command is used in creating a new format. This command sets all of the format parameters to known, default values. For a list of the parameters and their default values, see “FMTN” on page 1003. Use the following procedure to create a new format using interactive commands.

To create a new format using the command line interface:

1. Establish a session with the generator using HyperTerminal over a serial connection or Telnet over an Ethernet LAN. For instructions, see “Establishing a terminal session with the generator” on page 31 and “Establishing a Telnet session with the generator” on page 34.
2. Set the format path to the medium where you want the new format stored using the following command:

   ```
   FMTP /tffs0/Library/Formats  // sets format path to flashmem directory
   ```

3. Enter the following commands to initialize all parameters to default values and begin a format editing session:

   ```
   FMTN        // initializes all parameters to default values
   FMTB        // begins a format editing session
   ```

4. Enter the format parameter commands in sequence to set the values for the new format.

   ```
   HRES 654    // sets the horizontal resolution to 654 pixels
   .
   .           // other format parameters
   .
   HTOT 720    // sets the horizontal total to 720 pixels
   ```

   Note: *You do not need to enter a parameter value if it matches the FMTN default setting. You can query a parameter to determine its current value.*

5. End the editing session and save the new format using the following commands:

   ```
   FMTE                  // ends a format editing session
   ```

```
FMTA new_fmt_name      // saves format as new specified name
```

Format catalogs

Scrolling through all of the available formats on the Source list can be time consuming. This is particularly true if you regularly use only a few formats that may be scattered throughout the list. You can set up the generator to show only the formats you want, in the order you want, when you browse through the Source list.

The generator's format library is comprised of a set of format catalogs. A format catalog is an XML file that lists related format names. When a catalog is enabled, the format names in the catalog appear on the Source list.

The generator is configured with a default set of catalogs in the Source library. Each catalog represents a set of formats categorized per testing application. You can configure the generator to show only the formats contained in the catalogs you use regularly. Furthermore, you can create your own catalogs and enable them.


With 2.5.x an enhancement has been made to the format catalog function. You can now configure the generator such that your custom formats appear in the Source list along with the 882's default formats. Use the following procedures to create and enable format catalogs.

Using format catalogs


Use the following procedures to enable and disable format catalogs.

To enable catalogs in the Source library using the front panel:

1. Press the **Source** key. The list of formats appears on the generator's display.
2. Press the **Options** key repeatedly until the Library folder appears on the generator's display as shown below:



3. Choose the **Library** item by pressing the adjacent soft key. The format library appears as shown below. Each item in the format library is a format catalog.



4. Press the soft key adjacent to a catalog to enable or disable it. A + sign next to the item indicates the item is enabled; a - sign indicates it is disabled.

   For example, to see only the VESA formats when you press the **Source** key, disable all catalogs except DMT and CVT.

5. Press the **Source** key to see the formats in the selected catalogs.

Creating format catalogs

Use the following procedures to create format catalogs.

To create a new format catalog:

Note: *Format catalogs are created using the command line interface. Although the catalog itself is a file, you will use the Directory (DIR) commands to create the file.*

1. Determine the formats you want to include in your catalog. For example, to create a catalog for testing computer CRTs, you might include the following formats:

```
DMT0660     DMT0659
DMT00675    DMT0685
DMT0856     DMT0860
```

2. Establish a session with the generator using HyperTerminal over a serial connection or Telnet over an Ethernet LAN. For instructions, see "Establishing a terminal session with the generator" on page 31 and "Establishing a Telnet session with the generator" on page 34.

3. Verify or set directory path is set to the FormatLib directory using the following command:

```
DIRP?           // to view the current path
or...
DIRP /tffs0/Library/FormatLib // to set the path
```

4. Create the catalog by entering the following commands:

```
DIRN Vesa1      // creates a catalog named Vesa1
DIRT Source     // identifies new catalog as a source catalog
DIRB            // begins a directory editing session
NAMI 1 /tffs0/Library/Formats/DMT0660  // adds DMT0660 to catalog
 .
 .              // add other formats
 .
NAMI 6 /tffs0/Library/Formats/DMT0860  // adds DMT0860 to catalog
DIRE            // ends the directory editing session
DIRA Vesa1      // saves the catalog
DIRL Vesa1      // loads the catalog
DIRU            // applies the catalog
```

   When you press the **Source** key, the formats in the catalog you created appear in the Source list.

Note: *If other catalogs are also selected, the Source list will include the formats in those catalogs as well.*

Note: *If you power cycle the generator you will have to reinstate the format catalogs by loading with DIRL and using it with DIRU.*

To create a format catalog with both custom formats and default formats:

1. Create your custom formats using either the command line "Creating custom formats using the command line interface" on page 227 or the Format Editor "Creating custom formats using the Format Editor" on page 186.
2. Set the format path either through the Format Editor or the command line with the FMTP command "Setting the generator's path" on page 18 and shown below:

   ```
   FMTP /tffs0/library/userdata
   ```

3. Save the custom format in the directory pointed by the current format path.
4. Enable the User Source library.
   a. Press the Source key
   b. Press the Options key repeatedly until the Library listing is shown and select Library.
   c. Enable the User catalog by pressing the adjacent softkey such that it has a plus (+) sign next to it.

   The custom formats that you saved in the Userdata directory will now appear in the Source list with other default formats that have been enabled.

To remove a format from a format catalog:

1. Establish a session with the generator using HyperTerminal over a serial connection or Telnet over an Ethernet LAN. For instructions, see "Establishing a terminal session with the generator" on page 31 and "Establishing a Telnet session with the generator" on page 34.
2. Remove a format from a format catalog by entering the following commands:

   ```
   DIRL Vesa1      // loads the catalog
   DIRT Source
   DIRB            // begins a directory editing session
   NAMK /tffs0/Library/Formats/DMT0660 // deletes DMT0660
   Or...
   NAMY 1          // deletes first format in catalog
   DIRE            // ends the directory editing session
   DIRS            // saves the catalog
   DIRU            // applies the catalog
   ```

Deleting format catalogs

You can delete format catalogs either through the command line or through the FTP Browser. Procedures for both methods are provided below.

To delete a format catalog through the command line:


1. Establish a session with the generator using HyperTerminal over a serial connection or Telnet over an Ethernet LAN. For instructions, see “Establishing a terminal session with the generator” on page 31 and “Establishing a Telnet session with the generator” on page 34.
2. Delete a format catalog by entering the following command:

   ```
   DIRK /tffs0/Library/FormatLib/Vesa1.xml // deletes catalog named Vesa1
   ```

3. Power cycle the generator.


To delete a format catalog through the Generator FTP Browser:

1. Access the source generator’s Virtual Front Panel. See “Front panel interface” on page 10.



2. From the **Options** menu (upper left corner of the Virtual Front Panel), choose the **FTP Browser** menu item. The Generator FTP Browser appears.
3. In the **Instrument Files** area, click the down arrow and select the **tffs0**. This is the generator’s flash memory.
4. Double click the **Library** folder, and then double-click the **FormatLib** folder to open it.

5. Select the catalog you want to delete.



6. Click the **Delete** button to delete the catalog.

7 Working with Images

Topics in this chapter:

- Overview
- Viewing the Content list of images
- Creating custom images
- Rendering bitmap images
- Creating image catalogs

Overview

The 882 generator includes a library of 250 test images. The images in the library are compiled in the application and stored as .img files; you cannot modify them.

In addition to the library images there are other types of images that you can create and store on the generator media. You can create your own images either by writing your own code using the generator's Software Development Kit (SDK) or by entering image primitive commands using the command line interface. Furthermore, you can render JPEG images stored on the generator media or a file server PC.

Using the SDK, you can create complex, custom images through the C/C++ API. When you create images through the API, they reside on the generator as object files. You can then render them by selecting the image through the front panel or through the command line interface. When you select one of these images, it gets linked, compiled, and stored in the generator's cache. Please refer to the SDK manual for details on creating custom images using the API.

You can create static images through the command line interface using the image primitive commands, such as RECT (draw rectangle), OVAL (draw oval), Line (draw line), and so on. You can select the grayscale and color tables used in the image and save the images in flash memory. Drawing commands are processed by the generator and stored as XML files. These XML files can be modified if necessary.

JPEG and bitmap images can be stored on any of the generator media and rendered just like any other image type through the **Contents** key.

This chapter provides procedures for viewing lists of images, creating images using the drawing primitive commands, rendering bitmap and jpg images, and creating image catalogs.

Viewing the Content list of images

You can view the list of images available in the generator through the front panel or the command line interface. Use the following procedure to view the image list using the front panel.

Note: *The list of images that appears on the generator's display is determined by the image path. In addition, the list may be filtered based on the image catalogs that are enabled. For more information about setting the path, see "Setting the generator's path" on page 18. For more information about image catalogs, see "Creating image catalogs" on page 247.*

To view the images in the Content list using the front panel:

Press the **Content** key. A list of images appears on the generator's display as shown below. You can scroll through the list using the + and - keys.




Viewing and modifying image options

Procedures for viewing and modifying the image options through the front panel are provided below.

To view and modify a format's options using the front panel:

1. Press the **Contents** key and choose an image by pressing the adjacent soft key.
   a. Press the **Options** key. The image options appear on the generator's display as shown below.



2. Enable or disable the desired option by pressing the adjacent soft key.

Viewing image versions

Many images have secondary or alternate version and some images have many versions. Use the procedures below to view the alternate and multiple image versions.

To view an alternate version for an image in the Content list:

1. Select an image by pressing the **Content** key.
2. Enable and view the alternate image version as follows:
   a. Press the **Options** key. The following menu appears on the generator's display for images with a single, alternate image:

```
-Alternate
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

   b. Choose the **Alternate** item by pressing the adjacent soft key until a + appears next to the item.

```
+Alternate
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

3. Toggle back and forth between the images by pressing the soft key adjacent to Alternate.

To view multiple image versions in the Content list:

1. Select an image by pressing the **Content** key.
2. Enable and view image versions as follows:
   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

   c. Press the + and - keys to advance through the image versions.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

3. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0      // Disables sub images
```

Creating custom images

This section describes how to create images using drawing primitive commands and add them to the generator's Content list. The recommended method for sending drawing primitive commands to the generator is to create a text file containing the commands for creating the image, and then transfering the text file to the generator. For more information about using command files, see "Sending command files (serial interface only)" on page 36.

To create a custom image with a text file:

1. Using a text editor, open a text file on your computer and enter the following commands.

```
OUTG 0                  // gates all video and sync outputs off
IMGN new_image          // creates a new image
IMGB                    // begins an image editing session
XRES 640                // sets the horizontal resolution to 640
YRES 480                // sets the vertical resolution to 480
.
.                       // image drawing primitives
.
IMGE                    // ends an image editing session
IMGA path/new_image// saves image as new_image in specified path
OUTG 1                  // gates all video and sync outputs on
IMGU                    // draws the image
ALLU                    // applies buffer to the generator hardware
```

2. Save the text file with a *.txt extension.
3. Set the image path to the image folder where you want to store your image.


```
IMGP /tffs0/Library/Images  // sets image path to folder in flashmem
```

4. Establish a terminal session with the generator. See "Establishing a terminal session with the generator" on page 31.
5. At the R:> prompt, transfer the text file to the generator. For example, to transfer a file using HyperTerminal, do the following:
   a. On the **Transfer** menu, click **Send Text File**. The **Send Text File** dialog box appears.
   b. Select the text file you want to send, and then click **Open**. HyperTerminal displays the commands as they are sent.
   c. Press **Enter** once to ensure that the last command is sent.

   The generator processes the commands and creates an image XML file in the Images folder you specified above.

Command file example

The following sample command file creates the image shown in the graphic below.



Commands used to draw image above:

```
IMGN
IMGB                    // begins an editing session
XRES 640                                // sets the horizontal resolution
YRES 480                                // sets the vertical resolution
RECT White  129 97  7 8  GrayPat25
GRID White 3 3
LIMI White
CROS White
TRIA Magenta50  319 38  254 133  383 133  GrayPat100
OVAL Green50  129 97  256 192  GrayPat100
RECT White  129 97  8 376  GrayPat75
RECT White  129 97  502 9  GrayPat50
RECT White  129 97  503 374  GrayPat100
OVAL Blue50  129 97  426 191  GrayPat100
OVAL Red50  129 97  84 192  GrayPat100
LINE White 256 352 384 352
TEXT White 253 393 sys16 "TEST IMAGE"
IMGE                   // ends an editing session
IMGA /tffs0/Library/Images/MyImage.xml  // saves image as MyImage
```

Note: *It is recommended that you save custom images in a directory on the PCcard because of file storage limitations in the Flashmem.*

Editing images

When you create an image using the command line interface, the generator produces an image XML file. This XML file can be edited with any standard text editor. The XML file created from the above command file is shown below.

```
<?xml version="1.0" encoding="UTF-8" ?>
<DATAOBJ>
  <HEADER TYPE="IMG" VERSION="1.0" ></HEADER>
  <DATA>
    <PRIM>RECT White  129   97    7    8 graypat25</PRIM>
    <PRIM>GRID White    3    3</PRIM>
    <PRIM>LIMI White</PRIM>
    <PRIM>CROS White</PRIM>
    <PRIM>TRIA Magenta50  319   38  254  133  383  133 graypat100</PRIM>
    <PRIM>OVAL Green50  129   97  256  192 graypat100</PRIM>
    <PRIM>RECT White  129   97    8  376 graypat75</PRIM>
    <PRIM>RECT White  129   97  502    9 graypat50</PRIM>
    <PRIM>RECT White  129   97  503  374 graypat100</PRIM>
    <PRIM>OVAL Blue50  129   97  426  191 graypat100</PRIM>
    <PRIM>OVAL Red50  129   97   84  192 graypat100</PRIM>
    <PRIM>LINE White  256  352  384  352</PRIM>
    <PRIM>TEXT White  253  393 Sys16 "TEST IMAGE"</PRIM>
  </DATA>
</DATAOBJ>
```

Rendering bitmap images

Bitmap images residing in the generator's flash memory, on the PC card, or on the file server can be rendered on a display by selecting the image through the front panel or the command line interface. This section describes how to store and render bitmap images.

To render a bitmap image using the front panel:

1. Copy the bitmap image to the Image folder on either the file server or the generator's flash memory or PC card. See "Copying files from a PC to a generator" on page 24.

   Note: *You can transfer either a single bitmap or an entire folder of bitmaps. It is recommended that you save bitmaps in a directory on the PCcard because of file storage limitations in the Flashmem.*

2. Set the generator's image path to the image folder on the desired medium. See "Setting the generator's path" on page 18.
3. If necessary, place the generator in Basic mode by pressing and holding the **Tools** key.
4. Press the **Content** key. A list of images appears on the generator's display.
5. Press the soft key adjacent to the desired image to render the bitmap on the display.

To render a bitmap image using the command line interface:

1. Copy the bitmap image to the Image folder on either the file server or the generator's flash memory or PC card. See "Copying files from a PC to a generator" on page 24.

   Note: *You can transfer either a single bitmap or an entire folder of bitmaps.*

2. Establish a terminal session with the generator. See "Establishing a terminal session with the generator" on page 31.
3. Set the generator's image path to the image folder on the desired medium. In the command syntax, specify the medium as follows:
   - Flash memory: tffs0
   - PC card: card0
   - File server: server_name (case sensitive without a forward slash in front, and with a colon after the name)

   Enter the following command for flash memory and PC card:

   ```
   IMGP /medium/Library/Images
   ```

   Enter the following command for file server:

   ```
   IMGP server_name:
   ```

4. Enter the following commands to select and render the image from flash memory or PC card:

```
IMGL image_name // Select the test image
IMGU            // Draw the selected test image
```

Setting image component values

You can increment the color component values or can decrement the color component values for all pixels of any image through the front panel or the command line. This feature enables you to increment or decrement the values in increments (or decrements) of 1, 10 or 100 throughout a range of 0 to 255 through the front panel or by any increment 1 or greater through the command line. The LEVP feature increments or decrements all color component values (R,G,B) for each action by the user either through the command line or through the front panel.

You can also increment the R, G, B color component values individually through the command line in increments of 1 or greater using the LEVP:R command. And you can use the LEVP:R and LEVP commands together.

Note: *These commands are best used with component color formats (RGB color scheme). The color mode is set by the AVST or DVST command. AVST 2 is analog RGB color mode; DVST 10 is digital RGB color mode. If you have a format and configuration with color difference (YPbPr or YCbCr) you see a reduction or increase of the chrominance difference values but the Y component values will remain. Therefore as your reduce the color component values for red, green and blue you will see a pronounced green image.*

This subsection describes these procedures.

To increment or decrement all color component values for an image:

1. Select an image by pressing the **Content** key.
2. Press the **Options** key repeatedly to access the component increment menu. The following menu appears on the generator's display:



3. Set the increment value to either 001, 010 or 100 by pressing the soft key adjacent to the **Inc:001** item on the menu.
4. Increment or decrement the image color component values by pressing the + and - keys.

To increment or decrement all color component values for an image through the command line:

1. Select any image you want to modify by pressing the **Content** key.

   Alternatively you can enter the following command:

```
IMGL SMPTEBar   // Loads the SMPTEbar test image
IMGU            // Renders the test image that is loaded
```

2. Enter the following commands to set the color component values:

```
LEVP:R 52          // Sets all color component (R,G,B) at 52% full
color
```

To increment or decrement each color component value individually for an image:

1. Select any image you want to modify by pressing the **Content** key.

   Alternatively you can enter the following command:

   ```
   IMGL SMPTEBar    // Loads the SMPTEbar test image
   IMGU             // Renders the test image that is loaded
   ```

2. Enter the following commands to select and render the image:

   ```
   LEVP:R 33        // Sets the red component at 33% of maximum color
   LEVP:G 50        // Sets the green component at 50% of maximum color
   LEVP:B 66        // Sets the blue component at 66% of maximum color
   ```

Creating image catalogs

An image catalog is an XML file that lists image names. When a catalog is enabled, the image names in the catalog appear in the Content list. You can create image catalogs and use them to control which image names appear when you press the Content key. If your test environment requires only a subset of the built-in images (for example, only images for testing TV CRTs), you can create an image catalog containing only those image names. You can arrange the image names in the order you want them to appear in the Content list, and you can create multiple catalogs and use them simultaneously. You can create an image catalog with images from the default library or custom images created either with the SDK or through the command line.

Creating image catalogs is a two-step process. The first step is to create the catalog. The second step is to add the catalog to the Content library. Once in the Content library, you can enable one or more catalogs to control which images appear when you press the Content key.


Creating an image catalog

The process for creating image catalogs is somewhat different than creating format catalogs. The generator is not configured with an image catalog library as there is for formats. Therefore you first have to create an image library (ImageLib) to put the image catalogs in. Also the images are stored in cache and because of this there is some administration overhead involved in re-establishing the default content list of images that is not required for the source list of formats.

Image catalogs are created using the command line interface. Although the catalog itself is a file, you will use the Directory (DIR) commands to create the file. Follow the procedures below to create an image catalog and add it to the Content library.


To create an image catalog using the Generator FTP Browser:

1. Access the generator's Virtual Front Panel. See "Working with the Virtual Front Panel" on page 21.




2. From the **Options** menu (upper left corner of the Virtual Front Panel), choose the **FTP Browser** menu item. The Generator FTP Browser appears.

3. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0**. This is the generator's flash memory.




4. Create a folder named ImageLib as follows:

   a. Click the **New** button. The Enter a New Folder Name dialog box appears.



   b. Enter **ImageLib** in the box, and then click **OK**. The ImageLib folder appears in the list of files and folders.



To create an image catalog using the command line interface:

1. Determine the images you want to include in your catalog. For example, you may want to create a catalog that includes the following images for testing CRT televisions:

```
SMPTE133    SMPTEBar
TVBar100    PulseBar
Regulate    Geom_1
```

   Or, you may want to create a catalog that includes custom images created using the SDK or the command line.

```
Ramp        Flat
barpulse    myimage
SMPTE133    Grays32
```

2. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN see “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.

3. Create the catalog by entering the commands shown below. This example creates a catalog called TVimages.xml.

```
DIRN TVImages      // creates a catalog named TVImages
DIRT Content       // identifies the catalog as a Content catalog
DIRB               // begins a directory editing session
NAMI 1 /Cache0/Images/SMPTE133        // add SMPTE133 to catalog
 .
 .                 // add other images to the catalog
 .
NAMI 6 /Cache0/Images/Geom_1          // add Geom_1 to catalog
DIRE               // ends the directory editing session
DIRA /tffs0/Library/ImageLib/TVImages // saves the catalog
DIRL /tffs0/Library/ImageLib/TVImages // loads the TVImages catalog
DIRU                                  // applies the TVImages catalog
```

This example creates a catalog called FPDImage.xml.

```
DIRN FPDImage      // creates a catalog named FPDImage
DIRT Content       // identifies new catalog as a content catalog
DIRB               // begins a directory editing session
NAMI 1 /Cache0/Images/Ramp              // add Ramp to the catalog
NAMI 2 /Cache0/Images/Flat
NAMI 3 /tffs0/Library/userdata/myimage  // adds a custom image created
                                           through the command line
NAMI 4 /tffs0/Library/Images/barpulse.o // adds a custom image created
                                           through the SDK
NAMI 4 /Cache0/Images/SMPTE133
NAMI 6 /Cache0/Images/Grays32           // add Grays32 to catalog
DIRE               // ends the directory editing session
DIRA /tffs0/Library/ImageLib/FPDImages  // saves the catalog
DIRL /tffs0/Library/ImageLib/FPDImages  // loads the FPDImages catalog
DIRU                                    // applies FPDImages catalog
```

To restore the default image library:

1. Power cycle the generator.

   Or, you can restore the default Source list of images by entering the commands below.

```
DIRN               // creates a blank catalog
DIRB               // begins a directory editing session
DIRT Contentlib    // identifies new catalog as a contentlib catalog
DIRE               // ends the directory editing session
DIRU               // applies the empty catalog
```

To restore the custom image library:

1. You can restore your custom Source list of images by entering the commands below.

```
DIRL /tffs0/Library/ImageLib/FPDImages  // loads the FPDImages catalog
DIRU                                    // applies FPDImages catalog
```

To enable catalogs in the Content list using the front panel:

1. Press the **Content** key. The list of images appears on the generator's display.

2. Press the **Options** key repeatedly until the Library folder appears on the generator's display as shown below:




3. Choose the **Library** item by pressing the adjacent soft key. The image library appears as shown below. Each item in the image library is an image catalog.



4. Press the soft key adjacent to a catalog to enable or disable it. A + sign next to the item indicates the item is enabled; a - sign indicates it is disabled.

5. Press the **Content** key to see the images in the selected catalogs.



To remove an image from a catalog:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN.see "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

2. To remove an image from a catalog, enter the following commands:


```
DIRL /tffs0/Library/ImageLib/TVImages // loads the TVImages catalog
DIRT ContentLib       // identifies directory as a content directory
DIRB                  // begins a directory editing session
NAMK /cache0/Library/Images/TVImages/SMPTE133.img
Or...
NAMY 1                // deletes SMPTE133 (index 1)
DIRE                  // ends the directory editing session
DIRS                  // saves the catalog
```

Deleting an image catalog

You can delete an image catalogs either through the command line or through the Generator FTP Browser. Procedures for both methods are provided below.


To delete a image catalog using the Generator FTP Browser:

1. Access the source generator's Virtual Front Panel. See "Working with the Virtual Front Panel" on page 21.



2. From the **Options** menu (upper left corner of the Virtual Front Panel), choose the **FTP Browser** menu item. The Generator FTP Browser appears.
3. In the **Instrument Files** area, click the down arrow by the **Look in** box and select **tffs0**. This is the generator's flash memory.
4. Double click the **Library** folder, and then double click the **ImageLib** folder to open it.

5. Select the catalog file you want to delete, and then click the **Delete** button. A message appears asking you to confirm that you want to delete the file. Click **OK**.



8 Working with Test Sequences

Topics in this chapter:

- Overview
- Viewing the test sequence list
- Running a test sequence
- Creating a test sequence
- Deleting a test sequence

Overview

When testing video displays, you typically select a format using the Source key, and then select an image using the **Content** key. In a production environment, where there might be a need to test several combinations of formats and images, you can create a test sequence to automate the process of selecting formats and images. Test sequences provide a way to progress through a pre-defined sequence of format and images, either manually or automatically. Multiple test sequences can be stored in the generator and selected by the operator.

This section describes how to create and run test sequences. New test sequences are created through the command line interface and stored as XML files. Existing sequences can be modified by editing the sequence XML files using a text editor. Test sequences can be activated (run) or deactivated through the generator front panel or the command line interface.

Viewing the test sequence list


You can view the list of test sequences stored in the generator using the generator front panel controls or the command line interface.

Viewing the test sequence list using the front panel

Use the following procedure to view the test sequence list using the generator's front panel.


To view the sequence list using the front panel:

1. Press the **Tools** key. The Tools menu appears as shown below:



2. Choose the **Sequence** item by pressing the adjacent softsoft key.

   A list of sequences appears as shown below. If necessary, press the - key to scroll down the list.



Viewing the test sequence list using the command line interface

Use the following procedure to view the test sequence list using the command line interface.

To view the sequence list using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Set the sequence path to the medium and location you want to query. For example, if you want to view the sequence files in the generator's flash memory, enter the following command:

```
SEQP /tffs0/Library/Sequence
```

To set the sequence path to view the sequence files on the PC card, enter the following command:

```
SEQP /card0/Library/Sequence
```

3. List the contents of the sequence folder by entering the following command:

```
SEQQ? 1 4  // lists test sequences from the first through the fourth
```

Running a test sequence

Test sequences are initiated through the generator's front panel or the command line interface. A sequence can run in one of three modes:


- Step and stop mode, where the progression of the sequence is under user control, and the sequence halts after the final step.
- Step and wrap mode, where the progression of the sequence is under user control, and it continuously loops (repeats the sequence steps).
- Automatic mode, which enables automatic progression through the sequence list with continuous looping.

The instructions for running test sequences using the front panel and command line interface are provided below.


Running a test sequence using the front panel

To run a sequence using the front panel:

1. Press the **Tools** key. The Tools menu appears as shown below:



2. Choose the **Sequence** item by pressing the adjacent soft key. To see all of the sequences, press the + and - keys.



3. Choose the sequence you want to run by pressing the adjacent soft key. The settings for the selected sequence are shown on the generator's display:

```
+Red myseq          ACS
+Grn Auto:00001     DCS
+Blu DMT0660        DSS*
 Inv SMPTE133       Out+
```

Depending on the mode of the sequence, the sequence will either start automatically, or you can press the + or - keys to move forward or backward manually through the sequence steps.

The generator's display shows the format and image name for each step, the mode, and the current step number. Additionally, the sync gate status and output status appear on the right, and the color gate status appears on the left, as shown below.

```
+Red myseq          ACS
+Grn Step:00001     DCS
+Blu DMT0660        DSS*
 Inv SMPTE133       Out+
```

To stop a sequence or change the sequence mode:

1. With a sequence running, press the **Options** key. The mode menu appears as shown below.

```
*Step
 Wrap
 Auto
 Stop
```

2. Choose the desired mode by pressing the adjacent soft key.

Mode	Description
Step	Step and stop mode
Wrap	Step and wrap mode
Auto	Automatic mode.
Stop	Stops the sequence

3. Press the **Options** key to return to the sequence settings.

Running a test sequence using the command line interface

To run a sequence using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with

the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

2. Enter the following commands:

```
SEQL seqname      // loads the sequence into sequence edit buffer
SMOD 1            // where 1=step&stop; 2=step&wrap; 3=auto
SEQU              // starts running the sequence
```

The generator's display shows the format and image name for each step, the mode, and the current step number. Additionally, the sync gate status and output status appear on the right, and the color gate status appears on the left, as shown below:

```
+Red myseq          ACS
+Grn Step:00001     DCS
+Blu DMT0660        DSS*
 Inv SMPTE133       Out+
```

If the sequence is set to auto, it begins running. Otherwise, press the + and - keys to move through the sequence steps.

To stop a sequence:

Enter the following command:

```
SMOD 0
SEQU
```

To run a sequence at power up:

1. Run the sequence in the desired mode.
2. Cycle the power to the generator. Depending on the selected mode, the sequence will start automatically, or you can press the + and - keys to step through the sequence.

Creating a test sequence

You create test sequences using the command line interface. Test sequences consist of multiple steps. Each step specifies the format and image to display, as well as the duration of the step. You can create multiple sequence files, which are stored in the generator's flash memory.

Creating a test sequence using the command line interface

You can develop test sequences using the command line interface, either by entering commands interactively through a terminal session or by entering a series of commands in a text file and then sending the file to the generator through a terminal emulation program such as HyperTerminal. When developing long test sequences, the recommended procedure is to enter commands in a text file, and then send the file to the generator. This approach enables you to change the test sequence without entering the entire command script.

It is important to note that for digital formats you will need to create separate formats using the format editor to ensure that the digital video signal type (DVST) is set properly. When a format is loaded during a test sequence its video type defaults to analog. So if you want to create for example a test sequence for HDMI for testing high definition televisions you will need to create the HDMI version of the format setting DVST appropriately. Examples are provided below.

Use the following procedure to create a test sequence and save it to the sequence directory on the generator.

To create and save an analog test sequence interactively using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Set the sequence path to the sequence directory in the generator's flash memory or on the PC card. For example, to set the path to the generator's flash memory, enter the following command:

   ```
   SEQP /tffs0/Library/Sequence
   ```

   To set the sequence path to the PC card, enter the following command:

   ```
   SEQP /card0/Library/Sequence
   ```

3. Enter the following commands to create a three-step sequence named *MySeq*.

   ```
   SEQN          // initializes the sequence edit buffer
   SEQB          // begins a sequence editing session
   STEP 1        // selects a step to be edited
   ```

```
SDLY 5.0       // sets the delay for the current step to five seconds
FMTL 480p59    // loads a format
IMGL SMPTEbar  // loads an image
STEP 2         // selects a step to be edited
SDLY 5.0       // sets the delay for the current step to five seconds
FMTL 720p60    // loads a second format (same image)
IMGL Outline1  // loads an image
STEP 3         // selects a step to be edited
SDLY 5.0       // sets the delay for the current step to five seconds
FMTL 1080i29   // loads a third format
IMGL Geom_4    // loads another image
SEQE           // ends the sequence editing session
SEQA MySeq     // saves the current contents of the sequence editor
```

After sending the last command, the file is automatically converted to an XML file and is available to use at the generator.

To create and save an analog test sequence from a text file:

1. Using a text editor, open a text editor on your computer and enter the following commands to create a three-step sequence named *MySeq*:

   ```
   SEQN           // initializes the sequence edit buffer
   SEQB           // begins a sequence editing session
   STEP 1         // selects a step to be edited
   SDLY 5.0       // sets the delay for the current step to five seconds
   FMTL 480p59    // loads a format
   IMGL SMPTEbar  // loads an image
   STEP 2         // selects a step to be edited
   SDLY 5.0       // sets the delay for the current step to five seconds
   FMTL 720p60    // loads a second format (same image)
   IMGL Outline1  // loads an image
   STEP 3         // selects a step to be edited
   SDLY 5.0       // sets the delay for the current step to five seconds
   FMTL 1080i29   // loads a third format
   IMGL Geom_4    // loads another image
   SEQE           // ends the sequence editing session
   SEQA MySeq     // saves the current contents of the sequence editor
   ```

   Note: *If you wish to use a format or image that is in a location that is not the current location of the format path (fmtp) or image path (imgp) you will have to specify the complete path. For example if you wand to use an image from the PCcard in the Library/Image directory you would use the following:*

   ```
   IMGL /card0/library/images/SMPTEbar   // loads an image from PCcard
   ```

   And if you wanted to use a format from the PCcard but the current format path was set to Flashmem, you would enter the following:

   ```
   FMTL /card0/library/formats/DMT0660a // loads a format from PCcard
   ```

2. Save the text file with a .txt extension.

Note: *When you send the .txt file to the generator, the file will be automatically converted to an XML file.*

3. Set the sequence path to the sequence directory on the generator's flash memory or the PC card. For example, to set the path to the generator's flash memory, enter the following command:

   ```
   SEQP /tffs0/Library/Sequence
   ```

   To set the sequence path to the PC card, enter the following command:

   ```
   SEQP /card0/Library/Sequence
   ```

4. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

5. Transfer the text file to the generator. For example, to transfer the file using HyperTerminal, do the following:

   a. On the **Transfer** menu, click **Send Text File**. The **Send Text File** dialog box appears.

   b. Select the text file you want to send, and then click **Open**. HyperTerminal displays the commands as they are sent.

   c. Press **Enter** once to ensure that the last command is sent.


To create and save a test sequence with HDMI digital formats using a text file:

1. Create HDMI digital versions of the formats you will be using in the test sequence.

   We recommend using the Format Editor. Please refer to “Creating custom formats using the Format Editor” on page 186.

   a. Load the format that you wish to use.

   b. Specify the Color Encoding Method to set the digital video signal type as in the example below:



   c. Save the format under a different name. For example if you are using 1080p60, you might name the new format as 1080p60h.

2. Using a text editor, open a text editor on your computer and enter the following commands to create a three-step sequence named *MySeq*:

```
SEQN           // initializes the sequence edit buffer
SEQB           // begins a sequence editing session
STEP 1         // selects a step to be edited
SDLY 5.0       // sets the delay for the current step to five seconds
FMTL 1080p60h  // loads an HDMI digital format
IMGL SMPTEbar  // loads an image
STEP 2         // selects a step to be edited
SDLY 5.0       // sets the delay for the current step to five seconds
FMTL 720p60h   // loads a second format (same image)
IMGL Outline1  // loads an image
STEP 3         // selects a step to be edited
SDLY 5.0       // sets the delay for the current step to five seconds
FMTL 1080i29h  // loads a third format
```

```
IMGL Geom_4     // loads another image
SEQE            // ends the sequence editing session
SEQA MySeq      // saves the current contents of the sequence editor
```

3. Save the text file with a .txt extension.

   Note: *When you send the .txt file to the generator, the file will be automatically converted to an XML file.*

4. Set the sequence path to the sequence directory on the generator's flash memory or the PC card. For example, to set the path to the generator's flash memory, enter the following command:

   ```
   SEQP /tffs0/Library/Sequence
   ```

   To set the sequence path to the PC card, enter the following command:

   ```
   SEQP /card0/Library/Sequence
   ```

5. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.

6. Transfer the text file to the generator. For example, to transfer the file using HyperTerminal, do the following:

   a. On the **Transfer** menu, click **Send Text File**. The **Send Text File** dialog box appears.

   b. Select the text file you want to send, and then click **Open**. HyperTerminal displays the commands as they are sent.

   c. Press **Enter** once to ensure that the last command is sent.

Editing a test sequence XML file

You can modify an existing test sequence by copying the sequence XML file from the generator to a PC, editing the file, and then transferring the file back to the generator. Use the following procedure to edit an existing test sequence XML file.

To edit a test sequence:

1. Using the Generator FTP Browser, copy the sequence XML file from the generator to a PC. See "Copying files from a generator to a PC" on page 26 for instructions.

   Note: *You can also copy the contents of a test sequence file from the Generator FTP Browser to your text editor. Locate the file you want to copy in the Instrument Files area of the Generator FTP Browser window. Select the file, and then click the Open button. The sequence XML file will open in a window. Press CTRL-A to select the contents of the window. Press CTRL-C to copy the selected text. You can then paste the contents into a text editor on your PC.*

2. Open the XML file in a standard text editor.

   A sample sequence XML file for the sequence named MySeq01 is shown below:

```
<?xml version="1.0" encoding="UTF-8" ?>
<DATAOBJ>
  <HEADER TYPE="SEQ" VERSION="1.0" ></HEADER>
  <DATA>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0660.xml</FMT>
      <IMG>master.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0659.xml</FMT>
      <IMG>SMPTEBar.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0675.xml</FMT>
      <IMG>SMPTE133.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0685.xml</FMT>
      <IMG>Flat.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0856.xml</FMT>
      <IMG>Grill_11.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0680.xml</FMT>
      <IMG>Hatch4x3.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0872.xml</FMT>
      <IMG>ColorBar.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
    <STEP>
      <FMT>/tffs0/Library/TestAnalog/DMT0885.xml</FMT>
      <IMG>Ramp.img</IMG>
      <DELY>+3.0000000E+00</DELY>
    </STEP>
  </DATA>
</DATAOBJ>
```

3. Make the edits in the XML file as necessary. An example is provided below showing how to change the format, image, and delay for the second step in the test sequence.

Before:

```
...
<STEP>
  <FMT>/tffs0/Library/TestAnalog/DMT0659.xml</FMT>
  <IMG>SMPTEBar.img</IMG>
  <DELY>+3.0000000E+00</DELY>
</STEP>
...
```

After (modified text in bold):

```
...
<STEP>
  <FMT>/tffs0/Library/TestAnalog/DMT0856.xml</FMT>
  <IMG>PulseBar.img</IMG>
  <DELY>+4.0000000E+00</DELY>
</STEP>
...
```

4. Save the text file as an XML file.
5. Using the Generator FTP Browser, download the format XML file from your PC to the generator. See “Copying files from a PC to a generator” on page 24 for instructions.

Deleting a test sequence

You can delete a test sequence using the command line interface.

To delete a test sequence using the command line interface:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.
2. Set the sequence path to the medium and location you want to query. For example, if you want to delete the sequence files in the generator’s flash memory, enter the following command:

   ```
   SEQP /tffs0/Library/Sequence
   ```

   To delete sequence files on the PC card, enter the following command:

   ```
   SEQP /card0/Library/Sequence
   ```

3. Delete the sequence by entering the following commands:

   ```
   SEQK seqname
   ALLU
   ```

9 Analyzing Digital Sources and Cables

Topics in this chapter:

- Getting started
- Measuring timing of video signal
- Testing cables and distribution systems
- Testing video signal quality from a source
- Testing InfoFrames (HDMI only)
- Testing audio (HDMI only)
- Controlling the analyzer using the command line interface
- Controlling the analyzer with Signal Analysis Module

Getting started

The Analyzer option provides the generator with the ability to test and verify the quality of an HDMI or DVI video signal, respectively. Having both a transmitter and receiver, the generator with the Analyzer feature can be used to:


- **View timing of an HDMI/DVI video signal**. Connect an HDMI/DVI source to the HDMI IN connector to measure and analyze the timing parameters of the signal.
- **Test cables and distribution systems -** Test a cable or distributation system connected from the transmitter (HDMI OUT connector) to the receiver (HDMI IN connector) using pseudo-random noise.
- **Analyze pixel data at different frequencies**. Examine the quality of HDMI/DVI pixel transmission (including source, cables and distribution systems) for data errors and flickering pixels.
- **Viewing the pixel color components**. View the color components (R,G,B) of any pixel in the active video. The values shown in the analyzer can be compared against what the source is sending.
- **Generate pseudo-random noise test pattern.** Connect an HDMI/DVI display device to the HDMI OUT connector to receive pseudo-random noise for testing purposes.
- **View InfoFrame packets from an HDMI signal.** Display and validate InfoFrame packets transmitted from an HDMI source

This chapter provides procedures for testing with the analyzer through the front panel keys and through the command line interface.

Analyzer connections

HDMI 1.1

This subsection describes the generator's video interfaces for the connecting source devices to the 882CA analyzer. The HDMI video interfaces are shown below.




Interface	Description
6	**HDMI OUT 1** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
7	**HDMI OUT 2** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
8	**HDMI IN 1** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
9	**HDMI IN 2** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
10	**SPDIF-AV** connector inputs audio from an external source and enables you to extract audio from and incoming source.

Monitoring HDMI 1.1 analyzer signal input


With the 882CA analyzer option, you can externally monitor the HDMI 1.1 video and/or audio content of an incoming HDMI signal. This feature lets you view and hear HDMI content that is received at the HDMI In connector while analysis and testing functions are performed by the analyzer.

To monitor HDMI input:

- Use the VGA-to-RCA cable provided (part 30-00150) to connect the AV connector with a YPbPr display, and the audio connections, as shown below.



- If you do not have the analyzer option, you will have the VGA-to-RCA cable (part 30-00148). Connect the AV connector to the generator's SPDIF / AV port. Then connect the red RCA connector to the SPDIF output of the external audio source.



Monitoring HDMI 1.3 analyzer signal input

With the 882EA analyzer option, you can externally monitor the HDMI 1.3 deep color video and/or audio content of an incoming HDMI signal. This feature lets you view and hear HDMI content that is received at the HDMI In connector while analysis and testing functions are performed by the analyzer. However, unlike the 882CA where the video and audio are monitored through the SPDIF AV port, with the 882EA, the incoming video is monitored from the HDMI Tx (out) ports and the incoming audio is monitored through a separate SPDIF output port.

Note: *With the release of 2.19 on the 882EA, you can passthru HDMI video content that is protected via HDCP.*

The monitored video output is an HDMI video signal and requires an HDMI display. Monitoring the incoming video signal requires that you put the generator into a specific mode of operation called "passthru." Passthru mode is invoked through the Interface key by selecting Options or through the command line (these procedures are described

below). The monitored output from the HDMI Tx port is a pixel per pixel duplication of the resolution of the incoming signal. There are a couple important things to note about the passthru monitored video:

- The image resolution of the passthru video will not scale to the native resolution of the display used to monitor the incoming video. In other words, if the monitoring display is 1080 and the incoming video signal is 720p you will see the entire image in the upper left area of the monitoring display with unused portions of the display on the bottom and right area. Alternatively, if the 882EA generator/analyzer is receiving 1080 video but the monitoring display is only capable of displaying a 720p image then you will not see the entire image.
- When the generator is in passthru mode, you will not be able to monitor a video signal that is looped from that generator's HDMI Tx port (either the HDMI Tx 1 or the HDMI Tx 2).
- If the incoming video is in 4:2:2 sampling mode, the HDMI passthru video will be converted to 4:4:4 sampling. The 4:2:2 sampling mode is not supported in passthru mode.
- If the incoming video is in 12 bit deep color, the HDMI passthru video will only be able to display 10 bit deep color.
- The frame rate of the HDMI Tx passthru video is the frame rate of the format selected on the generator. This means that a scan conversion will occur. If the incoming video is 720p24 and the generator's output is set to 720p60, then the video signal displayed on the monitoring display will be at 720p at 60Hz.
- The scan setting (progressive or interlaced) of the HDMI Tx passthru video is the scan setting of the format selected on the generator for the HDMI Tx outputs.

The monitored audio output is available from the SPDIF Out BNC connector when the generator is in passthru mode. A BNC to RCA adapter cable (30-00123) is provided to enable you to connect the SPDIF audio to an RCA coaxial input of a sound system or a digital audio analyzer. The audio that is embedded into the outgoing HDMI passthru Tx stream is that of the 882EA's internal audio source.

To monitor HDMI 1.3 input:

1. Connect the HDMI source device to an HDMI IN connector on the generator.

2. Activate the HDMI-H interface on the output port:

   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                  CVBS
  HDMI-D           S-VIDEO
  HDMI-H               SDI
```

   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

```
  VGA                  CVBS
  HDMI-D           S-VIDEO
 *HDMI-H               SDI
```

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4              // Selects the HDMI-H interface
ALLU                // Applies the interface setting to the generator
```

3. Press the **Interface** key repeatedly until the following menu appears:

```
* HDMI IN 1
  HDMI IN 2
```

4. Choose the connector to which the transmit device is connected by pressing the adjacent soft key.
5. Monitor the HDMI 1.3 deep color video signal received on the HDMI IN connector by connecting an HDMI cable from the HDMI Tx output (either Tx 1 or Tx 2) to an HDMI display. (Ideally, the HDMI display should support the resolution of the incoming video.)

6. Put the 882EA into passthru mode.

   a. Press the **Interface** key to access the list of interfaces. The list of signal interfaces appears on the generator's display as shown below.



   b. Press the **Option** key to access the Passthru mode selection.

```
+Output           Mark#1-
-No Passthru
 HDCP Passthru
 Non-HDCP Passthru
```

   c. Enable Passthru by pressing the adjacent soft key. Select either with HDCP enabled (shown below) or without HDCP depending on your application.

```
+Output           Mark#1-
 No Passthru
+HDCP Passthru
 Non-HDCP Passthru
```

   d. Alternatively, to enable passthru mode via the command line interface, enter the following command:

```
PDAX:PASS 1        // Enables passthru mode
```

   To query the current state of the passthru mode via the command line, enter the following command:

```
PDAX:PASS?         // Returns 0 or 1 to indicate the status
```

   To disable passthru mode via the command line, enter the following command:

```
PDAX:PASS 0        // Disables passthru mode
```

Measuring timing of video signal

The Analyzer provides the ability to measure and analyze signal timing information of an external HDMI/DVI source device. This feature allows you to test a transmitted HDMI/DVI or DisplayPort signal for anomalies and verify that the proper timing is output by the HDMI/DVI or DisplayPort transmitter for a given signal format.

The analyzer provides three ways of viewing the measurement results:

- **Front panel display** – You can view the format timing measurements directly on the generator's front panel display.
- **Monitor** – You can view the format timing parameters on a display connected to the generator.
- **Reports** – You can view the format timing parameters on an HTML formatted report either on screen or printed.


The procedures below provide instructions for configuring the Analyzer through the front panel and through the command line where applicable.

Measuring timing parameters


You can measure timing with the analyzer and view the results on the generator's LCD, a connected display, and with HTML reports. The procedures below instruct you how to measure timing and view the results.

To view timing information of an external HDMI/DVI source signal on the LCD:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Press the **Interface** key repeatedly until the following menu appears:



3. Choose the connector to which the transmit device is connected by pressing the adjacent soft key.
4. If desired, monitor the video signal received on the HDMI IN connector (see page 275).
5. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.




6. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.

```
*Timing          PIX-ERR
 CableTest       PRN-ERR
 ReadRGB
```

7. Choose the **Timing** item by pressing the adjacent soft key. The **Timing** menu appears as shown below.

```
          TIMING
!Measure             Exit!
!Report
```

8. Choose the **Measure** item by pressing the adjacent soft key. The Analyzer measures the video signal and displays the values on the generator's display. Press the soft key next to **H** to see more values. See the example below for an explanation of the values.



To save timing measurements to a report:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Press the **Interface** key repeatedly until the following menu appears:

```
*HDMI IN 1
 HDMI IN 2
```

3. Choose the connector to which the transmit device is connected by pressing the adjacent soft key.
4. Activate the HDMI-H or HDMI-D interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                  CVBS
  HDMI-D             S-VIDEO
  HDMI-H                 SDI
```

   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

```
  VGA                  CVBS
  HDMI-D             S-VIDEO
 *HDMI-H                 SDI
```

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3 (or 4)      // Selects the HDMI-D (or HDMI-H) interface
ALLU               // Applies the interface setting to the generator
```

5. If desired, monitor the video signal received on the HDMI IN connector (see page 275).
6. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.

```
 System             Reports
  Sequence         ImgShift
  Probe            Analyzer
  AFC
```

7. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.

```
* Timing            PIX-ERR
  CableTest         PRN-ERR
  ReadRGB
```

8. Choose the **Timing** item by pressing the adjacent soft key. The **Timing** menu appears as shown below.


```
           TIMING
! Measure                Exit !
!Report
```

9. Choose the **Report** item by pressing the adjacent soft key. The generator indicates that it is measuring the timing and “Generating Report.”

   Note: *Be sure that you have transferred any existing timing reports to your PC otherwise generating a new report will overwrite the existing report in the Reports folder.*

10. Go back to the generator’s home page and select Generated Reports.


    A list of generated reports appears in the browser.



11. Select the Timing Report from this list of available reports.


    The Timing Report will appear in the browser window.

Note: *The Color Depth of the source's video signal is shown on the timing report (last line).*



12. (optional) Transfer the report from the generator to your PC, using the FTP browser, by highlighting the report and clicking on the upload activation button.

Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwriting existing reports.*



To view timing information of an external HDMI/DVI source signal on a display:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Activate the HDMI-H or HDMI-D interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                    CVBS
  HDMI-D               S-VIDEO
  HDMI-H                  SDI
```

   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

```
  VGA                    CVBS
  HDMI-D               S-VIDEO
 *HDMI-H                 SDI
```

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3 (or 4)      // Selects the HDMI-D (or HDMI-H) interface
```

```
ALLU                // Applies the interface setting to the generator
```

3. Press the **Interface** key repeatedly until the following menu appears:

```
*HDMI IN 1
 HDMI IN 2
```

4. Choose the connector to which the transmit device is connected by pressing the adjacent soft key.
5. If desired, monitor the video signal received on the HDMI IN connector (see page 275).
6. Connect an HDMI/DVI display to an HDMI OUT connector on the generator.
7. Press the **Source** key and choose a suitable format for the display (for example, DMT0660).


   Alternatively, to load a valid HDMI or DVI format into the analyzer, enter the following commands:

```
FMTL DMT0660   // loads the DMT0660 (e.g.) format into the edit buffer
FMTU           // applies the format to the generator/analyzer
```

8. Press the **Content** key and choose the **FormatRx** image by pressing the adjacent soft key.

   Alternatively, to activate the FormatRx image through the command line interface, enter the following commands:

```
IMGL FormatRx // loads the FormatRX image into the edit buffer
IMGU          // applies the FormatRX image to the generator/analyzer
```



Testing cables and distribution systems

This section describes how to test HDMI or DVI cables and distribution systems using pseudo-random noise. Using different signal formats, the HDMI/DVI cable can be tested over a wide range of frequencies.

The procedures below provide instructions for testing cable and distribution systems with the Analyzer both through the front panel and the command line.

To test a cable or distribution system through the front panel:

1. Connect the HDMI/DVI cable to be tested between an HDMI OUT and an HDMI IN connector on the generator.

   Note: *If you are testing a fiber optic cable, plug the fiber optic cable connector marked "transmitter" to the HDMI OUT connector on the generator, and plug the connector marked "receiver" to the HDMI IN connector on the generator. Use a 5 Vdc power supply adapter at the receiver side of the cable.*

   Note: *If you are testing a distribution system, connect an access cable to the distribution center to the HDMI OUT connector on the generator and a second access cable to the HDMI IN connector on the generator.*


2. Activate the HDMI-H or HDMI-D interface on the output port:

   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.

   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

3. Press the **Interface** key repeatedly until the following menu appears:

4. Choose the HDMI IN connector to which the cable is connected by pressing the adjacent soft key.

5. (HDMI only) If desired, monitor the video signal received on the HDMI IN connector (see "Monitoring HDMI 1.3 analyzer signal input" on page 275).

6. Press the **Source** key and choose the format you want to use.


   Any built-in formats may be used for this test. However, we recommend using several formats spread over a wide range of frequencies. For example, the Test150 format tests at the maximum supported pixel frequency for HDMI. The DMT0660 format can be used to test at a very low frequency (25.175 MHz).

   Note: *The list of formats that appears when you press the* ***Source*** *key may be a filtered or abbreviated list. Formats not suitable for the selected interface type will not appear by default on the* ***Source*** *list. You may have to enable the Test format library. If the Test format library is disabled you will not see the TEST150 format. To enable the Test format library, see "Format catalogs" on page 229.*

   Use the following formats to test HDMI over a range of frequencies:

Format	Pixel rate (MHz)
TEST150	150.000
1080p60	148.500
720p60	74.250
DMT0660	25.175

7. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



8. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.



9. Choose the **CableTest** item by pressing the adjacent soft key. The **CableTest** menu appears as shown below.




10. Choose the **Settings** item by pressing the adjacent soft key or press the **Settings** key to select the analysis duration in the number of sequences.


To change a setting value:

a. Position the blinking cursor on the value you want to change. To do this, press the soft key adjacent to the arrow by the setting value to move the cursor left or right until it appears on the digit you want to change.

b. Adjust the value of the setting up or down by pressing the + or - keys.



11. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:






To save the changes, choose the **Yes** item by pressing the adjacent soft key.

To exit without saving the changes, choose the **No** item.

To return to the parameters screen without saving the changes, choose the **Back** item.

12. To start the analysis, press the soft key adjacent to **Start**. The results of the analysis appear on the generator's display. Press the soft key next to the arrow to see all of the results. Refer to the table below for an explanation of the results.

13. To test the cable at a different frequency, return to step 6.

Results	Explanation
	**Total** shows the total number of pixel errors detected. The bottom line shows the number of pixels errors detected per color component. In this example, the total number of pixel errors is 9, with 9 errors on each of the color components.
	In the bottom row, the left value shows the number of pixels being measured in billions and the right side shows the number of pixel errors per billion. **Note:** When the number of pixel errors becomes very large, the text “Very high” is displayed in the bottom row in place of actual values. In this example, 4.255 billion pixels were measured and 0.88 billion pixel errors were detected.
	**ERR** shows the selected error number and **Fr** shows the frame in which the error occurred. The **X** and **Y** values are the screen coordinates at which the error occurred. The bottom line shows the measured RGB values. To view the errors, press the + and - keys. In this example, Error 001 occurred in Frame 00000001 at coordinates (44545,0000). The measured RGB values were R128, G016, B128.

Testing video signal quality from a source

The Analyzer can test the quality of video sources and report errors to the front panel display or as reports.

If the HDMI/DVI source can generate Quantum Data's BCM pseudo-random noise, the Analyzer can compare the pseudo-random noise from the source with a reference that you specify using the Pseudo-Random Noise test.

In cases where the HDMI/DVI source device cannot generate pseudo-random noise, the Analyzer can test and analyze the transmission quality of the external HDMI/DVI source using a Pixel Error (delta error) test.

You can also view the pixel color components (R,G,B) for a pattern transmitted by the source. The values shown in the analyzer can be compared against what the source is sending.

Instructions for testing using the Pseudo-Random Noise, Pixel Error, and ViewPix tests are given below. For instructions on implementing pseudo-random noise in the source device, see "Controlling the analyzer with Signal Analysis Module" on page 317.


The procedures below provide instructions for running the test both through the front panel and the command line.

Running the Pseudo-Random Noise test

The Pseudo-Random Noise test can be used to analyze pseudo-random noise generated by an HDMI/DVI source device. Your source device must have the QDI-BCM pseudo-random noise algorithm implemented. For instructions on implementing pseudo-random noise in the source device, see "Controlling the analyzer with Signal Analysis Module" on page 317.


To analyze pseudo-random noise from an external source through the front panel:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Press the **Interface** key repeatedly until the following menu appears:



3. Choose the connector to which the transmit device is connected by pressing the adjacent soft key.
4. If desired, monitor the video signal received on the HDMI IN connector (see "Monitoring HDMI 1.3 analyzer signal input" on page 275).

5. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



6. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.



7. Choose the **PRN-ERR** item by pressing the adjacent soft key. The **PRN-ERR** menu appears as shown below.



8. (Optional) To generate a report during the test use the following procedures.

   a. Press the **Options** key. The following appears on the display.




   b. Enable reports by pressing the soft key adjacent to **Generate Report** item so that there is a "+" sign next to it.

   Note: *Be sure that you have transferred any existing pseudo-random noise reports to your PC otherwise generating a new report will overwrite the existing report in the Reports folder.*

   c. Press the **Options** key again to return to the PRN-ERR menu.

9. Choose the **Settings** item by pressing the adjacent soft key or press the **Settings** key. The Pseudo Noise settings appear on the generator's display as shown below. Press the soft keys adjacent to the arrows to see all of the settings.



10. Refer to the table below to locate the setting you want to change, for more information about a setting.


    To change a setting value:

    a. Position the blinking cursor on the value you want to change. To do this, press the soft key adjacent to the arrow by the setting value to move the cursor left or right until it appears on the digit you want to change.

    b. Adjust the value of the setting up or down by pressing the + or - keys.

Setting	Description
Analysis Duration Sequences	Sets the number of sequences to analyze(1-999999999).
Report Recorded Errors Max	Sets the maximum number of errors to record (1-9999)

11. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



    To save the changes, choose the **Yes** item by pressing the adjacent soft key.

    To exit without saving the changes, choose the **No** item.

    To return to the parameters screen without saving the changes, choose the **Back** item.


12. To start the analysis, press the soft key adjacent to **Start**. The results of the analysis appear on the generator's display. Press the soft key next to the arrow to see all of the results. Refer to the table below for an explanation of the results.

Results	Explanation
! Start Exit ! →ERRORS PER COMP. Total:0009 R:0009 G:0009 B:0009	**Total** shows the total number of pixel errors detected. The bottom line shows the number of pixels errors detected per color component. In this example, the total number of pixel errors is 9, with 9 errors on each of the color components.
! Start Exit ! →PIXEL ERROR RATE PELS/BILLION 4.255 0.88	In the bottom row, the left value shows the number of pixels being measured in billions and the right side shows the number of pixel errors per billion. **Note:** When the number of pixel errors becomes very large, the text "Very high" is displayed in the bottom row in place of actual values. In this example, 4.255 billion pixels were measured and 0.88 billion pixel errors were detected.
!Start 0009 Exit! →ERR:001 Fr:00000001 X:44545 Y:0000 R:128 G:016 B:128	**ERR** shows the selected error number and **Fr** shows the frame in which the error occurred. The **X** and **Y** values are the screen coordinates at which the error occurred. The bottom line shows the measured RGB values. To step through the errors, press the + and - keys. In this example, Error 001 occurred in Frame 00000001 at coordinates (44545,0000). The measured RGB values were R128, G016, B128.


To view the pseudo-random noise report:

1. Select a suitable directory on your PC to store the report by navigating in the FTP Browser.
2. Transfer the report from the generator' flash memory to your PC, using the FTP browser, by highlighting the report and clicking on the upload activation button.

Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwriting existing reports.*



3. Navigate to your PC and double click on the report. A sample of the report is shown below.




Running the Pixel Error test

If your source device does not have the Quantum Data BCM pseudo-random noise algorithm you can test the signal quality with the Pixel Error test. During the Pixel Error test, the Analyzer captures an external, still-frame image (reference frame) typically from the device under test and verifies that all pixels match over a user-specified number of successive frames. The results are output to the generator's display and can be issued as a report.


You can also capture a reference frame from another device (i.e. other than the device under test) and use that to compare with the frames from the device under test. This enables you to obtain valid results if you suspect that the device under test cannot produce an error-free reference frame. By using a reference frame from a known good source you are assured that the test results are viable.

To analyze an external HDMI/DVI signal for pixel errors:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Press the **Interface** key repeatedly until the following menu appears:



3. Choose the HDMI IN connector to which the transmit device is connected by pressing the adjacent soft key.
4. (HDMI only) If desired, monitor the video signal received on the HDMI IN connector (see “Monitoring HDMI 1.3 analyzer signal input” on page 275).
5. Press the **Tools** key. The **Tools** menu appears on the generator’s display as shown below.



6. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator’s display as shown below.



7. Choose the **PIX-ERR** item by pressing the adjacent soft key. The **Pixel Error** menu appears as shown below.




8. (Optional) To generate a report during the test use the following procedures.
   a. Press the **Options** key. The following appears on the display.



   b. Enable reports by pressing the soft key adjacent to **Generate Report** item so that there is a “+” sign next to it.

Note: *Be sure that you have transferred any existing pixel error reports to your PC otherwise generating a new report will overwrite the existing report.*

9. Choose the **Settings** item by pressing the adjacent soft key or press the **Settings** key. The pixel error testing settings appear on the generator's display as shown below. Press the soft keys adjacent to the arrows to see all of the settings.



10. Refer to the table below to locate the setting you want to change. For more information about a setting,

    To change a setting value:


    a. Position the blinking cursor on the value you want to change. To do this, press the soft key adjacent to the arrow by the setting value to move the cursor left or right until it appears on the digit you want to change.

    b. Adjust the value of the setting up or down by pressing the + or - keys.

    c. To save the changes, press the **Enter (Options)** key, and then press the soft key next to **Yes**.

Setting	Description
Analysis Duration Frames	Sets the number of frames to analyze(1-99999999).
Report Recorded Errors Max	Sets the maximum number of errors to record (1-9999)

11. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:



    To save the changes, choose the **Yes** item by pressing the adjacent soft key.

    To exit without saving the changes, choose the **No** item.

    To return to the parameters screen without saving the changes, choose the **Back** item.

12. Generate a static image from the HDMI/DVI transmit device.

13. Capture a static reference frame.

    You can either capture a reference frame from the device under test or from another device (i.e. other than the device under test). Note that you can capture a reference frame from the generator itself. The default selection is to capture a reference frame from the device under test.


    (Optional) To capture a reference frame from another device, use the following procedures.

    a. Connect the HDMI/DVI transmit device you want to use as a reference frame to an HDMI IN connector on the generator.


    b. Press the **Options** key. The following appears on the display.



    c. Access the **Manual Capture** option by pressing the soft key adjacent to the **Auto Capture** item. The following appears on the display.



    d. Select **Capture Frame** by pressing the adjacent soft key to capture the reference frame. The following appears on the display.



    e. To return to the setup screen, press the **Options** key item.





14. To start the analysis, press the soft key adjacent to **Start**.

    a. The results of the analysis appear on the generator's display. If there are no errors, the generator will display the following screen.




    b. Press the soft key next to the arrow to see all of the results. Refer to the table below for an explanation of the results.

Results	Explanation
	**Total** shows the total number of pixel errors detected. The bottom line shows the number of pixels errors detected per color component. In this example, the total number of pixel errors is 169, with 128 errors on the red component, 16 on the green, and 128 on the blue.
	**ERR** shows the selected error number and **Fr** shows the frame in which the error occurred. The **X** and **Y** values are the screen coordinates at which the error occurred. The bottom line shows the measured RGB values. To step through the errors, press the + and - keys. In this example, Error 001 occurred in Frame 00000001 at coordinates (0167,0000). The measured RGB values were R128, G016, B128.


To view the pixel error report:

1. Select a suitable directory on your PC to store the report by navigating in the FTP Browser.
2. Transfer the report from the generator to your PC, using the FTP browser, by highlighting the report and clicking on the upload activation button.

Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwriting existing reports.*



3. Navigate to your PC and double click on the report. A sample is shown below.



Pixel Error Report - Microsoft Internet Explorer

Apr 25 2005 [14:12:55] Quantum Data Inc

Pixel Error Report

Pixel Error Totals

Frames Analyzed: 7
Total Red Component Errors: 2153
Total Green Component Errors: 2153
Total Blue Component Errors: 2152
Total Pixel Errors: 2153

Error Details

Maximum Error Count: 100
Actual Error Count: 100
Overflow: Yes

				Measured			Expected		
Error #	Frame #	X	Y	R	G	B	R	G	B
0001	7	0650	0213	128	235	128	128	235	128
0002	7	0662	0213	128	235	128	128	235	128
0003	7	0664	0213	128	235	128	128	235	128
0004	7	0666	0213	128	235	128	128	235	128
0005	7	0671	0213	128	235	128	128	235	128
0006	7	0676	0213	128	235	128	128	235	128
0007	7	0706	0213	128	235	128	128	235	128
0008	7	0708	0213	128	235	128	128	235	128
0009	7	0720	0213	128	235	128	128	235	128
0010	7	0760	0213	128	235	128	128	235	128
0011	7	0764	0213	128	235	128	128	235	128
0012	7	0767	0213	128	235	128	128	235	128
0013	7	0769	0213	128	235	128	128	235	128
0014	7	0771	0213	128	235	128	128	235	128
0015	7	0774	0213	128	235	128	128	235	128
0016	7	0148	0216	128	235	128	128	235	128
0017	7	0162	0216	128	235	128	128	235	128
0018	7	0172	0216	128	235	128	128	235	128
0019	7	0174	0216	128	235	128	128	235	128

Done My Computer

Running the ViewPix test

During the ViewPix test (previously called the ReadRGB test), the Analyzer captures one complete frame of pixel data. You can then view the RGB data from any pixel in the frame by specifying the coordinates. This way if you know what the source is transferring or sending for a pixel(s) you can compare it with what the analyzer detects.


You can view the captured image out the HDMI transmit port with the View Data function.

Procedures are provided below for the ViewPix test both through the front panel and the command line.


To capture and read pixel data from the front panel:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. (Optional) Connect an HDMI/DVI display to an HDMI OUT connector on the generator.


3. Press the **Interface** key repeatedly until the following menu appears:




4. Choose the HDMI IN connector to which the transmit device is connected by pressing the adjacent soft key.
5. (HDMI only) If desired, monitor the video signal received on the HDMI IN connector (see "Monitoring HDMI 1.3 analyzer signal input" on page 275).
6. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



7. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.



8. Choose the **ViewPix** item by pressing the adjacent soft key. The **ViewPix** menu appears as shown below:



9. Choose the **Capture** item by pressing the adjacent soft key. The Analyzer captures a frame of video, and then allows you to read the RGB values of any pixel by selecting the pixel coordinates on the generator's display, as shown below.




! View Data

2. Activate the HDMI-H or HDMI-D interface on the output port:

   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                  CVBS
  HDMI-D           S-VIDEO
  HDMI-H               SDI
```

   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

```
  VGA                  CVBS
  HDMI-D           S-VIDEO
 *HDMI-H               SDI
```

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3 (or 4)      // Selects the HDMI-D (or HDMI-H) interface
ALLU               // Applies the interface setting to the generator
```

3. Press the Content key to select an image.

4. Enable pseudo-random noise using the following steps:

   a. Press the **Options** key. The following menu will appear on the generator's display for images with a single secondary image:

```
-Alternate
                       Red+
-NoGamma             Green+
-Noise                Blue+
```

   b. Choose the **Noise** item by pressing the adjacent soft key until a + appears next to the item.

Testing InfoFrames (HDMI only)

The HDMI analyzer can analyze InfoFrame data from an incoming HDMI signal. With this capability, an HDMI transmit device can be tested for its ability to transmit InfoFrame packets correctly.

Testing HDMI transmit device InfoFrame capability

The generator can monitor the InfoFrame content of the received HDMI signal.

To view current HDMI InfoFrame contents received from an HDMI transmitter:

1. Connect an HDMIdisplay to an HDMI OUT connector on the generator.
2. Connect the HDMI source to an HDMI IN connector on the generator.
3. Activate the HDMI-H interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.




   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.



   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3 (or 4)      // Selects the HDMI-D (or HDMI-H) interface
ALLU               // Applies the interface setting to the generator
```

4. Press the **Interface** key again. The following menu appears:



5. Choose the HDMI IN connector to which the HDMI source is connected by pressing the adjacent soft key.

6. If desired, monitor the video signal received on the HDMI Rx connector (see “Monitoring HDMI 1.3 analyzer signal input” on page 275).
7. Press the **Source** key and select an appropriate format for the connected HDMI display.
8. Press the **Content** key and select the **PacketRx** image.

   The PacketRx image appears on the connected HDMI display. Shown in the image are the current settings for the AVI InfoFrame input.




9. Enable and view image versions for the PacketRx image as follows:

   a. Press the **Options** key. The following menu appears on the generator’s display:



   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.



   c. Press the + key to advance through the image versions.

Note: *The contents of the appropriate InfoFrame input appears on the HDMI display.*

Alternatively, to select an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```


10. Select additional InfoFrame subimages (as desired) to verify proper InfoFrame handling.
11. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

    Alternatively, to disable image versions using the command line interface, enter the following command:


```
ISUB 0     // Disables sub images
```

To generate a report for the PacketRx image:

1. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



2. Choose the **Reports** item by pressing the adjacent soft key. The **Reports** menu appears on the generator's display as shown below.



3. Choose the **Packets** item by pressing the adjacent soft key. The **Packet** menu appears on the generator's display as shown below.



Note: *Be sure that you have transferred any existing PacketRx reports to your PC otherwise generating a new report will overwrite the existing report.*

4. Select the !**PacketRx** item by pressing the adjacent soft key to generate the report. The following appears on the display.


```
RX PACKETS

Finished
```


5. Select a suitable directory on your PC to store the report by navigating in the FTP Browser.

6. Transfer the report from the generator to your PC, using the FTP browser, by highlighting the report and clicking on the upload activation button.

   Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwriting existing reports.*



7. Navigate to your PC and double click on the report. A sample of part of the PacketRx report is shown below.



Testing audio (HDMI only)

The HDMI analyzer can process audio data from an incoming HDMI signal. With this capability, an HDMI source can be tested for its ability to successfully transmit audio packets.

Testing HDMI transmit device audio capability

The generator can monitor the audio content of the received HDMI signal.

To monitor audio content received from an HDMI transmitter:

1. Connect the HDMI audio transmit device to the HDMI Rx connector on the generator.
2. Activate the HDMI-H interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the HDMI-H item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.



   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

3. Monitor the audio signal received on the HDMI Rx connector from an external audio device (see "Monitoring HDMI 1.3 analyzer signal input" on page 275.

Controlling the analyzer using the command line interface

You can operate the Analyzer using the generator's command line interface. This section describes Analyzer functions and commands and provides examples of command sequences you can use to perform Analyzer tasks.

For command descriptions, see Appendix A, "Command Reference."

Signal timing analysis commands

This section provides command line procedures for running and viewing signal timing parameters.

Viewing specific timing parameters

The following is an example of using commands to view the total number of horizontal pixels and horizontal frequency of the HDMI/DVI signal.

To view specific timing information of an external HDMI/DVI source signal:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Using a terminal emulator, establish a terminal connection with the generator. Refer to "Establishing a terminal session with the generator" on page 31.
3. Choose the connector to which the transmit device is connected by entering the following commands:

```
XVSI:IN 1      // Selects the HDMI-1 input connector
ALLU           // Applies the interface setting to the generator
```

4. Choose the **HDMI-H** (or **HDMI-D**) item by entering the following commands:

```
XVSI 4 (or 3)  // Selects the HDMI-H or HDMI-D interface
ALLU           // Applies the interface setting to the generator
```

5. Enter the following commands to load a valid HDMI or DVI format into the analyzer.

```
FMTL DMT0660   // loads the DMT0660 (e.g.) format into the edit buffer
FMTU           // applies the format to the generator/analyzer
```

6. Enter the following commands to initiate the measurement of timing parameters.

```
TMAU         // measure external signal's timing parameters
TMAX:RPTG 1  // enables generation of an HTML report
TMAX:SCAN?  // queries for the SCAN parameter (interlaced or
               progressive
TMAX:HRAT?  // queries for the HRAT parameter (horizontal rate)
```

Pseudo-random noise generation commands

This section provides command line procedures for configuring and controlling the transmission of pseudo-random noise from the generator's output.

Configuring pseudo-random noise output parameters

The following is an example of using commands to configure pseudo-random noise output parameters.

To generate pseudo-random noise:

1. Connect the HDMI cable or DVI to HDMI cable between an HDMI IN connector on the generator and the output interface on the device under test.
2. Using a terminal emulator, establish a terminal connection with the generator. Refer to "Establishing a terminal session with the generator" on page 31.
3. Choose the **HDMI-H** (or **HDMI-D**) item by entering the following commands:

```
XVSI 4 (or 3)  // Selects the HDMI-H or HDMI-D interface
ALLU           // Applies the interface setting to the generator
```

4. Choose the connector to which the transmit device is connected by entering the following commands:

```
XVSI:IN 1      // Selects the HDMI-1 input connector
ALLU           // Applies the interface setting to the generator
```

5. Enter the following commands to configure the pseudo-random noise parameters.

```
PNSA 1  // sets pseudo random noise to be calculated each pixel clock
PNSM 0  // sets pseudo random noise test to run in auto mode
PNSG 1  // enables the pseudo-random noise test
PNGU    // turns on the pseudo-random noise test
```

Analyzing pseudo-random noise from an external source

The following example tests an HDMI/DVI transmit device's pixel data using pseudo-random noise generated by an external source.

To analyze pseudo-random noise from an external source:

1. Connect the DVI or HDMI cable between an HDMI IN connector on the generator and the output interface on the device under test.
2. Using a terminal emulator, establish a terminal connection with the generator. Refer to "Establishing a terminal session with the generator" on page 31.
3. Choose the **HDMI-H** (or **HDMI-D**) item by entering the following commands:

```
XVSI 4 (or 3)  // Selects the HDMI-H or HDMI-D interface
ALLU           // Applies the interface setting to the generator
```

4. Choose the connector to which the transmit device is connected by entering the following commands:

```
XVSI:IN 1      // Selects the HDMI-1 input connector
ALLU           // Applies the interface setting to the generator
```

5. Enter the following commands to run the pseudo-random noise test.

```
PNSP 100  // sets pseudo-random noise for 100 sequencs
PNAU      // runs the pseudo-random noise test for the specified
             number of frames
```

Note: *The test will stop automatically if configured to run in the single or multi-shot mode. If you initiate the test in the continuous mode, you will have to enter a carriage return to halt the test after PNAU is invoked.*

6. Enter the following commands to view the results of the test.

```
GPER?     // returns the pixel error rate in errors per billion
GNPT?     // returns the number of pixels measured in billions
GCET?     // returns the number of bad pixels for R, G, B components
GFED?     // returns information about the first error encountered
```

To test cables through the command line:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Configuring the generator’s serial port” on page 32 or “Establishing a Telnet session with the generator” on page 34.
2. Connect the HDMI cable to be tested between an HDMI OUT and an HDMI IN connector on the generator.

   Note: *If you are testing a distribution system, connect an access cable to the distribution center to the HDMI OUT connector on the generator and a second access cable to the HDMI IN connector on the generator.*

3. Enter the following commands to activate the HDMI-H interface on the output port:

```
XVSI 4         // Selects the HDMI-H interface
ALLU           // Applies the interface setting to the generator
```

4. Choose the connector to which the transmit device is connected by entering the following commands:

```
XVSI:IN 1      // Selects the HDMI-1 input connector
ALLU           // Applies the interface setting to the generator
```

5. Set up the pseudo-random noise parameters in accordance with “Configuring pseudo-random noise output parameters” on page 312.
6. Enter the following commands to select an HDMI-H format:

```
FMTL TEST150      // Selects the TEST150 (e.g.) format
```

```
ALLU                // Applies the format to the generator
```

Any built-in formats may be used for this test. However, we recommend using several formats spread over a wide range of frequencies. For example, the Test150 format is commonly used to test at the maximum pixel frequency for HDMI. The DMT0660 format can be used to test at a very low frequency (25.175 MHz).

Use the following formats to test HDMI over a range of frequencies:

Format	Pixel rate (MHz)
TEST150	150.000
1080p60	148.500
720p60	74.250
DMT0660	25.200

7. Enter the following commands to run the pseudo-random noise test.

```
PNSP 100  // sets pseudo-random noise for 100 sequencs
PNAU      // runs the pseudo-random noise test for the specified
             number of frames
```

Note: *The test will stop automatically if configured to run in the single or multi-shot mode. If you initiate the test in the continuous mode, you will have to enter a carriage return to halt the test after PNAU is invoked.*

8. Enter the following commands to view the results of the test.

```
GPER?     // returns the pixel error rate in errors per billion
GNPT?     // returns the number of pixels measured in billions
GCET?     // returns the number of bad pixels for R, G, B components
GFED?     // returns information about the first error encountered
```

Analyzing pixel data (pixel error test)

The following is an example of using commands to test an HDMI/DVI transmit device's pixel data using pixel error test.

To view specific timing information of an external HDMI/DVI source signal:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Using a terminal emulator, establish a terminal connection with the generator. Refer to "Establishing a terminal session with the generator" on page 31.
3. Choose the connector to which the transmit device is connected by entering the following commands:

```
XVSI:IN 1      // Selects the HDMI-1 input connector
ALLU           // Applies the interface setting to the generator
```

4. Choose the **HDMI-H** (or **HDMI-D**) item by entering the following commands:

```
XVSI 4 (or 3)  // Selects the HDMI-H or HDMI-D interface
ALLU           // Applies the interface setting to the generator
```

5. Enter the following commands to load a valid HDMI or DVI format into the analyzer.

```
FMTL DMT0660   // loads the DMT0660 (e.g.) format into the edit buffer
FMTU           // applies the format to the generator/analyzer
```

6. Enter the following commands to setup the measurement of pixel data.

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
```

7. Enter the following commands to initiate the pixel data measurement test.

```
PDAU           //runs the pixel data analysis test
```

8. Enter the following command to query for the results of the pixel data measurement test.

```
PDAX:ERRQ? 10 100   //retrieves 100 errors starting at the 10th error
                      in the index.
2, 110, 220, 128, 255, 64, 129, 250, 64 // shows the results
```

9. Enter the following command to query for the number of detailed error records.

```
PDAX:NERR?         //retrieves number of detailed errors recorded.
111                // shows the results
```

Reading pixel data

The following is an example of using commands to read the pixel component values of a captured frame from an HDMI/DVI transmit device.

To view specific timing information of an external HDMI/DVI source signal:

1. Connect the HDMI/DVI transmit device to an HDMI IN connector on the generator.
2. Using a terminal emulator, establish a terminal connection with the generator. Refer to “Establishing a terminal session with the generator” on page 31.
3. Choose the connector to which the transmit device is connected by entering the following commands:

```
XVSI:IN 1      // Selects the HDMI-1 input connector
ALLU           // Applies the interface setting to the generator
```

4. Choose the **HDMI-H** (or **HDMI-D**) item by entering the following commands:

```
XVSI 4 (or 3)  // Selects the HDMI-H or HDMI-D interface
ALLU           // Applies the interface setting to the generator
```

5. Enter the following commands to load a valid HDMI or DVI format into the analyzer.

```
FMTL DMT0660   // loads the DMT0660 (e.g.) format into the edit buffer
FMTU           // applies the format to the generator/analyzer
```

6. Enter the following commands to setup the measurement of pixel data.

```
PDAX:CAPF      //captures a frame of pixel data for the pixel
                 data analysis test
```

7. Enter the following command to query the pixel data of the captured frame.

```
GPEL? 10 100   //retrieves pixel values at X = 10 and Y = 100
```

Controlling the analyzer with Signal Analysis Module

You can operate the Analyzer timings functions through the Signal Analysis Module (SAM) application. The Signal Analysis Module is a Java-based GUI application available through the 882 generator's internal web server.

This section describes analyzer functions available through the Signal Analysis Module and provides examples of procedures you can use to perform analyzer tasks.

Setting up the Signal Analysis Module

The Signal Analysis Module application is a Java application or applet. You can run the application from the generator web server.

Note: *You must also have the Java Runtime Environment (JRE) 1.5 or later installed on your PC. You can download the JRE from the following website: http://www.java.com/en/download/windows_ie.jsp*

The Signal Analysis Module is supported on generators with Release 2.3.x and higher. This release has the following firmware and gateware configuration.

Software component	882CA Version
Boot Rom	01.04.11
vxWorks	20.1883000
Gateware 1	253F,75,4252006 (Tx p253fpga.bit)
Gateware 2	253A,7,4252006 (Rx p253Rxfpga.bit

Running the Signal Analysis Module

This subsection provides procedures on launching the Signal Analysis Module from the generator web server and from your PC.

To run the Signal Analysis Module from the web server:

1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/.

   The generator home page appears in the browser.




2. Click on **SAM+** (Signal Analysis Module).

   The Signal Analysis Module main page appears as a separate application window as shown below:

Measuring Timing with the Signal Analysis Module

This subsection provides procedures on measuring timing with the Signal Analysis Module. When measuring timing the application will measure the timing parameters and identify the format within the 882's default format library that most closely matches the values measured. It will then display that format and compare the measured timing values with the timing values of the identified standard format. A Pass/Fail indication is provided on the right-most field. The Pass/Fail determination is made by comparing the measured values from the source with expected values from the default format.



To set up the generator:

1. Connect an HDMI-to-HDMI cable between the HDMI source device under test and either of the HDMI IN connectors on the generator.
2. Activate the HDMI-H interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                    CVBS
  HDMI-D               S-VIDEO
  HDMI-H                  SDI
```

   b. Choose either the **HDMI-H** item by pressing the adjacent soft key.

   The interface is activated and the port outputs the currently selected image and format.


```
  VGA                    CVBS
  HDMI-D              S-VIDEO
 *HDMI-H                 SDI
```

   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```


To monitor measure timing:

1. Set up the generator/analyzer for HDMI in accordance with the instructions above.
2. In the Signal Analysis Module, input the appropriate information in the **Source Device Information** box. This includes the Source Device Type, Source Device Make, Source Device Model, Source Device Serial Number, and the HDMI Input Port Number information.




3. To take a measurement, click **Append Measurement** under the **Commands** box.

   Measurement will appear under appropriate headings in the table at bottom of the page.




TEST NUMBER	DVIC	NAME	HTOT	HRES	HSPD	HSPW	HSPP	HVPD	VTOT	VRES	VSPD	VSPW	VSPP	SCAN	FRAT	RESULT
1	1	DMT0660	800	640	16	96	0	0	525	480	10	2	0	1	60.000	PASS
2	4	720p60	1650	1280	110	40	1	0	750	720	5	5	1	1	60.001 60.000	PASS
3	5	1080i30	2200	1920	88	44	1	0	1125	1080	2	5	1	2	29.999 30.000	PASS

4. Check the **Display Headers and Values Using HDMI Compliance Test Specification Nomenclature** check box to display headers and values according to the HDMI Compliance Test Specification Nomenclature.




5. Click **Save Results** to save the results of the Append Measurement Command.




6. Browse to find the correct folder and type in the file name in the File Name box. Place a check mark next to **Generate HTML Report** to save the file in HTML format as well as an .xml format.

   A browser window will open displaying the html document as shown below.



   If **Generate HTML Report** is not checked, the file will be saved in XML format only. The XML file will not automatically display in the browser, you will need to manually open the browser window and browse for the XML file and open it.




```
- <test_results>
    <date>Jun 2, 2006</date>
    <time>12:32:36 PM</time>
  - <generator_id>
      QuantumData,882CA-AN-SDI-CEC-TME,6010027,20.1883200
    </generator_id>
    <generator_gateware_version>253C,36,127,2005:253F,75,4252006:253A,7,4252006</generator_gateware_version>
    <source_device_type>DVD</source_device_type>
    <source_device_make>ACME</source_device_make>
    <source_device_model>DVD-LX1</source_device_model>
    <source_device_serial_number>12345</source_device_serial_number>
    <source_device_hdmi_port>Port 1</source_device_hdmi_port>
    <present_using_hdmi>0</present_using_hdmi>
  - <result>
      <testnumber>1</testnumber>
      <perfect_match>0</perfect_match>
      <test_status>PASS</test_status>
      <closest_format>1080i30</closest_format>
      <hdmi_spec_format_name>1920x1080i @ 59.94/60Hz</hdmi_spec_format_name>
      <dvic>5</dvic>
      <scan>2</scan>
      <hspp>1</hspp>
      <vspp>1</vspp>
      <vtot>1125</vtot>
      <htot>2200</htot>
      <hres>1920</hres>
      <vres>1080</vres>
      <hspd>88</hspd>
      <vspd>2</vspd>
      <hspw>44</hspw>
      <vspw>2</vspw>
      <hvpd>0</hvpd>
      <hrat>33752</hrat>
      <frat>30.002</frat>
      <prat>74254400.000</prat>
```

Generating pseudo-random noise from an external source

This section explains how to implement pseudo-random noise is your own device. Once implemented, the Analyzer can test and analyze the transmission quality of an external HDMI/DVI transmit device using pseudo-random noise.

Implementing pseudo-random noise on an external source

The Analyzer can test and analyze pixel data received from an HDMI/DVI source. To accomplish this, a pseudo-random noise pattern is used that provides a sequence of highly dynamic pixel values.

To maximize your ability to analyze pixel data generated by set-top boxes, you must be able to generate pseudo-random noise. To facilitate this, you can use the lfsr.h and lfsl.cpp source code files from http://www.quantumdata.com/support/resources/pr_noise/QDI-BCM_PseudoNoise.ZIP, which enable you to generate QDI-BCM pseudo-random noise from your device.

Once implemented, you can verify that the code is implemented correctly by using the Dump10K() function to write the first 10,000 pixel values to a file. This result should match the contents of the PN_31_24.txt reference file included in http://www.quantumdata.com/support/resources/pr_noise/QDI-BCM_PseudoNoise.ZIP.

lfsr.h

The following source code is provided for the lfdr.h file.

```
// LFSR.h: interface for the CLFSR class.

#if !defined(AFX_LFSR_H__5947F6F9_1DBE_4E6E_9AFB_77D5D8857A10__INCLUDED_)
#define AFX_LFSR_H__5947F6F9_1DBE_4E6E_9AFB_77D5D8857A10__INCLUDED_

#if _MSC_VER > 1000
#pragma once
#endif // _MSC_VER > 1000

class CLFSR
{
public:
     void Dump10K();
     unsigned long GetPixel();
     void Reset();
     CLFSR();
     virtual ~CLFSR();

protected:
     int state;
     unsigned long seed;
```

```
};

#endif //
!defined(AFX_LFSR_H__5947F6F9_1DBE_4E6E_9AFB_77D5D8857A10__INCLUDED_)
```

lfsl.cpp

The following source code is provided for the tfsl.cpp file.

```
// Implementation of the CLFSR class
#include "LFSR.h"
#include <stdio.h>
#ifdef _DEBUG
#undef THIS_FILE
static char THIS_FILE[]=__FILE__;
#define new DEBUG_NEW
#endif

// enable this to light up pixels 1,2,3 as red,green,blue
// in horizontal order
// Pixel 1 represents the top left corner of the screen
// when this is enabled, all other pixels are black
//#define RGB_TEST

// Construction/Destruction

unsigned long pixelvalue;

CLFSR::CLFSR()
{

}

CLFSR::~CLFSR()
{

}

void CLFSR::Reset()
{
     state=0;
     seed=0x08000001;

}

// Pixel 1 should be 0x000000
// Pixel 2 should be 0x00 (7-bits) , Opcode(10-bits),  SeedHigh(7 bits)
// Pixel 3 should be SeedLow (24 bits)
// All other pixels are then set based on the results of the LFSR
calculations.
// The 10-bit Opcode is custom per Quantum Data's request and it will be
set to '00,0000,0111'.
unsigned long CLFSR::GetPixel()
```

```
{
     unsigned long temp;

     // states 0 to 2 are specific for QuantumData
     switch (state)
     {
     // pixel 1
     case 0:
               pixelvalue=seed;
               state++;

#ifdef RGB_TEST
               return (0xff0000); // red
#else
               return(0);
#endif
               break;

     // pixel 2
     case 1:
               temp=((0x007<<7) | (( seed &0x7f000000)>>24)) & 0xffffff;
               state++;
#ifdef RGB_TEST
               return (0x00ff00); // green
#else
               return(temp);
#endif
               break;

     // pixel 3
     case 2:
               temp=seed &0x00ffffff;
               state++;
#ifdef RGB_TEST
               return (0x0000ff); // blue
#else
               return(temp);
#endif
               break;

     default:


               pixelvalue= ((pixelvalue & 0x7f)<<24) | ( ((pixelvalue>>4)
& 0xffffff) ^ ((pixelvalue>>7) & 0xffffff) );
#ifdef RGB_TEST
               return (0x0); // blank
#else
               return(pixelvalue & 0xffffff);
#endif
               break;
               break;
     }
```

```
}

void CLFSR::Dump10K()
{
     int i;
     FILE* f;
     char s[100];
     f=fopen("c:\\temp\\noise.txt","w");
     Reset();
     for (i=0;i<10000;i++)
     {
          sprintf(s,"%.6lx",GetPixel());
          fprintf(f,"%s\r\n",s);
     }

//     AfxMessageBox("See c:\\temp\\noise.txt");
     fclose(f);
```

10 Testing HDMI Sink Devices

Topics in the chapter:

- Overview of HDMI display testing
- Setting up the generator for HDMI testing
- Testing HDMI displays
- Testing HDMI 1.3 displays
- Testing HDMI video pixel repetition (882 only)
- Testing HDMI audio
- Testing HDMI InfoFrames (882 only)

Overview of HDMI display testing

The HDMI option enables the generator to test HDMI-compliant displays. With the HDMI option, the generator outputs HDMI-compatible TMDS video and data packets containing audio and auxiliary information.

Note: *This chapter does not provide HDMI compliance test procedures. HDMI EDID compliance testing procedures are provided in "Testing EDID for HDMI compliance in display (sink) devices" on page 593.*

The HDMI option provides the following features:

- Advanced E-EDID parsing
- Generation of all EIA/CEA-861-C formats below 165 MHz (with all possible variations)
- Pixel repetition test capabilities
- Internal sine wave generator up to 8 channels and external SPDIF audio input for audio testing
- AFD test capabilities
- Automatic and manual InfoFrame configuration


Note: *This chapter refers to the EIA/CEA-861C standard, which may be purchased from http://global.ihs.com/.*

This section describes how to test digital displays with HDMI interfaces.

Physical connections


The generator has two HDMI OUT(Tx) connectors for testing HDMI displays. In addition, the generator also has an SPDIF-A/V connector which allows external SPDIF audio to be input to the HDMI signal. To use the SPDIF-A/V connector, an RCA-to-VGA cable is included with the generator.

The following figure shows the location of these connectors on a generator with the HDMI option.



Interface	Description
1	**SDI/HD-SDI** connector outputs a serial digital signal per SMPTE 259M and SMPTE 292M standards.
2	**CVBS** connector outputs an analog composite video baseband signal in accordance with SMPTE 170M standard.
3	**S-VIDEO** connector outputs an S-Video split luminance (Y) and chrominance (C) analog video signal.
4	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse • pixel clock signal
5	**VGA OUT** connector outputs a analog component video or analog RGB signal.
6	**HDMI OUT 1** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
7	**HDMI OUT 2** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
8	**HDMI IN 1** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
9	**HDMI IN 2** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
10	**SPDIF-AV** connector inputs audio from an external source.

This section describes the generator's video interfaces. The video interfaces on the 882D are shown below.



Interface	Description
1	**SDI/HD-SDI** connector outputs a serial digital signal per SMPTE 259M and SMPTE 292M standards.
2	**CVBS** connector outputs an analog composite video baseband signal in accordance with SMPTE 170M standard.
3	**S-VIDEO** connector outputs an S-Video split luminance (Y) and chrominance (C) analog video signal.
4	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse • pixel clock signal
5	**HDMI OUT** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
6	**DVI** connector outputs full dual link HDMI video.
7	**SPDIF** connector inputs audio from an external source.

Format selection

To support HDMI, the generator provides pre-defined formats for every video format specified in the EIA/CEA-861-C standard. These pre-defined formats support all aspects of the HDMI signal (video, audio, and auxiliary data).

The following table lists those generator formats used to test support for HDMI (EIA/CEA-861-C).

EIA/CEA-861-C Video Identification Code	Quantum Data format
1	DMT0659, DMT0660
2	480p59, 480p60, 480p59LH, 480p60LH
3	480p59SH, 480p60SH
4	720p59, 720p60
5	1080i29, 1080i30
6	480i2x29, 480i2x30, 480i2xL1, 480i2xL2
7	480i2xS1, 480i2xS2
8	240p2x_1, 240p2x_2, 240p2x_3, 240p2x_4, 240p2xL1, 240p2xL2, 240p2xL3, 240p2xL4
9	240p2xS1, 240p2xS4, 240p2xS3, 240p2xS4
10	480i4x29, 480i4x30, 480i4xL1, 480i4xL2
11	480i4xS1, 480i4xS2
12	240p4x_1, 240p4x_2, 240p4x_3, 240p4x_4, 240p4xL1, 240p4xL2, 240p4xL3, 240p4xL4
13	240p4xS1, 240p4xS2, 240p4xS3, 240p4xS4
14	480p2x59, 480p2x60, 480p2xL1, 480p2xL2
15	480p2xS1, 480p2xS2
16	1080p59, 1080p60
17	576p50, 576p50LH
18	576p50SH
19	720p50
20	1080i25
21	576i2x25, 576i2xLH
22	576i2xSH
23	288p2x_1, 288p2x_2, 288p2x_3, 288p2xL1, 288p2xL2, 288p2xL3
24	288p2xS1, 288p2xS2, 288p2xS3
25	576i4x25, 576i4xLH
26	576i4xSH
27	288p4x_1, 288p4x_2, 288p4x_3, 288p4xL1, 288p4xL2, 288p4xL3
28	288p4xS1, 288p4xS2, 288p4xS3

EIA/CEA-861-C Video Identification Code	Quantum Data format
29	576p2x50, 576p2xLH
30	576p2xSH
31	1080p50
32	1080p23, 1080p24
33	1080p25
34	1080p29, 1080p30
35	480p4xL1, 480p4xL2, 480p4x59, 480p4x60
36	480p4xS1, 480p4xS2
37	576p4xLH, 576p4x50
38	576p4xSH
39	108Oi25_
40	1080i50
41	720p100
42	576p100, 576p100L
43	576p100S
44	576i2x50, 576i2xL1
45	576i2xS1
46	1080i59, 1080i60
47	720p119, 720p120
48	480p119L, 480p120L, 480p119, 480p120
49	480p119S, 480p120S
50	480i2xL3, 480i2xL4, 480i2x59, 480i2x60
51	480i2xS3, 480i2xS4
52	576p200, 576p200L
53	576p200S
54	576i2x_1, 576i2xL2
55	576i2xS2
56	480p239, 480p240, 480p239L, 480p240L
57	480p239S, 480p240S
58	480i2x_1, 480i2x_2, 480i2xL5, 480i2xL6
59	480i2xS5, 480i2xS6

Image selection

Once you have determined the formats appropriate for testing HDMI displays, you will apply a series of images suitable for evaluating the display. For digital fixed pixel displays, you typically want to select images to test for pixel anomalies, photometry, luminance, centering, resolution, and persistence.

Each image in the generator's library is intended to test one or more attributes of a particular display type and video type.

Note: *You can also create your own images. See "Creating custom images" on page 240 for details.*

The table below provides a summary of display characteristics and the images used to evaluate them.

Display type	Display test	Recommended images
Digital flat panel (fixed pixel display)	Pixel anomalies (stuck pixels, misc sampling)	Flat, Raster, Ramp_B, Ramp_G, and Ramp_R, Focus_@6, Focus_@7, Focus_@8, Focus_@9, Text_9, Text_9T, Text_11, Text_12T, Text_16
	Photometry (chrominance, contrast, levels)	Flat, Flat07, Flat13, Flat20, Flat27, Flat33, Flat40, Flat47, Flat53, Flat60, Flat67, Flat73, Flat80, Flat87, Flat93, FlatGray, Flat_01, Flat_02, Flat_03, Flat_04, Flat_05, Flat_06, Flat_07, Flat_08, Flat_09, Flat_10, Flat_11, Flat_12, Flat_13, Flat_14, Flat_15, Flat_16, Ramp_B, Ramp_G, and Ramp_R, ColorBar, SMPTEbar, SMPTE133
	Luminance	SMPTE133 (grayscale), Grays5, Grays9, Grays11, Grays16, Grays32, Grays64
	Centering	Outline0, Outline1, Outline2, Outline3
	Resolution	BurstTCE, Grill_11, Grill_15, Grill_22, Grill_33, Grill_44
	Persistence	Animated images: Persist, Cubes, SlideX

Setting up the generator for HDMI testing

This section provides general procedures for setting up the generator for HDMI testing. The procedures below can be performed using the front panel or the command line interface.

To set up the generator for HDMI testing:

1. Connect an HDMI-to-HDMI cable between the HDMI display device under test and the either one of the HDMI OUT connectors on the generator.
2. Activate the HDMI-H interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H** item by pressing the adjacent soft key.

   The interface is activated and the port outputs the currently selected image and format.



   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

3. (Optional) Disable the second HDMI output:
   a. Press the **Options** key. The following information appears on the generator's display.



   b. Disable the second output by pressing the soft key adjacent to the Disable 2 option. A + appears next to Disable 2 option, indicating it is enabled.

4. (Optional) Add an identification mark on the monitor of the HDMI output number 1.

   a. Press the **Options** key. The following information appears on the generator's display.

   ```
   +Output          Mark #1-
                  Disable 2-
   ```

   b. Add an identification mark on the monitor connected to the HDMI output 1 by pressing the soft key adjacent to the Mark #1 option. A + appears next to Mark #1 option, indicating it is enabled.

   A small colored patch appears on the upper right of the display connected to HDMI output 1.

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

   ```
   FMTL DMT0660
   FMTU
   ```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, ColorBar) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

   ```
   IMGL ColorBar
   IMGU
   ```

5. Verify that the image appears on the display under test.

Selecting video format

Once you have selected the interface type for the display under test, you need to select a video output format. A format defines a set of video, timing, and sync parameters for a specific device or standard. This section explains how to configure the generator to output video formats that are supported by the display under test.

Important: *If the display under test has not implemented hot plug correctly, you will have to bypass hot plug detection in the generator to enable video output. See below for procedure on bypassing hot plug detection.*

Note: *For more information about formats, see Chapter 6, "Working with Formats."*


Setting Source list of formats

The generator provides a Source list of standard (pre-defined) formats. The Source list can be set automatically when connecting to a EDID-compatible display. Otherwise, you can manually set which formats are listed.


To automatically set Source list of formats for EDID-compatible display:

When testing EDID-compatible displays, the generator can automatically update the Source list to include only formats supported by the display under test. To do this:

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.



3. Press the **Options** key. The following information appears on the generator's display.



4. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats indicating enabled.


   The generator loads the Source list with formats supported by the connected display (hot-plug formats read via EDID structure of attached display).

5. To redisplay all formats, press the soft key adjacent to EDID Formats. A '-' (minus sign) next to EDID Formats indicates it is disabled.

To bypass hot plug detection:

If the display under test has not implemented hot plug correctly, you will have to bypass hot plug detection in the generator to enable video output.

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.



3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats       CDF↖
+HP Bypass
-Emulate
```

4. Choose the **HP Bypass** (hot plug bypass) item by pressing the adjacent soft key. A + appears next to HP Bypass indicating enabled.

To manually set Source list of formats for non-EDID-compatible display:

When testing a display that is not EDID-compliant, the Source list is filtered to display only those formats suitable for a particular interface type. For example, if you select CVBS, the Source list does not include the VESA formats.

The generator's format library is comprised of a set of format catalogs. You can set up the generator to show only the formats you want, in the order you want, when you browse through the Source list. See "Format catalogs" on page 229 for details.

To use Emulate mode:

Emulate mode automatically sets color space, synchronization type, and other settings based on the interface and format selected:

- For VGA interface, synchronization type and color space are automatically set and are not changeable.
- For HDMI interface, synchronization type and color space are automatically set, but color space can be changed.

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats       CDF↖
+HP Bypass
-Emulate
```

4. Choose the **Emulate** item by pressing the adjacent soft key. A + appears next to Emulate indicating enabled.

   Alternatively, to select the emulate mode through the command line interface, enter the command shown below:

```
EMUG 1        // Enables emulate mode
```

To disable the emulate mode through the command line interface, enter the command shown below:

```
EMUG 0        // Disables emulate mode
```

Selecting a format

From the Source list of formats, you select the video format output for your display under test.

To select a format:

1. Identify the type of display (composite television, component standard definition television, component high definition television, computer equipment, or other specialty display).

   Note: *The generator has a library of standard formats. For a description of how the library is organized, see "Understanding the format library" on page 46.*

2. For non-EDID compliant displays, check the specifications of your display for supported formats.

3. Press the **Source** key to access the list of formats. A list of formats appears on the generator's display as shown below. To see all of the formats, press the + and - keys.

   ```
   *DMT0660          DMT0672
    DMT0675          DMT0685
    DMT0785H         DMT0856
    DMT0860          DMT0872
   ```

   Note: *The list of formats displays when pressing the* ***Source*** *key may be a filtered or abbreviated list. Formats not suitable for the selected interface type will not appear by default on the* ***Source*** *list. Also, you can disable format catalogs to prevent certain formats from appearing on the Source list. For more information about format catalogs, see "Format catalogs" on page 229.*

4. Choose a format by pressing the adjacent soft key.

Upon selecting a format, you can modify the format options and settings if necessary. For instructions on this, see "Configuring format parameters" on page 181.

Testing HDMI displays

This section provides procedures for testing HDMI displays. The procedures below can be performed using the front panel or the command line interface.

To test HDMI displays:

1. Set up the generator for HDMI output. See “Setting up the generator for HDMI testing” on page 338.
2. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```

3. Press the **Content** key and select the first test image. For digital fixed pixel displays, you typically want to select images to test for pixel anomalies, photometry, luminance, centering, resolution, and persistence. For more details on what images test these specific display attributes, see “Image selection” on page 337 or Appendix B, “Image Reference.”

   Alternatively, you can load the image with the following command:

   ```
   IMGL image_name
   IMGU
   ```

4. Repeat steps 1 and 2 for all formats and test images.

   Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See “Creating a test sequence” on page 262.*

   Use the following guidelines to verify proper operation:

   - When testing photometry such as chrominance, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - To test luminance, you can use the SMPTE133 (grayscale) images. To test gamma correction, you can use the SMPTE133 (checkerbox) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”
   - When testing for centering, use the Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
   - When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.

- When testing for pixel anomalies, use the Flat, Raster, and Ramp images. Use the Raster and Flat images to look for pixels that may be stuck on or off, respectively. The luminance should increase uniformly for the Ramp image. Also look for sparkles indicating problems with sampling.
- When testing for persistence with the animated images (Cubes and Persist), look for bleeding or trails in the wake of the moving object.

Testing HDMI 1.3 displays

This section provides procedures for testing HDMI 1.3 deep color displays using the 882E. There are specific images that have been created to test HDMI 1.3 deep color displays and there is an Image Control Tool accessible from the 882E web page interface that enables you to control these images.


Testing Deep Color

Image Control Tool

There are four images that can be controlled from the Image Control Tool but only three are used to test HDMI 1.3 deep color displays. These are listed and described below:

- Ramp12
- RampDif
- Checkers

The the Image Control Tool is accessible through the generator's home web page. It enables you to change various format and generator parameters, that applied to the test images, through a browser. The following is a view of the Image Control Tool:




The following table describes the functions on the upper most tabs of the Image Control Tool.

Tab	Function
Reset to Saved	Resets the current parameter settings on the image to the saved settings.
Save	Saves the parameter settings currently indicated for the image shown
Set to Defaults	Resets the parameter settings to their defaults


Ramp12 image

This image is used to view a specific range of grayscale levels (ranges up to 1024) throughout the entire range allowed by deep color support in the generator (i.e. 36 bit/pixel or 12-bit/component = 4096). If you set the ramp to display the maximum color depth supported by the display under test you will see a nearly uniform ramp depending on the horizontal resolution of the active format.

The following is a sample of the RampDif image is rendered on a display.



Refer to the image and table below to better understand the configuration and use of this image.



The following table describes the parameters of the Ramp12 image through Image Control Tool.

Function/Field	Function
Starting Level	This slide bar sets the beginning (left most) grayscale level in the ramp. This is expressed as a percentage of the total range defined by the setting of Number of Bits per Component (NBPC) from 0% to 100%. For example, if NBPC is 12 the total range is 4096 with a full gamut setting. Note that the 882E can only display up to 1024 colors or shades of gray simultaneously on one image (if PELD = 32).
PELD	This is the pixel depth within the generator. It defines the number of colors available to the generator for rendering simultaneously on an image. The valid values for the PELD pulldown select box are 8 and 32. A setting of 8 means there is a maximum of 256 on-screen luminance levels. A setting of 32 means there is a maximum of 1024 on screen luminance levels.
Gamut (Range)	Sets the number gamut (range) of the output levels. This corresponds to the DVQM parameter. The values are Max (DVQM=0), MaxTV(DVQM=1) and NomTV (DVQM=2) this is the default for TV formats.
Clr (Color) Space	This pulldown select box specifies the color space. This field corresponds to the DVST and DVSM commands. Valid values are: RGB (DVSM=0), YCbCr4:2:2 (DVSM=2), YCbCr4:4:4 (DVSM=4).
NBPC	This pulldown select box specifies the color depth per component. By setting this value to 12, the generator will put out 12 bit/component deep color video. When you change this field the setting is applied to the generator. Valid values are 8, 10 and 12.
GET	The GET activation button updates all the fields on the image control in the event changes are made directly on the front panel or through the command line. Associated with the GET activation button is a string of information that tells you what format is currently active.

Note: *The generator LCD will not show the updated values changed using the Image Control Tool in real time. You have to press the + key on the generator to update the LCD.*

For example, given the following settings:


- Format = 1080i30 (HRES = 1920)
- NBPC = 12 for 12-bit/component color
- PELD = 32 (maximum generator color)
- Clr Space (DVST) = RGB
- Gamut (DVQM) = NomTV (256 to 3760 [with RGB and NBPC =12])

the maximum range available is (3760 - 256 = 3504) grayscale levels. Since PELD is set to 32 (24 pixel depth in the generator) the maximum number or grayscale levels that can be rendered by the generator on a display is 1024. So if you set the **Starting Level** at 25%, the Ramp12 image will begin at the left with a grayscale level of 1132 (3504 * 0.25 = 876 + 256) and end at the right with a grayscale level of 2156 (1132 + 1024 = 2156). Because the horizontal image resolution of the format is 1920, you would see a ramp with bands of ~2.0 pixels each (1920 / 1024 = 1.89).


RampDif image

This image has two ramps. One on the top and one on the bottom. It enables you to show a contrast of color depths. For example you can specify that the top ramp use 12-bit/component deep color and the bottom ramp 10-bit color. You can then view the image and see whether banding occurs and how pronounced, in the either of the ramps. If the display under test supports 12-bit/component color, the top ramp will show a near uniform ramp on the top (depending on the horizontal resolution of the active format). The bottom ramp will show more pronounced banding because the range of the ramp is greater than the color depth.

This image is used to view two specific range of grayscale or color levels (ranges up to 512) throughout the entire range allowed by deep color support in the generator (i.e. 36 bit or 4096). You need to set the pixel depth in the generator to 24 bit (PELD = 32) in order to access 512 grayscale or color levels on a single image rendered on a display. The following is a sample of the RampDif image is rendered on a display.



Refer to the image and table below to better understand the configuration and use of this image.



The following table describes the parameters of the Image Control Tool.

Function/Field	Function
Color 1	These slide bars set the beginning color component and grayscale level (left most value) of the top and bottom ramps. This is expressed as a percentage of the total range defined by the setting of Number of Bits per Component (NBPC) from 0% to 100%. For example, if NBPC is 12 the total range is 4096 with a full gamut setting. Note that the 882E can only display up to 512 colors simultaneously for each ramp on this RampDif image (if PELD = 32).
Color 2	These slide bars set the ending color component and grayscale level (right most value) of the top and bottom ramps. This is expressed as a percentage of the total range defined by the setting of Number of Bits per Component (NBPC) from 0% to 100%. For example, if NBPC is 12 the total range is 4096 with a full gamut setting. Note that the 882E can only display up to 512 colors simultaneously for this RampDif image (if PELD = 32).

Function/Field	Function
PELD	This is the pixel depth within the generator. It defines the number of colors available to the generator for rendering simultaneously on an image. The valid values for the PELD pulldown select box are 8 and 32. A setting of 8 means there is a maximum of 256 on-screen luminance levels per ramp. A setting of 32 means there is a maximum of 1024 on screen luminance levels but only 512 per ramp.
Gamut (Range)	Sets the number gamut of the output signal. This corresponds to the DVQM parameter. The values are Max (DVQM=0), MaxTV(DVQM=1) and NomTV (DVQM=2) this is the default for TV formats.
Clr (Color) Space	This pulldown select box specifies the color space. When you change this field the setting is applied to the generator. This field corresponds to the DVST and DVSM commands. Valid values are: RGB (DVSM=0), YCbCr4:2:2 (DVSM=2), YCbCr4:4:4 (DVSM=4).
NBPC	This pulldown select box specifies the color depth per component on the *top* ramp. By setting this value to 12, the generator will put out 12 bit/component deep color video on the top ramp. Valid values are 8, 10 and 12.
Number of bits	This pulldown select box specifies the color depth per component on the *bottom* ramp. By setting this value to 12, the generator will put out 12 bit/component deep color video on the bottom ramp. Valid values are 4-12.
Grayscale mode	When checked this will set all three slide bars for each color component on each Color 1 and Color 2 to the same value. When unchecked you are free to set each color component to any value.
GET	The GET activation button updates all the fields on the image control in the event changes are made directly on the front panel or through the command line. Associated with the GET activation button is a string of information that tells you what format is currently active.

Note: *The generator LCD will not show the updated values changed using the Image Control Tool in real time. You have to press the + key on the generator to update the LCD.*

For example given the following settings:


- Format = 720p60 (HRES = 1280)
- NBPC = 12 for 12-bit/component color
- Number of Bits = 8 for 8-bit/component color
- PELD = 32 (maximum generator color)
- Clr Space (DVST) = RGB
- Grayscale mode = Checked (enabled)
- Gamut (DVQM) = NomTV (256 to 3760 [with RGB and NPBC =12])

the maximum range available is (3760 - 256 = 3504) grayscale levels. Since PELD is set to 32 (24 bit depth) the maximum number or grayscale levels that can be rendered by the generator on a display with the RampDif image is 1024 (512 per ramp). So if you set the **Color1** slide bar at 25% and the **Color2** slide bar at 75%, the level on the left of the top ramp would be 1132 ([3504 * 0.25] + 256 = 1132) and the level on the right end would be 2884 ([3504 * 0.75] + 256 = 2884). Since the top ramp can render 512 distinct levels you would see bands of ~2.5 pixels each (1280 / 512 = 2.5). Since the bottom ramp can render 256 distinct levels you would see bands of 5.0 pixels each (1280 / 256 = 5.0).

Checkers image

This image has two color checker or tile types arranged in a checker board pattern. It enables you to show a contrast in the tiles at a specified color depth. You can move the slide bars of each color such that they are close in color space. You can then view the image and see whether distinquish between the two tile types. You need to set the pixel depth in the generator to 24 bit (PELD = 32) in order to access 512 grayscale or color levels for each tile for a single image rendered on a display.

The following is a sample of the Checkers image is rendered on a display.



Refer to the image and table below to understand the configuration and use of this image.



The following table describes the parameters of the Image Control Tool.

Function/Field	Function
Color 1	These slide bars set the color component and grayscale level for one set of tiles. This is expressed as a percentage of the total range defined by the setting of Number of Bits per Component (NBPC) from 0% to 100%. For example, if NBPC is 12 the total range is 4096.
Color 2	These slide bars set the color component and grayscale level for one the other set of tiles. This is expressed as a percentage of the total range defined by the setting of Number of Bits per Component (NBPC) from 0% to 100%. For example, if NBPC is 12 the total range is 4096.
PELD	This is the pixel depth within the generator. It defines the number of colors available to the generator for rendering simultaneously on an image. The valid values for the PELD pulldown select box are 8 and 32. This parameter does not effect this image.

Function/Field	Function
Gamut (Range)	Sets the number gamut of the output signal. This corresponds to the DVQM parameter. The values are Max (DVQM=0), MaxTV(DVQM=1) and NomTV (DVQM=2) this is the default for TV formats.
Clr (Color) Space	This pulldown select box specifies the color space. This field corresponds to the DVST and DVSM commands. Valid values are: RGB (DVSM=0), YCbCr4:4:2 (DVSM=2), YCbCr4:4:4 (DVSM=4).
NBPC	This pulldown select box specifies the color depth per component on the *top* ramp. By setting this value to 12, the generator will put out 12 bit/component deep color video on the top ramp. Valid values are 8, 10 and 12.
Grayscale mode	When checked this will set all three slide bars for each color component on each Color 1 and Color 2 to the same value. When unchecked you are free to set each color component to any value.
Square Checks	Fixes the aspect ratio of the tiles to be the same width and height.
Check Width	Determines the width of each tile (checker element)
Check Height	Determines the height of each tile (checker element)
GET	The GET activation button updates all the fields on the image control in the event changes are made directly on the front panel or through the command line. Associated with the GET activation button is a string of information that tells you what format is currently active.

Note: *The generator LCD will not show the updated values changed using the Image Control Tool in real time. You have to press the + key on the generator to update the LCD.*

For example given the following settings:

- NBPC = 12 for 12-bit/component color
- Clr Space (DVST) = RGB
- Grayscale mode = Checked (enabled)
- Gamut (DVQM) = NomTV (256 to 3760 [with RGB and NBPC =12])

the maximum range available is (3760 - 256 = 3504) grayscale levels. So if you set the **Color1** slide bar at 50% and the **Color2** slide bar at 51%, the level for **Color1** tiles would be 2008 ([3504 * 0.50] + 256 = 2008) and the level for **Color2** tiles would be 2043 ([3504 * 0.51] + 256 = 2043). If the display under test supports 12 bit deep color you would be able to distinguish between the two tiles because the difference in the value (or grayscale) level between the two tiles would be within the granularity of a 12-bit/component display.

Accessing the Image Control Tool

The procedures below describe how to access the Image Control Tool.

To access the Image Control Tool:

1. Set up the generator for HDMI output. See “Setting up the generator for HDMI testing” on page 338.
2. Press the **Source** key and select the desired format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```


3. Open a Web browser (such as Internet Explorer) and type the generator’s IP address in the address entry field. For example, enter the following: http://206.135.215.189/.

   The generator home page appears in the browser.



4. Select the Image Control Tool link.

   The Image Control Tool appears in the browser.



Testing xvYCC

The 882E series test instrument enables you to test xvYCC displays. The feature provides test images and support for transmission of the gamut boundry definition (metadata transmission profile (only P0 currently).


The xvYCC or extended-gamut YCC is a color space that supports 1.8 times as many colors as the sRGB color space. The xvYCC color space uses the full range of values (1 to 254 in an 8-bit space) to represent colors.

The Munsell Color System provides a standard way of describing colors and can be applied to video systems. The Munsell Color System is shown in the figure below. A single color is represented by three separate parameters of color: 1) Hue, 2) Value and 3) Chroma. There are ten hues consisting of 5 basic hues and 5 intermediate hues. For each hue there is a number from 0 to 10 placed before the symbol for the hue. This number denotes the value which is the measure of lightness. The whitest value is given a 10 and placed at the top while black is given a 0 and placed at the bottom. Chroma is the measure

of the saturation of the color. The central axis is achromatic (grayscale) and is defined as 0 and the scale is arranged concentrically. The farther one moves away from the center, the greater the saturation.

The steps are arranged such that the degree of differentiation between each step is preceived to be equal. A value differential of 1 and a chroma differential of 2 are set up such that they are preceived visually as having the same degree of difference.

The figure below depicts the Munsell Color System:



All colors in the Munsell color cascade can be mapped to the xvYCC color space but only 55% of these colors can be mapped to the sRGB color space.

The 882E instrument provides Munsell images for testing displays that support xvYCC color space. The following images are used:


- MnslGM - This is a color checker image with 24 colors arranged in a checker board.
- MnslCLR - There are a series of these images (40 in total) that are accessible as sub images through the 882E front panel. Each hue in the MnslCLR image set has 4 sub hues, labeled 2.5, 5, 7.5 and 10, that represent a hue as it traverses around the perimeter of the diagram above and transitions into the adjacent hues. Each such sub image depicts the chroma and value variances of one of these sub hues. Each sub image provides a color block for each chroma and value level for that sub hue. The value varies along the vertical axis and the chroma varies along the horizontal axis.

- MnslPG - There are a series of these images (5 in total) that are accessible as sub images through the 882E front panel. Each sub image depicts two hue families (each hue family contains 4 sub hues (2.5, 5, 7.5, 10). Each set of color blocks arranged along a horizontal axis depicts the chroma and value variations for one of the sub hues which is labeled on the left. Each such horizontal set of color blocks is a cancatenation of the value and chroma variations for that particular hue. These cancatenations can be derived from the MnslCLR images. In other words, the MnslPG image is a concatenation of 8 of the MnslCLR images.

The MnslGM Image is shown below.

Note: *The image as shown in this User Guide is not representative of how it will actually appear on an xvYCC display.*


This image can be used with a color probe to determine if the colors rendered on the xvYCC display match the true color.



The MnsCLR Image is shown below. The example below shows only one of the 40 subimages. There are a series of these images (40 in total) that are accessible as sub images through the 882E front panel. Each hue in the MnslCLR image set has 4 sub hues, labeled 2.5, 5, 7.5 and 10, that represent a hue as it traverses around the perimeter of the diagram above and transitions into the adjacent hues. Each such sub image in the MnslCLR image depicts the chroma and value variances of one of these sub hues. Each sub image provides a color block for each chroma and value level for that sub hue. The value varies along the vertical axis and the chroma varies along the horizontal axis.

Note: *The image as shown in this User Guide is not representative of how it will actually appear on an xvYCC display.*


When examining this image on an xvYCC display the differences between adjacent colors should be preceived to be the same. Note that this depends on how you have implemented the feature. Typically if you see adjacent colors that look very similar or strikingly different, then this indicates that the colors may not be represented properly on the display.



The MnsPG Image is shown below. The example below shows an image that displays two (2) of the eight (8) hue families (in this case Yellow and Green Yellow). There are a series of these images (40 in total) that are accessible as sub images through the 882E front panel. Each hue in the MnsICLR image set has 4 sub hues, labeled 2.5, 5, 7.5 and 10, that represent a hue as it traverses around the perimeter of the diagram above and transitions into the adjacent hues. Each such sub image depicts the chroma and value variances of one of these sub hues. Each sub image provides a color block for each chroma and value level for that sub hue. The value varies along the vertical axis and the chroma varies along the horizontal axis.

Note: *The image as shown in this User Guide is not representative of how it will actually appear on an xvYCC display.*

When examining this image on an xvYCC display the differences between adjacent colors should be preceived to be the same. Note that this depends on how you have implemented the feature. Typically if you see adjacent colors that look very similar or strikingly different, then this indicates that the colors may not be represented properly on the display.



To test an HDMI display for xvYCC:

1. Set up the generator for HDMI output. See “Setting up the generator for HDMI testing” on page 338.
2. Press the **Source** key and select the desired format.

   Alternatively, you can load the format with the following command:

```
FMTL format_name
FMTU
```

3. Press the **Options** key and select xvYCC colorimetry.

   There are two color standards, xvYCC601 and xvYCC709. The appropriate one is selected depending on the format.

```
 RGB              8-bits
 YCbCr           10-bits
*xvYCC           12-bits
*4:4:4             4:2:2
```

   Alternatively, you can load the xvYCC color space with the following command:

```
DVST 16
FMTU
```

4. Press the **Content** key and select the desired Munsell images as shown in the following menu.

```
 MESony_R        MnslCLR
*MnslGM           MnslPG
 MoireX         MoireX33
 MoireY         MoireY33
```

   Alternatively, you can load the format with the following command:

```
IMGL MnslClr
IMGU
```

5. Enable and view image versions as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                     Red+
-NoGamma           Green+
-Noise              Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + appears next to **More** and **Rendition** appears on the other side of the menu.

```
+More    Rendition: 000
                     Red+
-NoGamma           Green+
-Noise              Blue+
```

   c. Press the + and - keys to advance through the image versions. Each version shows the format parameters for a different format in the Source list.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
```

```
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
IVER 2      // Specifies the second image version
IMGU        // Activates the image version
```

6. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0      // Disables sub images
```

Testing HDMI video pixel repetition (882 only)

The EIA/CEA-861-B standard defines a number of progressively-scanned gaming formats which support variable horizontal resolutions. These formats maintain a fixed 2880-pixel format timing and use pixel repetition to provide 10 different effective horizontal resolutions. A special blanking scheme further reduces the number of active pixels (to those listed in the table below), thereby providing a horizontal safe area that insures that all of the pixels in a game will be visible on overscanned HDMI displays.

Note: *This feature is not supported on the 881 generator.*

To support HDMI gaming format and pixel repetition testing, the generator allows you to sequentially apply pixel repetition (up to 10 times) to a unique image. As the pixel repetition factor is increased, the horizontal resolution of the displayed image will decrease as shown in the table below.

Pixel repetition factor (image version)	Horizontal resolution
0	2880 pixels/line
1	2560 pixels/line
2	1280 pixels/line
3	853 pixels/line
4	640 pixels/line
5	512 pixels/line
6	427 pixels/line
7	366 pixels/line
8	320 pixels/line
9	284 pixels/line
10	256 pixels/line

To test HDMI video pixel repetition:

1. Set up the generator for HDMI output. See “Setting up the generator for HDMI testing” on page 338.

2. If you have auto configured the formats through the EDID you may have to disable this feature as follows:

   a. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

   b. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats       CDF↖
+HP Bypass
-Emulate
```

   c. Choose not to **EDID Formats** by pressing the adjacent soft key. A - appears next to EDID Formats, indicating it is disabled.


3. Press the **Source** key and select the first test format.

   Note: *Gaming formats on the generator have the characters "4x" in their names (such as "480i4x29" or "576i4x25"). For a listing of all HDMI formats, see the table on page 335. If you have auto configured the formats through the EDID you may have to disable this feature.*

   Alternatively, to select the format through the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL 480i4x29               // Loads the 480i4x29 format
FMTU                        // Activates the 480i4x29 format
```

4. Press the **Content** key and choose the PixelRep image by pressing the adjacent soft key. The PixelRep image appears on the HDMI display.



Alternatively, to select the PixelRep image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL PIXELREP               // Loads the PixelRep image
IMGU                        // Activates the PixelRep image
```

5. Enable and view image versions for the PixelRep image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```


   c. Press the + and - keys to advance through the image versions.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
```

```
IMGU        // Activates the image version
```

The pixel repetition factor appears in the center of the image. For instance, the image displaying a pixel repetition factor of 4 (“Sent 4”) is shown in the example below.



6. To verify proper handling of the selected HDMI gaming format, check the following in the image on the HDMI display:
   - The horizontal active area is resized to the appropriate number of clocked pixels using vertical bars to the left and right of the default (2880 pixel) image.
   - The white vertical borders and circles in the active area appear thicker.
   - The white text in the center of the active area appears stretched and bigger.
7. Select additional pixel repetition factors (as desired) to verify proper handling of the selected HDMI gaming format using variable horizontal resolutions.
8. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

   ```
   ISUB 0      // Disables sub images
   ```
9. To test another HDMI gaming format, return to step 3.

Testing HDMI audio

This section provides steps on how to test handling of audio packets by an HDMI display. Testing can be performed using audio originating from both internal (generator) and external sources. The generator supports both 2-channel SPDIF audio from internal source and external source and up to 8-channel audio from an internal audio source. There are separate sets of images for testing 2-channel SPDIF audio and 8-channel audio.

The procedures describe how you can vary the audio amplitude, audio frequency and audio sampling rate for 2-channel or 8-channel audio. Note that there are some limitations for the 8-channel audio at high sampling rates these are described below.

Testing 2-channel HDMI audio output from internal SPDIF source

To support testing of HDMI audio, the generator provides two-channel LPCM audio (using an internally-generated sinewave) at the highest audio sampling rate (48 kHz). Multiple scenarios are provided that allow you to test one or both audio channels at different amplitudes and frequencies, as well as test using the different supported sampling rates. The sampling rate for all channels is completed through a single image (AudioRAT).

The following table lists the images used to perform HDMI audio testing using an internal audio source.

Image	Description
AudioLR	Left and right audio channel output with adjustable amplitude.
AudioLRf	Left and right audio channel output with adjustable frequency.
AudioRAT	Left and right audio channel output with adjustable sampling rate.
Audio_L	Left audio channel output with adjustable amplitude.
Audio_Lf	Left audio channel output with adjustable frequency.
Audio_R	Right audio channel output with adjustable amplitude.
Audio_Rf	Right audio channel output with adjustable frequency.

To test an HDMI display using HDMI audio from the generator:

1. Set up the generator for HDMI output. See “Setting up the generator for HDMI testing” on page 338.
2. Press the **Source** key and select the first test format (either DMT0660 or 480i2x29).


   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL 480i2x29               // Loads the 480i2x29 format
```

```
FMTU                          // Activates the 480i2x29 format
```

3. Press the **Content** key and choose an audio image (for example, AudioLR).

   The selected image appears on the connected HDMI display. The image shows the current settings for the HDMI audio output. For example, the AudioLR image is shown below.



   Alternatively, to select the audio image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIOLR                // Loads the AudioLR image
IMGU                        // Activates the AudioLR image
```

4. Enable and view image versions for the AudioLR image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions.

Note: *Depending on the selected image, pressing the + and - keys will change the amplitude or frequency of the HDMI audio output.*

Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

5. To verify proper HDMI audio handling, check the following on the HDMI display:
   - Audio is output from the proper channels (left, right, or both).
   - When amplitude is adjusted, the volume is subsequently changed.
   - When frequency is adjusted, the pitch is subsequently changed.
6. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

   ```
   ISUB 0     // Disables sub images
   ```
7. Press the **Content** key and choose the AudioRAT image to test the sampling rate.

   The AudioRAT image appears on the connected HDMI display. The image shows the current settings for the HDMI audio output. Note that the sampling rate image (AudioRAT) applies to all audio channel.

   Alternatively, to select the AudioRAT image using the command line interface, enter the following commands:

   ```
   IMGP /tffs0/Library/Images  // Set image path to generator memory
   IMGL AUDIORAT               // Loads the AudioRAT image
   IMGU                        // Activates the AudioRAT image
   ```

8. Enable and view image versions for the AudioRAT image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions to change the audio sampling rate.

   Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

9. To test another HDMI audio output type, repeat the procedure.

Testing 8-channel HDMI audio output from internal source

To support testing of HDMI audio, the generator provides 8-channel LPCM audio (using an internally-generated sinewave) at the highest audio sampling rate (192 kHz). Multiple scenarios are provided that allow you to test all audio channels at different amplitudes and frequencies, as well as test using the different supported sampling rates. The sampling rate for all channels is completed through a single image (AudioRAT).

High audio sampling rates and channel counts may require additional bandwidth in the blanking intervals. The required additional blanking intervals may only be available with high definition formats for example 720p and 1080i. When outputting 8 channels, the audio sampling rate is only guaranteed to 96kHz and requires that you use a high definition format.

Only two channels are guaranteed at the 192kHz sampling rate. These two channels must be from the generator's internal sine wave generator as the SPDIF input is only guaranteed to 96kHz.

Note also that your receiving device must support 8-channel audio.

The following table lists the images used to perform HDMI audio testing using an internal audio source for 8 channels.

Note: *Selecting any of the numbered images (for example, Audio_1, Audio_2, etc.) causes all other channels to be deactivated.*

Image	Description
Audio_1	Channel 1 output with adjustable amplitude.
Audio_1f	Channel 1 output with adjustable frequency.
Audio_2	Channel 2 output with adjustable amplitude.
Audio_2f	Channel 2 output with adjustable frequency.
Audio_3	Channel 3 output with adjustable amplitude.
Audio_3f	Channel 3 output with adjustable frequency.
Audio_4	Channel 4 output with adjustable amplitude.
Audio_4f	Channel 4 output with adjustable frequency.
Audio_5	Channel 5 output with adjustable amplitude.
Audio_5f	Channel 5 output with adjustable frequency.
Audio_6	Channel 6 output with adjustable amplitude.
Audio_6f	Channel 6 output with adjustable frequency.
Audio_7	Channel 7 output with adjustable amplitude.
Audio_7f	Channel 7 output with adjustable frequency.
Audio_8	Channel 8 output with adjustable amplitude.
Audio_8f	Channel 8 output with adjustable frequency.
Audio_X	All channels output with adjustable amplitude.
Audio_Xf	All channels output with adjustable frequency.

To test an HDMI display using HDMI 8-channel audio from the generator:


1. Set up the generator for HDMI output. See “Setting up the generator for HDMI testing” on page 338.
2. Press the **Source** key and select the first test format (for example: DMT0660 or 480i2x29).

   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL 480i2x29               // Loads the 480i2x29 format
FMTU                        // Activates the 480i2x29 format
```

3. Press the **Content** key and choose one of the audio images used for amplitude adjustment (for example, Audio_1).

   The image appears on the connected HDMI display. The image shows the current settings for the HDMI audio output. For example, the Audio_1 image is shown below.



   Alternatively, to select the audio image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIO_1                // Loads the Audio_1 image
IMGU                        // Activates the Audio_1 image
```

4. Enable and view image versions to modify the audio amplitude for the Audio_1 image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions to change the audio intensity.


Note: *Depending on the selected image, pressing the + and - keys will change the amplitude or frequency of the HDMI audio output.*

Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

5. To verify proper HDMI audio handling, check the following on the HDMI display:
   - Audio is output from the proper channels (left, right, or both).
   - When amplitude is adjusted, the volume is subsequently changed.
6. Press the **Content** key and choose one of the audio images used for frequency adjustment (for example, Audio_1f).

   The image appears on the connected HDMI display. The image shows the current settings for the HDMI audio output. For example, the Audio_1f image is shown below.



   Alternatively, to select the audio image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIO_1f               // Loads the Audio_1f image
IMGU                        // Activates the Audio_1f image
```

7. To verify proper HDMI audio handling, check the following on the HDMI display:
   - Audio is output from the proper channels (left, right, or both).
   - When frequency is adjusted, the pitch is subsequently changed.

8. Press the **Content** key and choose the AudioRAT image to test the sampling rate.

   The AudioRAT image appears and shows the current settings for the HDMI audio output. Note that the sampling rate image (AudioRAT) adjusts the sampling rate for all audio images.

   Alternatively, to select the AudioRAT image using the command line interface, enter the following commands:


```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIORAT               // Loads the AudioRAT image
IMGU                        // Activates the AudioRAT image
```

9. Enable and view image versions for the AudioRAT image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:



   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.



   c. Press the + and - keys to advance through the image versions to change the audio sampling rate.

   Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

10. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a '-' (minus sign) appears next to it.

    Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0     // Disables sub images
```

11. To test another HDMI audio output channel or format, repeat the procedure.

Testing multi-channel compressed HDMI audio formats

The 882E instrument enables you to test HDMI compressed audio formats such as AC3, EAC3 and the HDMI 1.3 high bit rate lossless compressed audio such as Dolby TrueHD format. TrueHD's may carry up to 8 discrete audio channels, at a sample depth & rate of 24-bit/96 kHz (Blu-Ray Disc format specification allows also for encoding up to 6 channels at 192 kHz).

Multiple scenarios are provided that allow you to test all audio channels at different amplitudes and frequencies, as well as test using the different supported sampling rates. The sampling rate for all channels is completed through a single image (AudioRAT).

High audio sampling rates and channel counts may require additional bandwidth in the blanking intervals. The required additional blanking intervals may only be available with high definition formats for example 720p and 1080i. When outputting 8 channels, the audio sampling rate is only guaranteed to 96kHz and requires that you use a high definition format.

Only two channels are guaranteed at the 192kHz sampling rate. These two channels must be from the generator's internal sine wave generator as the SPDIF input is only guaranteed to 96kHz.

Note: *Unlike the uncompressed formats (linear PCM) the compressed audio test signals are generated from a file. As a result the amplitude and frequency cannot be adjusted through the audio test images.*

To test compressed audio formats on an HDMI device from the generator:

1. Set up the generator for HDMI output. See "Setting up the generator for HDMI testing" on page 338.
2. Press the **Source** key and select the first test format (for example: 720p60).


   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL 720p60                 // Loads the 720p60 format
FMTU                        // Activates the 720p60 format
```

3. Press the **Content** key and choose the Dolby audio image as shown below. Note that you can also select the DTS image to access the DTS audio clips.

```
ComFocus      ContBars
Crosshtc         Cubes
DecodAdj     DecodeChk
Diamond1         Dolby*
```

The image appears on the connected HDMI display. The image shows the currently selected compressed audio format.



Alternatively, to select the Dolby image using the command line interface, enter the following commands:

```
IMGP /Cache0/Images          // Set image path to generator memory
IMGL Dolby                   // Loads the Dolby image
IMGU                         // Activates the Dolby image
IMGL DTS                     // Loads the DTS image
IMGU                         // Activates the DTS image
```

Note: *You can output compressed audio formats through the command line without selecting the Dolby image. To do this you enter the following command:*

```
CAUD?   // Queries for the list of stored compressed audio clip
           configurations:
1:DTS, 5.1, 48000.00 [dts-48kHz-1509kbps-51ch.wav.pcm]
2:DTS(ES), 6.1, 48000.00 [DTES-ES-48kHz-1509kbps-61ch.wav.pcm]
3:DTS(HDHRA), 7.1, 192000.00 [dtshdhra-48kHz-5376kbps-71ch.wav.pcm]
4:DTS(HDHRA), 5.1, 192000.00 [dtshdhra-48kHz-3840kbps-51ch.wav.pcm]
5:DTS(HDHRA), 7.1, 192000.00 [dtshdhra-96kHz-5760kbps-71ch.wav.pcm]
6:DTS(HDMA), 5.1, 192000.00 [dtshdma-48kHz-VBR-51ch-HDMI_HBR.ba.pcm]
7:DTS(HDMA), 7.1, 192000.00 [dtshdma-48kHz-VBR-71ch-HDMI_HBR.ba.pcm]
```

```
8:DOLBY(AC3), 2.0, 48000.00 [2khz2ch-0dB_ac3.pcm]
9:DOLBY(EAC3), 2.0, 192000.00 [1khz2ch-20dB_ec3.pcm]
10:DOLBY(EAC3), 5.1, 192000.00 [1khz51ch-20dB_ec3.pcm]
11:DOLBY(EAC3), 7.1, 192000.00 [1khz71ch-1frame_ec3.pcm]
12:DOLBY(TRUEHD), 7.1, 192000.00 [1khz71ch-20dB_mlp.pcm]
13:DOLBY(TRUEHD), 2.0, 192000.00 [nxt2ch2s.mlp.pcm]
CAUD 8  // Sends a 2 channel Dolby AC3 clip with 192kHz sampling rate
           at 0dB out the HDMI output.
```

4. Enable and view image versions to select the other audio formats as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions to change the audio intensity.

   Note: *Depending on the selected image, pressing the + and - keys will change the amplitude or frequency of the HDMI audio output.*

   Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```


5. To verify proper HDMI audio handling, check the following on the HDMI display:
   - Audio is output from the proper channels (left, right, or both).
   - The proper audio format is shown on the Audio/Video receiver.

Testing HDMI audio using an external audio source


The 882 enables you to inject audio signals from an external SPDIF source (such as a DVD player) into the HDMI content stream. You can input IEC 61937 non-linear PCM encoded audio stream or compressed audio streams (for example AC-3 and DTS) into the SPDIF interface for output through the HDMI Tx connector.

To inject external audio into the HDMI stream:

- If you have the 882CA analyzer option you will have the VGA-to-RCA cable (part 30-00150). Connect the AV connector to the generator's SPDIF / AV port. Then connect the black RCA connector to the SPDIF output of the external audio source.



- If you have the 882C without the analyzer option, you will have the VGA-to-RCA cable (part 30-00148). Connect the AV connector to the generator's SPDIF / AV port. Then connect the red RCA connector to the SPDIF output of the external audio source.



- If you have the 882E, you will have the (30-00123) BNC to RCA adapter (provided) so you will need a standard RCA cable. Simply connect the RCA cable from the SPDIF IN connect to the SPDIF output of the external audio source.

To test an HDMI display using HDMI audio from an external source:

1. Set up the generator for HDMI output. See "Setting up the generator for HDMI testing" on page 338.
2. Connect the external audio source to the SPDIF-A/V connector on the generator as follows:
   a. For the 882CA, using the RCA-to-VGA cable provided with the generator, connect the J1 connector to the SPDIF-A/V connector on the generator. Then connect the red RCA connector to the external audio source.
   b. For the 882E, connect the external audio source to the SPDIF-A/V connector on the 882 using the BNC to RCA adapter provided with the 882.
3. Press the **Source** key and select a format suitable for the HDMI display (for example, DMT0660).

   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL DMT0660                // Loads the DMT0660 format
```

```
FMTU                          // Activates the DMT0660 format
```

4. Press the **Content** selection key and choose any image (for example, Master).

   Alternatively, to select the image using the command line interface, enter the following commands:

   ```
   IMGP /tffs0/Library/Images  // Set image path to generator memory
   IMGL MASTER                 // Loads the Master image
   IMGU                        // Activates the Master image
   ```

5. Configure the generator to use an external audio source by entering the following commands:

   ```
   SDMG 2
   FMTU
   ```

6. Set the sample frequency to match the frequency of the external source by entering the following command:

   ```
   ARAT 44.1E3 //(example only)
   ```

   Alternatively, configure the generator to detect the audio sampling rate from the channel header of the incoming digital audio by entering the following command:

   ```
   ARAT 0.0
   ```

   Note: *The default frequency is 48 kHz (which is used by DVD players). However, if the external source is an audio CD played on a DVD player, the player will output SPDIF with a sampling rate of 44.1 kHz (not 48 kHz). In this case, set the sampling frequency to 44.1 kHz (or reload the format, which will detect the sampling frequency automatically).*

7. Turn on the external audio source. The external audio signal will be encoded into the HDMI signal.

   Note: *The generator cannot independently control external source channels. You must use the device generating the audio signal to control the channels.*

8. To verify proper HDMI audio handling, check the following on the HDMI display:
   - Audio is output from the proper channels (left, right, or both).
   - When the volume is adjusted at the external source, the volume is subsequently changed.
9. Select additional audio images (as desired) to verify proper audio handling.
10. To test another HDMI audio output type, return to step 3.

Testing HDMI InfoFrames (882 only)

This section provides steps on how to test handling of auxiliary (InfoFrame) packets by an HDMI display. The generator loads and sends default Auxiliary Video Information (XAVI), Audio (XAUD), and Source Product Description (XSPD) InfoFrame packet buffers to the display for each format (see table on page 335 for a list of HDMI formats). The XAVI and the XAUD InfoFrame packets are sent at every frame (repeated mode), while the XSPD is sent only once. The XMPG and XGIF InfoFrames are gated off and not enabled.

Note: *This feature is not supported on the 881 generator.*

HDMI provides various types of auxiliary data in the form of InfoFrames. InfoFrames allow the HDMI source to keep an HDMI display informed as to "what is coming down the pipe" so that it can present the content optimally—without any viewer intervention.

There are five different types of InfoFrames:

- auxiliary video information (AVI)
- audio (AUD)
- source product description (SPD)
- MPEG information (MPG)
- generic (vendor-specific) information (GIF)

Each type carries information regarding a different aspect of the HDMI audio/video transmission.

The procedures below can be performed using the front panel or the command line interface.

Viewing InfoFrame contents (882 only)

The generator provides a convenient method for monitoring the InfoFrame content of the transmitted HDMI signal. The procedure below describes how to view current InfoFrame contents.

Note: *This feature is not supported on the 881 generator.*

To view current HDMI InfoFrame contents transmitted from the generator:

1. Set up the generator for HDMI output. See "Setting up the generator for HDMI testing" on page 338.
2. Press the **Source** key and choose a format suitable for the HDMI display (for example, DMT0660). Refer to the table in "Format selection" on page 334.

   Alternatively, to select the format using the command line interface, enter the following commands:


```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL DMT0660                // Loads the DMT0660 format
FMTU                        // Activates the DMT0660 format
```

3. Press the **Content** key and choose the PacketTx image.

   Alternatively, to select the image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images   // Set image path to generator memory
IMGL PacketTx                // Loads the PacketTx image
IMGU                         // Activates the PacketTX image
```

   The PacketTx image appears on the connected HDMI display. The image shows the current settings for the AVI InfoFrame output.



4. Enable and view image versions for the PacketTx image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                    Red+
-NoGamma          Green+
-Noise             Blue+
```

   c. Press the + key to advance through the image versions.

Note: *The contents of the appropriate InfoFrame output appears on the HDMI display.*

Alternatively, to select an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```


5. Select additional InfoFrame subimages (as desired) to verify proper InfoFrame handling.
6. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:


```
ISUB 0     // Disables sub images
```

To generate a report for the PacketTx image:

1. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



2. Choose the **Reports** item by pressing the adjacent soft key. The **Reports** menu appears on the generator's display as shown below.



3. Choose the **Packets** item by pressing the adjacent soft key. The **Packet** menu appears on the generator's display as shown below.



Note: *Be sure that you have transferred any existing PacketTx reports to your PC otherwise generating a new report will overwrite the existing report.*


4. Select the !**PacketTx** item by pressing the adjacent soft key to generate the report. The following appears on the display.

```
TX PACKETS


Finished
```

5. Select a suitable directory on your PC to store the report by navigating in the FTP Browser.
6. Transfer the report from the generator to your PC, using the FTP browser, by highlighting the report and clicking on the upload activation button.

   Make sure to change the names of any existing reports in the directory on your PC to avoid overwriting existing reports.



7. Navigate to your PC and double click on the report. A sample of part of the PacketTx report is shown below.



Testing with Active Format Description (AFD) (882 only)

When transporting HDMI video images from a source to a display, different formats may be used between the content, transmission signal, and display. To provide compatibility between the different formats, Active Format Description (AFD) is used.

Note: *This feature is not supported on the 881 generator.*

AFD describes the portion of the coded video frame that is “of interest” (or “active”). The appropriate AFD information is transmitted with the video to the HDMI display as part of AVI InfoFrame packets. Using AFD information, the display is able to present the image optimally.

For AFD testing, the generator allows you to apply different AFD cases using the AFDtest image, which provides 12 different cases (as image versions) for both 4:3 and 16:9 displays. As each image version appears, the appropriate AFD information is sent with the video to the display.

The following table lists the AFD cases (as specified in the *ETSI TR 101 154 v.1.4.1* standard) that are provided by the generator.

AFD case	Image Version (4:3 Format)	Image Version (16:9 Format)	Aspect Ratio of Active Area
2	8	7	box 16:9 (top)
3	5	4	box 14:9 (top)
4	9-12	9-12	box > 16:9 (center)
8	0	6	Same as the signal format
9	1	1	4:3 (center)
10	7	8	16:9 (center)
11	4	3	14:9 (center)
13	3	5	4:3 (with shoot and protect 14:9 center)
14	6	2	16:9 (with shoot and protect 14:9 center)
15	2	0	16:9 (with shoot and protect 4:3 center)

To test an HDMI display's ability to support AFD:

1. Set up the generator for HDMI output. See "Setting up the generator for HDMI testing" on page 338.
2. Press the **Source** key and choose a format suitable for the HDMI display (for example, DMT0660).

   Alternatively, to select the format using the command line interface, enter the following commands:

   ```
   FMTP /tffs0/Library/Formats // Set format path to generator memory
   FMTL DMT0660                // Loads the DMT0660 format
   FMTU                        // Activates the DMT0660 format
   ```

3. Press the **Content** key and choose the AFDtest image.

   Alternatively, to select the image using the command line interface, enter the following commands:

   ```
   IMGP /tffs0/Library/Images   // Set image path to generator memory
   IMGL AFDTEST                 // Loads the AFDtest image
   ```

```
IMGU                          // Activates the AFDtest image
```

The AFDtest image appears on the connected HDMI display.



4. Enable and view image versions for the AFDtest image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                        Red+
-NoGamma              Green+
-Noise                 Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More     Rendition: 000
                        Red+
-NoGamma              Green+
-Noise                 Blue+
```

   c. Press the + key to advance through the image versions.

Note: *Select the image version that corresponds to the AFD case (or code) you want to test. See the table on page 385 for a list of the image numbers that correspond with each AFD case.*


Alternatively, to enable and view the image versions using the command line interface, enter the following commands:

```
ISUB 1       // Enables sub images
IVER 1       // Specifies the first image version
IMGU         // Activates the image version
```

5. Using the selected AFD scenario, verify that the HDMI display presents the image correctly.

   Note: *Displays use the AFD information to determine how to present an image. Different displays may present HDMI video with the same AFD differently.*

6. Use the + and - keys to adjust the amplitude, frequency, or sampling rate (based on the selected image) of the HDMI audio output. The contents of the appropriate InfoFrame output appears on the HDMI display. For example, the image representing AFD case 11 (image version 4) on a 4:3 display is shown in the example below.



7. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0     // Disables sub images
```

11 CEC Interactive Troubleshooting Environment (ITE)

Topics in the chapter:

- Overview
- CEC Overview
- Testing CEC Devices
- CEC Bus Monitor

Overview

This chapter provides procedures for testing HDMI source and sink devices for CEC functionality using the Interactive Troubleshooting Environment (ITE). When testing HDMI-CEC source devices the generator (analyzer) will emulate a CEC sink device such as an HDTV. When testing HDMI-CEC sink devices, the 882 generator will emulate a CEC source device such as a set top box (STB) unless you instruct it not to.

Note: *The CEC ITE is an option available on generators with release 2.2.2 or higher. You must have the ITE option on your generator to use the ITE features. To determine if your generator has the the ITE option installed, view the GenStats image and check the information under Options. Refer to "Viewing generator configuration information" on page 130.*

The CEC ITE provides a set of commands to accomplish the following:

- Configure an HDMI port on the 882C(A) to emulate an HDMI source of sink
- Send and query messages on the CEC bus
- Query messages on the CEC bus
- Monitor the CEC bus for timing errors

CEC Overview

Consumer Electronic Control (CEC) is an HDMI option that provides automatic power-on, automatic signal routing, and single-point remote control for CEC-enabled products. The HDMI CEC Develoment & Compliance Test Suite enables manufacturers to quickly integrate CEC into their products and perform all CEC-related tests found in the HDMI Compliance Test Specification. There are two applications in the Suite that pertain to CEC:

- The Interactive Troubleshooting Environment (ITE) lets developers configure their CEC devices, and send messages and faults, so that both nominal and stressful conditions can be generated.
- The Test Management Environment (TME) is a graphical environment that houses all the tests. It runs on a PC and communicates with the generator over an Ethernet connection.

The physical interface for this bus is a single wire which connects to all of the devices in the system. The CEC protocol defines the specific use of that single wire at all times.

CEC devices

An HDMI environment can consist of several types of devices. Each of the devices can be tested using the 882CA generator/analzyer and the CEC TME application. The HDMI devices currently supported for testing are listed below.

- **TV** – A device with HDMI input that has the ability to display the input HDMI signal. Generally it has no HDMI output. However the HDMI specification does cover that case.
- **Recording device** – A device that has the ability to record a source such as an internal preset or an external connection.
- **Set top box** – A device that contains a tuner.
- **DVD player** – A playback device that has the ability to play media.
- **Audio device** – A device that is currently providing an AV stream via HDMI.
- **CEC switch** – An HDMI switch that responds to CEC commands to switch the source of audio/video.
- **Unknown** – Various other HDMI devices, such as:
    - Menu Providing Device A non-display device that may render a menu on TV.

CEC features

The CEC channel provides a number of recommended features designed to enhance the functionality and interoperability of devices within an HDMI environment. This section gives an overview of these features.

- **One Touch Play** – Allows a device to be played and become the active source with a single button press.
- **System Standby** – Enables the user to switch all devices to standby with one button press.
- **One Touch Record** – Offers a What You See Is What You Record (WYSIWYR) facility, meaning that whatever is shown on the TV screen is recorded on a selected recording device.
- **System Information** – Queries the system to determine device addresses and configurations (e.g. language and country)
- **Deck Control** – Enables a device to control (e.g., play, fast forward, etc.) and interrogate a playback device (a deck).
- **Tuner Control** – Allows a device to control the tuner of another device.
- **Vendor Specific Commands** – Allows a set of vendor-defined commands to be used between devices of that vendor.
- **OSD Display** – Enables a device to use the on-screen display of the TV to display text strings.
- **Device Menu Control** – Enables a device to control the menu of another device by passing through user interface commands.
- **Routing Control** – Allows the control of CEC Switches for streaming of a new source device.
- **Remote Control Pass Through** – Enables remote control commands to be passed through to other devices within the system.
- **Device OSD Name Transfer** – Enables devices to upload their preferred OSD name to the TV. The TV can then use this name in any menus associated with that device.

Testing CEC Devices

The CEC ITE enables you to test devices for CEC messaging and to perform stress testing on CEC devices. This section contains procedures for performing these tests.

Testing CEC devices for messaging

The CEC ITE enables customers to test their devices for CEC messaging. This process involves the following high level steps:

- Making physical connections
- Configuring the generator to emulate an HDMI source or sink device
- Verifying continuity over the CEC bus
- Setting up the CEC logging
- Sending CEC messages or causing other devices to send messages
- Querying the CEC message log


Making physical connections

The generator has two HDMI OUT(Tx) connectors for testing HDMI CEC sink devices and two inputs on the analyzer 882CA.

> ***Note:*** *The HDMI CEC bus is a single wire bus within an HDMI cable connecting HDMI devices in an HDMI environment. The CEC wire is on pin 13 of the HDMI Type A connectors. The CEC lead shares its ground with the DDC channel on pin 17 of the HDMI Type A connector. Verify that the cable has an active CEC bus with a continuity tester.*

To connect an HDMI device to the 882 HDMI port:

1. For testing a source device, use an HDMI cable to connect the HDMI output connector of the source device (for example, set top box) to one of the receiver (Rx) HDMI IN connectors of the generator. Refer to the figure below for the locations of the HDMI.
2. For testing a sink device, use an HDMI cable to connect the HDMI output connector of the sink device (for example, TV) to one of the transmitter (Tx) HDMI OUT connectors of the generator. Refer to the figure below for the locations of the HDMI.



Interface	Description
1	**SDI/HD-SDI** connector outputs a serial digital signal per SMPTE 259M and SMPTE 292M standards.
2	**CVBS** connector outputs an analog composite video baseband signal in accordance with SMPTE 170M standard.
3	**S-VIDEO** connector outputs an S-Video split luminance (Y) and chrominance (C) analog video signal.
4	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse • pixel clock signal
5	**VGA OUT** connector outputs a analog component video or analog RGB signal.
6	**HDMI OUT 1** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
7	**HDMI OUT 2** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
8	**HDMI IN 1** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
9	**HDMI IN 2** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
10	**SPDIF-AV** connector inputs audio from an external source.

Emulating an HDMI CEC device

The 882 generator has two HDMI OUT(Tx) connectors. Either one can be configured to emulate an HDMI CEC source device. There are two HDMI Rx connectors on the 882CA analyzer option. Both these outputs are configured together to emulate a single HDMI CEC sink device. The mapping of these connectors to an emulated CEC device type is shown in the following table:

HDMI Tx Out1	HDMI Tx Out2	HDMI Rx In1/2
CEC1	CEC2	CEC3

CEC addressing

CEC is a bus oriented protocol. It uses a DDC mechanism to allocate physical addresses to devices in the network. All CEC devices have a physical and a logical address.

Whenever a new physical address is discovered, a CEC device allocates the logical address and reports the association between its logical and physical addresses by broadcasting. This process allows any node to create a map of physical connections to logical addresses.

Each device appearing on the control signal line has a unique logical address. This address defines a device type as well as being a unique identifier. If a physical device contains the functions of more than one logical device then it should take the logical addresses for each of those logical devices.

Configure generator for HDMI

To use the CEC ITE, you have to activate the HDMI function. Use the procedures below to configure the generator to output HDMI.

To set up the generator for HDMI testing:

1. Connect an HDMI-to-HDMI cable between the HDMI display device under test and any of the HDMI connectors on the generator as long as a sink device under test is connected to an 882C(A) source (Tx) connector or a source device under test is connected to an 882CA sink connector.

2. Activate the HDMI-H interface on the output port:

   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H** item by pressing the adjacent soft key.

   The interface is activated and the port outputs the currently selected image and format.



   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

Configure an HDMI CEC device

Use the procedures below to configure the generator outputs as a particular CEC HDMI device. An 880 series generator with the CEC option is provisioned with a library of common HDMI CEC device types. You can either use one of these device types in the library or create your own descriptor file. Once you create a descriptor file you can modify it to characterize the emulated device to respond in a very specific way.

The following table lists the default device types and their parameters.

Note: *All these devices have vendor ID of 1962 (07AA in hex).*

Device Name	Physical Address (PA)	Product Type (PT)	OSDN	Logical Address (LA)
CECDev00	0 0 0 0	0 (TV)	TVOSDN	0
CECDev01	1 0 0 0	1 (Rec Dev)	RecDev1	1
CECDev02	2 0 0 0	1 (Rec Dev)	RecDev2	2
CECDev03	1 0 0 0	3 (Set Top Box)	STB1	3
CECDev04	1 0 0 0	4 (DVD)	DVD1	4
CECDev05	1 0 0 0	5 (Audio System)	Audio1	5
CECDev06	2 0 0 0	3 (Set Top Box)	STB2	6
CECDev07	3 0 0 0	3 (Set Top Box)	STB3	7

Device Name	Physical Address (PA)	Product Type (PT)	OSDN	Logical Address (LA)
CECDev08	2 0 0 0	4 (DVD)	DVD2	8
CECDev09	3 0 0 0	1 (Rec Dev)	RecDev3	9
CECDev10	1 0 0 0	10 (Reserved)	Reserved1	10
CECDev11	2 0 0 0	10 (Reserved)	Reserved2	11
CECDev12	3 0 0 0	10 (Reserved)	Reserved3	12
CECDev13	4 0 0 0	10 (Reserved)	Reserved4	13
CECDev14	4 0 0 0	0 (TV)	FreeUse	14
CECDev15	4 0 0 0	10 (Reserved)	Unregistered	15

To set up the generator to emulate an HDMI CEC device using default devices:

1. Establish a session with the generator using HyperTerminal over a serial connection or Telnet over an Ethernet LAN. For instructions, see "Establishing a terminal session with the generator" on page 31.
2. Query the device library to verify that it is provisioned in the generator:

   ```
   CECQ? 1 16
   ```

   The generator returns the CECDev types provisioned in the generator library.

   ```
   CECDEV00.xml
   .
   .
   .
   CECDEV15.xml
   ```

3. Query the location of the log file:

   ```
   CECX:LOGP?
   ```

   The generator returns the path of the log file.

   ```
   /card0/Library/CEC/Log
   ```

   Note: *By default the CEC log is on the PCCard. Therefore it is important to ensure that there is a PCcard installed on the generator at all times.*

4. Assign a CEC device to a connector:

   ```
   CEC1:CECL CECDEV03 //assigns CECDEV03 to HDMI Tx Output 1
   CEC1:CECU          //configures (uses) the assigned device
   ```

   Here is a second example:

   ```
   CEC3:CECL CECDEV00 //assigns CECDev00 to HDMI Rx Output 1 and 2
   CEC3:CECU          //configures (uses) the assigned device
   ```

5. Verify the configuration by querying the device parameters of HDMI Tx 1:

   ```
   CEC1:LA?   //queries logical address of device assigned to HDMI TX1
   ```

```
CEC1:PT?   //queries product (device) type assigned to HDMI TX1
CEC1:OSDN? //queries OSDN of device assigned to HDMI TX1
CEC1:VID?  //queries vendor ID of device assigned to HDMI TX1
```

Now query the device assigned to the Rx outputs:

```
CEC3:LA?   //queries logical address of device assigned to HDMI RX1/2
CEC3:PT?   //queries product (device) type assigned to HDMI RX1/2
CEC3:OSDN? //queries OSDN of device assigned to HDMI RX1/2
CEC3:VID?  //queries vendor ID of device assigned to HDMI RX1/2
```

To create a CEC device descriptor file:

1. Locate the file path for stored configurations:

```
CECX:CECP?
/card0/Library/CECData/
```

Change the path if necessary:

```
CECX:CECP /tffs0/Library/CECData/
```

2. Create a custom instance of a CEC device for CEC1 using the following commands:

```
CEC1:CECN <name> //e.g. myTV1
CEC1:CECB        //begins the CEC editing session
```

3. Configure the custom CEC device parameters using the following commands:

```
CEC1:PA 0 0 0 0   //configures the device physical address
CEC1:PT 1         //configures the product (device) type
```

The table below lists the device (product) types and their codes.

Device Type	Device Code
TV	0
Recording Device	1
Set Top Box	3
DVD	4
Audio System	5

```
CEC1:VID <vid>    //configures the device vendor ID
CEC1:OSDN         //configures the device OSDN
CEC1:PA 0 0 0 0   //configures the device physical address
```

4. Save the custom CEC device to a file:

```
CEC1:CECE        //ends the CEC editing session
CEC1:CECS        //saves the CEC device
```

5. Assign the custom CEC device to a connector:

```
CEC1:CECL myTV   //assigns myTV to HDMI Rx port
CEC1:CECU        //configures (uses) the assigned device
```

Configure generator to log CEC messages

The 882 can be configured to log CEC message and store them in a user defined directory.

To enable CEC logging:

1. Enter the following command to enable logging on the HDMI connector:

```
CEC1:LOGG 1   //enables logging on the HDMI Tx output 1 port
CEC3:LOGG 1   //enables logging on the HDMI Rx ports
```

2. Enable all logging with the following command:

```
CECX:LOGM 6  //enables logging of all CEC messages
```

To disable CEC logging:

1. Enter the following command to disable CEC logging:

```
CEC1:LOGG 0  //disables logging on the HDMI Tx output 1 port
CEC3:LOGG 0  //disables logging on the HDMI Rx ports
```

Verifying continuity over the CEC bus

The procedures below describe how to ping a device under test from an 880 that is emulating a CEC device. Note that the device you ping could be another emulated device on the 882 generator. You can ping a device through the front panel, through the command line or by using the CECTest image. Procedures for each of these methods are provided below.

To ping a CEC device under test through the front panel:


1. Determine the logical address of the device under test.
2. From the main menu choose the **CEC** item by pressing the adjacent soft key.

   The CEC menu is presented.



3. Select **CEC** item by pressing the adjacent soft key.

   The CEC ping menu is presented.



4. Select logical address of the device you want to ping by incrementing or decrementing the spot +/- keys.

   The logical address value for the **LA** item will change. For example, if you want to ping the device at logical address of 00 from a port that is connected to that port (e.g. CEC1 you would press the softkey adjacent to the **!PingCEC1** item.

```
!PingCEC1          LA: 00
!PingCEC2
!PingCEC3
```

   A successful ping will result in an “Acknowledged” message. If the ping fails, the message “Failed” will appear.

```
!PingCEC1          LA: 00
!PingCEC2
!PingCEC3
Acknowledged.
```

To ping a CEC device under test through the command line:

1. Determine the logical and physical address of the device under test.
2. Enter the following command to check for continuity.

```
CEC1:MSGX 3 0 83  //request physical addr of device at addr 0 from a
                    device at address 3 for example
```

3. View the results by querying the message log.

```
CEC1:MSGX?
```

   The following results would be returned.

```
0F 84 00 00 00
```

To ping a CEC device using the CEC Test image:


1. Press the **Content** key and select the CECTest1 or CECTest2 image.

   CECTest1 is for HDMI OUT1 and CECTest2 is for HDMI OUT 2.

   Alternatively, enter the following commands to load the CECTest image:

```
IMGL CECTest1.img; IMGU
```

The CECTest1 image appears as shown below.



When you invoke this image, the 882C sends two messages out the CEC1 core (HDMI Out 1) to the device that is connected to it. The two messages it sends querying for the physical address and the vendor ID. The results are shown on the screen above along with a Pass/Fail indication.

Sending CEC messages from an emulated HDMI CEC device

You can send messages to a device from an emulated device over the command line using the MSGX command. You can also receive messages from a device and view them in the CEC log. The procedures below describe how to send basic messages to a CEC device.

To send CEC messages to a device under test:

1. Determine the logical and physical address of the device.
2. Identify the CEC messages that a device responds to.

   Note: *The HDMI CEC spec lists the messages that particular devices must respond to. Consult this specification to ensure that the anticipated response of a device to a particular message. The CEC spec also provides a list of functions and associated operational codes that are specified on the CEC message command line.*

3. Send a message to the device under test to get its physical address.

```
CEC1:MSGX 3 0 83  //request physical addr of device at logical addr 0
                    from address 3
```

4. Query message log to view response.

```
CEC1:MSGX?        //view most recent response
```

   CEC bus query should return the following:

```
0F 84 10 00 03    //device under test returns its physical address
                    the first digit (0) is the logical address of
                    the target device the device under test);
                    the second digit (F) is the logical address of
                    the sending device (the emulated device);
                    the opcode (84) is the returned message code
                    (give logical address)
```

5. Send a message to the device under test to get its vendor ID.

```
CEC1:MSGX 3 0 8c  //request vendor ID of device at logical address 0
```

6. Query message log to view response (the most recent message).

```
CEC1:MSGX?        //view most recent response
```

   CEC bus query should return the following:

```
0F 87 00 07 AA       //device under test returns its vendor ID
```

7. Send a message to the sink device under test to return its tuner status.

```
CEC1:MSGX 3 0 08  //request tuner status of device at logical addr 0
```

Configuring generator to not respond to CEC messages

The 882 can be configured to not respond to CEC messages from a device. When the 882 is configured to not respond to CEC messages, it acknowledges (ACKs) messages, but does not send responses to commands/queries.

To disable responses to CEC messages:

1. Enter the following command to disable responses on the HDMI connector:

```
CEC1:RSPG 0   //disables responses on the HDMI Tx output 1 port
CEC3:RSPG 0   //disables responses on the HDMI Rx ports
```

To enable responses to CEC messages:

1. Enter the following command to enable responses on the HDMI connector:

```
CEC1:RSPG 1   //enables responses on the HDMI Tx output 1 port
CEC3:RSPG 1   //enables responses on the HDMI Rx ports
```

Querying the CEC message log


You can either view the CEC message log from a file or you can query the contents of the log through the command line. The message log is a circular queue with twelve messages (frames). You can view any message in the queue through a command line query using an indexing parameter. You can also clear the log through the command line. Each CEC message in the queue contains the following information:

- Source logical address
- Destination logical address
- Opcode
- Parameters (if any)
- Parameter list length

The procedures below show how to view the CEC log either as a file or through the command line with queries.

To view CEC messages through a file:

1. Connect the source generator to the PC using an Ethernet patch cable or cross over cable between the Ethernet ports on the PC and the generator “Establishing a network environment” on page 144.
2. Access the source generator’s Generator FTP Browser. See “Working with the Generator FTP Browser” on page 24.



3. Navigate to the CEC folder in the Library directory.

4. Select the Log folder and highlight the log file.
5. Select the **Open** activation key under Instrument Files to view the contents of the log file.

   The contents of the log file appear in a text window.

To view CEC messages through the command line:

1. Enter the following command to query the most recent message in the log.

   ```
   CEC1:MSGX?     //queries the message log for the most recent message
   ```

2. Enter the following command to query the log for a message with a specific opcode.

   ```
   CEC1:MSGX? 84  //queries log for message to request device addr
   ```

   CEC bus query might return the following:

   ```
   0F 84 00 00 00    //device under test returns its physical address
                       the first digit (0) is the logical address of
                       the target device (the device under test);
                       the second digit (3) is the logical address of
                       the sending device (the emulated device);
                       the opcode (84) is the returned message code
                       (give logical address)
   ```

3. Enter the following command to query the log for a message with a specific opcode and to only return specific parameter values.

   ```
   CEC1:MSGX? 83 D    //queries log for message with specified opcode
                        and request return of destination address
   ```

4. Enter the following command to query the value of a specific byte number of parameters a message with a user specified opcode:

   ```
   CEC1:MSGX? 83 P 2   //returns value of 2nd byte of the parameters of
                         a message with opcode 83
   ```

5. Enter the following command to query whether one message with a user specified opcode occurs before or after another.

   ```
   CEC1:MSGX? 83 O 84 //returns order of message with opcodes specified
   ```

   The response will be one of:

   0 - opcode 2 occurred before opcode 1
   1 - opcode 1 occurred before opcode 2
   2 - opcode 1 or opcode 2 not found
   3 - opcode 1 and opcode 2 not found
   255 - opcode 1 is the same as opcode 2

To clear the CEC message log:

1. Enter the following command to clear the messages in the log.

   ```
   CEC1:MSGC     //clears the message log
   ```

   You can also clear the message log with the following command:

CECU

Stress testing a CEC device

The CEC ITE provides both a command driven interface and a graphical Java-based application (CEC Controller) for stress testing CEC devices under test. The features in the ITE command line or CEC Controller can be used to verify certain compliance related tests under various adverse conditions such as boundry testing of timing, arbitration, corrupt bit timing, and acknowledgement.

Setting up the CEC Controller

You access the CEC Controller through the generator's web home page.

To run the CEC Controller:

1. From the generator home page select CEC Controller from the menu shown below. Refer to “Web interface” on page 21 for instructions on access the generator home page.




The CEC Controller application appears in the browser:



© 2006 Quantum Data, Inc. All Rights Reserved

www.quantumdata.com

2. Select the port and device on the 882CA that you wish to use for testing. This is the port of a device that you are emulating. Refer to the screen shot below which shows selection of HDMI In 1&2 ports as a TV:



Bit timing tests

You can set the timing of the logical 1 or logical 0 data bit as well as the start bit in such a way to test the ability of the device under test to handle bit timings that are at the edge of what is allowable. For example, a 1 bit's low period can be within the range from 0.4 to 0.8 milliseconds. You can set the time for the low period and entire period. When you set this timing using the commands described, it affects all 1 or 0 bits in all subsequent messages sent out by the emulated device.

To test the bit timing through the command line:

1. Enter the following command to modify the timing of the 1 bits in a message.

```
CEC1:CECT:1BIT 0.4 2.1      //sets the low period of a one bit to 0.4
                              milliseconds and the total bit time to
                              2.1 milliseconds
```

2. Enter the following command to modify the timing of the 0 bits in a message.

```
CEC1:CECT:0BIT 1.5 2.25     //sets the low period of a zero bit to 1.5
                              milliseconds and the total bit time to
                              2.25 milliseconds
```

3. Enter the following command to modify the timing of the start bit in a message.

```
CEC1:CECT:SBIT 3.7 4.5      //sets the low period of a start bit to 3.7
                              milliseconds and the total bit time to
                              4.5 milliseconds
```

To test the bit timing through the CEC Controller:

1. Access the CEC Controller using the procedures in "To run the CEC Controller:" on page 406.

   The table below describes the fields of the **Control Timing** portion of the CEC Controller dialog box.


Setting	Function
Start bit low period	sets the time duration of the start bit low period
Start bit total bit period	sets the time duration of the start bit total period which enables you to set the high period
1 bit low period	sets the time duration of the 1 bit low period
1 bit total period	sets the time duration of the start bit total period which enables you to set the high period
0 bit low period	sets the time duration of the 0 bit low period
0 bit total period	sets the time duration of the 0 bit total period which enables you to set the high period

2. Select the high period or low period of the start bit, logical 0 bit or logical 1 bit by selecting the associated radio button.

   Note that you can apply multiple settings for each command. For example you could change the timing for both the high and low periods of the start, 0 bit and 1 bits simultaneously. You have to reset each timing change.

3. Slide the slide bar to the desired timing setting as shown in the entry box above the slide bar.

   Refer to the screen shot below:



4. Select the device type in the **Initiator** and **Follower** pull down select boxes.

   For example if you have configured your generator to emulate a TV then you would specify the initiator as a TV and the follower as the device under test. Refer to the screen shot below:




© 2006 Quantum Data, Inc. All Rights Reserved

www.quantumdata.com


5. Select the command that you wish to send from the **Opcode** pull down select box.

   For example if you want to send a Report Physical Address command specify this opcode. Refer to the screen shot below:




6. Send the command by clicking on the **Send** activation button.

   Refer to the screen shot below:



If you wish to see the response on the CEC Controller interface you can click on the **Get Response** activation button. The response will appear in the text field next to the **Get Response** activation button.



7. Monitor the timing parameters of the affected commands using the ACA. Refer to "To monitor the CEC bus (channel):" on page 560 for instructions on monitoring the commands through the ACA.

Bus arbitration tests

You can test a device's response to arbitration errors through the command line. There are three arbitration tests that you can perform:

- Force a connected device to stop sending.
- Force a device's address to 0 to cause a sending device to stop sending.
- Force a bit of a sending device to go low when it should not be. This results in a corrupted bit and simulates a device accidently sending on the bus.

Bus arbitration tests involves sending a command to cause the device under test to try and seize the bus while also seizing the bus by the emulated device. This simulates a condition where two devices may start sending at the same time which means they try and seize the bus at the same time. When the device under test detects that another device is seizing the bus it should send a low signal (force the bus low) to indicate to other devices (the device emulated by the 880) that it (the device under test) has detected an error.

To test bus arbitration conflicts through the command line:

1. Enter the following commands to simulate arbitration errors.

```
CEC1:CECT:ARBM 1 0 0    /forces a sending device connected to the
                         bus to stop sending
CEC1:CECT:ARBM 0 1 0   //forces a device's address to 0
                         bus to stop sending
CEC1:CECT:ARBM 0 0 1   //forces a sending device to go low when it
                         should not be
```


To test bus arbitration conflicts through the CEC Controller:

1. Access the CEC Controller using the procedures in "To run the CEC Controller:" on page 406.
2. Select the arbitration test you wish to run.

   The table below describes the fields of the **Test Arbitration** portion of the CEC Controller dialog box. VERIFY

Setting	Function
Seize start bit	Holds the start bit on the next incoming session
Seize address bit	sets all initiator address bits to 0 on the next incoming message
Seize data bits	sets an incoming data low bit a next incoming message

Refer to the screen shot below which shows enabling the Seize address bus arbitration test:



3. Select the device type in the **Initiator** and **Follower** pull down select boxes.

   For example if you have configured your generator to emulate a TV then you would specify the initiator as a TV and the follower as the device under test. Refer to the screen shot below:




© 2006 Quantum Data, Inc. All Rights Reserved

www.quantumdata.com


4. Select the command that you wish to send from the **Opcode** pull down select box.

   For example if you want to send a Report Physical Address command specify this opcode. Refer to the screen shot below:




5. Send the command by clicking on the **Send** activation button.

   Refer to the screen shot below:



If you wish to see the response on the CEC Controller interface you can click on the **Get Response** activation button. The response will appear in the text field next to the **Get Response** activation button.



6. Monitor the effects of the arbitration test using the ACA. Refer to “To monitor the CEC bus (channel):” on page 560 for instructions on monitoring the commands through the ACA.

Bit corruption tests

You can simulate the corruption of any single bit of the 8 data bits in a block by changing their timing such that the total time is less than the minimum time (2.05 milliseconds), for example the time of the corrupt bit can be altered to 1.75 milliseconds. You have to specify which byte you want to corrupt and which bit within that byte that you want to corrupt. When you specify a byte and a bit to corrupt it applies to the specified byte and bit of the subsequent message on the CEC bus.

There are two commands that are used in tandem: 1) CEC1:CECT:BADS which takes an argument to specify which byte of the next message will be affected, and 2) CEC1:CECT:BADM which takes an argument to specify which bit of the specified byte will be affected (corrupted).

To test bit corruption:

1. Enter the following commands to cause a corrupt bit.

```
CEC1:CECT:BADS 2    //indicates that the bit error will occur on the
                      second byte of the next message.
CEC1:CECT:BADM 4    //indicates that the bit error will occur on the
                      fourth bit of the 2nd byte in the next message.
```


To test acknowledgement through the CEC Controller:

1. Access the CEC Controller using the procedures in "To run the CEC Controller:" on page 406.
2. Select the acknowledgement test you wish to run.

   The table below describes the checkbox fields of the **Enable Acks** portion of the CEC Controller dialog box.

Setting	Function
No. bits of	Determines which bit of a byte you want to corrupt
Byte	Determines which byte of a message you want to corrupt a bit

Refer to the screen shot below which shows setting the bit corruption:



3. Select the device type in the **Initiator** and **Follower** pull down select boxes.

   For example if you have configured your generator to emulate a TV then you would specify the initiator as a TV and the follower as the device under test. Refer to the screen shot below:




© 2006 Quantum Data, Inc. All Rights Reserved

www.quantumdata.com


4. Select the command that you wish to send from the **Opcode** pull down select box.

   For example if you want to send a Report Physical Address command specify this opcode. Refer to the screen shot below:



5. Send the command by clicking on the **Send** activation button.

   Refer to the screen shot below:



If you wish to see the response on the CEC Controller interface you can click on the **Get Response** activation button. The response will appear in the text field next to the **Get Response** activation button.



6. Monitor the effects of the corrupt bit test using the ACA. Refer to “To monitor the CEC bus (channel):” on page 560 for instructions on monitoring the commands through the ACA.

Message acknowledgement tests

You can simulate a condition where a message is improperly acknowledged. You can set which conditions the 882 will not acknowledge a message. There are four places where the message can be not acknowledged:

- Header of a directed message
- Data block of a directed message
- Header of a broadcast message
- Data block of a broadcast message

When a directed message is normally acknowledged the acknowledging device pulls the CEC bus low. In order to not acknowledge a message the target device will not pull the CEC bus low. When a broadcast message is normally acknowledged the acknowledging device(s) leave the CEC bus high. In order to not acknowledge a broadcast message the listening device will pull the CEC bus low.

The condition of incorrect acknowledgement will remain in place until you reset it. Therefore once activated the improper acknowledgement remains for all messages received by the 882.

To test message acknowledgement:

1. Enter the following command to simulate a message acknowledgement error.

```
CEC1:CECT:NACK 1 0 0 0  //indicates a directed header block will not
be acknowledged
CEC1:CECT:NACK 0 0 0 1  //indicates a broadcast data block will not be
acknowledged
```


To test acknowledgement through the CEC Controller:

1. Access the CEC Controller using the procedures in "To run the CEC Controller:" on page 406.
2. Select the acknowledgement test you wish to run.

   The table below describes the checkbox fields of the **Enable Acks** portion of the CEC Controller dialog box.

Setting	Function
Directed header	Sets whether or not incoming directed header bits are not acknowledged
Directed data	Sets whether or not incoming directed data bits are not acknowledged
Broadcast header	Sets whether or not incoming broadcast header bits are not acknowledged
Broadcast data	Sets whether or not incoming broadcast data bits are not acknowledged

Refer to the screen shot below which shows enabling the disabling acknowledgement on the received broadcast header byte:



3. Select the device type in the **Initiator** and **Follower** pull down select boxes.

   For example if you have configured your generator to emulate a TV then you would specify the initiator as a TV and the follower as the device under test. Refer to the screen shot below:




© 2006 Quantum Data, Inc. All Rights Reserved

www.quantumdata.com


4. Select the command that you wish to send from the **Opcode** pull down select box.

   For example if you want to send a Report Physical Address command specify this opcode. Refer to the screen shot below:



5. Send the command by clicking on the **Send** activation button.

   Refer to the screen shot below:



If you wish to see the response on the CEC Controller interface you can click on the **Get Response** activation button. The response will appear in the text field next to the **Get Response** activation button.



6. Monitor the effects of the acknowledge test using the ACA. Refer to "To monitor the CEC bus (channel):" on page 560 for instructions on monitoring the commands through the ACA.

End of message tests

You can simulate a condition where an end of message bit is placed improperly. The end of message bit should be placed in the last block of the message. However you can place the end of message bit in a block that is not the end of message and therefore cause an incomplete message to be sent since the target device is suppose to ignore additional blocks once the end of message bit is processed.

To simulate end of message anomolies:

1. Enter the following command to simulate an end of message anomoly.

```
CEC1:CECT:EOMS 2   //indicates that the end of message bit will be
                     placed in the second block of the message.
CEC1:CECT:EOMS 1   //indicates that the end of message bit will be
                     placed in the first (header) block of the
                     message.
```

CEC Bus Monitor

The 880 series CEC bus monitor is a powerful feature of the CEC ITE that enables you to identify timing defects on the CEC line that would normally required an oscilloscope and breakout box to identify using manual techniques. You can use the CEC bus monitor when you are emulating either an HDMI CEC source or sink.

Activating the CEC bus monitor

Use the procedures below to activate the bus monitor once you have configured the generator and/or analyzer to emulate a CEC device.

To activate the CEC bus monitor:

1. Enable the CEC bus monitor by entering the following command:

   ```
   CEC1:BUSM:ON        // Turns the bus monitor on for CEC1
   ```

2. Clear the bus monitor bit buffer by entering the following command:

   ```
   CEC1:BUSM:BITC      // Clears the bus monitor buffer for CEC1
   ```

   Note: *It is important to clear the buffer regularly to ensure that you do not lose data.*

To deactivate the CEC bus monitor:

1. Disable the CEC bus monitor by entering the following command:

   ```
   CEC1:BUSM:OFF       // Turns the bus monitor off for CEC1
   ```

Querying the CEC bus monitor

You can query the CEC bus monitor messages and bits. You can check for bit timing errors, query the timing parameters of each bit throughout a range of bits in the buffer or throughout the entire buffer. You can also query for the correctness of the acknowledge and end of message bits.

Query the bus monitor messages

You can query the bus monitor for all messages or specific messages based on an index that you include on the command line.

To query the bus monitor for all messages:

1. Query the bus monitor for all messages by entering the following command:

   ```
   CEC1:BUSM:MSGX?    // Queries for all messages in the buffer for CEC1
   ```

   The response will be:

```
S 03-- 83+- End signal free time: 42.47msec.
S 3F-+ 84-+ 10-+ 00-+ 03++ End signal free time: 41.57msec.
```

2. Query the bus monitor for particular messages

```
CEC1:BUSM:MSGX? -3  // Queries for message that occurred three
                       messages ago
```

The response will be:

```
S 3F-+ 84-+ 10-+ 00-+ 03++ End signal free time: 41.57msec.
```

```
CEC1:BUSM:MSGX? 1   // Queries for 5th message in the buffer
```

The response will be:

```
S 03-- 83+- End signal free time: 42.47msec.
```

Query the bus monitor for bit timing errors and bit values

You can query the bus monitor for the number of bits, bit timing, bit timing errors as well as the value of a specific bit.

To query the number of bit values in the bus monitor buffer:

1. Query the bus monitor for bit timing errors by entering the following command:

```
CEC1:BUSM:NBIT?       // Queries buffer for the number of bits
```

A typical response might be:

```
200                   // Indicates there are 200 bits in the buffer
```

To query the bus monitor for bit timing errors:

1. Query the bus monitor for bit timing errors by entering the following command:

```
CEC1:BUSM:CHEK?       // Queries buffer for bit timing errors
```

A typical response might be:

```
2                     // Indicates that a logical 0 bit error occurred
```

The range of responses are:

0 - no error has occurred
1 - an error has occurred in a one (logical 1) bit
2 - an error has occurred in a zero (logical 0) bit
4 - an error has occurred in a start bit
8 - an unknown error has occurred

To query the bus monitor for the timing of a series of bits in the buffer:

1. Query the bus monitor for the timing of a series of bits by entering the following command:

```
CEC1:BUSM:TIME? 3 1000  // Queries buffer for the timing of bits 3
                           through 1000 in the buffer for CEC1
```

The response will be in a format that lists the low time in milliseconds followed by the high time in milliseconds as shown below:

```
3.69 0.80
1.49 0.90
0.59 1.80
1.49 0.90
.
.
.
0.59 1.80
```

To query the bus monitor for the value of a bit in the buffer:

1. Query the bus monitor for the value of a bit in the buffer by entering the following command:

```
CEC1:BUSM:BITV? -4 // Queries CEC1 buffer for value of the bit that
                      occurred 4 bits ago.
CEC1:BUSM:BITV? 20 // Queries CEC1 buffer for the 20th bit in the
                      buffer
```

The response will be in the format

-1 - index does not exist or the bit was corrupted
0 - index is a logical zero data bit
1 - index is a logical one data bit
2 - index is a start data bit
3 - index corresponds to an idle period only (no data)
4 - index corresponds to an error signal (sent after a corrupted bit)

To query a message for the byte number of the end of message:

1. Query a message in the bus monitor for the end of message byte:

```
CEC1:BUSM:EOMB? -3  // Queries message in CEC1 buffer that occurred
                       3 messages ago
7                   // Indicates that the EOM byte was the 7th in
                       the message queried
CEC1:BUSM:EOMB? 4   // Queries the 4th message in CEC1 buffer for EOM
                       byte
5                   // Indicates that the EOM byte was the 5th in
                       the message queried
```

To query a message for the polarity of the acknowledge bits:

1. Query a message in the bus monitor for the polarity of the acknowledge bits in a specific message:

```
CEC1:BUSM:ACKV? -3    // Queries message in CEC1 buffer that occurred
                         3 messages ago for polarity of ack bits
```

```
0                    // Shows that the ACK bits were logical 0
                        indicating that it was a directed message
CEC1:BUSM:ACKV? 4    // Queries message in buffer that occurred 3
                        messages ago for polarity of ack bits
1                    // Shows that the ACK bits were logical 1
                        indicating that it was a broadcast message
```

12 CEC Compliance Testing

Topics in the chapter:

- Overview
- CEC Overview
- Setting up CEC compliance testing
- Running the CEC Compliance Test with the TME Software

Overview

This chapter provides an overview of the CEC compliance test and describes how to set up the compliance test.

Note: *You must have the CEC compliance option on your generator to run the CEC compliance test. To determine if your generator has the the CEC option installed, view the GenStats image and check the information under Options. Refer to "Viewing generator configuration information" on page 130.*

The TME software is java-based and runs on a standard Windows PC. Application control is established through a standard Ethernet IP connection to the 882 test instrument. Through the TME, the 882 test instrument can be quickly configured to emulate a CEC-capable HDMI source or sink device to support compliance testing. When configured to emulate a CEC device, the 882 can send CEC query messages or issue commands to connected devices under test and it will also respond to CEC messages sent from a device connected for compliance testing.

When testing HDMI source devices the generator (analyzer) will emulate a sink device such as an HDTV. When testing sink devices the 882 generator will emulate a source device such as a set top box (STB).

CEC Overview

Consumer Electronic Control (CEC) is an HDMI option that provides automatic power-on, automatic signal routing, and single-point remote control for CEC-enabled products. The HDMI CEC Develoment & Compliance Test Suite enables manufacturers to quickly integrate CEC into their products and perform all CEC-related tests found in the HDMI Compliance Test Specification. There are two applications in the Suite that pertain to CEC:

- The Interactive Troubleshooting Environment (ITE) lets developers configure their CEC devices, and send messages and faults, so that both nominal and stressful conditions can be generated.
- The CEC Test Management Environment (TME) is a graphical environment that houses all the tests. It runs on a PC and communicates with the generator over an Ethernet connection.

The physical interface for this bus is a single wire which connects to all of the devices in the system. The CEC protocol defines the specific use of that single wire at all times.

CEC devices

An HDMI environment can consist of several types of devices. Each of the devices can be tested using the 882CA generator/analzyer and the CEC TME application. The HDMI devices currently supported for testing are listed below.

- **TV** – A device with HDMI input that has the ability to display the input HDMI signal. Generally it has no HDMI output. However the HDMI specification does cover that case.
- **Recording device** – A device that has the ability to record a source such as an internal preset or an external connection.
- **Set top box** – A device that contains a tuner.
- **DVD player** – A playback device that has the ability to play media.
- **Audio device** – A device that is currently providing an AV stream via HDMI.
- **CEC switch** – An HDMI switch that responds to CEC commands to switch the source of audio/video.
- **Unknown** – Various other HDMI devices, such as:
    - Menu Providing Device A non-display device that may render a menu on TV.

CEC features

The CEC channel provides a number of recommended features designed to enhance the functionality and interoperability of devices within an HDMI environment. This section gives an overview of these features.

- **One Touch Play** – Allows a device to be played and become the active source with a single button press.
- **System Standby** – Enables the user to switch all devices to standby with one button press.
- **One Touch Record** – Offers a What You See Is What You Record (WYSIWYR) facility, meaning that whatever is shown on the TV screen is recorded on a selected recording device.
- **System Information** – Queries the system to determine device addresses and configurations (e.g. language and country).
- **Deck Control** – Enables a device to control (e.g. play, fast forward etc.) and interrogate a playback device (a deck).
- **Tuner Control** – Allows a device to control the tuner of another device.
- **Vendor Specific Commands** – Allows a set of vendor-defined commands to be used between devices of that vendor.
- **OSD Display** – Enables a device to use the on-screen display of the TV to display text strings.
- **Device Menu Control** – Enables a device to control the menu of another device by passing through user interface commands.
- **Routing Control** – Allows the control of CEC Switches for streaming of a new source device.
- **Remote Control Pass Through** – Enables remote control commands to be passed through to other devices within the system.
- **Device OSD Name Transfer** – Enables devices to upload their preferred OSD name to the TV. The TV can then use this name in any menus associated with that device.

Setting up CEC compliance testing

To prepare for a compliance test involves the following:


- Making physical connections
- Establishing and verifying IP connectivity with the generator
- Physically connecting the 882 generator to the device under test
- Configuring the generator for HDMI
- Verifying continuity over the CEC bus
- Additional equipment required

Making physical connections

This subsection describes how to connect your PC to the generator and also how to connect the generator to the device under test.

To connect an HDMI device under test to the 882 HDMI port:

The generator has two HDMI OUT(Tx) connectors for testing HDMI displays and two HDMI IN (Rx). Use an HDMI cable to connect the HDMI output connector to the device under test using the proper connector. Refer to the figure below for the location of the HDMI connectors.



Interface	Description
1	**SDI/HD-SDI** connector outputs a serial digital signal per SMPTE 259M and SMPTE 292M standards.
2	**CVBS** connector outputs an analog composite video baseband signal in accordance with SMPTE 170M standard.
3	**S-VIDEO** connector outputs an S-Video split luminance (Y) and chrominance (C) analog video signal.

Interface	Description
4	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse • pixel clock signal
5	**VGA OUT** connector outputs a analog component video or analog RGB signal.
6	**HDMI OUT 1** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
7	**HDMI OUT 2** connector outputs full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
8	**HDMI IN 1** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
9	**HDMI IN 2** connector for input of full single link HDMI video, as well as DVI and modern HDMI-compatible digital video signals.
10	**SPDIF-AV** connector inputs audio from an external source.
11	**ETHERNET** connector is used to connect the generator with a TCP/IP network, for remote administration and control, and for sharing resources from a file server

Establishing and verifying IP communication with the generator

This subsection describes how to establish and verify IP communication with the generator.

To connect your PC to the generator:

1. Connect your PC to the generator using the procedures described in “Connecting generators to the network” on page 144.

   Note: Refer to the figure above for the location of the Ethernet jack.

2. Set the IP address of the generator and PC to enable Ethernet IP connectivity using the procedures described in “Setting the generator’s IP address” on page 145.

Verify IP connectivity from your PC to your generator:


1. Press the **Tools** key. The Tools menu appears on the generator’s display as shown below.



2. Choose the **System** item by pressing the adjacent soft key. The System menu appears on the generator's display as shown below.



3. Choose the **Network** item by pressing the adjacent soft key. The generator's IP address appears on the generator's display as shown below.



4. Open up a DOS command window on your PC and telnet to the generator.

   To telnet to the generator with IP address 192.168.254.001 enter the following:

   ```
   telnet 192.168.254.001
   ```

   You then get the prompt from the generator:

   ```
   \tffs0>
   ```

Configuring the generator for HDMI

To use the CEC you have to activate the HDMI interface. Use the procedures below to configure the generator to output HDMI.

To set up the generator for HDMI testing:

1. Connect an HDMI-to-HDMI cable between the HDMI display device under test and the either one of the HDMI OUT connectors on the generator.

2. Activate the HDMI-H interface on the output port:

   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H** item by pressing the adjacent soft key.

   The interface is activated and the port outputs the currently selected image and format.



   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```


Verifying continuity over the CEC bus

The procedures below describe how to ping a device under test from an 880 that is emulating a CEC device. You can ping a device through the front panel, through the command line or by using the CECTest image. Procedures for each of these methods are provided below.

To ping a CEC device under test through the front panel:


1. Determine the logical and physical address of the device under test.
2. From the main menu choose the **CEC** item by pressing the adjacent soft key.

   The CEC menu is presented.



3. Select **CEC** item by pressing the adjacent soft key.

   The CEC ping menu is presented.



4. Select logical address of the device you want to ping by incrementing or decrementing the spot +/- keys.

   The logical address value for the **LA** item will change. For example, if you want to ping the device at logical address of 00 from a port that is connected to that port (e.g. CEC1 you would press the softkey adjacent to the **!PingCEC1** item.

```
!PingCEC1          LA: 00
!PingCEC2
!PingCEC3
```

   A successful ping will result in an Acknowledged message. If the ping fails the message “Failed” will appear.

```
!PingCEC1          LA: 00
!PingCEC2
!PingCEC3
Acknowledged.
```

To ping a CEC device under test through the command line:

1. Determine the logical and physical address of the device under test.
2. Enter the following command to check for continuity.

```
CEC1:MSGX 3 0 83  //request physical addr of device at addr 0
```

3. View the results by querying the message log.

```
CEC1:MSGX?
```

   The following results would be returned.

```
0F 84 00 00 00
```


To ping a CEC device using the CEC Test image:

1. Press the **Content** key and select the CECTest1 , CECTest2 or CECTest3 image.

   Alternatively, enter the following commands to load the CECTest image:

```
IMGL CECTest1.img; IMGU
```

Select the CECTest image that corresponds with the HDMI input or output that you want to ping from. The CECTest1 image will ping a connected device from HDMI Tx 1. The results of the CECTest ping are shown below.



When you invoke this image, the 882C sends two messages out the CEC1 core (HDMI Out 1) to the device that is connected to it. The two messages it sends querying for the physical address and the vendor ID. The results are shown on the screen above along with a Pass/Fail indication.

Configuring generator to not respond to CEC messages

The 882 can be configured to not respond to CEC messages from a device. When the 882 is configured to not respond to CEC messages, it acknowledges (ACKs) messages, but does not send responses to commands/queries.

To disable responses to CEC messages:

1. Enter the following command to disable responses on the HDMI connector:

```
CEC1:RSPG 0   //disables responses on the HDMI Tx output 1 port
CEC3:RSPG 0   //disables responses on the HDMI Rx ports
```


To enable responses to CEC messages:

1. Enter the following command to enable responses on the HDMI connector:

```
CEC1:RSPG 1   //enables responses on the HDMI Tx output 1 port
CEC3:RSPG 1   //enables responses on the HDMI Rx ports
```


Additional equipment required

Certain tests in the Electrical Specification section of the compliance test require the use of Test Point Adapters (TPAs) that Quantum Data manufactures and provides as part of the CEC compliance test option. The devices are shown below.




Dynamic Electrical Test Fixture - Model TPA-CEC-RR.

Switch Positions	Applications
1	Turns off the TPA to save the battery
2	Connects CEC line to 3.3v via a 3kohm ±5% resistor
3	Connects CEC line to ground via 150kohm +/-5% resistor



Quiescent Electrical Test Fixture - Model TPA-CEC-R.

Load	Application
1	Connects CEC line to DDC/CEC ground via a 1 MegOhm +/-5% resistor
2	Connects CEC line to 3.63V via a 27kohm ±5% resistor (multimeter in parallel with the resistor to measure the voltage drop; alternate (preferred) position for measuring the CEC line leakage current
3	Connects CEC line to 3.3v via a 27kohm ±5% resistor
4	Connects CEC line to DDC/CEC Ground via 1kO ±5%
5	Connects CEC line to 3.63V via a 27kohm ±5% resistor (multimeter in series with the resistor to measure the CEC line leakage current)
6	Measures open-circuit voltage across the CEC bus with the Multimeter (debugging only and does not correspond to any official HDMI CTS test)



Multi-Purpose TPA used for CEC Device Bridge - Model TPA-MP-4R.

Use the table below to determine the correct test device needed for each test.

Test ID	Test Device
7-1: CEC Bus Logic ‘0’ and ‘1’ Voltage Level	TPA-CEC-RR
7-2: CEC Maximum Rise Time and Fall Time	TPA-CEC-RR
7-15: CEC Line Degradation	TPA-CEC-R
8-14: CEC Line Degradation	TPA-CEC-R

Running the CEC Compliance Test with the TME Software

This section describes how to install and run the TME CEC compliance test application.

Installing the TME software

This subsection provides procedures on downloading and installing the TME software on your PC.

To install the TME software on your PC:

1. Download the TME software from the Quantum Data website at: http://www.quantumdata.com/downloads/index.asp.
2. Unzip the TME software and store the directory on your PC.


To run the TME software:

1. Locate the TME directory on your PC.

Note: *You must also have the Java Runtime Environment (JRE) 1.5 or later installed on your PC. You can download the JRE from http://www.java.com/en/download/windows_ie.jsp.*

2. Double click on the tme.jar file.

   The main screen of the TME software opens in a Java window.



Establishing communication between the TME software and the generator


This subsection describes how establish communication between the TME software and the 882C(A) generator that is used to test the device under test.

Note: *You can connect from the TME software to the generator but we highly recommend using the Ethernet interface.*

To communicate with the generator from the TME software:

1. Activate the Host softkey on the bottom of the TME interface and activate the radio button beside the next available port.

2. Enter the IP address of the generator in the field provided as shown below.



3. Click on the **Connect** activation button on the lower right of the interface.

   A success notification is provided as shown below. This message indicates that you have connected to the generator.



   If the connection fails, restart the TME to ensure proper operation.

Completing the Capabilities Declaration Form (CDF)

The first activity in executing a CEC compliance test is to identify the set of tests that apply to the particular CEC device that you are testing. The TME software contains a Compliance Test module (CEC-CT module) that greatly simplifies this initial activity. The test module provides a wizard-driven interface to populate the CEC Capabilities Declaration Form (CDF). Once the CDF is populated, the TME software automatically compiles the suite of tests necessary to test a particular device. Because the generic HDMI/CEC equipment types are modeled within the CEC-CT module, the CDF form can

be rapidly populated based on a particular device classification. However, the module offers the flexibility to modify the feature requirements specified generically on the form in order to meet the particular requirements of a device. The contents of the CDF can be edited at any time prior to compiling a test series. Once the CDF is compiled, the required test sections and distinct tests are configured in the TME software and ready to run.

Defining a CDF for a device under test


This subsection defines how to specify a CDF for the device under test. This involves selecting the generic product type or a custom type then choosing a specific unit.

In configuring a test you will either be using generic CDF for a product type and adding specific tests to it or you will be creating a custom device type and defining a CDF for an instance of that product type.

To select the generic device type:

1. Select the **Product** activation button on the top panel.

   The following dialog box appears with the **Product Type** tab activated.




2. Select the product type by clicking on the desired radio button.

   The example in the figure above shows TV/Display selected.

3. Click on the **Select Model: CDF** activation button on the top panel.


   The following dialog box appears. If you have added a new model description using the **Duplicate As** function you will see an additional entry in the **Select CDF** dialog box as shown below.



   You can either select the generic device or select one that you have created. If you are using a generic device you will have to add the specific capabilities to the CDF for your device under test and you may need to add specific tests to the custom device that you have created.

4. Click on **Duplicate As** activation button to define a new device type to test.

   The **Add New CDF** dialog box appears.



   The **Duplicate As** function enables you to define the capabilities for any type of CEC device using any existing model definition. The capabilities of the existing model definition are inherited in the new definition and you can then modify or enhance this definition to met the specific requirements to test your device.

5. Fill in the **Add New CDF** form and click on **Save Model** when you are complete.


   The following confirmation dialog box appears.



6. Click OK in the **Add** confirmation dialog box.


   The **Select Device** dialog box appears. This dialog box will be empty (as shown below) if you have not defined a CDF for any specific instance of the product type you have selected. The following steps show you how to define a CDF for a unit instance of the device (product) type.

   If you have defined a device then you can select it. When you select a device listed you are selecting a CDF definition for that device that you have previously defined and the TME application will activate the Test tab and present you with the initial test in the compliance suite of tests.



7. To create a CDF for an instance of a product type, click on the **Create** activation button in the **Select Device** dialog box.

   The **Add New Unit: Device** dialog box appears.




8. Fill out the information about your device on the form and click on **Add Unit**.

   The following confirmation dialog box appears.



9. Click OK in the **Add** confirmation dialog box.


   The Declare tab is activated enabling you to proceed through the list of features in order for you to select the ones that apply to your device. This initial screen in this list of features is shown below.



10. Specify a device capability by clicking on the check box for each test presented. Proceed to the next device capability to specify it by clicking on the **Next** activation button on the bottom panel. When you are done defining all the device capabilities the **Next** button will be grayed out.

11. Click on the **Finish** activation button on the bottom panel to compile the test suite.

    The following dialog box will appear.



12. Click OK in the **Status** dialog box.

    The CDF definition is completed for the model definition that you are testing and the TME application compiles the test suite. The TME application terminates and you will have to restart the TME application to run the compliance test.

Running the CEC Compliance Test


The TME software enforces the sequence of steps in a particular test but the sections of the overall test or specific tests within a test section can be performed in any order. You can suspend a test at any time and for any reason and then continue when convenient. However you cannot restart mid test. As the test proceeds through the sections and specific tests, the TME interface provides instructions where necessary to take physical actions such as making connections to the additional equipment defined in “Additional equipment required” on page 447. The equipment environment for each test is depicted through the TME interface to assist you in visualizing the test setup.

With Release 2.5.x the TME has been enhanced to run through test steps automatically where user input is not required.

To run the compliance test:


1. Locate the TME directory on your PC.
2. Double click on the tme.jar file.

   The main screen of the TME software opens in a Java window.



3. Select the **Product** activation button on the top panel.

   The following dialog box appears with the **Product Type** tab activated.




4. Select the product type by clicking on the desired radio button.

   The example in the figure above shows TV/Display selected.


5. Click on the **Select Model: CDF** activation button on the top panel.

   The following dialog box appears. If you have added a new product type using the **Duplicate As** function you will see an additional entry in the **Select CDF** dialog box as shown below.




6. Click on **Select** in the **Select CDF** dialog box.

   The following dialog box appears.




7. Create an instance of the product type you wish to test by clicking on **Create** in the **Select Device** dialog box.

   The following dialog box appears.




8. Click on the **Add Unit** activation button on the **Add New Unit:Device** dialog box.

   The following dialog box appears.




9. Highlight the unit you wish to test in the **Select Device** dialog box. Then click on the **Select** activation button on the bottom of the dialog box.

   The initial screen display for the first Electrical Specification is shown below.




10. Proceed through each test by clicking on the **Step** activation button on the bottom panel of buttons.

    The initial screen display for the first Electrical Specification is shown below.



When you complete the tests for a specific section the TME application will proceed to the first test in the next section. The initial test in the Signaling and Bit Timing test is shown below.




Viewing the results of the CEC compliance test

The status of a compliance test, for example what tests have been performed and what tests remain, as well as the results of each test completed, are available at any point. The TME software provides pass/fail results for all tests in the entire suite of tests. The results can be viewed on line, printed or saved in electronic form for viewing through a standard web browser. Because the TME software and 882CA test instrument offer a comprehensive solution for the CEC Compliance Test suite, manufacturers are assured that upon successful completion of the test series, the HDMI CEC product is ready for the compliance test.

To view the results of the compliance test:


1. Select the Report tab.

   The results of the initial test in the first test section (Electrical Specification) are shown first. See the screen below.



2. Click on the Test activation button on the bottom panel to view the test results from the next test in the section.

   The test results for the first test in the second section (Signaling and Bit Timings) are shown below.




3. To view all the test results, click on the **Hard Copy** activation button on the bottom panel.

   A sample report of the test results is shown below. You can view the results of all tests by scrolling through the list.

   If you want to save the results to a file, click on the **Save...** activation button on the bottom. A Java Save dialog box is provided so that you can browse to a location on the PC to save the file.

   If you want to print the results to a file, you can save the file then view it and print it from a browser. This is preferred to using the **Print** activation button on the bottom.



13 Testing DisplayPort Sinks

Topics in the chapter:

- Overview of DisplayPort sink testing
- Setting up the generator for DisplayPort testing
- Testing DisplayPort sinks
- Testing DisplayPort audio

Overview of DisplayPort sink testing

The DisplayPort option enables the generator to test DisplayPort sinks. With the DisplayPort option, the generator outputs DisplayPort-compatible video.

The DisplayPort option provides the following features:


- EDID parsing
- Generation of all VESA formats up to 270MHz (currently) with higher speeds available in future releases.
- HDCP compliance testing

Note: *Procedures for HDCP compliance testing are presented in "Testing DisplayPort sinks with HDCP" on page 672 for details.*

Physical connections

The generator has one DisplayPort OUT(Tx) connector for testing DisplayPort sinks.

The following figure shows the location of this connector on a generator with the DisplayPort option.



Interface	Description
1	**DISPLAYPORT TX** connected to the DisplayPort monitor
2	**SPECIAL** connector provides multiple outputs, including: • digital composite sync • line sync • frame sync • movable scope trigger (probe) pulse pixel clock signal
3	**SPDIF Out** (not used)
4	**SPDIF In** (not used)

Format selection

The following table lists those generator formats used to test support for DisplayPort sinks.

VESA DMT Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
DMT0659	640 x 480	Progressive	31.469	59.941	25.1752
DMT0660	640 x 480	Progressive	31.500	60.000	25.200
DMT0672	640 x 480	Progressive	37.861	72.809	31.500
DMT0675	640 x 480	Progressive	37.500	75.000	31.500
DMT0685	640 x 480	Progressive	43.269	85.008	36.000
DMT0685D	640 x 400	Progressive	37.861	85.080	31.500
DMT0685F	640 x 350	Progressive	37.861	85.080	31.500
DMT0785H	720 x 400	Progressive	37.927	85.039	35.500
DMT0856	800 x 600	Progressive	35.156	56.250	36.000
DMT0860	800 x 600	Progressive	37.879	60.317	40.000
DMT0872	800 x 600	Progressive	48.077	72.188	50.000
DMT0875	800 x 600	Progressive	46.875	75.000	49.500
DMT0885	800 x 600	Progressive	53.674	85.061	56.250
DMT1043	1024 x 768	Interlace	35.522	86.957	44.899808
DMT1060	1024 x 768	Progressive	48.363	60.004	65.000
DMT1070	1024 x 768	Progressive	56.476	70.069	75.000
DMT1075	1024 x 768	Progressive	60.023	75.029	78.750
DMT1085	1024 x 768	Progressive	68.677	84.997	94.500
DMT1170	1152 x 864	Progressive	63.851	70.013	94.500
DMT1175	1152 x 864	Progressive	67.500	75.000	108.000
DMT1185	1152 x 864	Progressive	77.094	84.999	121.500
DMT1243G	1280 x 1024	Interlace	46.433	86.871	78.750
DMT1260A	1280 x 960	Progressive	60.000	60.000	108.000
DMT1260G	1280 x 1024	Progressive	63.981	60.020	108.000
DMT1275A	1280 x 960	Progressive	75.000	75.000	126.000
DMT1275G	1280 x 1024	Progressive	79.976	75.025	135.000
DMT1285A	1280 x 960	Progressive	85.938	85.002	148.500
DMT1285G	1280 x 1024	Progressive	91.146	85.024	157.500
DMT1648	1600 x 1200	Interlace	62.500	96.080	135.000
DMT1660	1600 x 1200	Progressive	75.000	60.000	162.000
DMT1665	1600 x 1200	Progressive	81.250	65.000	175.500
DMT1670	1600 x 1200	Progressive	87.500	70.000	189.000
DMT1675	1600 x 1200	Progressive	93.750	75.000	202.500
DMT1680	1600 x 1200	Progressive	100.000	80.000	216.000
DMT1685	1600 x 1200	Progressive	106.250	85.000	229.500
DMT1760	1792 x 1344	Progressive	83.640	60.000	204.750
DMT1775	1792 x 1344	Progressive	106.270	74.997	261.000
DMT1860	1856 x 1392	Progressive	86.333	59.995	218.250
DMT1875	1856 x 1392	Progressive	112.500	75.000	288.000

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
DMT1960	1920 x 1440	Progressive	90.000	60.000	234.000
DMT1975	1920 x 1440	Progressive	112.500	75.000	297.000
DMT2060	2048 x 1536	Progressive	95.820	60.000	239.933008
DMT2075	2048 x 1536	Progressive	120.450	75.000	319.915008
SMT0660	640 x 480	Progressive	31.469	59.941	25.1752
SMT0660D	640 x 400	Progressive	31.469	59.941	25.1752
SMT0760H	720 x 400	Progressive	31.469	59.941	28.3221
SMT0760V	720 x 480	Progressive	31.469	59.941	28.3221

VESA CVT Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVR0660	640 x 480	Progressive	29.375	59.464	23.500
CVR0760	768 x 480	Progressive	29.634	59.866	27.500
CVR0860	800 x 600	Progressive	36.979	59.837	35.500
CVR0860H	848 x 4480	Progressive	29.514	59.745	29.750
CVR0960D	960 x 600	Progressive	37.054	59.957	41.500
CVR1060	1024 x 768	Progressive	47.297	59.870	56.000
CVR1060H	1064 x 600	Progressive	36.969	59.820	45.250
CVR1160D	1152 x 720	Progressive	44.398	59.916	58.250
CVR1260	1280 x 960	Progressive	59.201	59.920	85.250
CVR1260D	1224 x 768	Progressive	47.327	59.907	65.500
CVR1260E	1280 x 768	Progressive	47.396	59.995	68.250
CVR1260G	1280 x 1024	Progressive	63.194	59.957	91.000
CVR1260H	1280 x 720	Progressive	44.444	59.979	64.000
CVR1360H	1360 x 768	Progressive	47.368	59.960	72.000
CVR1460	1400 x 1050	Progressive	64.744	59.948	101.000
CVR1560D	1536 x 960	Progressive	59.257	59.977	100.500
CVR1660	1600 x 1200	Progressive	74.006	59.924	130.250
CVR1660D	1680 x 1050	Progressive	64.674	59.883	119.000
CVR1760D	1728 x 1080	Progressive	66.605	59.950	125.750
CVR1760H	1704 x 960	Progressive	59.147	59.865	110.250
CVR1860H	1864 x 1050	Progressive	64.723	59.929	131.000
CVR1960	1920 x 1440	Progressive	88.822	59.974	184.750
CVR1960D	1920 x 1200	Progressive	74.038	59.950	154.000
CVR1960H	1920 x 1080	Progressive	66.587	59.934	138.500
CVR2060	2048 x 1536	Progressive	94.769	59.980	209.250
CVR2160H	2128 x 1200	Progressive	74.082	59.986	169.499984
CVR2360D	2304 x 1440	Progressive	88.778	59.945	218.750
CVR2460D	2456 x 1536	Progressive	94.706	59.940	247.750
CVR2560	2560 x 1920	Progressive	118.474	59.987	322.250016
CVR2560E	2560 x 1536	Progressive	94.761	59.975	257.750
CVR2560H	2560 x 1440	Progressive	88.787	59.951	241.500
CVR2760H	2728 x 1536	Progressive	94.789	59.993	273.750016
CVR3060D	3072 x 1920	Progressive	118.425	59.962	382.749984
CVR3260	3200 x 2400	Progressive	148.140	60.000	497.749984
CVR3460H	3408 x 1920	Progressive	118.484	59.992	422.749984
CVR3860	3840 x 2880	Progressive	177.688	59.989	710.750016
CVR3860D	3840 x 2400	Progressive	148.125	59.994	592.499968
CVR4260H	4264 x 2400	Progressive	148.113	59.989	655.249984
CVR4660D	4608 x 2880	Progressive	177.695	59.992	847.249984
CVR5160H	5120 x 2880	Progressive	177.699	59.993	938.249984
CVT0650	640 x 480	Progressive	24.688	49.673	19.750
CVT0660	640 x 480	Progressive	29.688	59.375	23.750
CVT0675	640 x 480	Progressive	37.684	74.769	30.750
CVT0685	640 x 480	Progressive	42.892	84.600	35.000

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT0750D	640 x 680	Progressive	24.740	49.778	23.749998
CVT0760D	768 x 480	Progressive	29.948	59.896	28.750002
CVT0775D	768 x 480	Progressive	37.654	74.710	36.750
CVT0785D	768 x 480	Progressive	42.843	84.502	42.500
CVT0850	800 x 600	Progressive	30.998	49.916	30.750
CVT0850H	848 x 480	Progressive	24.621	49.540	26.000
CVT0860	800 x 600	Progressive	37.654	59.861	38.250
CVT0860H	848 x 480	Progressive	29.826	59.659	31.500
CVT0875	800 x 600	Progressive	47.115	74.905	49.000004
CVT0875H	848 x 480	Progressive	37.684	74.769	41.000
CVT0885	800 x 600	Progressive	53.741	84.898	56.750
CVT0885H	848 x 480	Progressive	42.969	84.751	46.750
CVT0950D	960 x 600	Progressive	30.833	49.651	37.000
CVT0960D	960 x 600	Progressive	37.212	59.635	45.250
CVT0975D	960 x 600	Progressive	47.075	74.841	58.750
CVT0985D	960 x 600	Progressive	53.600	84.676	67.750
CVT1050	1024 x 768	Progressive	39.634	49.980	51.999996
CVT1050H	1064 x 600	Progressive	30.871	49.712	40.750
CVT1060	1024 x 768	Progressive	47.816	59.920	63.500
CVT1060H	1064 x 600	Progressive	37.352	59.859	50.500
CVT1075	1024 x 768	Progressive	60.294	74.900	82.000
CVT1075H	1064 x 600	Progressive	47.146	79.954	65.250
CVT1085	1024 x 768	Progressive	68.677	84.895	94.500
CVT1085H	1064 x 600	Progressive	53.750	84.913	75.250
CVT1150D	1152 x 720	Progressive	37.025	49.764	54.500
CVT1160D	1152 x 720	Progressive	44.859	59.972	66.750
CVT1175D	1152 x 720	Progressive	56.415	74.721	85.750
CVT1185D	1152 x 720	Progressive	64.453	84.918	99.000
CVT1250	1280 x 960	Progressive	49.405	49.853	83.000
CVT1250D	1224 x 768	Progressive	39.499	49.809	62.250
CVT1250E	1280 x 768	Progressive	39.593	49.929	65.249996
CVT1250G	1280 x 1024	Progressive	52.679	49.838	88.500
CVT1250H	1280 x 720	Progressive	37.071	49.827	60.500
CVT1260	1280 x 960	Progressive	59.699	59.939	101.250
CVT1260D	1224 x 768	Progressive	47.739	59.823	76.000
CVT1260E	1280 x 768	Progressive	47.776	59.870	79.500
CVT1260G	1280 x 1024	Progressive	63.668	59.895	109.000
CVT1260H	1280 x 720	Progressive	44.772	59.855	74.500
CVT1275	1280 x 960	Progressive	75.231	74.857	130.000008
CVT1275D	1224 x 768	Progressive	60.191	74.771	97.750
CVT1275E	1280 x 768	Progressive	60.289	74.893	102.250
CVT1275G	1280 x 1024	Progressive	80.295	74.902	138.750
CVT1275H	1280 x 720	Progressive	56.456	74.777	95.750
CVT1285	1280 x 960	Progressive	85.793	84.859	148.250
CVT1285D	1224 x 768	Progressive	68.598	84.793	112.500
CVT1285E	1280 x 768	Progressive	68.633	84.837	117.500
CVT1285G	1280 x 1024	Progressive	91.456	84.839	159.500

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT1285H	1280 x 720	Progressive	64.398	84.846	110.250
CVT1350H	1360 x 768	Progressive	39.564	49.892	69.000
CVT1360H	1360 x 768	Progressive	47.720	59.799	84.750
CVT1375H	1360 x 768	Progressive	60.288	74.891	109.000
CVT1385H	1360 x 768	Progressive	68.668	84.880	125.250008
CVT1450	1400 x 1050	Progressive	54.113	49.965	100.000
CVT1460	1400 x 1050	Progressive	65.317	59.978	121.750
CVT1475	1400 x 1050	Progressive	82.279	74.867	156.000
CVT1485	1400 x 1050	Progressive	93.881	84.960	179.500
CVT1550D	1536 x 960	Progressive	49.479	49.929	99.750
CVT1560D	1536 x 960	Progressive	59.670	59.910	121.250
CVT1575D	1536 x 960	Progressive	75.218	74.844	155.250
CVT1585D	1536 x 960	Progressive	85.817	84.884	178.500
CVT1650	1600 x 1200	Progressive	61.795	49.915	131.500
CVT1650D	1680 x 1050	Progressive	54.121	59.974	119.500008
CVT1660	1600 x 1200	Progressive	74.537	59.869	161.000
CVT1660D	1680 x 1050	Progressive	65.290	59.954	146.250
CVT1675	1600 x 1200	Progressive	94.095	74.976	204.750
CVT1675D	1680 x 1050	Progressive	82.306	74.892	187.000
CVT1685	1600 x 1200	Progressive	107.208	84.951	235.000
CVT1685D	1680 x 1050	Progressive	93.859	84.941	214.750
CVT1750D	1728 x 1080	Progressive	55.616	49.925	127.250
CVT1750H	1704 x 960	Progressive	49.507	49.957	110.500
CVT1760D	1728 x 1280	Progressive	67.134	59.941	155.749984
CVT1760H	1704 x 960	Progressive	59.739	59.979	135.250
CVT1775D	1728 x 1080	Progressive	84.653	74.914	197.749984
CVT1775H	1704 x 960	Progressive	75.240	74.865	172.750
CVT1785D	1728 x 1080	Progressive	96.514	84.884	226.999984
CVT1785H	1704 x 960	Progressive	85.856	84.922	198.500
CVT1850H	1864 x 1050	Progressive	54.051	49.909	132.750008
CVT1860H	1864 x 1050	Progressive	65.314	59.976	162.500
CVT1875H	1864 x 1050	Progressive	82.341	74.924	207.500016
CVT1885H	1864 x 1050	Progressive	93.849	84.931	238.000
CVT1950	1920 x 1440	Progressive	74.171	49.980	192.250
CVT1950D	1920 x 1200	Progressive	61.816	49.932	158.250
CVT1950H	1920 x 1080	Progressive	55.621	49.929	141.500
CVT1960	1920 x 1440	Progressive	89.532	59.968	233.500
CVT1960D	1920 x 1200	Progressive	74.556	59.885	193.250
CVT1960H	1920 x 1080	Progressive	67.158	59.963	173.000
CVT1975	1920 x 1440	Progressive	112.879	74.953	298.000
CVT1975D	1920 x 1200	Progressive	94.038	74.930	245.250
CVT1975H	1920 x 1080	Progressive	84.643	74.906	220.750
CVT1985	1920 x 1440	Progressive	128.599	84.940	339.499968
CVT1985D	1920 x 1200	Progressive	107.184	84.932	281.249984
CVT1985H	1920 x 1080	Progressive	96.513	84.884	253.249984
CVT2050	2048 x 1536	Progressive	79.118	49.980	219.000
CVT2060	2048 x 1536	Progressive	95.446	59.654	267.250

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT2075	2048 x 1536	Progressive	120.384	74.959	339.000
CVT2085	2048 x 1536	Progressive	137.182	84.943	388.500
CVT2150H	2128 x 1200	Progressive	61.794	49.914	175.000
CVT2160H	2128 x 1200	Progressive	74.633	59.516	213.750016
CVT2175H	2128 x 1200	Progressive	94.095	74.976	272.500
CVT2185H	2128 x 1200	Progressive	107.229	84.967	312.250016
CVT2350D	2304 x 1440	Progressive	74.179	49.986	230.249984
CVT2360D	2304 x 1440	Progressive	89.525	59.963	280.750016
CVT2375D	2304 x 1440	Progressive	112.847	74.932	357.500
CVT2385D	2304 x 1440	Progressive	128.612	84.948	409.500
CVT2450D	2456 x 1536	Progressive	79.066	49.947	262.500
CVT2460D	2456 x 1536	Progressive	95.465	59.966	320.000
CVT2475D	2456 x 1536	Progressive	120.346	74.935	407.249984
CVT2485D	2456 x 1536	Progressive	137.206	84.957	466.499968
CVT2550	2560 x 1920	Progressive	98.816	49.957	346.250016
CVT2550H	2560 x 1440	Progressive	74.146	49.964	256.250
CVT2560	2560 x 1920	Progressive	119.247	59.953	419.749984
CVT2560H	2560 x 1440	Progressive	89.521	59.961	312.250016
CVT2575	2560 x 1920	Progressive	150.408	74.979	534.249984
CVT2575H	2560 x 1440	Progressive	112.855	74.937	397.250016
CVT2585	2560 x 1920	Progressive	171.453	84.962	609.000
CVT2585H	2560 x 1440	Progressive	128.606	84.944	454.750016
CVT2750H	2728 x 1536	Progressive	79.108	49.973	291.750016
CVT2760H	2728 x 1536	Progressive	95.430	59.944	335.000
CVT2775H	2728 x 1536	Progressive	120.336	74.929	451.500
CVT2785H	2728 x 1536	Progressive	137.208	84.959	516.999968
CVT3050D	3072 x 1920	Progressive	98.819	49.959	414.250016
CVT3060D	3072 x 1920	Progressive	119.259	59.959	503.749984
CVT3075D	3072 x 1920	Progressive	150.376	74.963	640.000
CVT3085D	3072 x 1920	Progressive	171.465	84.968	732.500032
CVT3250	3200 x 2400	Progressive	123.528/	49.991	545.499968
CVT3260	3200 x 2400	Progressive	149.086	59.970	660.749952
CVT3275	3200 x 2400	Progressive	187.948	74.969	839.000
CVT3285	3200 x 2400	Progressive	214.230	84.978	959.749952
CVT3450H	3408 x 1920	Progressive	98.851	49.975	460.250016
CVT3460H	3408 x 1920	Progressive	119.294	59.977	559.250048
CVT3475H	3408 x 1920	Progressive	150.424	74.987	710.000
CVT3485H	3408 x 1920	Progressive	171.453	84.962	812.000
CVT3850	3840 x 2880	Progressive	148.179	49.976	789.499968
CVT3850D	3840 x 2400	Progressive	123.537	49.995	794.250048
CVT3860	3840 x 2880	Progressive	178.845	59.975	955.750016
CVT3860D	3840 x 2400	Progressive	149.071	59.964	794.250048
CVT3875	3840 x 2880	Progressive	225.493	74.964	1212.249984
CVT3875D	3840 x 2400	Progressive	187.966	74.977	1007.500032
CVT3885	3840 x 2880	Progressive	257.048	84.975	1386.000
CVT3885D	3840 x 2400	Progressive	214.239	84.982	1151.750016
CVT4250H	4264 x 2400	Progressive	123.512	49.985	726.249984

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT4260H	4264 x 2400	Progressive	149.061	59.960	881.250048
CVT4275H	4264 x 2400	Progressive	149.061	59.960	1117.250048
CVT4285H	4264 x 2400	Progressive	214.262	84.991	1277.000064
CVT4650D	4608 x 2880	Progressive	148.222	49.991	946.250048
CVT4660D	4608 x 2880	Progressive	178.850	59.976	1147.500032
CVT4675D	4608 x 2880	Progressive	225.496	74.966	1454.000
CVT4685D	4608 x 2880	Progressive	257.039	84.972	1661.500032
CVT5150H	5120 x 2880	Progressive	148.191	49.980	1052.749952
CVT5160H	5120 x 2880	Progressive	178.882	59.987	1276.499968
CVT5175H	5120 x 2880	Progressive	225.516	74.972	1616.499968
CVT5185H	5120 x 2880	Progressive	257.064	84.980	1846.750080

Image selection

Once you have determined the formats appropriate for testing DisplayPort sinks, you will apply a series of images suitable for evaluating the display. For digital fixed pixel displays, you typically want to select images to test for pixel anomalies, photometry, luminance, centering, resolution, and persistence.

Each image in the generator's library is intended to test one or more attributes of a particular display type and video type.

Note: *You can also create your own images. See "Creating custom images" on page 240 for details.*

The table below provides a summary of display characteristics and the images used to evaluate them.

Display type	Display test	Recommended images
Digital flat panel (fixed pixel display)	Pixel anomalies (stuck pixels, misc sampling)	Flat, Raster, Ramp_B, Ramp_G, and Ramp_R, Focus_@6, Focus_@7, Focus_@8, Focus_@9, Text_9, Text_9T, Text_11, Text_12T, Text_16
	Photometry (chrominance, contrast, levels)	Flat, Flat07, Flat13, Flat20, Flat27, Flat33, Flat40, Flat47, Flat53, Flat60, Flat67, Flat73, Flat80, Flat87, Flat93, FlatGray, Flat_01, Flat_02, Flat_03, Flat_04, Flat_05, Flat_06, Flat_07, Flat_08, Flat_09, Flat_10, Flat_11, Flat_12, Flat_13, Flat_14, Flat_15, Flat_16, Ramp_B, Ramp_G, and Ramp_R, ColorBar, SMPTEbar, SMPTE133
	Luminance	SMPTE133 (grayscale), Grays5, Grays9, Grays11, Grays16, Grays32, Grays64
	Centering	Outline0, Outline1, Outline2, Outline3
	Resolution	BurstTCE, Grill_11, Grill_15, Grill_22, Grill_33, Grill_44
	Persistence	Animated images: Persist, Cubes, SlideX

Setting up the generator for DisplayPort testing

This section provides general procedures for setting up the generator for DisplayPort testing. The procedures below can be performed using the front panel or the command line interface.

To set up the generator for DisplayPort testing:

1. Connect a DisplayPort-to-DisplayPort cable between the DisplayPort sink device under test and the DisplayPort OUT connector on the generator.
2. Press the **Interface** key.
3. Activate the DisplayPort interface on the output port by selecting the **DisplayPort** item with the adjacent soft key.

   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 10        // Selects the DisplayPort interface
ALLU           // Applies the interface setting to the generator
```

To verify the test set-up:

1. Press the **Source** key to access the list of formats.
2. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL DMT0660
FMTU
```

3. Press the **Content** key to access the list of images.
4. Choose a suitable image (for example, ColorBar) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

```
IMGL ColorBar
IMGU
```

5. Verify that the image appears on the display under test.

Selecting video format

Once you have selected the interface type for the display under test, you need to select a video output format. A format defines a set of video, timing, and sync parameters for a specific device or standard. This section explains how to configure the generator to output video formats that are supported by the display under test.

Important: *If the display under test has not implemented hot plug correctly, you will have to bypass hot plug detection in the generator to enable video output. See below for procedure on bypassing hot plug detection.*

Note: *For more information about formats, see Chapter 6, "Working with Formats."*


Setting Source list of formats

The generator provides a Source list of standard (pre-defined) formats. The Source list can be set automatically when connecting to an EDID-compatible display. Otherwise, you can manually set which formats are listed.


To automatically set Source list of formats for EDID-compatible display:

When testing EDID-compatible displays, the generator can automatically update the Source list to include only formats supported by the display under test. To do this:

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following menu appears on the generator's display.



3. Press the **Options** key. The following manu appears on the generator's display.



4. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats indicating enabled.

   The generator loads the Source list with formats supported by the connected display (hot-plug formats read via EDID structure of attached display).

5. To redisplay all formats, press the soft key adjacent to EDID Formats. A '-' (minus sign) next to EDID Formats indicates it is disabled.

To bypass hot plug detection:

If the display under test has not implemented hot plug correctly, you will have to bypass hot plug detection in the generator to enable video output.

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:DEL
Product Code:41003
Serial#:7011007
Week:52 Year:2007
```

3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats
+HP Bypass
-Emulate
```

4. Choose the **HP Bypass** (hot plug bypass) item by pressing the adjacent soft key. A + appears next to HP Bypass indicating enabled.

To use Emulate mode:

Emulate mode automatically sets color space, and other settings based on the interface and format selected:

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:DEL
Product Code:41003
Serial#:7011007
Week:52 Year:2007
```

3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats
+HP Bypass
-Emulate
```

4. Choose the **Emulate** item by pressing the adjacent soft key. A + appears next to Emulate indicating enabled.

   Alternatively, to select the emulate mode through the command line interface, enter the command shown below:

   ```
   EMUG 1        // Enables emulate mode
   ```

   To disable the emulate mode through the command line interface, enter the command shown below:

```
EMUG 0        // Disables emulate mode
```

Selecting a format

From the Source list of formats, you select the video format output for your display under test.

To select a format:

1. Identify the type of display (composite television, component standard definition television, component high definition television, computer equipment, or other specialty display).

   Note: *The generator has a library of standard formats. For a description of how the library is organized, see "Understanding the format library" on page 46.*

2. For non-EDID compliant displays, check the specifications of your display for supported formats.

3. Press the **Source** key to access the list of formats. A list of formats appears on the generator's display as shown below. To see all of the formats, press the + and - keys.

*DMT0660	DMT0672
DMT0675	DMT0685
DMT0785H	DMT0856
DMT0860	DMT0872

   Note: *The list of formats displays when pressing the **Source** key may be a filtered or abbreviated list. Formats not suitable for the selected interface type will not appear by default on the **Source** list. Also, you can disable format catalogs to prevent certain formats from appearing on the Source list. For more information about format catalogs, see "Format catalogs" on page 229.*

4. Choose a format by pressing the adjacent soft key.

Upon selecting a format, you can modify the format options and settings if necessary. For instructions on this, see "Configuring format parameters" on page 181.

Testing DisplayPort sinks

This section provides procedures for testing DisplayPort sinks. The procedures below can be performed using the front panel or the command line interface.

To test DisplayPort displays:

1. Set up the generator for DisplayPort output. See “Setting up the generator for DisplayPort testing” on page 481.
2. Press the **Source** key and select the first test format.

   Alternatively, you can load the format with the following command:

   ```
   FMTL format_name
   FMTU
   ```

3. Press the **Content** key and select the first test image. For digital fixed pixel displays, you typically want to select images to test for pixel anomalies, photometry, luminance, centering, resolution, and persistence. For more details on what images test these specific display attributes, see “Image selection” on page 479 or Appendix B, “Image Reference.”

   Alternatively, you can load the image with the following command:

   ```
   IMGL image_name
   IMGU
   ```

4. Repeat steps 1 and 2 for all formats and test images.

   Note: *You can customize your generator to run through a specified set of formats and images automatically or manually by creating test sequences. See “Creating a test sequence” on page 262.*

   Use the following guidelines to verify proper operation:

   - When testing photometry such as chrominance, use the ColorBar, SMPTE133, or SMPTEbar images. Look for missing bars which may indicate a dead or unconnected channel. Also, look at the transitions between the bars; they should be sharp and distinct. Each bar also should be uniform in color and intensity across its entire width.
   - To test luminance, you can use the SMPTE133 (grayscale) images. To test gamma correction, you can use the SMPTE133 (checkerbox) image. The detailed methods for verifying these parameters on the SMPTE133 image are provided in Appendix B, “Image Reference.”
   - When testing for centering, use the Outline images. The detailed methods for verifying centering with the Outline images (Outline0, Outline1, Outline2, Outline3) are provided in Appendix B, “Image Reference.”
   - When testing resolution with the Grill images, you should be able to see individual and distinct stripes in all areas of the display at all four resolutions.

- When testing for pixel anomalies, use the Flat, Raster, and Ramp images. Use the Raster and Flat images to look for pixels that may be stuck on or off, respectively. The luminance should increase uniformly for the Ramp image. Also look for sparkles indicating problems with sampling.
- When testing for persistence with the animated images (Cubes and Persist), look for bleeding or trails in the wake of the moving object.

Testing DisplayPort audio

This section provides steps on how to test handling of audio packets by a DisplayPort display. Testing can be performed using audio originating from both internal (882) and external sources. The 882 supports both 2-channel and multi-channel LPCM and compressed audio from an internal source or external source. There are separate sets of images for testing 2-channel audio and 8-channel audio.

The procedures in this section describe how you can vary the audio amplitude, audio frequency and audio sampling rate for 2-channel or 8-channel audio. Note that there are some limitations for the 8-channel audio at high sampling rates depending on the number of lanes and the lane rate supported and also depending on the active format.

Testing DisplayPort 2-channel LPCM audio output from internal source

The 882E DisplayPort instrument supports two-channel and multi-channel LPCM audio (using an internally-generated sinewave) at the highest audio sampling rate (192kHz). Multiple scenarios are provided that allow you to test one or both audio channels at different amplitudes and frequencies, as well as test using the different supported sampling rates. The sampling rate for all channels is completed through a single image (AudioRAT).

The following table lists the images used to perform DisplayPort audio testing using an internal audio source.

Image	Description
AudioLR	Left and right audio channel output with adjustable amplitude.
AudioLRf	Left and right audio channel output with adjustable frequency.
AudioRAT	Audio channel outputs with adjustable sampling rate.
Audio_L	Left audio channel output with adjustable amplitude.
Audio_Lf	Left audio channel output with adjustable frequency.
Audio_R	Right audio channel output with adjustable amplitude.
Audio_Rf	Right audio channel output with adjustable frequency.

To test a Display monitor using DisplayPort audio from the generator:

1. Set up the generator for DisplayPort output. See “Setting up the generator for DisplayPort testing” on page 481.
2. Press the **Source** key and select the first test format (either DMT0660).


   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL DMT0660                // Loads the DMT0660 format
```

```
FMTU                          // Activates the DMT0660 format
```

3. Press the **Content** key and choose an audio image (for example, AudioLR).

   The selected image appears on the connected DisplayPort monitor. The image shows the current settings for the DisplayPort audio output. For example, the AudioLR image is shown below.



   Alternatively, to select the audio image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIOLR                // Loads the AudioLR image
IMGU                        // Activates the AudioLR image
```

4. Enable and view image versions for the AudioLR image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions.

Note: *Depending on the selected image, pressing the + and - keys will change the amplitude or frequency of the DisplayPort audio output.*

Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

5. To verify proper DisplayPort audio handling, check the following on the DisplayPort monitor:
   - Audio is output from the proper channels (left, right, or both).
   - When amplitude is adjusted, the volume is subsequently changed.
   - When frequency is adjusted, the pitch is subsequently changed.
6. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

   ```
   ISUB 0     // Disables sub images
   ```
7. Press the **Content** key and choose the AudioRAT image to test the sampling rate.

   The AudioRAT image appears on the connected DisplayPort display. The image shows the current settings for the DisplayPort audio output. Note that the sampling rate image (AudioRAT) applies to all audio channel.

   Alternatively, to select the AudioRAT image using the command line interface, enter the following commands:


   ```
   IMGP /tffs0/Library/Images  // Set image path to generator memory
   IMGL AUDIORAT               // Loads the AudioRAT image
   IMGU                        // Activates the AudioRAT image
   ```

8. Enable and view image versions for the AudioRAT image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:



   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.



   c. Press the + and - keys to advance through the image versions to change the audio sampling rate.

   Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

9. To test another DisplayPort audio output type, repeat the procedure.

Testing DisplayPort 8-channel LPCM audio output from internal source

To support testing of DisplayPort audio, the generator provides 8-channel LPCM audio (using an internally-generated sinewave) at the highest audio sampling rate (192 kHz). Multiple scenarios are provided that allow you to test all audio channels at different amplitudes and frequencies, as well as test using the different supported sampling rates.

The following table lists the images used to perform DisplayPort audio testing using an internal audio source for 8 channels.

Note: *Selecting any of the numbered images (for example, Audio_1, Audio_2, etc.) causes all other channels to be deactivated.*

Image	Description
Audio_1	Channel 1 output with adjustable amplitude.
Audio_1f	Channel 1 output with adjustable frequency.
Audio_2	Channel 2 output with adjustable amplitude.
Audio_2f	Channel 2 output with adjustable frequency.
Audio_3	Channel 3 output with adjustable amplitude.

Image	Description
Audio_3f	Channel 3 output with adjustable frequency.
Audio_4	Channel 4 output with adjustable amplitude.
Audio_4f	Channel 4 output with adjustable frequency.
Audio_5	Channel 5 output with adjustable amplitude.
Audio_5f	Channel 5 output with adjustable frequency.
Audio_6	Channel 6 output with adjustable amplitude.
Audio_6f	Channel 6 output with adjustable frequency.
Audio_7	Channel 7 output with adjustable amplitude.
Audio_7f	Channel 7 output with adjustable frequency.
Audio_8	Channel 8 output with adjustable amplitude.
Audio_8f	Channel 8 output with adjustable frequency.
Audio_X	All channels output with adjustable amplitude.
Audio_Xf	All channels output with adjustable frequency.

To test an DisplayPort monitor using DisplayPort 8-channel audio from the 882:


1. Set up the generator for DisplayPort output. See “Setting up the generator for DisplayPort testing” on page 481.
2. Press the **Source** key and select the first test format (for example: DMT0660).

   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL DMT0660                // Loads the DMT0660 format
FMTU                        // Activates the DMT0660 format
```

3. Press the **Content** key and choose one of the audio images used for amplitude adjustment (for example, Audio_1).

   The image appears on the connected DisplayPort monitor. The image shows the current settings for the DisplayPort audio output. For example, the Audio_1 image is shown below.



   Alternatively, to select the audio image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIO_1                // Loads the Audio_1 image
IMGU                        // Activates the Audio_1 image
```

4. Enable and view image versions to modify the audio amplitude for the Audio_1 image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions to change the audio intensity.


Note: *Depending on the DisplayPort image, pressing the + and - keys will change the amplitude or frequency of the DisplayPort audio output.*

Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

5. To verify proper DisplayPort audio handling, check the following on the DisplayPort monitor:
   - Audio is output from the proper channels (left, right, or both).
   - When amplitude is adjusted, the volume is subsequently changed.
6. Press the **Content** key and choose one of the audio images used for frequency adjustment (for example, Audio_1f).

   The image appears on the connected DisplayPort monitor. The image shows the current settings for the DisplayPort audio output. For example, the Audio_1f image is shown below.



   Alternatively, to select the audio image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIO_1f               // Loads the Audio_1f image
IMGU                        // Activates the Audio_1f image
```

7. To verify proper DisplayPort audio handling, check the following on the DisplayPort display:
   - Audio is output from the proper channels (left, right, or both).
   - When frequency is adjusted, the pitch is subsequently changed.

8. Press the **Content** key and choose the AudioRAT image to test the sampling rate.

   The AudioRAT image appears and shows the current settings for the DisplayPort audio output. Note that the sampling rate image (AudioRAT) adjusts the sampling rate for all audio images.

   Alternatively, to select the AudioRAT image using the command line interface, enter the following commands:

```
IMGP /tffs0/Library/Images  // Set image path to generator memory
IMGL AUDIORAT               // Loads the AudioRAT image
IMGU                        // Activates the AudioRAT image
```

9. Enable and view image versions for the AudioRAT image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.

```
+More    Rendition: 000
                      Red+
-NoGamma            Green+
-Noise               Blue+
```

   c. Press the + and - keys to advance through the image versions to change the audio sampling rate.

   Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

10. When testing is complete, disable image versions by pressing the **Options** key and choosing **More** until a '-' (minus sign) appears next to it.

    Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0     // Disables sub images
```

11. To test another DisplayPort audio output channel or format, repeat the procedure.

Testing DisplayPort multi-channel compressed audio formats

The 882E instrument enables you to test DisplayPort compressed audio formats such as Dolby AC3 format and DTS.

Unlike the uncompressed formats (linear PCM) the compressed audio test signals are generated from a file in the 882. As a result, the amplitude, frequency and sampling rate cannot be adjusted through the audio test images.

To test compressed audio formats on an DisplayPort device from the generator:

1. Set up the generator for DisplayPort output. See “Setting up the generator for DisplayPort testing” on page 481.
2. Press the **Source** key and select the first test format (for example: `DMT0660`).

   Alternatively, to select the format using the command line interface, enter the following commands:

   ```
   FMTP /tffs0/Library/Formats // Set format path to generator memory
   FMTL DMT0660                // Loads the DMT0660 format
   FMTU                        // Activates the DMT0660 format
   ```

3. Press the **Content** key and choose the Dolby audio image as shown below. Note that you can also select the DTS image to access the DTS audio clips.

   ```
   ComFocus      ContBars
   Crosshtc         Cubes
   DecodAdj    DecodeChk
   Diamond1        Dolby*
   ```

   The image appears on the connected DisplayPort display. The image shows the currently selected compressed audio format.

   Alternatively, to select the Dolby image using the command line interface, enter the following commands:

   ```
   IMGP /Cache0/Images         // Set image path to generator memory
   IMGL Dolby                  // Loads the Dolby image
   IMGU                        // Activates the Dolby image
   ```

```
IMGL DTS                    // Loads the DTS image
IMGU                        // Activates the DTS image
```

Note: *You can output compressed audio formats through the command line without selecting the Dolby or DTS image. To do this you enter the following command:*


```
CAUD?   // Queries for the list of stored compressed audio clip
           configurations:
1:DTS, 5.1, 48000.00 [dts-48kHz-1509kbps-51ch.wav.pcm]
2:DTS(ES), 6.1, 48000.00 [DTES-ES-48kHz-1509kbps-61ch.wav.pcm]
8:DOLBY(AC3), 2.0, 48000.00 [2khz2ch-0dB_ac3.pcm]
CAUD 2  // Sends a 2 channel DTS (ES) clip with 48kHz sampling rate
           at 0dB out the DisplayPort output.
```

4. Enable and view image versions to select the other audio formats as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:



   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.



   c. Press the + and - keys to advance through the image versions to change the audio intensity.

   Alternatively, to enable and view an image version using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

5. To verify proper DisplayPort audio handling, check the following on the DisplayPort display:

   - Audio is output from the proper channels (left, right, or both).
   - The proper audio format is shown on the Audio/Video receiver.

Testing DisplayPort audio using an external audio source

The 882E enables you to inject multichannel audio signals from an external SPDIF source (such as a DVD player) into the DisplayPort stream. You can input LPCM 2 channel or multi-channel audio as well as compressed audio (for example Dolby AC-3 and DTS) into the SPDIF input BNC connector. A BNC to RCA adapter cable (30-00123) is provided to enable you to connect the SPDIF audio to an RCA coaxial input of an audio source.

To test a DisplayPort display using DisplayPort audio from an external source:

1. Set up the generator for DisplayPort output. See “Setting up the generator for DisplayPort testing” on page 481.
2. Connect the external audio source to the SPDIF-A/V connector on the 882 using the BNC to RCA adapter provided with the 882.
3. Press the **Source** key and select a format suitable for the DisplayPort display (for example, DMT0660).

   Alternatively, to select the format using the command line interface, enter the following commands:

   ```
   FMTP /tffs0/Library/Formats // Set format path to generator memory
   FMTL DMT0660                // Loads the DMT0660 format
   FMTU                        // Activates the DMT0660 format
   ```

4. Press the **Content** selection key and choose any image (for example, Master).

   Alternatively, to select the image using the command line interface, enter the following commands:

   ```
   IMGP /tffs0/Library/Images  // Set image path to generator memory
   IMGL MASTER                 // Loads the Master image
   IMGU                        // Activates the Master image
   ```

5. Configure the generator to use an external audio source by entering the following commands:

   ```
   SDMG 2
   FMTU
   ```

6. Set the sample frequency to match the frequency of the external source by entering the following command:

   ```
   ARAT 44.1E3 //(example only)
   ```

   Alternatively, configure the generator to detect the audio sampling rate from the channel header of the incoming digital audio by entering the following command:

   ```
   ARAT 0.0
   ```

Note: *The default frequency is 48 kHz (which is used by DVD players). However, if the external source is an audio CD played on a DVD player, the player will output SPDIF with a sampling rate of 44.1 kHz (not 48 kHz). In this case, set the sampling frequency to 44.1 kHz (or reload the format, which will detect the sampling frequency automatically).*

7. Turn on the external audio source. The external audio signal will be encoded into the DisplayPort signal.

   Note: *The generator cannot independently control external source channels. You must use the device generating the audio signal to control the channels.*

8. To verify proper DisplayPort audio handling, check the following on the DisplayPort display:
   - Audio is output from the proper channels (left, right, or both).
   - When the volume is adjusted at the external source, the volume is subsequently changed.
9. Select additional audio images (as desired) to verify proper audio handling.
10. To test another DisplayPort audio output type, return to step 3.

14 DisplayPort Link Layer Testing

Topics in this chapter:

- Overview
- Running the Link Layer compliance test for DisplayPort sink devices
- Running the Link Layer compliance test for DisplayPort source devices

Overview

You can use the 882E to test DisplaPort sink and source devices. The procedures in this chapter instruct you on how to complete the Link Layer compliance tests for DisplayPort sink and source devices. You can initiate these tests through the 882 front panel, the command line or through the Link Layer graphical interface available through the 882's home web page. This chapter provides procedures for initiating the tests through either of these interfaces.

If you have the optional DisplayPort Auxiliary Channel Analyzer you can monitor the link layer transactions during the link layer compliance tests or at any time during normal operation.

Note: *The DisplayPort Link Layer compliance tests are optional features. You must purchase the optional license for these features.*

Running the Link Layer compliance test for DisplayPort sink devices

The 882E supports the running of a Link Layer compliance test on DisplayPort sinks.

Overview

The Link Layer compliance test system enables developers of DisplayPort products to perform a fast and comprehensive Link Layer compliance test. Because the 882E can emulate DisplayPort Link Layer sources devices it can perform a complete Link Layer compliance test on any sink.

The Link Layer compliance test can be run entirely through the 882E front panel or through the command line. The DisplayPort commands enable you to run a specific subset of the tests in the series of tests.

Note: *While running the link layer compliance test, you can monitor the transactions using the Auxiliary Channel Analyzer (ACA) application. Refer to "Monitoring the DisplayPort auxiliary channel" on page 572.*

The following table describes the sink link layer compliance tests that can be performed.

Index	Test	Description
0	5.2.1.1	Read One Byte from Valid DPCD Address
1	5.2.1.2	Read Twelve Bytes from Valid DPCD Address
2	5.2.1.3	Write One Byte to Valid DPCD Address
3	5.2.1.4	Write Nine Bytes to Valid DPCD Addresses
4	5.2.1.5	Write Nine Bytes to Read-Only DPCD Address
5	5.2.1.6	Write EDID Offset (One Byte I^2C-Over-Aux Write)
6	5.2.1.7	Read One EDID Byte (One Byte I^2C-Over-Aux Read)
7	5.2.1.8	EDID Read (1 Byte I^2C-Over-Aux Segment Write, 1 Byte I^2C-Over-Aux Offset Write, 128 Byte I^2C-Over-Aux Read)
8	5.2.1.9	Illegal Aux Request Syntax
9	5.2.2	EDID Read
10	5.3.1.1	Successful Link Training at All Supported Lane Counts and Link Speeds
11	5.3.1.2	Successful Link Training with Request of Higher Differential Voltage Swing during Clock Recovery Sequence

Index	Test	Description
12	5.3.1.3	Successful Link Training to a Lower Link Rate Due To Clock Recovery Lock Failure During Clock Recovery Sequence
13	5.3.1.4	Successful Link Training with Request of a Change to Pre-Emphasis And/Or Voltage Swing Setting During Channel Equalization Sequence
14	5.3.1.5	Successful Link Training at Lower Link Rate Due to Loss of Symbol Lock During Channel Equalization Sequence
15	5.3.1.6	Lane Count Reduction
16	5.3.1.7	Lane Count Increase
17	5.3.2.1	IRQ_HPD Pulse Due to Loss of Symbol Lock and Clock Recovery Lock
18	5.3.2.2	IRQ HPD Pulse Due to Loss of Inter-lane Alignment Lock
19	5.4.1.1	Pixel data reconstruction
20	5.4.1.2	Main Stream Data Unpacking and Unstuffing – Least Packed TU
21	5.4.1.3	Main Stream Data Unpacking and Unstuffing – Most Packed TU
22	5.4.2.	Main Video Stream Format Change Handling

Setting up the tests

Prior to running the link layer compliance tests you will need to setup the generator and the equipment under test for DisplayPort testing. After the test has been setup you can begin testing.

Use the procedures below to setup the generator for link layer compliance testing of sink devices.

Setting up the 882 for DisplayPort testing:

1. Activate the DisplayPort interface by pressing the **Interface** key and choosing the DisplayPort interface as shown below.



   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 10        // Activates the DisplayPort interface
ALLU           // Applies the interface setting to the generator
```

2. Press the **Source** key to access the list of formats. A list of formats appears on the generator's display as shown below. To see all of the formats, press the + and - keys.

```
*DMT0660          DMT0672
 DMT0675          DMT0685
 DMT0785H         DMT0856
 DMT0860          DMT0872
```

Note: *The list of formats displays when pressing the* ***Source*** *key may be a filtered or abbreviated list. Formats not suitable for the selected interface type will not appear by default on the* ***Source*** *list. Also, you can disable format catalogs to prevent certain formats from appearing on the Source list. For more information about format catalogs, see "Format catalogs" on page 229.*

3. Choose a format by pressing the adjacent soft key.

Upon selecting a format, you can modify the format options and settings if necessary. For instructions on this, see "Configuring format parameters" on page 181.

4. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL DMT0660
FMTU
```

5. Press the **Content** key to access the list of images.
6. Choose a suitable image (for example, ColorBar) by pressing the adjacent soft key.

   Alternatively, you can load the image with the following command:

```
IMGL ColorBar
IMGU
```

7. Verify that the image appears on the display under test.

To automatically set Source list of formats for EDID-compatible display:

When testing EDID-compatible displays, the generator can automatically update the Source list to include only formats supported by the display under test. To do this:

1. Connect the generator to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats       CDF↖
+HP Bypass
-Emulate
```

4. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats indicating enabled.

   The generator loads the Source list with formats supported by the connected display (hot-plug formats read via EDID structure of attached display).

5. To redisplay all formats, press the soft key adjacent to EDID Formats. A '-' (minus sign) next to EDID Formats indicates it is disabled.

To use Emulate mode:

Emulate mode reads the EDID of the connected display and sets the output based on the preferred format and also sets the color space.

1. Connect the 882 to the display you want to test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

3. Press the **Options** key. The following information appears on the generator's display.

```
-EDID Formats       CDF↖
+HP Bypass
-Emulate
```

4. Choose the **Emulate** item by pressing the adjacent soft key. A + appears next to Emulate indicating enabled.

   Alternatively, to select the emulate mode through the command line interface, enter the command shown below:

```
EMUG 1        // Enables emulate mode
```


   To disable the emulate mode through the command line interface, enter the command shown below:

```
EMUG 0        // Disables emulate mode
```

To run the Link Layer compliance test on DisplayPort sinks (receiver) through the front panel:

1. Connect a cable between the DisplayPort Tx connector on the generator and the device's DisplayPort receiver interface with the DisplayPort function.

   The following diagram depicts the test setup:



2. Setup the 882 for DisplayPort testing. Refer to "Setting up the 882 for DisplayPort testing:" on page 502.

3. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.

```
System          Reports
Sequence       ImgShift
Probe          Analyzer
AFC
```

   The following is displayed on the generator's LCD.

```
EDID
Misc                HDCP
Link Test
AFC
```

4. Set the Link Layer test parameters.

   There are some parameters that you can set to control the way the link layer tests are run in automation mode. These parameters have to be set through the command line. The following parameters can be set:

   Delay time between tests:

```
DPTX:SATW 15          // sets the wait time between link layer tests
                         to 15 seconds.
```

5. Select **Link Test** to access the Link Layer compliance test menu.

   The following is displayed on the generator's LCD.

```
!SinkRpt
!SrcRpt
```

6. Select **!SinkRpt** by pressing the adjacent soft key to run the Sink Link Layer compliance test and generate a report.


Alternatively, you can run the link layer compliance test through the command line interface by entering the following command:

```
DPTX:LLCT? 3 4    // Runs the link layer compliance test 3:(5.2.1.4)
                     "Write nine bytes to valid DPCD address" four
                     times.
```

To run the Link Layer compliance test on DisplayPort sinks (receiver) through the GUI:

1. Connect a cable between the DisplayPort Tx connector on the generator and the device's DisplayPort receiver interface with the DisplayPort function.


   The following diagram depicts the test setup:



2. Setup the 882 for DisplayPort testing. Refer to "Setting up the 882 for DisplayPort testing:" on page 502.

3. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/.

   The generator home page appears in the browser.




4. Click **Link Layer Compliance**.

   The Link Layer Compliance application appears as a separate application window. The Link Layer Compliance application has four tabs, two for the sink test and two for the source test. For each of the tests (sink or source) there is a tab and associated window to declare the capabilities for the test and a second tab to run the tests.

5. Click on the **Sink Config** tab.

   The Sink Config window is shown below. This is the window you use to configure the parameters of the test.



6. Specify the test capability parameters for the test. These are shown in the table below:

Function/Field	Function
Maximum Lane Count pull down box	Specifies the maximum lane count supported in the Sink Device Capability list
Maximum Link Rate specification pull down box	Specifies the maximum link rate supported in the Sink Device Capability list.
Devices Fixed Timing check box	Specifies whether the test should be run only at the preferred timing. If this check box is selected, you should not check or specify anything for the following: VESA Timings RGB CEA Timings YCbCr 4:4:4 YCbCr 4:2:2
RGB check box	Defines whether the sink device under test supports the RGB color mode.

Function/Field	Function
YCbCr 4:4:4 check box	Defines whether the sink device under test supports the YCbCr color mode with 4:4:4 sampling.
YCbCr 4:2:2 check box	Defines whether the sink device under test supports the YCbCr color mode with 4:2:2 sampling.
VESA Timings List select box	Enables you to select the VESA formats (timings) that the sink device under test supports. Use the Shift key or the Control key to select multiple timings.
CEA Timings List select box	Enables you to select the CEA related formats (timings) that the sink device under test supports. Use the Shift key or the Control key to select multiple timings.
Max Bits per Component pull down box	Defines the maximum bits per component that the sink device under test supports.
Test Automation check box	Indicates whether the DPCD extension for device test automation is supported.
Receiver Capability Field	Enter the 12 bytes of the Receiver's Capability field. These are the bytes 00000h through 0000Bh in the sinks DPCD.

7. Click on the **Sink** tab to access the window to run the tests.

   The source window is shown below:




8. Select the tests you wish to run, the number of times you wish to run them and select the lane configurations in accordance with the table below:

Function/Field	Function
Select All activation buttons	Enables you to quickly select all tests for a test suite.
Deselect All activation buttons	Enables you to deselect all tests. Typically used prior to selecting a few specific tests.
Tests check boxes	Enables you to select a few specific tests for a test suite.
Time Between Tests (secs) spin selection box	Enables you to specify the amount of wait time between tests.
Individual selection check boxes for each test	Enables you to specify the number of times you want a specific test to run during a test suite.
Number of Times spin selection box	Enables you to specify the number of times you want the test suite to be executed.
Start Test Activation Buttons	Initiates the test suite.

Monitoring the link layer transactions during a sink test with the ACA

If you have the optional DisplayPort Auxiliary Channel Analyzer you can monitor the link layer transactions during the link layer compliance tests or at any time during normal operation. The illustration below depicts the setup for monitoring the link layer transactions during testing of a DisplayPort sink:




For procedures on configuring the Auxiliary Channel Analyzer for monitoring DisplayPort link layer transactions refer to “To monitor the aux channel transactions on the DisplayPort:” on page 574.

To view the DisplayPort Link Layer compliance report:


1. Open a Web browser (such as Internet Explorer) and type the generator’s IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.




Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*

2. Choose the **Generated Reports** item. The Generator the provides a list of reports currently available as shown above.



3. Select the DP_Link_Compliance_Sink test report from the list. The report then appears in the browser window as shown below. You can then save the report as a web page file for distribution. The following is an example of a report for the Link Layer compliance test for a display.

Link Layer sink testing operations



You can test the aux channel link layer functionality of a DisplayPort sink device by overridding the link training function. This enables you to control the link parameters that are normally determined during link training. The following procedures can be used to manually test the link layer.

To test the Link Layer manually:

1. Turn off the link layer output with the following command:

   ```
   DPTX:DTOP 0      // Disables the DisplayPort link layer output
   ```

2. Set the number of lanes using the following command:

   ```
   DPTX:SLAC 1      // Sets the lane count to 2 lanes.
   ```

3. Set the link rate using the following command:

```
DPTX:SLNR 1      // Sets the link rate to 2.7Gb/s.
```

Alternatively, instead of using the DPTX:SLNR and DPTX:SLAC commands you perform both operations with the single command as follows:

```
DPTX:FLRC 1 4    // Sets the link rate to 2.7Gb/s and the
                    lane count to 4 lanes.
```

4. Initiate the manual link training using the following command:

```
DPTX:LNKU        // Runs the link training using the values
                    specified manually above.
```

Link Layer sink control operations

The 882E enables you to control the DisplayPort link layer functions directly through the command line and to a limited degree through the front panel. This section provides procedures to control these link layer functions.

Link Layer sink control operations through command line

The following table describes the set of controls you have over the link layer.

Command	Description		
DPTX:CLEV DPTX:CLEV?	Specifies the current level from 1 to 4. Queries for the current setting of the current level.		
	Arguments	**Valid Values**	
	Current:	0 = sets current level to 1 1 = sets current level to 2. 2 = sets current level to 3. 3 = sets current level to 4.	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:CLEV 1	Sets current level to level 2.
	Query:	DPTX:CLEV?	Queries to determine current level setting.
DPTX:DPCD?	Query reads the value from the specified address.		
	Arguments	**Valid Values**	
	Address:	Any DPCD address in hex	
	Bytes read:	Number of bytes you want to read in decimal	
	Examples	**Syntax**	**Explanation**
	Query:	DPTX:DPCD? 0 12	Returns the value of the 12 bytes starting at address 0000 hex.
DPTX:DTOP DPTX:DTOP?	Enables or disables the outputs with respect to link training. Queries for the current value of the DTOP parameter.		
	Arguments	**Valid Values**	

Command	Description		
	Enable:	0 = disables outputs 1 = enables outputs	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:DTOP 1	Enables the outputs.
	Query:	DPTX:DTOP?	Queries to determine if the link training outputs are enabled or disabled.
DPTX:EMPH DPTX:EMPH?	Sets the pre-emphasis level of the link. Query the current setting fo the pre-emphasis.		
	Arguments	**Valid Values**	
	Preemphasis:	0 = no pre-emphasis 1 = pre-emphasis level 1 2 = pre-emphasis level 2 3 = pre-emphasis level 3	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:EMPH 1	Sets pre-emphasis to level 1
	Query:	DPTX:EMPH?	Queries the current value of the pre-emphasis level parameter.
DPTX:FLRC DPTX:FLRC?	Forces a link rate and lane count regardless of the link training status. Queries for the current value of the link rate parameter.		
	Arguments	**Valid Values**	
	Link rate:	0 = 1.62Gb/s 1 = 2.7Gb/s	
	Lane count:	1 = one lane 2 = two lanes 4 = four lanes	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:FLRC 1 4	Sets the link rate to 2.7Gb/s and the lane count to 4 lanes.
DPTX:LLCT?	Runs the specified link layer tests a specified number of times.		
	Arguments	**Valid Values**	
	Test number:	0 - 22	
	Test runs:	1 to 10	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:LLCT? 3 4	Causes the link layer test number 5.2.1.4 to be run 4 times.
DPTX:LNKU	Performs link training using the set of values for number of lanes, link rate, etc.		
	Arguments	**Valid Values**	
	N/A	N/A	


Command	Description		
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:LNKU	Intiates link training with currently defined values. For example it will use the setting defined for DPTX:SLNR for the link rate.
DPTX:MVAL DPTX:MVAL?	Sets the MVAL Queries for the current value of the MVAL parameter.		
	Arguments	**Valid Values**	
	Mval:	0 - 32,768	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:MVAL 1	Sets the MVAL parameter to 1.
	Query:	DPTX:MVAL?	Queries for the current value of the MVAL parameter.
DPTX:NVAL DPTX:NVAL?	Sets the NVAL parameter. Queries for the current value of the NVAL parameter.		
	Arguments	**Valid Values**	
	Nval:	0 - 32,768	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:NVAL 1	Sets the NVAL parameter to 1.
	Query:	DPTX:NVAL?	Queries for the current value of the NVAL parameter.
DPTX:PBS7 DPTX:PBS7	Specifies the PRBS7 test pattern for link training or disables the test pattern. Queries for the current value of the PBS7 parameter.		
	Arguments	**Valid Values**	
	Pattern:	0 = (00) disables outputs 1 = (01) test pattern 1 transmitted (unscrambled). 2 = (10) symbol error rate measurement pattern transmitted. 3 = (11) PRBS7 test pattern transmitted.	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:PBS7 3	Transmits the PRBS7 test pattern (11).
	Query:	DPTX:PBS7?	Queries to determine the current setting of the PRBS7 test pattern parameter.
DPTX:PTLT	Performs link training.		
	Arguments	**Valid Values**	
	N/A	N/A	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:PTLT	Intiates link training.

Command	Description		
DPTX:SATW DPTX:SATW?	Sets the wait time in second between link layer test. Queries the wait time in seconds of this parameter.		
	Arguments	**Valid Values**	
	Wait time:	1 to 60 seconds	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:SATW 3	Causes the link layer test suite to wait 3 seconds between each test.
	Query:	DPTX:SATW?	Queries for the current value of the SATW parameter
DPTX:SCRG DPTX:SCRG?	Specifies the whether scrambling is enabled or disabled. Queries for the current setting of the SCRG scrambling parameter.		
	Arguments	**Valid Values**	
	Enable:	0 = disables scrambling 1 = enables scrambling	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:SCRG 1	Enables scrambling.
	Query:	DPTX:SCRG?	Queries to determine is scrambling is enabled or disabled.
DPTX:SLAC DPTX:SLAC?	Sets the number of main link lanes to use. Queries for the current setting for the lanes.		
	Arguments	**Valid Values**	
	Lanes:	1 = one lane 2 = two lanes 4 = four lanes	
	Examples	**Syntax**	**Explanation**
	Command:	DPTX:SLAC 1	Sets the number of lanes to 1. When DPRX:LNKU is run, it will use this setting.
	Query:	DPTX:SLAC?	Queries for the current value of the number of lanes (SLAC) parameter.
DPTX:SLNR DPTX:SLNR?	Sets the link rate to low (1.62Gb/s) or high (2.7Gb/s). Queries for the current value of the link rate parameter.		
	Arguments	**Valid Values**	
	Link rate:	0 = 1.62Gb/s 1 = 2.7Gb/s	
	Examples	**Syntax**	**Explanation**

Command	Description	
Command:	DPTX:SLNR 1	Sets the link rate to 2.7Gb/s. When DPRX:LNKU is run, it will use this setting.
Query:	DPTX:SLNR?	Queries for the current value of the SLNR parameter.

Link Layer sink control operations through front panel

The section describes how to configure the 882E Tx link layer parameters. You can configure the link layer parameters through the DisplayPort Interface Options menu as shown below:



Item	Setting	Function
Output	+ Enabled - Disabled	Enables you to Enable or Disable the DisplayPort output.
Scrambler	+ Enabled - Disabled	Enables you to Enable or Disable scrambling on the DisplayPort output.
Lanes	Toggle between: 1 lane 2 lanes 4 lanes	Enables you to specify the number of lanes explicitely for link training or for use in forcing the link to a specific number of lanes.
Rate	Toggle between: 1.62Gb/s 2.7Gb/s	Enables you to specify the link rate explicitely for link training or for use in forcing the link to a specific rate.

Item	Setting	Function
!Train	Activation button	When pressed this causes link training with the values specified for **Lane** and **Rate** to be used.
!Force	Activation button	When pressed this causes the link to use the values specified for **Lane** and **Rate** to be used. Link training is not performed.

Running the Link Layer compliance test for DisplayPort source devices

The 882E supports the running of an Link Layer compliance test on DisplayPort sources.

The Link Layer compliance test system enables developers of DisplayPort products to perform a fast and comprehensive Link Layer compliance test. Because the 882E can emulate DisplayPort Link Layer sink devices it can perform a complete Link Layer compliance test on any source.

The Link Layer compliance test can be run entirely through the 882E front panel or through the command line. The DisplayPort commands enable you to run a specific subset of the tests in the series of tests.

Note: *While running the Link Layer compliance test on sink devices, you can monitor the transactions using the optional Auxiliary Channel Analyzer (ACA) application. For procedures on this "Monitoring the DisplayPort auxiliary channel" on page 572.*

The following table describes the tests that can be performed.


Index	Test	Description
0	4.2.1.1	Source DUT Retry on No-Reply During Aux Read after Hot Plug Event
1	4.2.1.2	Source Retry on Invalid Reply During Aux Read after Hot Plug Event
2	4.2.2.1	EDID Read upon Hot Plug Event
3	4.2.2.2	DPCD Receiver Capability Read upon Hot Plug Event
4	4.2.2.3	EDID Read
5	4.2.2.4	EDID Absence Detection
6	4.2.2.5	EDID Corruption Detection
7	4.3.1.1	Successful Link Training Upon Hot Plug detect
8	4.3.1.2	Successful Link Training at All Supported Lane Counts and Link Speeds
9	4.3.1.3	Successful Link Training with Request of Higher Differential Voltage Swing during Clock Recovery Sequence
10	4.3.1.4	Successful Link Training to a Lower Link Rate #1: Iterate at Maximum Voltage Swing
11	4.3.1.5	Successful Link Training to a Lower Link Rate #2: - Iterate at Minimum Voltage Swing
12	4.3.1.6	Successful Link Training with Request of a Higher Pre-emphasis Setting During Channel Equalization Sequence

Index	Test	Description
13	4.3.1.7	Successful Link Training at Lower Link Rate due to Loss of Symbol Lock During Channel Equalization Sequence
14	4.3.1.8	Unsuccessful Link Training at Lower Link Rate #1: Iterate at Maximum Voltage Swing
15	4.3.1.9	Unsuccessful Link Training at Lower Link Rate #2: - Iterate at Minimum Voltage Swing
16	4.3.1.10	Unsuccessful Link Training due to Failure in Channel Equalization Sequence (loop count > 5)
17	4.3.1.11	Lane Count Reduction
18	4.3.1.12	Lane Count Increase
19	4.3.2.1	Successful Link Re-training After IRQ HPD Pulse Due to Loss of Symbol Lock
20	4.3.2.2	Successful Link Re-training After IRQ HPD Pulse Due to Loss of Clock Recovery Lock
21	4.3.2.3	Successful Link Re-training After IRQ HPD Pulse Due to Loss of Inter-lane Alignment Lock
22	4.3.2.4	No link re-training required after IRQ HPD pulse
23	4.4.1.1	Pixel Data Steering
24	4.4.1.2	Main Stream Data Packing and Stuffing – Least Packed TU
25	4.4.1.3	Main Stream Data Packing and Stuffing – Most Packed TU
26	4.4.2	Main Video Stream Format Change Handling

To run the Link Layer compliance test on DisplayPort source (transmitter):

1. Connect a cable between the DisplayPort Rx connector on the generator and the device's DisplayPort transmitter interface with the DisplayPort function.

   The following diagram depicts the test setup:



2. Activate the DisplayPort interface by pressing the **Interface** key and choosing the DisplayPort interface as shown below.




Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 10         // Activates the DisplayPort interface
ALLU            // Applies the interface setting to the generator
```


3. Press the **Tools** key.

The following is displayed on the generator's LCD.



4. Press the **Reports** item by pressing the adjacent soft key.

The following is displayed on the generator's LCD.



5. Set the Link Layer test parameters.


There are some parameters that you can set to control the way the link layer tests are run in automation mode. These parameters have to be set through the command line. The following parameters can be set:

Delay time between tests:

```
DPRX:SATW 15          // sets the wait time between link layer tests
                         to 15 seconds.
```

6. Select **Link Test** to access the Link Layer compliance test menu.

The following is displayed on the generator's LCD.



7. Select **!SrcRpt** to run the Source Link Layer compliance test and generate a report.


Alternatively, you can run the link layer compliance test through the command line interface by entering the following command:

```
DPRX:LLCT? 4 3   // Runs the link layer compliance test 4:(4.2.2.3)
                    "EDID Read" three times.
```

To run the Link Layer compliance test on DisplayPort sinks (receiver) through the GUI:

1. Connect a cable between the DisplayPort Rx connector on the 882E and the device's DisplayPort transmitter interface with the DisplayPort function.


   The following diagram depicts the test setup:



2. Setup the 882 for DisplayPort testing. Refer to "Setting up the 882 for DisplayPort testing:" on page 502.

3. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/.

   The generator home page appears in the browser.




4. Click **Link Layer Compliance**.

   The Link Layer Compliance application appears as a separate application window. The Link Layer Compliance application has four tabs, two for the sink test and two for the source test. For each of the tests (sink or source) there is a tab and associated window to declare the capabilities for the test and a second tab to run the tests.

5. Click on the **Source Config** tab.

   The Source Config window is shown below. This is the window you use to configure the parameters of the test.




6. Specify the test capability parameters for the test. These are shown in the table below:

Function/Field	Function
Maximum Lane Count pull down box	Specifies the maximum lane count supported by the source device under test.
Maximum Link Rate specification pull down box	Specifies the maximum link rate supported by the source device under test.
Devices Fixed Timing check box	Specifies whether the test should be run only at the preferred timing. If this check box is selected, you should not check or specify anything for the following: VESA Timings CEA Timings RGB YCbCr 4:4:4 YCbCr 4:2:2
RGB check box	Defines whether the source device under test supports the RGB color mode.
YCbCr 4:4:4 check box	Defines whether the source device under test supports the YCbCr color mode with 4:4:4 sampling.
YCbCr 4:2:2 check box	Defines whether the source device under test supports the YCbCr color mode with 4:2:2 sampling.
VESA Timings List select box	Enables you to select the VESA formats (timings) that the source device under test supports. Use the Shift key or the Control key to select multiple timings.
CEA Timings List select box	Enables you to select the CEA related formats (timings) that the source device under test supports. Use the Shift key or the Control key to select multiple timings.
Max Bits per Component pull down box	Defines the maximum bits per component that the source device under test supports.
Test Automation check box	Indicates whether the DPCD extension for device test automation is supported.
Test Link Training (test automation) check box	Indicates whether the source device under test supports the link training test with test automation.
Test EDID_Read (test automation) check box	Indicates whether the source device under test supports the read EDID test with test automation.
Test EDID_Checksum (test automation) check box	Indicates whether the source device under test supports the EDID checksum test with test automation.

Function/Field	Function
Test Pattern (test automation) check boxes	Indicates whether the source device under test supports the test pattern with test automation for the following test patterns: - Color ramps - Black/White vertical lines - Color square.
Test Timing (test automation) check boxes	Indicates whether the source device under test supports the following test timings: - Horizontal total - Vertical total - Horizontal start - Vertical start - Horizontal sync - Vertical sync - Horizontal width - Vertical height.
Test Synchronous Clock (test automation) check box	Indicates whether the source device under test supports the synchronous clock test with test automation.
Test Color Format (test automation) check box	Indicates whether the source device under test supports the color format test with test automation.
Test Dynamic Range (test automation) check box	Indicates whether the source device under test supports the dynamic range test with test automation.
Test YCbCr Coefficients (test automation) check box	Indicates whether the source device under test supports the YCbCr coefficients test with test automation.
Test Bit Depth (test automation) check box	Indicates whether the source device under test supports the bit depth test with test automation.
Test Refresh Denominator (test automation) check box	Indicates whether the source device under test supports the refresh denominator test with test automation.
Test Interlaced (test automation) check box	Indicates whether the source device under test supports the interlaced test with test automation.
Spread Spectrum Clocking check box	Defines whether the source device under test supports Spread Spectrum Clocking.

Function/Field	Function
Video Format Change without Link Training check box	Defines whether the source device under test supports a video format change without performing link training.
Lane Count Reduction check box	Defines whether the source device under test supports a lane count reduction without performing link training.
Power Save check box	Defines whether the source device under test supports the Power Save mode.

7. Click on the **Source** tab to access the window to run the tests. The source window is shown below:




8. Select the tests you wish to run, the number of times you wish to run them and select the lane configurations in accordance with the table below:

Function/Field	Function
Select All activation buttons	Enables you to quickly select all tests for a test suite.
Deselect All activation buttons	Enables you to deselect all tests. Typically used prior to selecting a few specific tests.

Function/Field	Function
Tests check boxes	Enables you to select a few specific tests for a test suite.
Long HPD Pulse Width (msec) pin selection box	Initiates the duration of the long hot plug pulse.
Time Between Tests (secs) spin selection box	Enables you to specify the amount of wait time between tests.
Individual selection boxes for each test	Enables you to specify the number of times you want a specific test to run during a test suite.
Number of Times spin selection box	Enables you to specify the number of times you want the test suite to be executed.
Start Test Activation Buttons	Initiates the test suite.

Monitoring the link layer transactions during a source test with the ACA


If you have the optional DisplayPort Auxiliary Channel Analyzer you can monitor the link layer transactions during the link layer compliance tests or at any time during normal operation. The illustration below depicts the setup for monitoring the link layer transactions during testing of a DisplayPort source: For procedures on configuring the Auxiliary Channel Analyzer for monitoring DisplayPort link layer transactions refer to “To monitor the aux channel transactions on the DisplayPort:” on page 574.



To view the DisplayPort Link Layer compliance report:


1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.




Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*

2. Choose the **Generated Reports** item. The Generator the provides a list of reports currently available as shown below.



3. Select the DP_Link_Compliance_Source test report from the list. The report then appears in the browser window as shown below. You can then save the report as a web

page file for distribution. The following is an example of a report for the Link Layer compliance test for a display.



DisplayPort Link Layer Compliance Report

quantumdata

HOME

Generator Information

Model = 3325
Unit Revision = A
Unit SN = 07120074
Date = 12/12/2007
Firmware = 20.1885400

SOURCE TEST SUMMARY

NOT JUDGED	4.2.1.1	Source DUT retry on no-reply during Aux read after Hot Plug event
NOT JUDGED	4.2.1.2	Source retry on invalid reply during Aux read after Hot Plug event
NOT JUDGED	4.2.2.1	EDID read upon Hot Plug event
NOT JUDGED	4.2.2.2	DPCD receiver capability read upon Hot Plug event
NOT JUDGED	4.2.2.3	EDID read
NOT JUDGED	4.2.2.4	EDID absence detection
NOT JUDGED	4.2.2.5	EDID corruption detection
PASS	4.3.1.1	Successful link training upon Hot Plug detect
PASS	4.3.1.2	Successful link training at all supported lane counts and link speeds
PASS	4.3.1.3	Successful link training with request of higher differential voltage swing during clock recovery sequence
TIMED OUT	4.3.1.4	Successful link training to a lower link rate #1: Iterate at maximum voltage swing
TIMED OUT	4.3.1.5	Successful link training to a lower link rate #2: Iterate at minimum voltage swing
PASS	4.3.1.6	Successful link training with request of higher pre-emphasis setting during channel equalization sequence
FAIL	4.3.1.7	Successful link training to a lower link rate due to loss of symbol lock during channel equalization sequence
PASS	4.3.1.8	Unsuccessful link training to a lower link rate #1: Iterate at maximum voltage swing
PASS	4.3.1.9	Unsuccessful link training to a lower link rate #2: Iterate at minimum voltage swing
PASS	4.3.1.10	Unsuccessful link training due to failure in channel equalization sequence (loop count > 5)
TIMED OUT	4.3.1.11	Lane count reduction
PASS	4.3.1.12	Lane count increase
PASS	4.3.2.1	Successful link re-training after IRQ_HPD pulse due to loss of symbol lock
PASS	4.3.2.2	Successful link re-training after IRQ_HPD pulse due to loss of clock recovery lock
PASS	4.3.2.3	Successful link re-training after IRQ_HPD pulse due to loss of inter-lane alignment lock
PASS	4.3.2.4	No link re-training required after IRQ_HPD pulse
PASS	4.4.1.1	Pixel data steering
PASS	4.4.1.2	Main stream data packing and stuffing - Least packed TU
PASS	4.4.1.3	Main stream data packing and stuffing - most packed TU
PASS	4.4.2	Main video stream format change handling

Link Layer source control operations

Command	Description		
DPRX:DPCD DPRX:DPCD?	Writes a specified value to a specified DPCD address. Query reads the value from the specified address.		
	Arguments	**Valid Values**	
	Address:	Any DCPD address in hex	
	Value:	Any valid value (in binary) for parameter at the address identified	
	Examples	**Syntax**	**Explanation**

Command	Description		
	Command:	DPRX:DPCD 206 F5	Sets value of DPCD register 206 (Adjust_Request_Lane0_1) to F5 (11110101 for bits 7->0) which sets the following: -Pre-emphasis Lane1 (bits 7/6) = 11 (level 3) -Voltage swing Lane1 (bits 5/4) = 11 (Level 3) -Pre-emphasis Lane0 (bits 3/2) = 01 (Level 1) -Voltage swing Lane0 (bits 1/0)= 01 (Level 1)
	Query:	DPRX:DPCD?	
DPRX:LLCT?	Runs the specified link layer tests a specified number of times.		
	Arguments	**Valid Values**	
	Test number:	0 - 26	
	Test runs:	1 to 10	
	Examples	**Syntax**	**Explanation**
	Command:	DPRX:LLCT? 3 4	Causes the link layer test number 3 (4.2.2.2) to be run 4 times.
DPRX:SATW DPRX:SATW?	Sets the wait time in second between link layer test. Queries the wait time in seconds of this parameter.		
	Arguments	**Valid Values**	
	Wait time:	1 to 60 seconds	
	Examples	**Syntax**	**Explanation**
	Command :	DPRX:SATW 3	Causes the link layer test suite to wait 3 seconds between each test.
	Query:	DPRX:SATW?	Queries for the current value of the SATW parameter

15 MCCS

Topics in the chapter:

- Overview
- Accessing the MCCS application
- Using the MCCS application

Overview

The Monitor Control Command Set (MCCS) application allows you to test a display's MCCS support. The MCCS application queries the connected display to determine the Virtual Control Panel (VCP) codes supported by the display. The application presents the supported codes in a graphical user interface, allowing you to monitor MCCS transactions and operate the display through the interface. In addition, you can manually execute MCCS commands through the Script pane in the interface.

For more information about the MCCS standard, refer to the "VESA Monitor Control Command Set (MCCS) Standard," available at www.vesa.org. This standard describes the standardized list of control commands that may be used to control a display by means of an application running on the host. This concept is referred to a 'virtual control panel' or VCP and individual commands are referred to as "VCP codes'.

Accessing the MCCS application


To access the MCCS application:

1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: 192.168.254.001.

   The generator home page appears in the browser.




2. On the generator Home page, click **MCCS**. A message appears asking you to choose whether you want the application to query the display and then open the application, or open the application without querying the display. Click the appropriate button.



3. The MCCS application main window appears. Refer to the graphic below to familiarize yourself with the MCCS application main window. The table below the graphic provides a description of each area. Note that the functional tabs are designated and organized in a manner similar to the way they are in the VESA MCCS specification. Therefore in

order to understand the control parameters available in each tab, you will need to refer to the VESA MCCS specification available at www.vesa.org



Menu	Item	Description
Tool bar	Connect/Disconnect	Allows you to disconnect from or connect to a generator. If you are connecting to a generator, you will need the generator's IP address.
	Re-check Display Status	Checks the connection status of the display. The results are shown in the status bar.
	Refresh Current Panel	Queries the display to get the current settings for all items on the current tab. The information appears on the current tab and the Message Exchange Log pane.
	Check Capability	Queries the display to determine which settings on the current tab are supported by the display. The information appears on the current tab and the Message Exchange Log pane.
Control group tabs	Preset Command	Contains commands for restoring factory default values and storing/restoring user saved values.

Menu	Item	Description
	Image Adjustments	Contains adjustments for the displayed image, excluding geometric adjustments. For example, luminance and color.
	Display Control Adjustments	Contains adjustments for the overall control of the display. For example, the number of hours the display has been in use.
	Geometry Adjustments	Provides adjustments for image geometry and spatial components.
	Misc. Adjustments	Provides adjustments for items not included elsewhere.
	Audio Adjustments	Provides adjustments for items relating to the audio inputs and outputs of the display device.
	DPVL Support	Contains the commands required to support the VESA Digital Packet Video Link standard.
Message pane		Displays command execution messages.
Script pane		Allows you to manually execute MCCS commands and scripts.
Status bar		Shows the IP address of the connected generator, the connection status of the display, the last setting changed, and the setting's read/write and function attributes.

Using the MCCS application

In this section you will find procedures related to the MCCS application. These include:

- Connecting to and disconnecting from a generator
- Adjusting display settings on a tab
- Creating and executing MCCS command scripts
- Using the message log
- Checking the connection status of the display
- Refreshing the settings on the current tab
- Checking display capabilities

Note: *These example procedures are just a sampling of some of the many functions you can perform using the MCCS application.*

Connecting to and disconnecting from a generator

To connect to a generator:

1. Click **Connect/Disconnect**. The Connect to Generator dialog box appears.



   If you are already connected to a generator, click **Disconnect** to disconnect from that generator.

2. In the **Connect To** box, enter the IP address of the generator you want to connect to, and then click **Connect**.
3. Check the status bar to verify that the connection was made successfully.



To disconnect from a generator:

1. Click **Connect/Disconnect**. The Connect to Generator dialog box appears.




2. Click **Disconnect**, and then click **Close** to close the Connect to Generator dialog box.

Adjusting display settings on a tab

This section provides procedures on executing the Virtual Control Panel (VCP) commands through the MCCS GUI application.


Image Adjustments

The image adjustment commands relate to the adjustment of the displayed image excluding geometric adjustments. The following is a screen shot of the Image Adjustment tab:




To adjust display settings on a tab:

1. Click the **Image Adjustments** tab.



2. Adjust the settings as required. Note that only those settings supported by the connected display will be active; inactive settings will appear grayed out.

Example 1 (refer to the graphic below): To change the luminance, slide the bar left or right to decrease or increase the luminance. The Message Exchange Log pane shows the corresponding commands sent to the display.




Example 2 (refer to the graphic below): To select a color preset, click the down arrow on the **Color Preset** box, and then click a setting. Click **Set** to send the command. The Message Exchange Log pane shows the corresponding commands sent to the display.




Display Control Adjustments

The display control adjustment commands cover items relating to information and overall control of the display e.g. the number of hours that display has been in use and the OSD (On Screen Display) language. The following is a screen shot of the Display Control Adjustment tab:




To adjust display control settings on a tab:

1. Click the **Display Control Adjustments** tab.
2. Adjust the settings as required. Note that only those settings supported by the connected display will be active; inactive settings will appear grayed out.



Geometry Adjustments


The geometry adjustment commands provides support for image geometry and spatial adjustments. The following is a screen shot of the Geometry Adjustments tab:



To adjust geometry settings on a tab:


1. Click the **Geometry Adjustments** tab.
2. Adjust the settings as required. Note that only those settings supported by the connected display will be active; inactive settings will appear grayed out.

Example (refer to the graphic below): To change the display scaling to Max Hz 1, select that item from the pull down menu as shown below and then hit the **Set** activation button.



Audio Adjustments


The audio adjustment items relate to the audio (input and output) of the display device. The following is a screen shot of the Audio Adjustments tab:



To adjust audio settings on a tab:


1. Click the **Audio Adjustments** tab.
2. Adjust the settings as required. Note that only those settings supported by the connected display will be active; inactive settings will appear grayed out.

Example (refer to the graphic below): To change the Audio Processor Mode to Stereo Expanded select that item from the Audio Processing mode pulldown select box and then press the **Set** activation button.



DPVL Adjustments


The DPVL adjustment items are required to support the VESA Digital Packet Video Link standard. The following is a screen shot of the DPVL Adjustments tab:



To adjust DPVL settings on a tab:

1. Click the **DPVL Support** tab.
2. Adjust the settings as required. Note that only those settings supported by the connected display will be active; inactive settings will appear grayed out.

Example (refer to the graphic below): To change the Link Control Mode to enable Link Shutdown select the check box and hit the Set activation button as shown below.




Creating and executing MCCS command scripts

To open an existing script:

1. In the Script pane, click **Open**.


   A message appears asking you to confirm that you want to open a script and overwrite the contents of the Script pane.



2. Do one of the following:

   - If you want to proceed and overwrite the contents of the Script pane, click **Yes**. The Open Script dialog box appears.
   - If you want to save the contents of the Script pane before overwriting it, click **No**. See To save the script in the Script pane.

3. Select a script, and then click **Open**, the script appears in the Script pane.




To create a new script:

In the Script pane, type the MCCS commands you want to execute.

To execute the script in the Script pane,

Click the **Exec** button in the Script pane. The commands are executed and the results are shown in the Message Exchange Log pane.



To save the script in the Script pane

1. Click the **Save** button in the Script pane. The Save Script dialog box appears.
2. In the **File Name** box, type a name for the script, and then click **Save**.

To start a new script

1. Click the **New** button in the Script pane. A message appears asking you to confirm that you want to open a new script and overwrite the contents of the Script pane.



2. Do one of the following:
   - If you want to save the contents of the Script pane before starting a new script, click **Yes**. See To save the script in the Script pane.
   - If you want to start a new script without saving the contents of the Script pane, click **No**. The Script pane is cleared.

Using the Message Exchange Log

To erase the Message Exchange Log:

1. Click the **Erase All** button in the Message Exchange Log pane. A message appears asking you to confirm that you want to erase the log.



2. Do one of the following:
   - To erase the log without saving the data, click **Erase log without save**. The contents of the message log are erased.
   - To save the data to a text file before erasing, click **Save current log first**. The Save Message Log dialog box appears. In the **File Name** box, type a name for the log, and then click **Save**.

To save the Message Exchange Log without erasing it:

1. Click the **Save** button in the Message Exchange Log pane. The Save Message Log dialog box appears.
2. In the **File Name** box, type a name for the log, and then click **Save**.

To open a saved Message Exchange Log:

1. Click the **Open** button in the Message Exchange Log pane. A message appears asking you to confirm that you want to overwrite the contents of the Message Exchange Log pane with a saved log.



2. Do one of the following:
   - To overwrite the contents of the Message Exchange Log pane, click **Open another log without Save**. The Open Message Log dialog box appears. Select a message log, and then click **Open**. The log appears in the Message Exchange Log pane.
   - To save the contents of the Message Exchange Log pane before opening an existing log, click **Save current log first**. The Save Message Log dialog box appears. In the **File Name** box, type a name for the message log, and then click **Save**. The contents of the Message Exchange Log pane are saved, and the Open Message Log dialog box appears. Select a log to open, and then click **Open**. The log appears in the Message Exchange Log pane.

Checking the connection status of the display

To check the connection status of the display:

1. Click the **Re-check Display Status** button on the tool bar.
2. Check the status bar to verify the connection status.



Refreshing the settings on the current tab

To refresh the settings on the current tab:

Click the **Refresh Current Panel** button on the tool bar. The application queries the display to get the current settings for all items on the current tab. The information appears on the current tab and in the Message Exchange Log pane.

Checking display capabilities

To check display capabilities:

Click the **Check Capability** button on the tool bar. The application queries the display to determine which settings on the current tab are supported by the display. The information appears on the current tab and in the Message Exchange Log pane.

16 Auxiliary Channel Analyzer

Topics in the chapter:

- Auxiliary Channel Analyzer Overview
- Setting up and using the ACA
- Monitoring the HDMI auxiliary channels
- Monitoring the DisplayPort auxiliary channel

Auxiliary Channel Analyzer Overview

The Auxiliary Channel Analyzer (ACA) is a graphical application that can be used to monitor auxiliary channels such as the DDC and CEC buses in the HDMI interface or the auxiliary channel of the DisplayPort interface. You can monitor multiple channels simultaneously. For example, you can monitor HDCP transactions on the DDC bus while also capturing data for the CEC bus.

The ACA is accessible either from an external Java application (Jar file) downloadable from the Quantum Data web site or from the embedded web server on the 882 generator.

Setting up and using the ACA

The ACA application is a Java application or applet. You can download and install the application on your PC, and then run it locally, or you can run the application from the generator web server.

Note: *You must also have the Java Runtime Environment (JRE) 1.5 or later installed on your PC. You can download the JRE from the following website: http://www.java.com/en/download/windows_ie.jsp*


Running the ACA

This subsection provides procedures on launching the ACA from the generator web server and from your PC.

To run the ACA from the web server:


1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/.

   The generator home page appears in the browser.



2. Click **Auxiliary Channel Analyzer**.

   The ACA main page appears as a separate application window as shown below:



To run the ACA from your PC:

1. In Windows Explorer, locate the directory where you downloaded the ACA application.
2. Double click the **aca.jar** file.

   The ACA main window appears as shown above.

ACA File menu options

This subsection describes the File menu options of the ACA.

Menu Item	Description
Connect to Instrument	Enables you to connect to a generator through the Ethernet LAN port. A dialog box will appear allowing you to enter in the IP address of the 882 that you wish to connect to.
New Trace	Initiates a new trace file.
Open Saved Trace	Allows you to load an existing trace file from your PC.
Save Trace As	Allows you to save a trace file that you have collected from an 882 to your PC using a name you specify in the standard trace file format.

Menu Item	Description
Save Trace	Allows you to save a trace file that you have collected from an 882 to your PC using the default name in the standard trace file format.
Save to HTML	Allows you to save a trace file as an HTML file.
Save to Text	Allows you to save a trace file as a text file.
Save EDID from Trace	Allows the user to save an EDID in the trace file to an XML file. The XML file can then be loaded into the EDID Editor utility for viewing or modifying. The EDID saved from the ACA is the first EDID that is logged in the trace file. For instructions on loading an XML EDID file with the EDID Editor please refer to "Loading EDIDs with the EDID Editor" on page 620.

ACA Filters

This subsection describes filters on the ACA. The filters are the select buttons on the top of the ACA interface.

Filter	Description
EDID	Enables or disables the viewing of EDID log records on the HDMI traces.
DDC/CI	(Future) Enables or disables the viewing MCCS log records for DisplayPort traces.
HDCP	Enables or disables the viewing HDCP transaction log records for HDMI and DisplayPort traces.
CEC	Enables or disables the viewing CEC transaction log records for HDMI traces.
DPCD	Enables or disables the viewing DPCD transaction log records for DisplayPort traces. This includes link training, HDCP and EDID transactions over the DisplayPort auxiliary channel.
Events	Enables or disables the viewing of Events such as hot plugs.
Other	Not used.
All Packets	Enables viewing of all available transactions log available in the active trace file.
Delta/Cumulative mode	Toggles between the Delta and Cumulative mode. Delta mode provide a time reference on the highlighted record to which the times of all other traces are compared. Cumulative provides time stamp for all records sequentially from the time the ACA was launched and began capturing records.


ACA search

This subsection describes the ACA search capabilities.

To search through a trace file

1. Load a trace file or collect a trace file in the ACA.
2. Select the Search item from the top level menu.

   The Search dialog box appears as shown in the screen shot below:



The following table describes the selection items in the search dialog box:

Selection	Description
ASCII String radio button and text field	Specifies a search through the trace file loaded in the ACA for an ascii text string specified in the associated text field.
Hex String radio button and text field	Specifies a search through the trace file loaded in the ACA for an hex text string specified in the associated text field.
CEC radio button and pull down menu	Specifies a search through the CEC trace file that is loaded in the ACA for the opcode selected by the pull down menu.
HDCP Register radio button and pull down menu	Closes the file in the current editor tab.
EDID radio button	Saves the file in the current editor tab.
Search backwards check box	Initiates a search through records prior to the highlighted record.
Find Next activation button	Initiates a search on the trace through records after to the highlighted record. The search will occur on the currently loaded trace file using the criteria defined.
Close activation button	Closes out the Search dialog box.

Monitoring the HDMI auxiliary channels

This subsection provides procedures on operating the ACA for monitoring the HDMI auxiliary channels such as the HDCP and EDID transactions over the DDC or the CEC transactions over the CEC bus. The procedures are the same regardless of whether you run the ACA from the web server or from your PC.

To set up the generator for monitoring the DDC on HDMI:

1. Connect the generator to the HDMI display device or source device under test by doing one of the following:
   a. Connect an HDMI-to-HDMI cable between the HDMI display device or source device under test and either of the HDMI OUT connectors on the generator.
   b. If you are using the analyzer, connect an HDMI-to-HDMI cable between the HDMI display device or source device under test and the HDMI IN connector on the generator.
2. Activate the HDMI-H interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose either the **HDMI-H** item by pressing the adjacent soft key.

   The interface is activated and the port outputs the currently selected image and format.



   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

To monitor the CEC bus (channel):

1. Set up the generator/analyzer for HDMI in accordance with the instructions above.


2. In the ACA, from the **File** menu, select **Connect to Analyzer**. The **Connect to Analyzer** dialog box appears.



3. In the **Connect To** box, enter the IP address of the generator you want to connect to, and then click **Connect**.
4. From the **CEC** menu, point to **Port**, and the select the port you want to monitor.
5. On the toolbar, click the **CEC** button to enable it. Make sure all other buttons are disabled.
6. From the **File** pull down menu specify **New Trace.**
7. Click the **Capture** button.

8. Initiate the actions necessary to cause CEC messages to be transmitted between the HDMI source and sink device.

   The ACA begins the trace and displays the results in the main window, as shown below.




   When you click on a specific transaction you can see the detail timing information are the data. The table below describes the information in the Details and Data panels.

Details	Data
Time since last reset: Field not currently supported	**Data size:** The number of bytes in the message
Size of message: The size of the message in bytes (example 5 bytes)	**Data**: The data is shown for each message. The "+" sign indicates that the last bit, the acknowledge bit is a logical 1; the "-" sign indicates that the last bit, the acknowledge bit was a logical 0.

Details	Data
Message Source: The type of device (product type) and the logical address of the device that sent the message	
Message Destination: The destination device of the message. If a targeted device then its logical addres is provided. If the message is a broadcast “All” is shown and the logical address is F (hex)	
Message Opcode: The CEC operational code for the function of the message	
Device Vendor ID: The identification code for the vendor equipment	
Bit Timings: These are the timings for each bit in the block. They are numbered on the left. The timings for the bit high times are listed and the timings for the low bit times	

1. (Optional) Click the **Save** button on the toolbar to save the trace to a file. The **Save Trace** dialog box appears. Navigate to the folder where you want to save the file. In the **File Name** box, type a name for the file, and then click **Save**.



2. (Optional) The ACA includes a command utility available from the **Options** pull down menu. This utility enables you to enter CEC commands and monitor the results.

To monitor the HDCP transactions on the DDC (I2C) bus (channel):


1. Set up the generator/analyzer for HDMI in accordance with the instructions above “To set up the generator for monitoring the DDC on HDMI:” on page 560.

2. In the ACA, from the **File** menu, select **Connect to Analyzer**. The **Connect to Analyzer** dialog box appears.




3. In the **Connect To** box, enter the IP address of the generator you want to connect to, and then click **Connect**.
4. From **DDC** menu, point to **Port**, and the select the port you want to monitor.
5. On the toolbar, click the **HDCP** button to enable it. Make sure all other buttons are disabled.
6. From the **File** pull down menu specify **New Trace.**
7. Click the **Capture** activation button.
8. Initiate the actions necessary to cause HDCP transactions to occur. This might be selecting the HDCPprod image on the generator if the 882 is emulating a source for testing an HDMI sink.


   The ACA begins the trace and displays the results in the main window, as shown below.



The trace above shows the timestamps in Cumulative mode which shows the time stamps from the beginning of the trace. To view the time differences between a reference record and any other record you can use the Delta time feature by clicking on the activation button on the upper right. An ACA with the Delta time selected is shown below:




9. (Optional) Click the **Save** button on the toolbar to save the trace to a file. The **Save Trace** dialog box appears. Navigate to the folder where you want to save the file. In the **File Name** box, type a name for the file, and then click **Save**.



To monitor the EDID transactions on the DDC (I2C) bus (channel):


1. Set up the generator/analyzer for HDMI in accordance with the instructions above “To set up the generator for monitoring the DDC on HDMI:” on page 560.

2. In the ACA, from the **File** menu, select **Connect to Analyzer**. The **Connect to Analyzer** dialog box appears.




3. In the **Connect To** box, enter the IP address of the generator you want to connect to, and then click **Connect**.
4. From **DDC** menu, point to **Port**, and the select the port you want to monitor.
5. On the toolbar, click the **DDC** and **Events** buttons to enable them. Make sure all other buttons are disabled.
6. From the **File** pull down menu specify **New Trace.**
7. Click on the **Capture** activation button.
8. Initiate the actions necessary to cause a hot plug event for EDID transmission to occur. This might be unplugging the HDMI cable on the generator if the 882 is emulating a source for testing an HDMI sink.

   The ACA begins the trace and displays the results in the main window, as shown below.



9. (Optional) Click the **Save** button on the toolbar to save the trace to a file. The **Save Trace** dialog box appears. Navigate to the folder where you want to save the file. In the **File Name** box, type a name for the file, and then click **Save**.



Passive monitoring between an HDMI source and a sink

The procedures for following procedures provide instructions on how to passively monitor between an HDMI source and and HDMI sink.

To monitor the HDCP DDC transactions between a source and a sink:

1. Configure the generator to operate in the HDMI mode.

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                  CVBS
  HDMI-D           S-VIDEO
  HDMI-H               SDI
```

   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

```
  VGA                  CVBS
  HDMI-D           S-VIDEO
* HDMI-H               SDI
```

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```


2. For the TPA-ACA-3R, connect the cables as follows:

   a. Connect an HDMI-to-HDMI cable between the HDMI connector on the source device under test and the first HDMI connector on the TPA-ACA-3R Test Point Adapter labeled DUT1.


   b. Connect an HDMI-to-HDMI cable between the HDMI connector on the sink device under test and the second HDMI connector on the TPA-ACA-3R Test Point Adapter labeled DUT2.

   c. Connect an HDMI-to-HDMI cable between the HDMI OUT connector on the 882 generator/analyzer and the third HDMI connector on the TPA-ACA-3R Test Point Adapter labeled OUT1.

   The figure below shows the TPA-ACA-3R device.



   The following diagram illustrates the test setup.




3. For the TPA-MP-4R, connect the cables as follows:

   a. Connect an HDMI-to-HDMI cable between the HDMI connector on the source device under test and the HDMI connector on the TPA-MP-4R Test Point Adapter labeled “Source DUT”.


   b. Connect an HDMI-to-HDMI cable between the HDMI connector on the sink device under test and the HDMI connector on the TPA-MP-4R Test Point Adapter labeled “Sink DUT”.

   c. Connect an HDMI-to-HDMI cable between the HDMI OUT connector on the 882 generator/analyzer and the HDMI connector on the TPA-MP-4R Test Point Adapter labeled “Sink DUT”.

   The figure below shows the TPA-MP-4R device.




   The following diagram illustrates the test setup.



4. Run the ACA to view the DDC transactions. Refer to the procedure “To monitor the HDCP transactions on the DDC (I2C) bus (channel):” on page 563.

   The ACA begins the trace and displays the results in the main window, as shown below.



Monitoring the DisplayPort auxiliary channel

This subsection provides procedures on monitoring the auxiliary channels of the DisplayPort interface. The DisplayPort interface uses the auxiliary channel for link training and HDCP as well as I2C emulation for EDID reads.

Note: *The Auxiliary Channel Analyzer for DisplayPort is an optional feature.*

You can monitor the auxiliary channel while the 882E is emulating a DisplayPort device or you can monitor the auxiliary channel passively between two DisplayPort devices. In the first case, the 882E can emulate a DisplayPort source to monitor its aux channel transactions with a DisplayPort sink device under test. Or you can have the 882E emulate a DisplayPort sink device to monitor its auxiliary channel transactions with a DisplayPort source device under test.

For passive monitoring you connect two DisplayPort devices, a source device and a sink device, through the 882E and monitor the auxiliary channel transactions between the two devices passively.


Monitoring the DisplayPort auxiliary channel between the 882E and a DisplayPort device

The following procedures provide instructions on how to monitor the auxiliary channel between the 882E and a DisplayPort sink device under test.


To set up the generator for DisplayPort:

1. Connect the generator to the DisplayPort device as follows:

   a. Sink Testing - The illustration below depicts the setup for monitoring the link layer transactions during testing of a DisplayPort sink:



   b. Source Testing - The illustration below depicts the setup for monitoring the link layer transactions during testing of a DisplayPort sink:



2. Activate the DisplayPort interface by pressing the **Interface** key and choosing the DisplayPort interface as shown below.



   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 10        // Activates the DisplayPort interface
```


```
ALLU            // Applies the interface setting to the generator
```

To monitor the aux channel transactions on the DisplayPort:

1. Set up the generator/analyzer for DisplayPort in accordance with the instructions above "To set up the generator for DisplayPort:" on page 573.
2. Set up the Auxiliary Channel Analyzer in accordance with the instructions in "Setting up and using the ACA" on page 555.
3. In the ACA, from the **File** menu, select **Connect to Analyzer**. The **Connect to Analyzer** dialog box appears.




4. In the **Connect To** box, enter the IP address of the generator you want to connect to, and then click **Connect**.
5. From **DisplayPort** menu, point to **Port**, and the select the **AUX-MON DP** you want to monitor as shown below:



6. From the **File** pull down menu specify **New Trace** or click on the new trace icon.
7. Click the **Capture** activation button.

8. Initiate the actions necessary on the DisplayPort devices to ensure that the aux channel transactions you wish to monitor are occurring. This might be running a link layer compliance test, initiating link training through the command line, or unplugging and plugging in the sink DisplayPort cable to initiate a hot plug to monitor link training or to run HDCP.

   The ACA begins the trace and displays the results in the main window, as shown below:




   Under the Source column there are two types of entries: 1) **Native** refers to aux channel transactions for DPCD reads and writes for link layer operations and HDCP transactions; 2) **I2C** refers to EDID reads.

   You can view details of the transactions by highlighting on a record and then viewing the Details and Data sections below. The Details section parses out the fields into human readable text.

   The trace above shows the timestamps in Cumulative mode which shows the time stamps from the beginning of the trace. To view the time differences between a reference record and any other record you can use the Delta time feature by clicking on the activation button on the upper right.

9. (Optional) Click the **Save** button on the toolbar to save the trace to a file. The **Save Trace** dialog box appears. Navigate to the folder where you want to save the file. In the **File Name** box, type a name for the file, and then click **Save**.



Passive monitoring between a source and a sink


The procedures for following procedures provide instructions on how to passively monitor the auxiliary channel between a DisplayPort sink device and a DisplayPort source device.

To passively monitor the DisplayPort transactions between a source and a sink:

1. Configure the generator to operate in the DisplayPort mode. “To set up the generator for DisplayPort:” on page 573.
2. Connect an DisplayPort-to-DisplayPort cable between the DisplayPort connector on the source device under test and the DisplayPort connector on the 882E labeled **To Source**.


3. Connect an DisplayPort-to-DisplayPort cable between the DisplayPort connector on the sink device under test and the DisplayPort connector on the 882E labeled **To Sink**.

   The following diagram depicts the test setup for passively monitoring a DisplayPort source and sink:



4. Run the ACA to view the aux channel transactions. Refer to the procedure “To monitor the HDCP transactions on the DDC (I2C) bus (channel):” on page 563.

   The ACA begins monitoring the transactions and displaying the results in the main window, as shown below:



Under the Source column there are two types of entries: 1) **Native** refers to aux channel transactions for DPCD reads and writes for link layer operations and HDCP transactions; 2) **I2C** refers to EDID reads.

You can view details of the transactions by highlighting on a record and then viewing the Details and Data sections below. The Details section parses out the fields in to human readable text.

The trace above shows the timestamps in Cumulative mode which shows the time stamps from the beginning of the trace. To view the time differences between a reference record and any other record you can use the Delta time feature by clicking on the activation button on the upper right.

17 Testing EDID for HDMI and DisplayPort

Topics in this chapter:

- Overview
- Testing with display (sink) devices
- Testing with source devices
- Testing EDID for HDMI compliance in display (sink) devices
- EDID emulation for physical layer testing of source devices
- Using the EDID Editor tool
- Using the EDID Compare tool
- Testing EDID for DisplayPort verification in display (sink) devices

Overview

This chapter provides procedures for testing EDID generation and handling. The generator can be configured to:

- emulate an HDMI, DVI, or VGA source device to test an HDMI, DVI, or VGA sink (display) device, or
- emulate an HDMI/DVI sink (display) device to test an HDMI/DVI source device.

With the generator, you can both view EDID from a display, and write EDID to a display device (with writable EEPROM). In addition, you can test an HDMI display device's EDID structure and transmission in accordance with the HDMI Compliance Test Specification 1.2.

Additional EDID tests require the analyzer option. These include testing the EDID handling capabilities of a source device, and the HDMI compliance EDID testing for a sink (display) device.

Testing with display (sink) devices

The generator can emulate a source device in order to test a display device's EDID generation. The EDID data received from a connected display device can be displayed via image or HTML report.

For display devices with writable EEPROM, the generator can also put (write) a new EDID to the device.

Viewing EDID from a display (882 only)

Follow the procedure to view EDID data received from a DDC-compliant VGA, HDMI, DisplayPort or DVI display connected to the generator.

Note: *This feature is not supported on the 881 generator.*

To view EDID data received from a connected display device:

1. Connect the display under test to the generator.
2. Press the **Source** key and choose a suitable format for the display (for example, DMT0660).

   Alternatively, to select the format using the command line interface, enter the following commands:

```
FMTP /tffs0/Library/Formats // Set format path to generator memory
FMTL DMT0660                // Load the DMT0660 format
FMTU                        // Activate the DMT0660 format
```

3. Read the EDID from the display as follows:

   a. Press the **Sink** key. The following information appears on the generator's display.

   ```
   Manufacturer:SNY
   Product Code:144
   Serial#:7011007
   Week:20 Year:1998
   ```

   b. Press the **Options** key. The following information appears on the generator's display.

   ```
   -EDID Formats       CDF↖
   +HP Bypass
   -Emulate
   ```

   c. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats, indicating it is enabled.

   The generator loads the Source list with formats supported by the connected display (hot-plug formats read via EDID structure of attached display).


   Note: *To disable hot plug formats, press the soft key adjacent to EDID Formats. A - next to EDID Formats indicates it is disabled.*

4. Press the **Content** key. A list of images appears on the generator's display.
5. Choose the **EdidData** image by pressing the adjacent soft key. The image appears on the display as shown below.

   Alternatively, to select the image using the command line interface, enter the following commands:

   ```
   IMGL EDIDDATA                // Loads the EdidData image
   ```

```
IMGU                          // Activates the EdidData image
```



	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
0	00	FF	FF	FF	FF	FF	FF	00	4D	D9	F8	01	01	01	01	01
10	00	0E	01	03	80	00	00	78	0A	0D	C9	A0	57	47	98	27
20	12	48	4C	20	00	00	01	01	01	01	01	01	01	01	01	01
30	01	01	01	01	01	01	01	1D	80	18	71	1C	16	20	58	2C
40	25	00	10	09	00	00	00	9E	8C	0A	D0	8A	20	E0	2D	10
50	10	3E	96	00	04	03	00	00	00	18	00	00	00	FC	00	53
60	4F	4E	59	20	54	56	0A	20	20	20	20	20	00	00	00	FD
70	00	3B	3D	0F	2E	08	00	0A	20	20	20	20	20	20	01	DF

6. Enable and view image versions for the EdidData image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:

```
-More
                          Red+
-NoGamma                Green+
-Noise                   Blue+
```

   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.


```
+More     Rendition: 000
                          Red+
-NoGamma                Green+
-Noise                   Blue+
```

   c. Press the + and - keys to advance through the image versions.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1       // Enables sub images
IVER 1       // Specifies the first image version
```

```
IMGU        // Activates the image version
```



7. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

   ```
   ISUB 0     // Disables sub images
   ```

To view EDID data received from a connected display device using the command line interface:

1. Connect the display under test to the generator.
2. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.
3. Enter one of the following commands:
   - To view the current EDID in ASCII hex format, enter the EDID? command..
   - To view a specific segment of EDID, enter the I2CR? (OUT1:I2CR?, OUT2:I2CR?, VGA:I2CR?) command (refer to the command description identify the arguments of this query).

Generating an EDID Information Report


Follow the procedure to generate an HTML report of EDID data received from a DDC-compliant VGA, HDMI, DisplayPort or DVI display connected to the generator.

To generate a report of EDID data received from a connected display device:


1. Connect the display under test to the generator.
2. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



3. Press the **Reports** key. The **Reports** menu appears on the generator's display as shown below.




4. Choose the **EDID** item by pressing the adjacent soft key. The **EDID reports** menu appears on the generator's display as shown below.




Note: *Be sure that you have transferred any existing EDID reports to your PC. Otherwise, generating a new report overwrites the existing report.*

5. Choose **!DataRpt** item by pressing the adjacent soft key. An EDID Information Report is generated and stored on the PCMCIA card in the **/card0/Library/Reports/Edid_Data.htm** file.
6. Open the FTP Browser on the generator and select a suitable directory on your PC to store the report.
7. Using the FTP Browser, transfer the report from the generator PCMCIA card to your PC like shown below.

Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwritting existing reports.*


FTP Browser
quantumdata
Instrument Files
Host Files
Open
Use
Upload
New
Rename
Delete
Snapshot
Download
Look in:
Rename
Enter a new name:
OK
Cancel

8. Navigate to your PC and double click on the report. A sample is shown below.



EDID Information Report - Microsoft Internet Explorer

Apr 27 2005 [16:20:51] Quantum Data Inc

EDID Information Report

	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
00:	00	FF	FF	FF	FF	FF	FF	00	44	89	B2	00	05	00	00	00
10:	0D	0C	01	03	80	50	2D	78	0A	0D	C9	A0	57	47	98	27
20:	12	48	4C	20	00	00	01	01	01	01	01	01	01	01	01	01
30:	01	01	01	01	01	01	01	1D	80	18	71	1C	16	20	58	2C
40:	25	00	C4	8E	21	00	00	9E	8C	0A	D0	8A	20	E0	2D	10
50:	10	3E	96	00	13	8E	21	00	00	18	00	00	00	FC	00	48
60:	44	4D	49	20	54	56	0A	20	20	20	20	20	00	00	00	FD
70:	00	3B	3D	0F	2E	08	00	0A	20	20	20	20	20	20	01	08

Block 0

	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
00:	02	03	1C	F1	49	85	04	08	02	01	06	14	12	16	23	09
10:	07	07	83	01	00	00	65	03	0C	00	10	00	01	1D	00	72
20:	51	D0	1E	20	6E	28	55	00	C4	8E	21	00	00	1E	D6	09
30:	80	A0	20	E0	2D	10	10	60	22	00	12	8E	21	08	08	18
40:	8C	0A	D0	90	20	40	31	20	0C	40	55	00	C4	8E	21	00
50:	00	18	01	1D	80	D0	72	1C	16	20	10	2C	25	80	C4	8E
60:	21	00	00	9E	8C	0A	A0	14	51	F0	16	00	26	7C	43	00
70:	13	8E	21	00	00	98	00	00	00	00	00	00	00	00	00	94

Block 1

PRODUCT ID

- Manufacturer:QDI
- Model ID:178
- Serial Number:5
- Week Made: 13
- Year Made:2002

Modifying EDID in a display

If the EEPROM in the display is writable, you can write a new EDID to the device. Follow the procedure to overwrite the EDID structure stored in the connected display device with a new EDID structure.

Important: *Be sure to save a backup copy of the EDID stored on the display device. Writing an EDID using this procedure will overwrite the EDID currently stored on the display device.*

To write an EDID to the display device:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.
2. Connect the display under test to the generator.
3. Load an EDID from the generator using the following command:

```
DIDL filename
```

4. Write the EDID to connected display device using the following command:

   ```
   EDA<n>:PDID
   ```

   Where <n> is the HDMI output port (1 or 2). For example, the command below writes the EDID out the HDMI Out 2 port.

   ```
   EDA2:PDID
   ```

Testing with source devices

With the Analyzer option, the generator can emulate an HDMI/DVI sink (display) in order to test an HDMI source device's EDID handling. With this capability, an HDMI/DVI source device can be tested for its ability to handle an EDID received from virtually any DDC-compatible display.

The analyzer emulates HDMI/DVI displays using a built-in, configurable EDID structure. You can configure the analyzer to use an EDID structure obtained directly from a display device, or from a EDID XML file stored in the generator's file system.

Capturing and storing EDID from display device

Follow the procedure to capture and store an EDID structure from a display device connected to the generator's HDMI output (Tx) port.

To capture and store an EDID from a connected HDMI/DVI display device:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Connect the 882 HDMI output (Tx) port to the display device whose EDID you wish to capture.
3. Activate the HDMI-H or HDMI-D interface on the output port:
   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the HDMI-H or HDMI-D item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.



   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3 (or 4)      // Selects the HDMI-D (or HDMI-H) interface
ALLU               // Applies the interface setting to the generator
```

4. Capture the EDID from the connected display device by entering the following command:

   `EDA<port>:GDID`

   Where *port* is the HDMI output port (1 or 2) that the display is connected to. For example, the command below loads an EDID from a display device connected to the 882's HDMI Out port 1.

   ```
   EDA1:GDID
   ```

   Note: *The EDAport:GDID is a command that is new with Release 2.3.0.*

5. Store the captured EDID in the 882's internal file system by entering the following command:

   `DIDA filename`

   Where *filename* is the name of a file in the default directory identified by DIDP. For example, the command below store an EDID to the default EDID path.

   ```
   DIDA myedid1
   ```

   If you want to store the EDID file in a location that is not the default path, you can either list the path explicitely on the DIDA command line or change the EDID path with DIDP. For example, the command below loads an EDID from a different directory in flashmem.

   ```
   DIDA /tffs0/library/userdata/myedid1
   ```

6. (Optional) Use the captured EDID to emulate the display device on the analyzer by entering the following command:

   `EDE<port>:DIDU`

   Where *port* is the HDMI input (Rx) port (1 or 2) that you want to configure to emulate the EDID. For example, the command below loads the EDID stored in the EDID edit buffer for emulation into the HDMI input (Rx) port 2.

   ```
   EDE2:DIDU
   ```

Creating or editing EDID contents

You can create or modify an EDID structure to emulate a specific display device using one of the following methods:

- Using the EDID Editor tool. See "Using the EDID Editor tool" on page 620 for details on using the EDID Editor tool
- Loading EDID into memory buffer and creating/modifying content using EDID editing commands. See following procedure for details.

To create/edit an EDID using EDID editing commands:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.
2. To create a new EDID, follow these steps:
   a. Create a new EDID file by entering the following command:

      ```
      DIDN filename
      ```

   b. Define EDID structure content using EDID edit commands. The following example shows how you can create EDID content:

      ```
      DIDB          // begins an edid editing session
      XDID 0 80
      00FFFFFFFFFFFF005A63118F01010101130D010380221B782A4706A55C47
      9C251E4F54BFEF008180310A01010101010101010101010101302A009851002A4030
      701300520E1100001E000000FF00413233303331393135335390A000000FD0032
      4B1E530E000A20202020202000000FC0056583730302D330A20202020200095
      DIDE            // ends an edid editing session
      ```

      Note: *The EDID edit buffer commands are new with Release 2.3.0.*

   c. Save EDID file to the generator by entering the following command:

      ```
      DIDS            // saves the edid
      ```

3. To modify an existing EDID (stored on the generator), follow these steps:
   a. Load an EDID from the 882’s internal file system:

      ```
      DIDL filename
      ```

      Where *filename* is the name of a file in a the default directory identified by DIDP. For example, the command below loads an EDID from the default EDID path.

      ```
      DIDL myedid1
      ```

      If the EDID you want to load is not in the default path, you can either list the path explicitely on the DIDL command line or change the EDID path with DIDP. For example, the command below loads an EDID from a different directory in flash memory.

      ```
      DIDL /tffs0/library/userdata/myedid1
      ```

   b. Modify EDID structure content using EDID edit commands. The following example shows how you can modify EDID content:

      ```
      DIDB          // begins an edid editing session
      XDID 19 A E88A82A0564796240F48 // edits EDID at 19 for 10 (0x0A)
      bytes
      DIDE            // ends an edid editing session
      ```

Note: *The EDID edit buffer commands are new with Release 2.3.0.*

c. Save edits to EDID file to the generator by entering the following command:

```
DIDS            // saves the edid
```

Testing EDID handling of source device

To use analyzer to test source device EDID handling:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Select EDID to be used on the analyzer to test source device:
   - To use an EDID of a specific display device, perform steps described in "Capturing and storing EDID from display device" on page 589. In that procedure, be sure to perform step 6 to select the captured EDID structure to be used on the analyzer.
   - To use an EDID file stored on the generator, enter the following commands:

     ```
     DIDL EDID filename
     EDE<port>:DIDU
     ```

     Where *port* is the HDMI input (Rx) port (1 or 2) that you want to configure to emulate the EDID. For example, the command below loads the EDID stored in the EDID edit buffer for emulation into the HDMI input (Rx) port 2.

     ```
     EDE2:DIDU
     ```

   Note: *To create or modify an EDID structure, see "Creating or editing EDID contents" on page 590 for details.*
3. If desired, use the STRG command to stretch the SCL low signal for 5 ms in the analyzer's receiver.
4. Connect the 882 HDMI input (Rx) port to the source device you wish to test.

   Upon receiving the HDMI/DVI signal at the HDMI input connector, the generator sends the EDID structure to the source device.
5. At the HDMI/DVI source device, compare the processed EDID information with the EDID structure defined in the generator.

Testing EDID for HDMI compliance in display (sink) devices

The generator supports the following EDID and video HDMI compliance tests in accordance with the HDMI Compliance Test Specification 1.3 (CTS):

- Test ID 8-1: EDID Readable
- Test ID 8-2: EDID VESA Structure
- Test ID 8-3: CEA Timing Extension Structure
- Test ID 8-17: 861B Format Support Requirements
- Test ID 8-18: HDMI Format Support Requirements
- Test ID 8-19: Pixel Encoding Requirements
- Test ID 8-20: Video Format Timing

These tests are intended for in-house testing of products before submission to an HDMI ATC for full certification testing.

Note: *This feature is not supported on the 881 generator.*

Testing HDMI sink device for EDID compliance

HDMI sink compliance testing is conducted through the generator's HDMI OUT connector. A standard HDMI-to-HDMI cable connects the device under test to the generator. The generator must be configured to output HDMI signals.

You can run the EDID compliance test on an HDMI sink device in three ways: 1) through the front panel using the EDIDHDMI image, 2) using the EDID Compliance report also available through the front panel or 3) using the Compliance Controller. The Compliance Controller is an application (available in release 2.18 or later) that is available on the 882 web home page. This section includes procedures for running the EDID compliance test in all of the three ways.

Defining the capabilities of the display device under test

After making the physical connections, you must specify the capabilities of the sink display under test, which are based on the Capabilities Declaration Form (Appendix 3) of the Compliance Test Specification. This enables the generator to compare the expected results with the actual results measured from the display.

The manner in which you define the CDF depends on which method you are using to run the test (front panel or Compliance Controller). The following table provides a description of the parameters in the EDID CDF that need to be defined. Use this table as a reference when entering the CDF for any test regardless of the test method (i.e. front panel or Compliance Controller). One key advantage of using the Compliance Controller to run the

test and set the CDF is that it enables you to automatically generate a baseline CDF from the sink devices EDID. The following table describes the EDID CDF parameters and their settings.

Parameter	Explanation
HDMI Output Count	The number of outputs the sink under test has. It is a value in the range of 0-9.
HDMI Input Port	The CEC input on the sink under test. It is a value in the range of 1-15.
CEC Root Device	Indicates if the CEC device is a root device (i.e. a TV without a repeater). The values are + for yes and - for no.
Primary AR: 4:3	Indicates the primary aspect ratio of the sink device under test. This can be either 4:3, 16:9 or both. The values are + for yes and - for no.
HDTV	Indicates if the sink under test supports HDTV. The values are + for yes and - for no. The values are + for yes and - for no.
YUV on Other	Indicates if the sink under test supports YUV. The values are + for yes and - for no. The values are + for yes and - for no.
60Hz	Indicates whether the device supports formats with 60Hz frame rate. The values are + for yes and - for no.
50Hz	Indicates whether the sink under test supports formats with 50Hz frame rate. The values are + for yes and - for no.
640x480p/60	Indicates whether the sink supports the DMT0660 format. The values are + for yes and - for no.
720x480p/60 4:3	Indicates whether the sink supports the 480p60 format with a 4:3 aspect ratio. The values are + for yes and - for no.
720x480p/60 16:9	Indicates whether the sink supports the 480p60SH format with a 16:9 aspect ratio. The values are + for yes and - for no.
1280x720p/60 16:9	Indicates whether the sink under test supports the 720p60 format. The values are + for yes and - for no.
1920x1080i/60 16:9	Indicates whether the sink under test supports the 1080i60 format. The values are + for yes and - for no.
1440x480i/60 4:3	Indicates whether the sink under test supports the 480i2x60 format with double clocking at 4:3 aspect ratio. The values are + for yes and - for no.
1440x480i/60 16:9	Indicates whether the sink under test supports the 480i2x60 format with double clocking at 16:9 aspect ratio. The values are + for yes and - for no.

Parameter	Explanation
720x576p/50 4:3	Indicates whether the sink supports the 576p50 format with a 4:3 aspect ratio. The values are + for yes and - for no.
720x576p/50 16:9	Indicates whether the sink supports the 576p50 format with a 16:9 aspect ratio. The values are + for yes and - for no.
1280x720p/50 16:9	Indicates whether the sink under test supports the 720p50 format. The values are + for yes and - for no.
1920x1080i/50 16:9	Indicates whether the sink under test supports the 1080i50 format. The values are + for yes and - for no.
1440x576i/50 4:3	Indicates whether the sink under test supports the 576i2x50 format with double clocking at 4:3 aspect ratio. The values are + for yes and - for no.
1440x576i/50 16:9	Indicates whether the sink under test supports the 576i2x50 format with double clocking at 16:9 aspect ratio. The values are + for yes and - for no.
1440x480i/50 4:3	Indicates whether the sink under test supports the 480i2x50 format with double clocking at 4:3 aspect ratio. The values are + for yes and - for no.
1440x480i/50 16:9	Indicates whether the sink under test supports the 480i2x50 format with double clocking at 16:9 aspect ratio. The values are + for yes and - for no.
720p/60 On Other	Indicates whether the sink under test supports the analog component video input for 720p60. The values are + for yes and - for no.
1080i/60 On Other	Indicates whether the sink under test supports the analog component video input for 1080i60. The values are + for yes and - for no.
480p/60 On Other	Indicates whether the sink under test supports the analog component video input for 480p60. The values are + for yes and - for no.
720p/50 On Other	Indicates whether the sink under test supports the analog component video input for 720p50. The values are + for yes and - for no.
1080i/50 On Other	Indicates whether the sink under test supports the analog component video input for 1080i50. The values are + for yes and - for no.
576p/50 On Other	Indicates whether the sink under test supports the analog component video input for 576p50. The values are + for yes and - for no.
Supports AI	Indicates whether the sink under test supports audio information. The values are + for yes and - for no.
Basic Audio	Indicates whether the sink supports basic audio. The values are + for yes and - for no.

Parameter	Explanation
Connector Type A	Indicates whether the sink under test input connector is a Type A connector.
Write Protected	Indicates whether the EDID of the sink under test is write protected.
HDMI 1.3B CTS	Indicates whether to test sink against HDMI Compliance Test Specification (CTS) 1.3b or 1.2a. The values are + for 1.3b or - for 1.2a.
Deep Color	Indicates whether the sink under test supports deep color. The values are + for yes and - for no.
DC 30 Bit	Indicates whether the sink under test supports deep color at 30 bits per pixel. The values are + for yes and - for no.
DC 36 Bit	Indicates whether the sink under test supports deep color at 36 bits per pixel. The values are + for yes and - for no.
DC 48 Bit	Indicates whether the sink under test supports deep color at 48 bits per pixel. The values are + for yes and - for no.
DC YCbCr 4:4:4	Indicates whether the sink under test supports deep color in YCbCr 4:4:4. The values are + for yes and - for no.
xvYCC	Indicates whether the sink under test supports xvYCC601 or xvYCC709. The values are + for yes and - for no.
Above 165MHz	Indicates whether the sink under test supports any video format/color mode with a TMDS clock frequency above 165MHz. The values are + for yes and - for no.
1920x1080p/60 16:9	Indicates whether the sink under test supports the 1080p60 format at 16:9 aspect ratio. The values are + for yes and - for no.
1920x1080p/50 16:9	Indicates whether the sink under test supports the 1080p50 format at 16:9 aspect ratio. The values are + for yes and - for no.
Dual-Link DVI	Indicates whether the sink under test supports dual-link DVI. The values are + for yes and - for no.
Lipsync Indicated	Indicates whether the EDID of the sink under test indicates lipsync latency values. The values are + for yes and - for no.
Dual Latencies	Indicates whether the sink under test's audio and video latency is substancially different when handling interlaced video formats versus when handling progressive video formats. The values are + for yes and - for no.

Setting up generator for HDMI sink device EDID compliance testing

Follow these procedures to set up the generator for HDMI sink testing for EDID compliance. You will use this procedure regardless of whether you are running the EDID compliance test through the front panel or the Compliance Controller.

To set up the generator for HDMI sink EDID compliance testing:

1. Connect an HDMI-to-HDMI cable between the HDMI OUT connector on the generator and the HDMI connector on the display under test.
2. Press the **Source** key and choose a valid HDMI format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, to select the format through the command line interface, enter the following command:

   ```
   FMTL DMT0660
   FMTU
   ```

3. Activate the HDMI-H interface on the output port as follows:

   Note: *You may have to select a valid HDMI format at this point.*

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.


   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

   ```
   XVSI 4          // Selects the HDMI-H interface
   ALLU            // Applies the interface setting to the generator
   ```

4. Press the **Sink** key, and then press the **Options** key. The following menu appears on the generator's display:

5. Choose the **CDF** item by pressing the adjacent soft key. The CDF parameters appear on the generator's display as shown below.

```
0:HDMI Output Count
1:HDMI Input Port
-CEC Root Device
>Primary AR: 4:3
```

6. Set characteristics of the display under test using CDF parameters. Scroll through the list by pressing the + key.

   Refer to "Defining the capabilities of the display device under test" on page 593 for definitions for each parameter in the CDF.

   Note: *If you are running the EDID compliance test through the Compliance Controller, you do not need to configure the CDF through the front panel.*

Running the EDID compliance test through the front panel

Use the following procedure to run the EDID compliance test through the front panel. You can run the EDID compliance test through the front panel either by using the EDIDHDMI image or the EDID compliance report. Refer to "Running the HDMI EDID Compliance test report" on page 605 for instructions on running the EDID compliance test through the compliance report feature.

To perform HDMI sink EDID compliance testing using the EDID HDMI image:

1. Set up generator for HDMI sink testing for EDID compliance. See Setting up generator for HDMI sink device EDID compliance testing on page 597 for details.
2. Press the **Content** key and choose the **EdidHDMI** image for testing displays connected to HDMI output 1 (usee **EDIDHDM2** image for HDMI output 2) by pressing the adjacent soft key.

   Alternatively, to select the image through the command line interface, enter the following command:


```
IMGL EdidHDMI
IMGU
```

3. Enable image versions for the EdidHDMI/EdidHDM2 image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:



   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.



   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

4. Press the + key to advance through the image versions and view results for tests 8-1, 8-2, 8-3, 8-17, 8-18, and 8-19. Test descriptions and sample screens are provided below.

- **Testing EDID readability (Test ID 8-1)**—this test verifies that the EDID can be read properly.

	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
0	00	FF	FF	FF	FF	FF	FF	00	4D	D9	F8	01	01	01	01	01
10	00	0E	01	03	80	00	00	78	0A	0D	C9	A0	57	47	98	27
20	12	48	4C	20	00	00	01	01	01	01	01	01	01	01	01	01
30	01	01	01	01	01	01	01	1D	80	18	71	1C	16	20	58	2C
40	25	00	10	09	00	00	00	9E	8C	0A	D0	8A	20	E0	2D	10
50	10	3E	96	00	04	03	00	00	00	18	00	00	00	FC	00	53
60	4F	4E	59	20	54	56	0A	20	20	20	20	20	00	00	00	FD
70	00	3B	3D	0F	2E	08	00	0A	20	20	20	20	20	20	01	DF

Test ID 8-1: EDID Readable
PASS->Block 0 header
PASS->Block 0 checksum
PASS->Number of extension blocks is 1

Block 0

To go to the next step...
Increment the Image Rendition

	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
0	02	03	1A	76	47	85	02	03	04	06	07	01	23	09	07	07
10	83	01	00	00	65	03	0C	00	10	00	01	1D	00	72	51	D0
20	1E	20	6E	28	55	00	10	09	00	00	00	1E	8C	0A	A0	14
30	51	F0	16	00	26	7C	43	00	04	03	00	00	00	98	8C	0A
40	D0	8A	20	E0	2D	10	10	3E	96	00	10	09	00	00	00	18
50	8C	0A	A0	14	51	F0	16	00	26	7C	43	00	10	09	00	00
60	00	98	00	00	00	00	00	00	00	00	00	00	00	00	00	00
70	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	97

(Continue...) Test ID 8-1: EDID Readable
PASS->Block 1 checksum


Block 1


To go to the next step...
Increment the Image Rendition

- T**esting EDID VESA structure (Test ID 8-2)**—this test verifies that the data in the base EDID 1.3 block and basic EDID Extension handling is correct and meets all aspects of the relevant specifications.





- **Testing CEA timing extension structure (Test ID 8-3)**—this test verifies that the data in any CEA Timing Extension present in EDID is formatted properly and meets all aspects of the relevant specifications.







- **Testing 861C format support requirements (Test ID 8-17)**—this test verifies that no 861C-defined video format is declared only in a Detailed Timing Descriptor.








- **Testing HDMI format support requirements (Test ID 8-18)**—this test verifies that the display under test indicates support for all required video formats in its EDID.



- **Testing Pixel Encoding Requirements (Test ID 8-19)**—verifies that the display under test supports YCpCr pixel encoding when required.




Running the HDMI EDID Compliance test report


Follow the procedure to generate an HTML report of EDID compliance test results. Prior to running this test you will need to configure the generator for the test. Refer to “Setting up generator for HDMI sink device EDID compliance testing” on page 597 for instructions on setting up the generator for the EDID test.

To generate a report of EDID compliance test results:


1. Press the **Tools** key. The **Tools** menu appears on the generator’s display as shown below.



2. Press the **Reports** key. The **Reports** menu appears on the generator’s display as shown below.



3. Choose the **EDID** item by pressing the adjacent soft key. The **EDID reports** menu appears on the generator's display as shown below.



Note: *Be sure that you have transferred any existing EDID reports to your PC. Otherwise, generating a new report overwrites the existing report.*

4. Define the capabilities declaration form for the sink device you are going to test by selecting the **EditCDF** item. Select the adjacent soft key.


   Refer to "Defining the capabilities of the display device under test" on page 593 for instructions on defining the CDF.

5. Choose **!CompRpt** item by pressing the adjacent soft key. An HDMI EDID Compliance Report is generated and stored on the PCMCIA card in the **/card0/Library/Reports/Edid_Compliance.htm** file.


6. Open the FTP Browser on the generator and select a suitable directory on your PC to store the report.

7. Using the FTP Browser, transfer the report from the generator PCMCIA card to your PC like shown below.

Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwritting existing reports.*



8. Navigate to your PC and double click on the report. A sample is shown below.



Running the HDMI EDID Compliance using the Compliance Controller

Follow the procedure below to run the EDID HDMI compliance test using the Compliance Controller (available in release 2.18 or later). Prior to running this test you will need to configure the generator for the test. Refer to “Setting up generator for HDMI sink device EDID compliance testing” on page 597 for instructions on setting up the generator for the EDID test.


To run the EDID HDMI compliance test using the Compliance Controller:

1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.



2. Lauch the Compliance Controller by clicking on the **Compliance Controller** link. The Compliance Controller appears as shown below.



3. Select the **EDID** tab.
4. Define the capabilities declaration form for the sink device you are going to test by selecting (checking) off the parameters that are supported by the sink device you are testing.

   Refer to “Defining the capabilities of the display device under test” on page 593 for information on the EDID parameters used in defining the CDF.

5. (Optional) You can expedite the CDF definition process by reading the EDID directly from the display device under test using the **Auto Generate CDF** feature.



Please note however that the specifications of the display may differ from the implementation. That is the purpose in running the test. Using the Auto Generate CDF feature is a way of populating the CDF form with a configuration that is at least quite similar to the specification.


6. Click the **Use CDF** actitivation button located at the bottom of the interface, to load the CDF defined in the screen for use in the test.



7. Click the **Run Test** actitivation button to run the EDID compliance test.


   The test runs without interruption.

8. Select the Report tab on the Compliance Controller interface to view the list of reports as shown below.



9. Click on the EDID Compliance report you wish to view.

   The report is display in the browser window as shown below.




Verifying pixel encoding and rate support

For test IDs 8-19 and 8-20, visual inspection of display under test is necessary to ensure proper support of pixel encoding sampling and minimum and maximum pixel clock rates using different formats. Test ID 8-19 involves testing each format with both YCbCr 4:4:4 and YCbCr 4:2:2 pixel sampling, while test ID 8-20 requires testing each format listed in the EDID at both minimum and maximum pixel clock frequencies permitted by the source device. Pixel clock rate values are as follows:

- For 50 Hz formats, the values are 49.75 Hz and 50.25 Hz (50 Hz ± 0.5%).
- For 59.94 Hz or 60 Hz formats, the frequencies are 59.64 Hz (59.94 Hz – 0.5%) and 60.3 Hz (60Hz + 0.5%).
- The tested pixel clock frequency accuracy shall be ±0.05%


To support this testing, a list of SVD formats are provided in the Source list. For **pixel encoding** testing, the format naming nomenclature used is shown below:

Example



- **SVD** – Short Video Descriptor
- **01** – EIA/CEA-861-C Format Video Identification Code (for example, 01, 02, 06, etc., listed on page 149)
- **Y2** – Y indicates color difference. 2 = 4:2:2 pixel sample encoding. 4 = 4:4:4.
- **1** – Represents DMT0659 format, which is the first format (index 1) listed under video identification code 01 in the table on page 335.

For **pixel rate** testing, the format naming nomenclature used is shown below:



- **SVD** – Short Video Descriptor
- **01** – EIA/CEA-861-C Format Video Identification Code (for example, 01, 02, 06, etc,. listed on page 335)
- **H** – Indicates the format is using the maximum (H = High) frequency required by the compliance test; L indicates the format is using the minimum (L = Low) frequency required by the compliance test.
- **01** – Represents the index of the format as listed under video identification code on page 335.

To verify proper pixel encoding and pixel rate support:

1. Connect the generator to the display under test.
2. Press the **Sink** key. The following information appears on the generator's display.

```
Manufacturer:SNY
Product Code:144
Serial#:7011007
Week:20 Year:1998
```

3. Press the **Options** key. The following information appears on the generator's display.



4. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats, indicating it is enabled.

   The generator loads the Source list with formats supported by the connected display (hot-plug formats read via EDID structure of attached display).

5. Press the **Content** key. The following information appears on the generator's display.



6. Select an image suitable for testing the display type (such as **Master**) by pressing the soft key adjacent to the image.

   Alternatively, to select the image using the command line interface, enter the following command:

```
IMGL Master
IMGU
```

7. Press the **Source** key and select a format beginning with SVD by pressing the adjacent soft key.
8. On display under test, verify format displays image properly.
9. Repeat steps 7 and 8 to test each SVD format.

Testing EDID for HDMI compliance in source devices

The analyzer supports the following EDID and video HDMI compliance tests in accordance with the HDMI Compliance Test Specification 1.3 (CTS):

- Test ID 7-1: EDID Related Behavior

This test is intended for in-house testing of products before submission to an HDMI ATC for full certification testing.

Note: *This feature is not supported on the 881 generator.*

Overview of HDMI compliance testing

HDMI source compliance Test ID 7-1 is conducted through the generator's HDMI Rx In connector. A standard HDMI-to-HDMI cable connects the device under test to the generator. The generator must be configured to output HDMI signals.

Testing HDMI source devices for EDID compliance

The procedures for EDID and video testing of HDMI sink devices in accordance with the HDMI Compliance Test Specification 1.3 are provided below.

To run the HDMI EDID source compliance test:

1. Configure the generator to operate in the HDMI mode.
   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.



   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```


2. Configure the generator/analyzer to emulate the desired EDID using the procedures in “Testing EDID handling of source device” on page 592 or “Emulating an EDID” on page 637.

   If you need to create a custom EDID, use the EDID Editor utility described in “Creating a new EDID” on page 627.


3. Connect an HDMI-to-HDMI cable between the HDMI OUT connector on the source device under test and the first HDMI connector on the TPA-DDC-RR Test Point Adapter.

4. Connect an HDMI-to-HDMI cable between the HDMI IN connector on the 882 generator/analyzer and the second HDMI connector on the TPA-DDC-RR Test Point Adapter.

   The figure below shows the TPA-DDC-RR device.



   The following diagram illustrates the test setup.



5. Set the capacitance to the desired value by flipping the toggle switch to the “1” or “2” position.

6. Follow the procedures in the HDMI CTS specification.


   You can use the ACA to view the transactions of the EDID read. Refer to the procedure “To monitor the EDID transactions on the DDC (I2C) bus (channel):” on page 566.

   During the procedure, you will have to pulse the hot plug detect lead. To do this with the DIDU command:

   ```
   DIDU
   ```

EDID emulation for physical layer testing of source devices


The 882C/E supports some of the physical layer tests called out in the HDMI CTS such as eye measurements and TMDS rise and fall time measurements. These tests are performed using commercially available oscillocopes recommended in the HDMI CTS. In support of these tests, the Multi-Purpose Adaptor (TPA-MP-4R shown below) provides EDID emulation, a hot plug source and AVcc power source.



While standard HDMI-to-HDMI cables connect the generator to the TPA-MP-4R device, cables available as an option through Quantum Data are used to connect that device to the source device under test. Two methods for testing EDID compliance with HDMI source devices are shown below. One uses the Tektronix Test Instrument and the second uses the Agilent Test Instrument.


Using Tektronix Test Instruments

The 882 series analyzer provides EDID emulation and DDC, EDID, hot plug and CEC transaction monitoring. The TPA-MP-4R provides +3.3Vcc via the P40 2-wire cable. The TPA-MP-4R connects the 882E/CA HDMI Rx 1 to the Tek TPA-P-DI via P30 8-wire cable. TPA-P-DI connects Rx DDC, Hot Plug Detect and CEC to the source device under test. The following illustration depicts these connections.



Using Agilent Test Instruments

The 882E/CA provides EDID emulation and DDC, EDID, hot plug and CEC transaction monitoring. The TPA-MP-4R provides +3.3Vcc via the Pomona 5069 8-wire cable. The TPA-MP-4R connects the 882CA HDMI Rx 1 to the Agilent TPA-P via 5069 8-wire cable. TPA-P connects Rx DDC, Hot Plug Detect and CEC to the source device under test. The following illustration depicts these connections.



Using the EDID Editor tool

The 882 provides an EDID Editor Tool. This tool is useful for creating, modifying, and saving EDIDs, as well as applying EDIDs to HDMI emulator ports for source testing.

Using the EDID Editor Tool involves the following basic steps:

1. Loading an EDID into the Editor. An EDID is loaded from a file stored on the generator file system or host PC, or by capturing and loading an EDID from a display connected to the 882CA HDMI or VGA interface.
2. Modifying EDID settings using the tool's user-friendly graphical interface. Operations are accomplished using check boxes, text fields and pull-down list boxes with human readable field descriptions and value options.
3. Saving a modified EDID to a file stored on the generator file system or host PC, and/or by putting (writing) the EDID on a display connected to the 882CA HDMI interface (display must have writable EEPROM).
4. For source testing, applying an EDID to one of the HDMI Rx ports for emulation.

Note: *When creating EDIDs for source testing (for computer monitors in the IT market or TV displays in the CE market), it is important to understand the specifications which define the structure of the EDID you are creating. The EDID structure is defined by VESA and and the extensions are defined by the CEA in the 861 specification.*

Loading EDIDs with the EDID Editor

The procedure below provides instructions on loading EDIDs into the EDID Editor Tool.

To load an EDID:

1. Make appropriate cable connection as follows:
   - If you are capturing and loading an EDID from an HDMI display, connect an HDMI-to-HDMI cable between the HDMI OUT connector on the generator and the HDMI connector on the display under test.
   - If you are loading an EDID from one of the HDMI Rx ports on the generator, connect an HDMI-to-HDMI cable between the HDMI Tx connector on the generator and the HDMI Rx input ports that is configured with the EDID you wish to load.
   - If you are capturing and loading an EDID from a VGA monitor, connect a VGA-to-VGA cable between the VGA connector on the generator and the VGA connector on the display under test.

2. Press the **Source** key and choose a valid HDMI or VGA format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, to select the format through the command line interface, enter the following command:

```
FMTL DMT0660
FMTU
```

3. Activate the HDMI-H, HDMI-D or VGA interface on the output port as follows:

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H, HDMI-D or VGA** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   c. Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Selects the HDMI-H interface
or
XVSI 3          // Selects the HDMI-D interface
XVSI 9          // Selects the VGA interface


ALLU            // Applies the interface setting to the generator
```

4. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.



5. Click the **EDID Editor** link. The EDID Editor appears as shown below.




Note: *The EDID Editor is provisioned with the default Quantum Data EDID when opened.*

6. Choose the EDID you want to load into the Editor. You can load EDIDs from a connected device, the generator file system, or from your PC. The following table describes what selection ports map to which physical interface:


Load EDID From...	Location
882	A valid EDID XML file stored on the generator file system (in flash memory or on the PC card).
Device connected to 882	A device that is connected either to the generator's HDMI Tx ports or the VGA port: - 882 Analyzer Port 1 - HDMI Tx 1 - 882 Analyzer Port 2 - HDMI Tx 2 - 882 Analyzer Port 3 - VGA
File on PC	A valid EDID XML file stored in the host PC.

   a. If you are loading an EDID XML file stored on the 882 generator, select **Load EDID From** > **882** from the **File** menu. Select a valid file.




   The EDID is loaded into the Editor.

   b. If you are capturing and loading an EDID from a connected display device, select **Load EDID From** > **Device Connected to** > **882 Analyzer Port** *<x>* from the **File** menu. (Port 1 is HDMI Tx 1, Port 2 is HDMI TX 2, and Port 3 is VGA.)



c. If you are loading an EDID XML file stored on the host PC, select **Load EDID From > File on PC** from the **File** menu. Select a file.




The EDID is loaded into the Editor.

Editing an existing EDID


The procedure below provides instructions on editing EDIDs in the EDID Editor Tool.

To edit an existing EDID:

1. Open the EDID Editor and load an EDID using the procedures described in “Loading EDIDs with the EDID Editor” on page 620.




2. Expand the EDID Block in the navigation view.



3. Double-click on the EDID data blocks you wish to edit.

   Edit the pull-down select boxes, text fields and check boxes in accordance with the requirements of the EDID you are creating. The screen shot below shows a typical dialog box for editing the Timing Descriptor Detailed Timing Descriptor. Make sure to click on the **OK** button when you have completed the edits for each dialog box.



4. Save the modified EDID using the procedures described in “Saving an EDID to a file” on page 635.

Creating a new EDID


The procedure below provides instructions on creating a new EDID in the EDID Editor Tool. This procedure shows how you would create a new, 4-block EDID from the default Quantum Data 2-block EDID.

Note: *To create a new EDID, you will need to obtain all the information for the various fields in the EDID.*


To create a new EDID:

1. Open the EDID Editor and load the EDID using the procedures “Loading EDIDs with the EDID Editor” on page 620.

   Upon power up the HDMI Rx ports are configured with the Quantum Data 2 block EDID.




2. Expand the EDID Block in the navigation view.




3. Edit the fields in Block#1 in accordance with your requirements.


   This screen shows the Vendor/Product Information screen where you will need to make some edits. When you change the value of any field (either a free form text field, pull-down select box or check box), make sure to click the **OK** button to invoke the change. If you make a change by mistake, click on the **Cancel** button.



4. Add the CEA extension blocks by selecting **New CEA Block** from the **Add** pull down menu as shown below.



When you add a CEA block, both Block #2 and Block #3 are added. In addition, the **Extension Flag** field in Block #0 is updated with the value of 3.




5. Add a CEA extension data block.


   a. Highlight the CEA Data Block where you want to add the extension block.

   b. Select **New CEA Extension Blocks** from the **Add** pull down menu.

   The example below shows adding a CEA Video Data Block.




   When you add a CEA extension block, it is added to the selected CEA data block as shown below.



   c. Edit the fields in the data block in accordance with your requirements.

d. Click the **OK** button to save the data block that you added.




6. Add detailed timing descriptor (DTD) data.

   a. Highlight the CEA DTDs block where you want to add the DTD.

   b. Select **New DTD** from the **Add** pull down menu.

   The example below shows adding a Custom Timing Descriptor.




   When you add a DTD, it is added to the selected DTD data block as shown below.

   c. Edit the fields in the data block that in accordance with your requirements.


   d. Click the **OK** button to save the data block that you added.

7. (Optional) If you need to delete an item such as a CEA extension block or data block, select the block in the EDID Blocks window, then select **Delete Selected Item** from the **Tools** pull-down menu as shown below.



8. Complete your edits by double clicking on the EDID data blocks you wish to modify.

   Edit the pull down select boxes, text fields and check boxes in accordance with the requirements of the EDID you are creating. The screen shot below shows a typical dialog box for editing the Timing Descriptor Detailed Timing Descriptor.



9. Save the modified EDID using the procedures described in “Saving an EDID to a file” on page 635.


Saving an EDID to a file

The procedure below provide instructions on saving an EDID to an EDID XML file used by the 882 generator.

To save an EDID to a file:

1. If not already loaded in the Editor, load the EDID using the procedure “Loading EDIDs with the EDID Editor” on page 620.

2. Select **Save EDID to...** from the **File** pull down menu as shown below.



3. Select the location you want to store the file.
   a. If you are saving the EDID to the generator file system, select **882** and enter a filename. The EDID XML file is stored in flash memory.
   b. If you are saving the EDID to the host PC, select **File on PC** and enter a filename. The EDID XML file is stored on the PC.

The EDID is saved to a EDID XML file used by the 882 generator.

Putting (Writing) EDID to a display

Note: *The connected display device must have writable EEPROM to use this feature.*

Important: *This procedure will overwrite the EDID contents of your display device.*

The procedure below provide instructions on putting (writing) an EDID to a display device connected to one of the generator's HDMI Tx ports.

To put (write) an EDID to a connected display device:

1. If not already connected, connect an HDMI-to-HDMI cable between the HDMI OUT connector on the generator and the HDMI connector on the display device.
2. If not already loaded in the Editor, load the EDID using the procedure "Loading EDIDs with the EDID Editor" on page 620.

3. Select **Save EDID to...** > **Device connected to 882...** > **882 Analyzer Port** *<x>* from the **File** menu. (Port 1 is HDMI Tx 1, and Port 2 is HDMI Tx 2.)

The EDID is written to the writable EEPROM on the display device.


Emulating an EDID

The procedures below provide instructions on configuring one of the analyzer ports to emulate an EDID that you have loaded in the Editor tool. You can configure either or both HDMI Rx ports with any viable EDID .xml file that you have stored.

To emulate an EDID:

1. Load an existing EDID using the procedures described in "Loading EDIDs with the EDID Editor" on page 620.
2. Select **Use EDID on...** from the **File** pull down menu.

   The example below shows how you would configure the EDID loaded into the editor on HDMI Rx port 1.




   The EDID that was loaded into the EDID Editor tool is now configured on the HDMI Rx port you selected (882 HDMI Rx 1 port in the example above).

Running an EDID HDMI compliance test

You can run the EDID HDMI compliance test on an HDMI EDID that is loaded into the EDID Editor. When you run the test, the tool automatically generates the HTML report as well. When you run this test the CDF that is used is the one that is currently saved in the generator. The procedures below provide instructions on running the EDID HDMI compliance test from the EDID Editor.

To run an EDID HDMI compliance test:

1. Load an existing EDID using the procedures described in "Loading EDIDs with the EDID Editor" on page 620.
2. Configure the CDF in accordance with the procedures in "Testing HDMI sink device for EDID compliance" on page 593.
3. Select **Generate/View Compliance Test** from the **Tools** pull down menu as shown below.




The EDID HDMI Compliance test report appears in the window.

Running an EDID data report

You can run the EDID data report in an HDMI EDID that is loaded into the EDID Editor. This function generates an HTML report that appears in the window when compete. The procedures below provide instructions on running the EDID data report from the EDID Editor.

To run an EDID data report:

1. Load an existing EDID using the procedures described in “Loading EDIDs with the EDID Editor” on page 620.
2. Select **Generate/View Compliance Test** from the **Tools** pull down menu as shown below.



The EDID report appears in the window.

Using the EDID Compare tool

The 882 provides an EDID Compare tool. This tool allows you to capture an EDID from a connected display, then compare its contents to subsequent EDID readings. This allows you to verify the display device is consistently generating an identical EDID.

Comparing EDIDs

Follow this procedure to verify the display device is generating an identical EDID:


To compare EDIDs:

1. Connect an HDMI-to-HDMI cable between the HDMI OUT connector on the generator and the HDMI connector on the display under test.
2. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/


   The generator home page appears in the browser.



3. Click the **EDID Compare Tool** link. The EDID Compare Tool appears.




4. Click the **Capture Reference** button. The following message appears.



Note: *You can use the tool to save a copy of the EDID onto your PC by clicking on the* **Browse** *button. This enables you to browse for a location on your PC and store the EDID.*

5. Click the **Compare to Reference** button. The following message appears if EDID contents are identical.



If EDID contents are not identical, you see the message **`Mis-Matched EDID's`** displayed.

Testing EDID for DisplayPort verification in display (sink) devices

The 882E test instrument supports an EDID verifcation test in accordance with VESA Enhanced Extended Display Identification Data (E-EDID) Verification Guide.

The DisplayPort EDID Verification Test feature is an option and therefore requires that you purchase the license for it. The EDID verification test was introduced in release 2.19. The following sections are tested: Section 3-1 through 3-10.

DisplayPort EDID verification test overview

DisplayPort sink EDID verifcation testing is conducted through the generator's DisplayPort OUT connector. A standard DisplayPort-to-DisplayPort cable connects the device under test to the generator. The generator must be configured to output DisplayPort signals. You initiate the EDID verifcation test on a DisplayPort sink device through the front panel. Procedures are provided in the sections below.

The work flow for running the DsiplayPort EDID verifcation test is as follows:

- Obtain a reference EDID.
- Make the physical connection between the 882E and the DisplayPort monitor under test.
- Power up the display under test and activate the DisplayPort interface.
- Configure the 882E instrument to output DisplayPort.
- Initiate the test
- Viewing the test report

Obtaining a "Reference EDID" for the test

Prior to initating the test, you must obtain a reference EDID for the test. The reference EDID can be obtained from a spec sheet, a known good unit of the same model type or from the unit under test. If you run the EDID verifcation test with the EDID captured directly from the display device under test you are only running a basic validation check on the display's EDID. You can create the reference EDID from a spec sheet using the 882E EDID Editor tool or by entering the appropriate commands through the command line interface.

To obtain a reference EDID using the EDID Editor:

1. Enter the EDID from your product spec sheet into the EDID Editor.

   If you have a known good device that you can capture an EDID from, use the EDID Editor to capture it and load it into the 882E. Refer to “Loading EDIDs with the EDID Editor” on page 620.

2. Save the reference EDID to the Library/EDID directory in the 882E Flash memory.


Running the DisplayPort EDID Verification Test

Follow the procedure below to run the EDID DisplayPort verification test through the front panel.

To perform DisplayPort sink EDID verification test through the front panel:

1. Connect a DisplayPort-to-DisplayPort cable between the DisplayPort sink device under test and the DisplayPort OUT connector on the generator.

   The following diagram depicts the test setup for the 882E:




2. Press the **Interface** key.
3. Activate the DisplayPort interface on the output port by selecting the **DisplayPort** item with the adjacent soft key.




   Alternatively, to select the interface through the command line, enter the following commands:

```
XVSI 10        // Selects the DisplayPort interface
```

4. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.




5. Press the **Reports** key. The **Reports** menu appears on the generator's display as shown below.



6. Choose the **EDID** item by pressing the adjacent soft key.

   A list of reference EDIDs appear on the LCD as shown below.



   Note: *Be sure that you have transferred any existing EDID reports to your PC. Otherwise, generating a new report overwrites the existing report.*

7. Initiate the test with the desired reference **EDID** by pressing the adjacent soft key.

   The test will run and a report will be stored in the Library/Reports format on the memory card media.

   Note: *You can transfer the report to your host PC using the FTP browser. For instructions on this please refer to* *"Working with the Generator FTP Browser" on page 24*.

Viewing the DisplayPort EDID Verification test report

The DisplayPort EDID verification test report is an HTML report formated as a table. The table below describes the fields in the table and what they mean. There are several sections of the report:

- Manufacturer/Product Information
- Basic Display Parameters and Features
- Standard Timings
- Descriptors

- Extension Flag & Checksum

Each section has the same columns as described in the table below:

:

Test Cases Number	Section Number	Data Field Addresses	Byte/Bit Definitions	Specification Data	EDID 1.4 Stored Data in Data Field	Pass/Fail
This field is the test case number of the test in the VESA EDID verification spec.	This field is the section number of the test in the VESA EDID verifcation spec.	This field describes the address in the EDID where this data is located.	This field describes the function of the data.	The data in these fields are the data of the reference EDID that you are using for the test.	The data in these fields are the data of the EDID read from the display device that you are testing.	These are the pass or fail result indicates which is comparison of the expected data (reference EDID and the actual EDID of the device under test.

To view the DisplayPort EDID verification test report:

1. Navigate to the main web page of the 882 as shown below.



2. Click on **Generated Reports** to view the list of reports on the 882.

3. Click on the EDID Verification report you wish to view.

   The report is display in the browser window as shown below. The first page is the header section which shows the EDID blocks in hex form.



EDID Under Test

	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
00:	00	FF	FF	FF	FF	FF	FF	00	10	AC	2B	A0	53	44	38	31
10:	13	12	01	04	A5	34	20	78	22	B3	25	AC	51	30	B4	26
20:	10	50	54	A5	4B	00	81	80	A9	40	71	4F	01	01	01	01
30:	01	01	01	01	01	01	28	3C	80	A0	70	B0	23	40	30	20
40:	36	00	07	40	21	00	00	1A	00	00	00	FF	00	4A	55	34
50:	33	36	38	35	36	31	38	44	53	0A	00	00	00	FC	00	44
60:	45	4C	4C	20	32	34	30	38	57	46	50	0A	00	00	00	FD
70:	00	38	4C	1E	53	11	01	0A	20	20	20	20	20	20	00	C4

Block 0

Reference EDID

	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
00:	00	FF	FF	FF	FF	FF	FF	00	44	89	B2	00	05	00	00	00
10:	0D	0C	01	03	80	50	2D	78	0A	0D	C9	A0	57	47	98	27
20:	12	48	4C	20	00	00	01	01	01	01	01	01	01	01	01	01
30:	01	01	01	01	01	01	01	1D	80	18	71	1C	16	20	58	2C
40:	25	00	C4	8E	21	00	00	9E	8C	0A	D0	8A	20	E0	2D	10
50:	10	3E	96	00	13	8E	21	00	00	18	00	00	00	FC	00	48
60:	44	4D	49	20	54	56	0A	20	20	20	20	20	00	00	00	FD
70:	00	3B	3D	0F	2E	08	00	0A	20	20	20	20	20	20	03	06

Block 1

   The next section of the report is the Manufacture and Product Information. The following is an example.

Manufacturer/Product Information						
Test Case Number	**Section Number**	**Data Field Address(es)**	**Byte/Bit Definitions**	**Specification Data**	**EDID 1.4 Stored Data in Data Field**	**Pass/Fail**
1	3.1	**00h -> 07h** (Required)	Header =	(00 FF FF FF FF FF FF 00)h	**(00 FF FF FF FF FF FF 00)h**	PASS
2	3.2.1	**08h -> 09h** (Required)	ID Manufacturer PNPID Code:	QDI converts to (**44 89**)h	DEL converts to (**10 AC**)h	FAIL - Mismatch
3	3.2.2	**0Ah -> 0Bh** (Required)	ID Product Code: LSB: MSB:	(**B2 00**)h	(**2B A0**)h	FAIL - Mismatch
4	3.2.3	**0Ch -> 0Fh** (Optional)	ID Serial Number:	(5)d converts to (**05 00 00 00**)h	(825771091)d converts to (**53 44 38 31**)h	FAIL - Mismatch
5-1	3.2.4	**10h** (Optional)	Week of Manufacture:	(13)d converts to (**0D**)h or (FF)h	(**13**)h = Week #19	FAIL
5-2 (5-3 is omitted)	3.2.4	**11h** (Required)	Year of Manufacture:	(2002)d converts to (**0C**)h	(**12**)h = Year 2008 or (18)d	FAIL - Mismatch
6	3.3	**12h -> 13h** (Required)	EDID Structure: Version Number: Revision Number:	(**1**)d converts to (01)h (**4**)d converts to (04)h	(**01 04**)h	PASS

The next section of the report is the Basic Display Parameters and Features. The following is an example.

Manufacturer/Product Information						
Test Case Number	**Section Number**	**Data Field Address(es)**	**Byte/Bit Definitions**	**Specification Data**	**EDID 1.4 Stored Data in Data Field**	**Pass/Fail**
1	3.1	**00h -> 07h** (Required)	Header =	(00 FF FF FF FF FF FF 00)h	**(00 FF FF FF FF FF FF 00)h**	PASS
2	3.2.1	**08h -> 09h** (Required)	ID Manufacturer PNPID Code:	QDI converts to (**44 89**)h	DEL converts to (**10 AC**)h	FAIL - Mismatch
3	3.2.2	**0Ah -> 0Bh** (Required)	ID Product Code: LSB: MSB:	(**B2 00**)h	(**2B A0**)h	FAIL - Mismatch
4	3.2.3	**0Ch -> 0Fh** (Optional)	ID Serial Number:	(5)d converts to (**05 00 00 00**)h	(825771091)d converts to (**53 44 38 31**)h	FAIL - Mismatch
5-1	3.2.4	**10h** (Optional)	Week of Manufacture:	(13)d converts to (**0D**)h or (FF)h	(**13**)h = Week #19	FAIL
5-2 (5-3 is omitted)	3.2.4	**11h** (Required)	Year of Manufacture:	(2002)d converts to (**0C**)h	(**12**)h = Year 2008 or (18)d	FAIL - Mismatch
6	3.3	**12h -> 13h** (Required)	EDID Structure: Version Number: Revision Number:	(**1**)d converts to (01)h (**4**)d converts to (04)h	(**01 04**)h	PASS

The next section of the report is the Standard Timings. The following is an example.

Standard Timings

Test Case Number	Section Number	Data Field Address(es)	Byte/Bit Definitions	Specification Data	EDID 1.4 Stored Data in Data Field	Pass/Fail
13-1	3.7	**26h & 27h**	Standard Timing 1 =	Unused converts to (01 01)h	Data at addresses **26h & 27h** = (**81 80**)h converts to 1280 x 1024 @ 60 Hz	FAIL - Mismatch
13-2	3.7	**28h & 29h**	Standard Timing 2 =	Unused converts to (01 01)h	Data at addresses **28h & 29h** = (**A9 40**)h converts to 1600 x 1200 @ 60 Hz	FAIL - Mismatch
13-3	3.7	**2Ah & 2Bh**	Standard Timing 3 =	Unused converts to (01 01)h	Data at addresses **2Ah & 2Bh** = (**71 4F**)h converts to 1152 x 864 @ 75 Hz	FAIL - Mismatch
13-4	3.7	**2Ch & 2Dh**	Standard Timing 4 =	Unused converts to (01 01)h	Data at addresses **2Ch & 2Dh** = (**01 01**)h **(Unused)**	PASS
13-5	3.7	**2Eh & 2Fh**	Standard Timing 5 =	Unused converts to (01 01)h	Data at addresses **2Eh & 2Fh** = (**01 01**)h **(Unused)**	PASS
13-6	3.7	**30h & 31h**	Standard Timing 6 =	Unused converts to (01 01)h	Data at addresses **30h & 31h** = (**01 01**)h **(Unused)**	PASS
13-7	3.7	**32h & 33h**	Standard Timing 7 =	Unused converts to (01 01)h	Data at addresses **32h & 33h** = (**01 01**)h **(Unused)**	PASS
13-8	3.7	**34h & 35h**	Standard Timing 8 =	Unused converts to (01 01)h	Data at addresses **34h & 35h** = (**01 01**)h **(Unused)**	PASS

The next section of the report is the Timing Descriptors. The following is an example.

Descriptor #1

Test Case Number	Section Number	Data Field Address (es)	Byte/Bit Definitions	Specification Data	EDID 1.4 Stored Data in Data Field	Pass/Fail
14-1	3.8.1	**36h -> 47h** (Required)	Preferred & **Native** Timing Mode =	The Preferred Timing Mode is: 1920 x 1080 i @ 60.053381 Hz converts to (01 1D 80 18 71 1C 16 20 58 2C 25 00 C4 8E 21 00 00 9E)h	Data at addresses **36h -> 47h** = (**28 3C 80 A0 70 B0 23 40 30 20 36 00 07 40 21 00 00 1A**)h converts to 1920 x 1200 p @ 59.950171 Hz	FAIL - Mismatch
18-1	3.9	**36h & 37h**	Pixel Clock Frequency = (Bytes 0 & 1)	74.25 MHz converts to (**01 1D**)h (LSB first)	Data stored in Bytes 0 & 1 = (**28 3C**)h converts to 154.00 MHz	FAIL - Mismatch
18-2	3.9	**38h & 3Ah**	Horizontal Addressable Video = (Byte 2 & Byte 4{Upper Nibble})	1920 Pixels converts to 12 bits: Upper Nibble of Byte 4 = (0111)b and Byte 2 = (80)h	Data stored in: Upper Nibble of Byte 4 = (**0111**)b and Byte 2 = (**80**)h or (**10000000**)b (1920 Pixels)	PASS
18-3	3.9	**39h & 3Ah**	Horizontal Blanking = (Byte 2 & Byte 4{Lower Nibble})	280 Pixels converts to 12 bits: Lower Nibble of Byte 4 = (0000)b and Byte 3 = (18)h	Data stored in: Lower Nibble of Byte 4 = (**0000**)b and Byte 3 = (**A0**)h or (**10100000**)b (160 Pixels)	FAIL - Mismatch

The next section of the report is the Extension Flag & Checksum. The following is an example.

Extension Flag & Checksum						
Test Case Number	**Section Number**	**Data Field Address(es)**	**Byte/Bit Definitions**	**Specification Data**	**EDID 1.4 Stored Data in Data Field**	**Pass/Fail**
32-1	3.11	**7Eh** (Required)	Number of Extension Blocks:	3 converts to (**03**)h	Data stored in Address **7Eh** = (**00**)h	FAIL
			Extension Block Tag Numbers:	F0 02 02		FAIL
32-2	3.11	**7Fh** (Required)	Calculated Checksum=	(C4)h	Data stored in Address **7Fh** = (**C4**)h	PASS

18 Testing Lipsync

Topics in this chapter:

- Overview
- Testing display (sink) devices
- Testing source devices

Overview

This chapter provides procedures for testing the HDMI Auto Lipsync Correction feature. The generator can be configured to:

- emulate an HDMI source device to test an HDMI sink (display) device, or
- emulate an HDMI sink (display) device to test an HDMI source device.


With the generator, you can obtain audio and video latency values from the EDID of a connected display, generate a test image with audio/video latency correction applied, and view the image on the display device to determine correct audio/video synchronization.

With the analyzer option, you can test the lipsync correction feature of a HDMI source device. The analyzer can emulate a display device with audio and video latency. Using a test image, the source device applies audio/video latency correction and sends back the test image to the analyzer. Using a built-in application, the analyzer measures for the correct audio/video latency.

Testing display (sink) devices

The generator can emulate a source device in order to test an HDMI display device's auto lipsync correction handling. With this capability, an HDMI display device can be tested for proper audio and video synchronization using a lipsync test image.

A display's EDID provides audio and video latency fields in the HDMI vendor specific data block of the CEA extension block. Upon reading the EDID, the generator uses an embedded application to process the audio and video latency values and compensates for the difference within a generated lipsync test image. Using a blinking white box and an audible beep, the lipsync test image allows you to assess proper audio/video synchronization at the display. The illustration below depicts this application.



To test display device auto lipsync correction:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Connect the 882 HDMI output (Tx) port to the display device.

3. Activate the HDMI-H interface on the output port:

   a. Press the **Interface** key to access the list of interfaces. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose **HDMI-H** by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.




   c. Alternatively, to activate the interface through the command line interface, enter the following commands:


```
XVSI 4              // Selects the HDMI-H interface
ALLU                // Applies the interface setting to the generator
```

4. Read the EDID from the display as follows:

   a. Press the **Sink** key. The following information appears on the generator's display.



   b. Press the **Options** key. The following information appears on the generator's display.



   c. Choose the **EDID Formats** item by pressing the adjacent soft key. A + appears next to EDID Formats, indicating it is enabled.

5. Enable lipsync testing in generator as follows:

   a. Press the **Content** key. The following information appears on the generator's display.

```
Acer1           Acer2
Acer3           Acer4
Acer5           Acer6
Acer7           Acer8
```

   b. Choose either the **LipSyncB** or **LipSync** image.

   c. Press the **Settings** key. The following information appears on the generator's display.

```
          Image          ->
        LipSync          ->
  LSGM   TLAT   PLAT
  1     0.0000    0   ->
```

   d. Set the **LSGM** setting to 1 by pressing the soft keys adjacent to the bottom row until the cursor appears on the digit. Press the + or - keys to adjust the setting up or down.

   e. Press the **Enter** (**Options**) key to save the new setting.

   Alternatively, to enable the generator to measure lipsync correction through the command line interface, enter the following command:


```
LSGX:LSGM 1     // Enables lipsync testing
LSGX:LSGU       // Activates lipsync testing
```

6. Press the **Content** key. The following information appears on the generator's display.

```
Acer1           Acer2
Acer3           Acer4
Acer5           Acer6
Acer7           Acer8
```


7. Choose the image to use for lipsync testing.

- For basic testing, choose the **LipSyncB** test image on display device is similar to shown below.



The **LipSyncB** image utilizes a flashing white box with audible click to verify correct audio/video synchronization.


- For more detailed testing, choose the **LipSync** test image on display device is similar to shown below.



The **LipSync** image utilizes a moving box with audible beep to verify correct audio/video synchronization. When the moving box's right edge touches the middle of a vertical line in the image, an audible beep is sent to the display.

8. (Optional when using **LipSync** image only) To adjust vertical line spacing (thus changing frequency of audible beeps), follow these steps:

   a. Choose **More** by pressing the adjacent soft key. A **+** and **Rendition** appears next to the item.



   b. Press + and - keys to adjust vertical line interval. Changing the interval adjusts calculated moving time for white box between two lines.

   Alternatively, to adjust vertical line intercal using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

   c. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0      // Disables sub images
```

9. (Optional) To adjust lipsync testing parameters in the generated test image, follow these steps:


   a. Press the **Content** key. The following information appears on the generator's display.




   b. Choose the **LipSyncB** or **LipSync** image.

   c. Press the **Options** key to access the Options menu.

   d. Enable LipSync settings by pressing the adjacent soft key. A + appears next to the **LipSync** item indicating that you can adjust it settings.



   e. Press the **Settings** key. The following information appears on the generator's display.



   f. To select which data stream (audio or video) is generated first, edit the **PLAT** setting (0=video sent first, 1=audio sent first) by pressing the soft keys adjacent to the bottom row until the cursor appears on the digits. Press the + or - keys to adjust the settings up or down.

   g. To adjust audio/video latency, edit the **TLAT** setting between 0.0 and 0.5 seconds by pressing the soft keys adjacent to the bottom row until the cursor appears on the digits. Press the + or - keys to adjust the settings up or down.

   h. Press the **Enter** (**Options**) key to save the new setting(s).


   Alternatively, to set lipsync testing paramters in the test image through the command line interface, enter the following command:

```
LSGX:TLAT       // Sets audio/video latency
LSGX:PLAT       // Sets which data stream is generated first
                  (0-Video, 1-Audio)
LSGX:LSGU       // Updates hardware
```

Testing source devices

With the Analyzer option, the generator can emulate an HDMI sink (display) in order to test an HDMI source device's auto lipsync correction handling. With this capability, an HDMI source device can be tested for its ability to handle audio and video latency values received in the HDMI vendor specific data block of the CEA extension block of a display's EDID.

The EDID Editor application enables users to populate the audio and video latency fields in the HDMI vendor specific data block on the analyzer. These fields can be adjusted to test the source's ability to process and compensate for any permissible range of latency values. The source can then send a test image with both an audio and video component to the generator. When received, an embedded application in the generator measures the relative delay on the test image between the audio and video components of the image. The illustration below depicts this application.




Testing HDMI source device for Lipsync handling

Follow this procedure to perform auto lipsync correction testing on a connected HDMI source device.

To use analyzer to test source device auto lipsync correction handling:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Set EDID audio/video latency values on analyzer using the EDID Editor application. See "Using the EDID Editor tool" on page 620 for details on loading, editing, and

emulating an EDID on the analyzer. In the EDID Editor, the Vendor Specific Block screen with the **Video Latency** and **Audio Latency** fields is shown below:



3. Press the **Interface** key repeatedly until the following menu appears:

```
* HDMI IN 1
  HDMI IN 2
```

4. Choose the connector to which the source device is connected by pressing the adjacent soft key.
5. Connect an HDMI-to-HDMI cable between the HDMI IN connector on the analyzer and HDMI Port on the source device. The EDID is read from emulated display on the analyzer, and lipsync latency values are processed by the source device.
6. From source device, generate supplied lipsync test image.
7. On the generator, press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.

```
System          Reports
Sequence        ImgShift
Probe           Analyzer
AFC
```

8. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.

```
*Timing          PIX-ERR
 CableTest       PRN-ERR
 ViewPix         LipSync
```

9. Choose the **LipSync** item by pressing the adjacent soft key. The **LipSync** menu appears on the generator's display as shown below.

```
          LIPSYNC
!Measure             Exit!
!Report
```

Alternatively, to enable the analyzer to measure lipsync correction through the command line interface, enter the following command:

```
LSAX:LSGM 1     // Enables lipsync analyzer
LSAX:LSGU       // Activates lipsync analyzer
```

10. Choose **!Measure** to measure audio/video latencies in the test image.

If audio/video latency is exceeded, the following appears on the generator's display asshown below.

```
          LIPSYNC
!Stop                Exit!
     Latency Exceeded
```

Alternatively, to measure audio/video latencies in the test image through the command line interface, enter the following command:

```
LSAX:TLAT?       // Returns audio/video latency in milliseconds
LSAX:PLAT?       // Returns which data stream was received first
                    (0-Video, 1-Audio)
LSAX:LSGU       // Updates hardware
```

11. Press **!Stop** to halt lipsync measurements.

Generating an HDMI source Lipsync data report


Follow the procedure to generate an HTML report of lipsync measurement test results.

To generate a report of lipsync measurement test results:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with

the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.


2. Perform steps 2 - 6 of "Testing HDMI source device for Lipsync handling" on page 659 to set up analyzer for lipsync testing.
3. Press the **Tools** key. The **Tools** menu appears on the generator's display as shown below.



4. Choose the **Analyzer** item by pressing the adjacent soft key. The **Analyzer** menu appears on the generator's display as shown below.



5. Choose the **LipSync** item by pressing the adjacent soft key. The **LIPSYNC** menu appears on the generator's display as shown below.



Note: *Be sure that you have transferred any existing Lipsync reports to your PC. Otherwise, generating a new report overwrites the existing report.*


6. Choose **!Report** item by pressing the adjacent soft key. A Lipsync Measurements Report is generated and stored on the PCMCIA card in the **/card0/Library/Reports/LipSync_Data.htm** file.

   Alternatively, to generate a lipsync measurement report through the command line interface, enter the following command:


```
LSAX:RPTG 1     // generate lipsync measurement report
LSAX:LSGU       // Activates lipsync analyzer
```

7. Open the FTP Browser on the generator and select a suitable directory on your PC to store the report.
8. Using the FTP Browser, transfer the report from the generator PCMCIA card to your PC like shown below.

Note: *Make sure to change the names of any existing reports in the directory on your PC to avoid overwritting existing reports.*



9. Navigate to your PC and double click on the report. A sample is shown below.



19 Testing HDCP on HDMI and DisplayPort

Topics in this chapter:

- Overview
- Testing DVI displays with HDCP
- Testing HDMI displays with HDCP
- Running an HDMI HDCP self-test
- Understanding the HDCP test
- Running the HDCP compliance test for HDMI devices
- Running the HDCP compliance test for DisplayPort devices

Overview

You can use the generator with the High-bandwidth Digital Content Protection (HDCP) to test HDCP 1.0 and 1.1 compliant devices. The procedures in this chapter instruct you on how to complete the HDCP tests for a DVI, HDMI or DisplayPort sink devices.

The 882E and 882C are compliant HDMI-HDCP sources. For more information about HDCP, see http://www.digital-cp.com/.

Testing DVI displays with HDCP

This section describes how to test DVI and HDMI receivers with HDCP.

To set up the generator for testing a DVI display:

1. Connect an HDMI-to-DVI converter cable between the HDMI OUT connector on the generator and the device's DVI receiver.
2. Activate the HDMI-D interface on the output port as follows:

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-D** item by pressing the adjacent soft key. The interface is activated, and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3        // Activates the HDMI-D interface
ALLU          // Applies the interface setting to the generator
```

3. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL DMT0660
FMTU
```

4. Choose the **HDCPprod** test image, or, if you are using HDMI OUT port 2, choose the **HDCP2** test image.

   If you are testing a device with a production key, select the **HdcpProd** image (or, if you are using HDMI OUT port 2, choose the **HDCP2** test image). These test images assume that both the HDCP transmitter and receiver have a production key.



   The image will indicate if the test passed or failed. If the test fails, see “Understanding the HDCP test” on page 677.

5. To test another device, connect the cable to the new device.

   The HDCP test starts automatically.

   Alternatively, you can enter the following command to initiate and run the test with any image displayed. A zero is returned if the HDCP test is successful.

   ```
   HDCP? (OUT1:HDCP?, OUT2:HDCP?)
   ```

   You can also specify a number of frames to run the test for. For example to run the test for 2000 frames you would enter:

   ```
   HDCP? (OUT1:HDCP?, OUT2:HDCP?) 2000
   ```

Testing HDMI displays with HDCP

To test HDCP with an HDMI device:

1. Connect an HDMI cable between the HDMI OUT connector on the generator and the HDMI display.
2. Activate the HDMI-H interface on the output port as follows:
   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

3. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

```
FMTL DMT0660
FMTU
```

4. Choose the **HDCPprod** test image, or, if you are using HDMI OUT port 2, choose the **HDCP2** test image.

   If you are testing a device with a production key, select the **HdcpProd** image, or, if you are using HDMI OUT port 2, choose the **HDCP2** test image. These test images assume that both the HDCP transmitter and receiver have a production key.



   The image will indicate if the test passed or failed. If the test fails, see “Understanding the HDCP test” on page 677.

5. To test another device, connect the cable to the new device.

   The HDCP test starts automatically.

   Alternatively, you can enter the following command to initiate and run the test with any image displayed. A zero is returned if the HDCP test is successful.

   ```
   HDCP? (OUT1:HDCP?, OUT2:HDCP?)
   ```

   You can also specify a number of frames to run the test for. For example to run the test for 2000 frames you would enter:

   ```
   HDCP? (OUT1:HDCP?, OUT2:HDCP?) 2000
   ```

HDCP? (OUT1:HDCP?, OUT2:HDCP?) 2000



The image will indicate if the test passed or failed. If the test fails, see “Understanding the HDCP test” on page 677.

6. To test another device, connect the cable to the new device.

   The HDCP test starts automatically.

Testing DisplayPort sinks with HDCP

This section describes how to test DisplayPort sinks with HDCP.

To set up the generator for testing a DisplayPort sinks:

1. Connect a DisplayPort cable between the DisplayPort OUT connector on the generator and the device's DisplayPort input.
2. Activate the DisplayPort interface on the output port as follows:

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.

   b. Choose the **DisplayPort** item by pressing the adjacent soft key. The interface is activated, and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

   ```
   XVSI 10       // Activates the DisplayPort interface
   ALLU          // Applies the interface setting to the generator
   ```

3. Choose a standard format (for example, DMT0660) by pressing the adjacent soft key.

   Alternatively, you can load the format with the following command:

   ```
   FMTL DMT0660
   FMTU
   ```

4. Choose the **HDCPprod** test image.

   If you are testing a device with a production key, select the **HdcpProd** image. These test images assume that both the HDCP transmitter and receiver have a production key.



   The image will indicate if the test passed or failed. If the test fails, see “Understanding the HDCP test” on page 677.

5. To test another device, connect the cable to the new device.

   The HDCP test starts automatically.

   Alternatively, you can enter the following command to initiate and run the test with any image displayed. A zero is returned if the HDCP test is successful.

   ```
   HDCP? (OUT1:HDCP?, OUT2:HDCP?)
   ```

   You can also specify a number of frames to run the test for. For example to run the test for 2000 frames you would enter:

   ```
   HDCP? (OUT1:HDCP?, OUT2:HDCP?) 2000
   ```

Running HDCP test in step mode

The generator normally runs the steps in the HDCP test automatically. However, to troubleshoot a failed test, you can run the test in “step” mode. This enables you to read the values at the step where the test failed.

To run the HDCP test in step mode:

1. Connect a cable between the HDMI or DisplayPort OUT connector on the generator and the device’s input.
2. Activate the HDMI-H, HDMI-D or DisplayPort interface on the output port as follows:
   a. Press the **Interface** key. A listing of signal interfaces appears on the generator’s display as shown below.



   b. Choose either the **HDMI-H**, **HDMI-D** or **DisplayPort** item by pressing the adjacent soft key. The interface is activated, and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
                   (3 for HDMI-D or 10 for DisplayPort)
ALLU            // Applies the interface setting to the generator
```


3. Press the **Content** key and choose the **HdcpProd** image by pressing the adjacent soft key. Or, if you are using HDMI OUT port 2, choose the **HDCP2** test image.

4. Enable and view image versions for the test image as follows:

   a. Press the **Options** key. The following menu appears on the generator's display:



   b. Choose the **More** item by pressing the adjacent soft key until a + and Rendition appears next to the item.



   c. Press the + key to advance through the image versions.

   Alternatively, to enable and view image versions using the command line interface, enter the following commands:

```
ISUB 1      // Enables sub images
IVER 1      // Specifies the first image version
IMGU        // Activates the image version
```

5. When you are finished, disable image versions by pressing the **Options** key and choosing **More** until a - appears next to it.

   Alternatively, to disable image versions using the command line interface, enter the following command:

```
ISUB 0     // Disables sub images
```

Running an HDMI HDCP self-test

An HDCP self-test checks that HDCP authentication is working properly between the transmitter and receiver on the analyzer. This test can also be used to confirm that a cable is not interfering with HDCP authentication, and that the DDC clock and DDC data pins (used by the I2C bus) are working correctly.

To run an HDCP self-test:

1. Connect the HDMI cable between the HDMI IN and HDMI OUT connectors on the generator.
2. Activate the HDMI-H interface on the output port as follows:
   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose **HDMI-H** item by pressing the adjacent soft key. The interface is activated, and the port outputs the currently selected image and format.

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 3        // Selects the HDMI-H interface
ALLU          // Applies the interface setting to the generator
```

3. Enter the following command to initiate and run the test with any image displayed. A zero is returned if the HDCP test is successful.

```
HDCP? (OUT1:HDCP?, OUT2:HDCP?)
```

   You can also specify a number of frames to run the test for. For example to run the test for 2000 frames you would enter:

```
HDCP? (OUT1:HDCP?, OUT2:HDCP?) 2000
HDCP? (OUT1:HDCP?, OUT2:HDCP?) 2000
```

Understanding the HDCP test

Understanding what the generator does during an HDCP test can help you determine why an HDCP test failed.

HDMI HDCP test sequence:

The HDMI HDCP test sequence performed by the generator is listed below.

1. Reset the transmitter HDCP engine.
2. Initialize the transmitter.
3. Check Bcaps over the DDC bus to determine if the sink is a receiver or a repeater and generate a new An value (8 byte random session number) in the transmitter.
4. Transmitter writes An to the receiver using the DDC bus.
5. Transmitter writes Aksv to the receiver using the DDC bus.
6. Read Bksv from the receiver over the DDC bus and validate that it has exactly 20 zeroes and 20 ones in it. You can query this value with the following command:

   ```
   i2cr? hdl 74 0 5
   I2CR? (OUT1:I2CR?, OUT2:I2CR?, VGA:I2CR?)
   ```

   The display may return a value such as the following which is:

   ```
   07BE05CEA9
   ```

   The value in binary is 0000011110111110000001011100111010101001 which contains 20 zeros and 20 ones.
7. Write the Bksv value to the transmitter to trigger calculation of R0.
8. Wait for the R0 calculation in the transmitter to complete.
9. Wait for at least 100 milliseconds and then read the R0' value out of the receiver over the DDC bus and compare the value with the R0 calculation in the transmitter. If this step fails, then go to step 1.
10. Enable encryption and read Ri' from the receiver over the DDC bus every 128 frames and compare it to the Ri value calculated in the transmitter. As long as the Ri value matches the Ri' value from the receiver continue to check these every 128 frames.

DisplayPort HDCP test sequence:

The DisplayPort HDCP test sequence performed by the generator is listed below.

1. Reset the transmitter HDCP engine.
2. Initialize the transmitter.

3. Check Bcaps over the Aux Channel DPCD address 0x68028 to determine if the sink is a receiver or a repeater and generate a new An value (8 byte random session number) in the transmitter.
4. Transmitter writes An to the receiver over the Aux Channel to DPCD address 0x6800C.
5. Transmitter writes Aksv to the receiver over the Aux Channel to DPCD address 0x68007.
6. Read Bksv from the receiver over the Aux Channel bus from DPCD address 0x68000 and validate that it has exactly 20 zeroes and 20 ones in it. You can query this value with the following command:

   ```
   dptx:dpcd? 680000 5
   ```

   The display may return a value such as the following which is:

   ```
   07BE05CEA9
   ```

   The value in binary is 0000011110111110000001011100111010101001 which contains 20 zeros and 20 ones.
7. Write the Bksv value to the transmitter to trigger calculation of R0.
8. Wait for the R0 calculation in the transmitter to complete.
9. Wait for at least 100 milliseconds and then read the R0' value out of the receiver over the Aux Channel from DPCD address 0x68005 and compare the value with the R0 calculation in the transmitter. If this step fails, then go to step 1.
10. Enable encryption and read Bstatus over the Aux Channel at DPCD address 0x68029 to determine if a Link Verification Failure has occurred.

Running the HDCP compliance test for HDMI devices

Overview

The 882CA and 882E-Analyzer (882EA) support the running of an HDCP compliance test on HDCP-enabled HDMI sources, sinks and repeaters. The HDCP compliance test was developed while working closely with Digital Content Protection. The 882E HDCP Compliance test tool has been approved by DCP.

Note: *The HDCP compliance test is an optional feature available only with the 882 analyzer. You must purchase the license for this feature.*

The HDCP compliance test system enables developers of HDMI products to perform a fast and comprehensive HDCP compliance test. Because the 882 can emulate HDMI HDCP sources, sinks and repeaters, it can perform a complete HDCP compliance test on any HDCP capable HDMI source, sink or repeater.

The HDCP compliance test can be run entirely through the 882 front panel or through the command line. In some cases for the 882CA, some of the tests need to be completed through the command line. The HDCP commands enable you to run a specific subset of the tests in the series of tests.

Compliance Controller


In release 2.18 the Compliance Controller was introduced. The Compliance Controller is GUI application accessible from the 882E web home page that enables you to configure the Product Capabilities Parameters (PCP) for the test as well as initiate the HDCP compliance test.

The HDCP compliance test procedures in this section describe how to run the HDCP compliance test through the front panel or using the Compliance Controller. The Compliance Controller is a web application that is accessible from the 882 home page.

To launch the Compliance Controller:

1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/.


   The generator home page appears in the browser.



2. Click **Compliance Controller**.

3. Select the **HDCP** tab.

   The Compliance Controller appears as shown below:



Encryption Status Tester

Some of the HDCP compliance tests for an HDMI source, sink and repeater device require the use of the standalone hardware device called the Encryption Status Tester (EST) (below). The EST device is currently only used for the 882E model. For the 882E, the EST device is connected into the test setup for all tests beginning with the 2.17.x release of the 882E model. The EST cannot be used for the 882CA model for now.



The following table lists the HDCP compliance tests that the EST is specifically used for.

Index	Test	EST Function
1	1A_01 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Measures the position of the encryption enable pulse.
10	1B_01 (Transmitter Downstream w/Repeater)	Measures the position of the encryption enable pulse.
19	2C_04 (Receiver Upstream w/Transmitter) (w/DVI Transmitter)	Positions the encryption enable pulse in the vsync or vertical blanking at three different locations (beginning, center and end.

Index	Test	EST Function
20	3A_01 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Measures the position of the encryption enable pulse.
25	3B_01 (Repeater Downstream w/Repeater)	Measures the position of the encryption enable pulse.

List of Tests

The following table describes the HDCP compliance tests that can be performed.

Index	Test	Description
1	1A_01 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Regular Procedure: With HDMI Capable Receiver
2	1A_02 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Regular Procedure: HPD After Writing Aksv
3	1A_03 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Regular Procedure: HPD After Starting Third Part of Authentication
4	1A_04 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (First Part of Authentication) HDPC Port Access
5	1A_05 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (First Part of Authentication) Verify Bksv
6	1A_06 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (First Part of Authentication) Verify R0'
7	1A_07 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (Third Part of Authentication) Verify Ri'
8	1A_08 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: SRM. Requires SRM DVD disc.
9	1A_09 (Transmitter Downstream w/Receiver) w/DVI Receiver	Regular Procedure: With DVI Receiver
10	1B_01 (Transmitter Downstream w/Repeater)	Regular Procedure: With Repeater
11	1B_02 (Transmitter Downstream w/Repeater)	Regular Procedure: HPD After Reading R0'
12	1B_03 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Timeout of KSV List READY

Index	Test	Description
13	1B_04 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
14	1B_05 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS EXCEEDED
15	1B_06 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE EXCEEDED
16	2C_01 (Receiver Upstream w/Transmitter) (w/HDMI Capable Transmitter)	Regular Procedure: With HDMI Capable Transmitter
17	2C_02 (Receiver Upstream w/Transmitter) (w/HDMI Capable Transmitter)	Irregular Procedure: (First Part of Authentication) New Authentication
18	2C_03 (Receiver Upstream w/Transmitter) (w/HDMI Capable Transmitter)	Irregular Procedure: (Third Part of Authentication) New Authentication
19	2C_04 (Receiver Upstream w/Transmitter) (w/DVI Transmitter)	Regular Procedure: With DVI Transmitter
20	3A_01 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Regular Procedure: With HDMI Capable Receiver
21	3A_02 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) HDCP Port Access
22	3A_03 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) Verify Bksv
23	3A_04 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) Verify R0'
24	3A_05 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and DVI Receiver)	Regular Procedure: With DVI Receiver
25	3B_01 (Repeater Downstream w/Repeater)	Regular Procedure: With Repeater
26	3B_02 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Timeout of KSV List READY
27	3B_03 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'

Index	Test	Description
28	3B_04 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS_EXCEEDED
29	3B_05 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE_EXCEEDED
30	3C_I_01 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Regular Procedure: Transmitter – DUT – Receiver
31	3C_I_02 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Regular Procedure: HPD Pulse Output Caused By User Operation
32	3C_I_03 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) New Authentication
33	3C_I_04 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Second Part of Authentication) New Authentication
34	3C_I_05 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Third Part of Authentication) New Authentication
35	3C_I_06 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Second Part of Authentication) Verify Bksv
36	3C_I_07 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Second Part of Authentication) Verify R0'
37	3C_II_01 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: Transmitter – DUT – Repeater-Receiver
38	3C_II_02 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: HPD After Writing Aksv
39	3C_II_03 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: HPD After Reading R0'

Index	Test	Description
40	3C_II_04 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: HPD After Starting Third Part of Authentication
41	3C_II_05 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
42	3C_II_06 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) DEVICE_COUNT
43	3C_II_07 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) DEPTH
44	3C_II_08 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS_EXCEEDED
45	3C_II_09 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE_EXCEEDED

There are several configurations depending on what type of HDCP device you are testing. Procedures for each are provided below.

Running HDCP compliance test on HDMI transmitters

To run the 1A and 1B series HDCP compliance tests on an HDMI source (transmitter):

Note: *For the 882E, the 1A-08 test requires that you use the SRM disc for the 1A-08 test if the source device has an optical drive. Refer to "To run the 1A-08 HDCP compliance test using the SRM disc:" on page 696.*

1. For the 882E analyzer, connect the cables as follows:

   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.


   b. Connect an HDMI cable from the source device under test output to the EST HDMI port labeled, “HDMI IN.”

   c. Connect an HDMI cable from the 882 HDMI Rx 1 port to the EST HDMI port labeled “HDMI OUT.”

   d. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”


   e. Connect an HDMI cable from the 882 HDMI Tx 1 port to the HDMI input of the display device (used to monitor the video).

   The following diagram depicts the test setup for the 882EA:



2. For the 882CA, connect an HDMI cable from the source device under test output to the 882 HDMI Rx 1 port.

   The following diagram depicts the test setup for the 882CA:



3. Activate the HDMI-H interface on the output port as follows:

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.




   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the display is shown below.



   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

4. Press the **Interface** key repeatedly until the following menu appears:



5. Choose the HDMI IN 1 by pressing the adjacent soft key.

6. For the 882E when using the EST, verify that the source is sending in video using the timing measurement function of the analzyer. Refer to "To view timing information of an external HDMI/DVI source signal on a display:" on page 246 for information on running the timing test.

   Verify that the source is outputting one of the following formats:

   - 640x480p at 59.94/60Hz
   - 720x480p at 59.94/60Hz
   - 720x576p at 50Hz

   Verify that the source is outputing the RGB mode:


   If the 882 cannot detect the incoming video, enter the following command to turn on the EST:

```
QD:PROD:EST          // Turns on the EST.
```

7. (For Front Panel Operation) Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.


Note: *You can set the Product Capabilities Parameters through the Compliance Controller, see instructions in Step 9 below.*

The following is displayed on the generator's LCD.




8. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.



9. Select **EditPCP** to define the capabilities of the HDCP device under test.


   The following is displayed on the generator's LCD.



The following table describes the test parameters and their settings (gray = N/A).

Parameter	Explanation
DUT type	Specifies the type of device under test. This can be one of Sink, Source, Repeater, Repeater3AB, or Repeater3C. For this test, select Source.
Source Max KSV	Specifies the maximum number of KSVs the source can read. The valid values are 1 through 127.
Source Authentication Control	Specifies the number of times a source DUT attempts authentication before transitioning into the authentication state. The valid values are 1 or greater.
Source Out Only Repeater	Indicates whether the DUT outputs contents to a repeater to which no downstream device is connected. The values are + for yes and - for no.
Sink 1.1 Features Supported	Indicates whether the DUT supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Sink 1.1 Audio Supported	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater 1.1 Features Supported	Indicates whether supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Repeater Audio Support	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater HPD Pulse	Indicates whether the DUT has the capability to output HPD pulse by user operation. The values are + for yes and - for no.
Repeater Max KSV	Specifies the maximum number of KSVs the repeater can read. The valid values are 2 through 127.
Repeater Out OnlyRep	Indicates whether the DUT outputs content to the downstream repeater that has no downstream device connected. The values are + for yes and - for no.

Alternatively you can define the PCP parameters through the Compliance Controller. Launch the Compliance Controller using the procedures in “To launch the Compliance Controller:” on page 680. Specify the values using the check box and entry fields using the information in the following steps and then click on the **Use PCP** activation button.



10. Select **Source** device by pressing the adjacent soft key to specify that the device under test is a source.

    Alternatively, you can specify the device under test as a source using the following commands:

    ```
    CPTX:DUTT 1      // specifies the device under test as a source.
    ```

    You can query the current value of the parameter with:

    ```
    CPTX:DUTT?       // returns the device under test type.
    ```

11. (Optional) Specify the remaining parameters in the **EditPCP** menu using the table above.

    Alternatively, you can specify the parameters through the command line as follows:

    ```
    CPTX:SKSV 10     // specifies maximum number of downstream devices
                        listed in the KSV list of the device under test.
                        Valid values are 1-127.
    ```


```
CPTX:SRAC 5      // specifies number of times a source DUT attempts
                    authentication before transitioning into the
                    authenticated state. Valid values, 1 or greater.
CPTX:SOOR 1      // Indicates whether DUT (source) outputs contents
                    to repeater with no downstream devices.
                    1 = yes; 0 = no.
CPTX:SDCZ 0      // indicates whether the 882 should use a downstream
                    device count of 0 or the device count as specified
                    by the SKSV command (Source Max KSV).
                    Note 1: This parameter is only used for the
                    1B-01 test and this test should be run for both
                    settings: 0 or 1 (use setting of SKSV).
                    Note 2: For the 882CA you will have to run the
                    1B-01 test using the command line. The 882E
                    starting in release 2.17.x will run these two
                    iterations of the test automatically in batch
                    mode.
```

12. Press the **Options** key to save the capabilities definition.

    The generator LCD will display the message “Saved”.


13. Press the **Tools** key get back to the Reports menu.

    The generator LCD will display the reports menu as shown below.



14. Select **HDCP** to access the HDCP compliance test menu.

    The following is displayed on the generator’s LCD.



15. Select **!CompRpt** to initiate the HDCP compliance test.

    The message “HDCP Compliance Test” is shown and then all the tests are shown in sequence.


    Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

    Alternatively, you can run the tests using the following command:

```
CPTX:CPTR 46     // specifies that all applicable tests will be run.
```

```
CPTX:CPTU        // Initiates the execution of the test
```

Another alternative is that you can initiate the tests through the Compliance Controller. Specify the tests you want to run using the check boxes and then click on the **Run Tests** activation button.



16. For the 882CA (0nly), run the 1B-01 test through the command line for both settings of the SDCZ parameter which indicates whether the 882 should use a downstream device count of 0 or the device count specified by the SKSV parameter (Source Max KSV).

    a. Set the SDCZ parameter to indicate that the 882 should use a downstream device count of 0:

    ```
    CPTX:SDCZ 0      // indicates that the 882 should use a downstream
                        device count of 0.
    ```

    b. Run the 1B-01 test using the following command:

    ```
    CPTX:CPTR 10     // Selects specific test (e.g. 1B_01) see table below
    ```

```
CPTX:CPTU        // Initiates the execution of the test.
```

c. Set the SDCZ parameter to indicate that the 882 should use the device as specified by the SKSV parameter (Source Max KSV):

```
CPTX:SDCZ 1      // indicates that the 882 should use the device count
                    as specified by the SKSV command (Source Max KSV).
```

d. Run the 1B-01 test using the following command:


```
CPTX:CPTR 10     // Selects specific test (e.g. 1B_01).
CPTX:CPTU        // Initiates the execution of the test.
```

17. Monitor the 882E (with release 2.17.x) LCD for a set of prompts during the 1A-01, 1A-09, and 1B-01 tests.

Note: *You will not be prompted as shown below when using 882E releases prior to 2.17.x nor will you be prompted when running the test with the 882CA.*

e. When prompted with the screen shown below, examine the video on the display under test and press the appropriate button adjacent to the indication (Yes! or No!) to continue.

Note: *The prompt asks you if the video appearing on the connected display looks good. "Looks good" means that there is a picture and an absence of excessive snow.*



18. (Optional) To run a specific test with the generator as **sink** (1A tests), you can use the command line as shown below:

```
CPTX:CPTR 1      // Selects specific test (e.g. 1A_01) see table below
CPTX:CPTU        // Initiates the execution of the test.
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?       // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTR?       // Queries the selected test to run (see table)
```

19. (Optional) To run a specific test with the generator as **repeater** (1B tests), you can use the command line as shown below:

```
CPTX:CPTR 10     // Selects specific test (e.g. 1B_01) see table below
CPTX:CPTU        // Initiates the execution of the test.
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?       // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTR?       // Queries the selected test to run (see table)
```

The following table describes the tests that can be performed.

CPTX:CPTR

Index	Test	Description
1	1A_01 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Regular Procedure: With HDMI Capable Receiver
2	1A_02 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Regular Procedure: HPD After Writing Aksv
3	1A_03 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Regular Procedure: HPD After Starting Third Part of Authentication
4	1A_04 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (First Part of Authentication) HDPC Port Access
5	1A_05 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (First Part of Authentication) Verify Bksv
6	1A_06 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (First Part of Authentication) Verify R0'
7	1A_07 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: (Third Part of Authentication) Verify Ri'
8	1A_08 (Transmitter Downstream w/Receiver) w/HDMI Capable Receiver	Irregular Procedure: SRM. Requires SRM disc.
9	1A_09 (Transmitter Downstream w/Receiver) w/DVI Receiver	Regular Procedure: With DVI Receiver
10	1B_01 (Transmitter Downstream w/Repeater)	Regular Procedure: With Repeater
11	1B_02 (Transmitter Downstream w/Repeater)	Regular Procedure: HPD After Reading R0'
12	1B_03 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Timeout of KSV List READY
13	1B_04 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
14	1B_05 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS EXCEEDED
15	1B_06 (Transmitter Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE EXCEEDED

To run the 1A-08 HDCP compliance test using the SRM disc:

1. Set up the test as described in “To run the 1A and 1B series HDCP compliance tests on an HDMI source (transmitter):” on page 686 using the instructions for the 882E analyzer.

   Note: *The SRM test is only supported on the 882E analyzer. You can insert the SRM disc into the source device and run the HDCP tests in batch mode rather than through the command line.*

2. Insert the SRM disc into the optical drive.

   Note: *The SRM test does not apply for source devices that cannot play a DVD.*

3. To run 1A-08 test, use the command line as shown below:

   ```
   CPTX:DUTT 1      // Selects the device type as a source.
   CPTX:CPTR 8      // Selects specific test (e.g. 1A_08).
   CPTX:CPTU        // Initiates the execution of the test.
   ```

   Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

Running HDCP compliance tests on HDMI receivers

The receiver tests are the 2C-0x series. The test procedures differ somewhat for the 882E analyzer and the 882CA.

For the 882E the 2C-01 and 2C-04 tests are run multiple times for various settings. The 2C-01 test is required to be run in two configurations: 1) combined reads and 2) short reads. The 2C-04 test is required to be run in six (6) configurations. There are two read configurations: 1) short read and 2) combined read and there are three encryption pulse configurations: 1) in the beginning of the vertical blanking; 2) in the middle of the vertical blanking and 3) at the end of the vertical blanking.

With 882E releases prior to 2.17.x, these multiple iterations for the 2C-01 and 2C-04 test have to run through the command line. For the 2.17.x release, these multiple iterations are handled in the batch mode but you can choose to run them through the command line as well.

For the 882CA (with release 2.13.3) only the 2C-01 test is run multiple times for the two configurations: 1) combined reads and 2) short reads. These tests must be run through the command line.

Refer to “To run the 2C-01 HDCP compliance test on an HDMI sink (receiver):” on page 704 for procedures on running this test. Refer to “To run the 2C-04 HDCP compliance test on an HDMI sink (receiver):” on page 705 for procedures on running this test.

To run the 2C series HDCP compliance test on an HDMI sink (receiver):

1. For the 882E analyzer connect the cables as follows:


   a. Apply power to the Encryption Status Tester (EST) using the power adapter that is supplied with the EST.

   b. Connect an HDMI cable from the sink device under test input to the EST HDMI port labeled, “HDMI OUT.”

   c. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled “HDMI IN.”


   d. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   The following diagram depicts the test setup for the 882EA:



2. For the 882CA, connect an HDMI cable from the sink device under test input to the 882 HDMI Tx 1 port.

   The following diagram depicts the test setup for the 882CA:



3. Activate the HDMI-H interface on the output port as follows:

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.



   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the display is shown below.




   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

4. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.



   Note: *You can set the Product Capabilities Parameters through the Compliance Controller, see instructions in Step 6 below.*


5. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.



6. Select **EditPCP** to define the capabilities of the HDCP device under.


   The following is displayed on the generator's LCD.



The following table describes the test parameters and their settings (gray = N/A).

Parameter	Explanation
DUT type	The type of device under test. This can be one of Sink, Source, Repeater, Repeater3AB, or Repeater3C. For this test, select Sink.
Source Max KSV	Specifies the maximum number of KSVs the source can read. The valid values are 1 through 127.
Source Authentication Control	Specifies the number of times a source DUT attempts authentication before transitioning into the authentication state. The valid values are 1 or greater.
Source Out Only Repeater	Indicates whether the DUT outputs contents to a repeater to which no downstream device is connected. The values are + for yes and - for no.
Sink 1.1 Features Supported	Indicates whether the DUT supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Sink 1.1 Audio Supported	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater 1.1 Features Supported	Indicates whether supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Repeater Audio Support	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater HPD Pulse	Indicates whether the DUT has the capability to output HPD pulse by user operation. The values are + for yes and - for no.
Repeater Max KSV	Specifies the maximum number of KSVs the repeater can read. The valid values are 2 through 127.
Repeater Out OnlyRep	Indicates whether the DUT outputs content to the downstream repeater that has no downstream device connected. The values are + for yes and - for no.

Alternatively you can define the PCP parameters through the Compliance Controller. Launch the Compliance Controller using the procedures in “To launch the Compliance Controller:” on page 680. Specify the values using the check box and entry fields using the information in the following steps and then click on the **Use PCP** activation button.



7. Select **Sink** device by pressing the adjacent soft key to specify that the device under test is a sink.

   The following is displayed on the generator's LCD.

```
Sink            :DUT Type
0       :Source_Max_KSV
1       :Source_Authe_Cnt
+Source_Out_OnlyRep     ↓
```

   Alternatively, you can specify the device under test as a sink using the following commands:

```
CPTX:DUTT 0     // specifies the device under test as a sink.
```

   You can query the current value of the parameter with:

```
CPTX:DUTT?      // returns the device under test type.
```

8. (Optional) Specify the remaining parameters in the **EditPCP** menu using the table above.

   Alternatively, you can specify the parameters through the command line as follows:


```
CPTX:SRFT 0      // indicates whether DUT (sink) supports 1.1
                    features such as Advanced Cipher and Enhanced
                    Link Verification. 1 = yes; 0 = no.
```

9. Press the **Options** key to save the capabilities definition.

   The generator LCD will display the message “Saved”.


10. Press the **Tools** key get back to the Reports menu.

    The generator LCD will display the reports menu as shown below.



11. Select **HDCP** to access the HDCP compliance test menu.

    The following is displayed on the generator’s LCD.



12. Select **!CompRpt** to initiate the HDCP compliance test.

    The message “HDCP Compliance Test” is shown and then all the tests are shown in sequence.


    Alternatively, you can run the tests using the following command:

```
CPTX:CPTR 46     // specifies that all applicable tests will be run.
```

```
CPTX:CPTU        // Initiates the execution of the test
```

Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.


Another alternative is that you can initiate the tests through the Compliance Controller. Specify the tests you want to run using the check boxes and then click on the **Run Tests** activation button.



13. Monitor the 882E LCD (with release 2.17.x) for a set of prompts during the 2C-01 test.

Note: *You will not be prompted as shown below when using 882E releases prior to 2.17.x.*


a. When prompted shown below occurs, power cycle the device under test:



b. Press the button adjacent to the Next! indication after the device under test is back on to continue.

c. When prompted with the screen shown below, examine the video on the display under test and press the appropriate button adjacent to the indication (Yes! or No!) to continue.

Note: *The prompt asks you if the video appearing on the connected display looks good. "Looks good" means that there is a picture and an absence of excessive snow.*



14. (Optional) To run a specific test you can use the command line as shown below:

```
CPTX:CPTR 16     // Selects specific test (e.g. 2C_01) see table below
CPTX:CPTU        // Initiates the execution of the test
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?       // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTR?       // Queries the selected test to run (see table)
```

The following table describes the tests that can be performed.

CPTX:CPTR

Index	Test	Description
16	2C_01 (Receiver Upstream w/Transmitter) (w/HDMI Capable Transmitter)	Regular Procedure: With HDMI Capable Transmitter
17	2C_02 (Receiver Upstream w/Transmitter) (w/HDMI Capable Transmitter)	Irregular Procedure: (First Part of Authentication) New Authentication

CPTX:CPTR

Index	Test	Description
18	2C_03 (Receiver Upstream w/Transmitter) (w/HDMI Capable Transmitter)	Irregular Procedure: (Third Part of Authentication) New Authentication
19	2C_04 (Receiver Upstream w/Transmitter) (w/DVI Transmitter)	Regular Procedure: With DVI Transmitter

To run the 2C-01 HDCP compliance test on an HDMI sink (receiver):

For the 882E releases prior to 2.17.x and for the 882CA, the 2C-01 tests are required to be run with 2 different set ups through the command line for both read configurations: 1) short read and 2) long read.

1. For the 882E analyzer connect the cables as follows:


   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.

   b. Connect an HDMI cable from the sink device under test input to the EST HDMI port labeled, “HDMI OUT.”

   c. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”


   d. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled, “HDMI IN.”

   The following diagram depicts the test setup for the 882EA:



2. For the 882CA connect an HDMI cable from the sink device under test input to the 882 HDMI Tx 1 port.

   The following diagram depicts the test setup for the 882CA:



3. Ensure that the 882 settings used for the 2C-0x series described in “To run the 2C series HDCP compliance test on an HDMI sink (receiver):” on page 697, are maintained during this test. This includes selection of the HDMI interface, selection of the key PCP parameters such as the device type, etc.
4. To run 2C-01 tests using the short read, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:CPTU        // Initiates the execution of the test.
```

5. To run 2C-01 tests using the combined read, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:CPTU        // Initiates the execution of the test.
```

   Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

To run the 2C-04 HDCP compliance test on an HDMI sink (receiver):

For the 882E releases prior to 2.17.x, the 2C-04 tests are required to be run with 6 different set ups through the command line. There are two read configurations: 1) short read and 2) long read and there are three encryption pulse configurations: 1) in the beginning of the vertical blanking; 2) in the middle of the vertical blanking and 3) at the end of the vertical blanking.

1. For the 882E analyzer connect the cables as follows:


   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.

   b. Connect an HDMI cable from the sink device under test input to the EST HDMI port labeled, “HDMI OUT.”

   c. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   d. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled, “HDMI IN.”

   The following diagram depicts the test setup for the 882EA:



2. Ensure that the 882 settings used for the 2C-0x series described in “To run the 2C series HDCP compliance test on an HDMI sink (receiver):” on page 697, are maintained during this test. This includes selection of the HDMI interface, selection of the key PCP parameters such as the device type, etc.

3. To run 2C-04 tests using the short read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:OESS 1      // Positions pulse at beginning of vsync.
CPTX:CPTR 19     // Selects specific test (e.g. 2C_04).
CPTX:CPTU        // Initiates the execution of the test.
```

4. To run 2C-04 tests using the short read with the encryption enable pulse positioned at the center of the vsync pulse, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:OESS 3      // Positions pulse at center of vsync.
CPTX:CPTR 19     // Selects specific test (e.g. 2C_04).
CPTX:CPTU        // Initiates the execution of the test.
```

5. To run 2C-04 tests using the short read with the encryption enable pulse positioned at the end of the vsync pulse, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:OESS 2      // Positions the pulse at end of vsync.
CPTX:CPTR 19     // Selects specific test (e.g. 2C_04).
CPTX:CPTU        // Initiates the execution of the test.
```

6. To run 2C-04 tests using the combined read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:OESS 1      // Positions pulse at beginning of vsync.
CPTX:CPTR 19     // Selects specific test (e.g. 2C_04).
CPTX:CPTU        // Initiates the execution of the test.
```

7. To run 2C-04 tests using the combined read with the encryption enable pulse positioned at the center of the vsync pulse, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:OESS 3      // Positions pulse at center of vsync.
CPTX:CPTR 19     // Selects specific test (e.g. 2C_04).
CPTX:CPTU        // Initiates the execution of the test.
```

8. To run 2C-04 tests using the combined read with the encryption enable pulse positioned at the end of the vsync pulse, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:OESS 2      // Positions the pulse at end of vsync.
CPTX:CPTR 19     // Selects specific test (e.g. 2C_04).
CPTX:CPTU        // Initiates the execution of the test.
```


Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

Running HDCP compliance tests on HDMI repeaters

To run the 3A series HDCP compliance tests on an HDMI repeater:

1. For the 882E analyzer connect the cables as follows:
   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.
   b. Connect an HDMI cable from the repeater device under test output to the EST HDMI port labeled, “HDMI IN.”
   c. Connect an HDMI cable from a compliant source device output to the input of the repeater device under test.
   d. Connect an HDMI cable from the 882 HDMI Rx 1 port to the EST HDMI port labeled “HDMI OUT.”
   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”
   f. Connect an HDMI cable from the 882 HDMI Tx 1 port to the HDMI input of the display device (used to monitor the video).

   The following diagram depicts the test setup for the 882EA:




2. For the 882CA connect the cables as follows:

   a. Connect an HDMI cable from the repeater device under test output to the 882 HDMI Rx 1 port.

   b. Connect an HDMI cable from a compliant source device such as a DVD player (shown) to the input of the repeater device under test.

   The following diagram depicts the test setup for the 882CA:



3. Activate the HDMI-H interface on the output port as follows:

   c. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                    CVBS
  HDMI-D               S-VIDEO
  HDMI-H                  SDI
```

   d. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the display is shown below.

```
  VGA                    CVBS
  HDMI-D              S-VIDEO
 *HDMI-H                  SDI
```

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

4. Press the **Interface** key repeatedly until the following menu appears:

```
* HDMI IN 1
  HDMI IN 2
```

5. Choose the HDMI IN 1 by pressing the adjacent soft key.

6. Verify that the repeater is sending in video using the Timing measurement function of the analzyer. Refer to "To view timing information of an external HDMI/DVI source signal on a display:" on page 246 for information on running the timing test.

   Verify that the source is outputting one of the following formats:

   - 640x480p at 59.94/60Hz
   - 720x480p at 59.94/60Hz
   - 720x576p at 50Hz

   Verify that the source is outputing the RGB mode:

   If the 882 cannot detect the incoming video, enter the following command to turn on the EST:

   ```
   QD:PROD:EST          // Turns on the EST
   ```

7. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.

   ```
   EDID              Packets
   Misc                 HDCP
   ```

   Note: *You can set the Product Capabilities Parameters through the Compliance Controller, see instructions in Step 9 below.*

8. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.

   ```
   !CompRpt          EditPCP↖
   ```

9. Select **EditPCP** to define the capabilities of the HDCP device under.


   The following is displayed on the generator's LCD.

   ```
   Source           :DUT Type
   0       :Source_Max_KSV
   1       :Source_Authe_Cnt
   +Source_Out_OnlyRep     ↓
   ```

The following table describes the test parameters and their settings (gray = N/A).

Parameter	Explanation
DUT type	The type of device under test. This can be one of Sink, Source, Repeater, Repeater3AB, or Repeater3C. For this test, select Repeater3AB.
Source Max KSV	Specifies the maximum number of KSVs the source can read. The valid values are 1 through 127.
Source Authentication Control	Specifies the number of times a source DUT attempts authentication before transitioning into the authentication state. The valid values are 1 or greater.
Source Out Only Repeater	Indicates whether the DUT outputs contents to a repeater to which no downstream device is connected. The values are + for yes and - for no.
Sink 1.1 Features Supported	Indicates whether the DUT supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Sink 1.1 Audio Supported	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater 1.1 Features Supported	Indicates whether supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Repeater Audio Support	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater HPD Pulse	Indicates whether the DUT has the capability to output HPD pulse by user operation. The values are + for yes, repeater DUT allows the user to initiate a HPD; and - for no, the repeater DUT does not support a user to manually force of a hot plug pulse.
Repeater Max KSV	Specifies the maximum number of KSVs the repeater can read. The valid values are 2 through 127.
Repeater Out OnlyRep	Indicates whether the DUT outputs content to the downstream repeater that has no downstream device connected. The values are + for yes, the repeater will forward encrypted video to a downstream repeater when there are no other downstream devices; and - for no, the repeater will not forward encrypted video to a downstream repeater when there are no other downstream devices.

Alternatively you can define the PCP parameters through the Compliance Controller. Launch the Compliance Controller using the procedures in “To launch the Compliance Controller:” on page 680. Specify the values using the check box and entry fields using the information in the following steps and then click on the **Use PCP** activation button.



10. Select **Repeater3AB** device by pressing the adjacent soft key to specify that the device under test is a repeater.

    The following is displayed on the generator's LCD.

```
Repeater3AB     :DUT Type
0       :Source_Max_KSV
1       :Source_Authe_Cnt
+Source_Out_OnlyRep     ↓
```

    Alternatively, you can specify the device under test as a repeater for the 3A test using the following commands:

```
CPTX:DUTT 3       // specifies the device under test as a repeater
                     for test 3AB.
```

    You can query the current value of the parameter with:

```
CPTX:DUTT?        // returns the device under test type.
```

11. (Optional) Specify the remaining parameters in the **EditPCP** menu using the table above.

    Alternatively, you can specify the parameters through the command line as follows:

```
CPTX:RPFT 0      // indicates whether DUT (repeater) supports 1.1
                    features such as Advanced Cipher and Enhanced
                    Link Verification. 1 = yes; 0 = no.
CPTX:RKSV 10     // specifies maximum number of downstream devices
                    that can be supported in the repeater's KSV list
CPTX:ROOR 0      // indicates whether DUT (repeater) outputs outputs
                    content to the downstream repeater that does not
                    have any downstream device connected.
                    1 = yes; 0 = no.
```

12. Press the **Options** key to save the capabilities definition.


    The generator LCD will display the message “Saved”.

13. Press the **Tools** key get back to the Reports menu.

    The generator LCD will display the message “Saved”.

14. Select **HDCP** to access the HDCP compliance test menu.

    The following is displayed on the generator's LCD.



15. Select **!CompRpt** to initiate the HDCP compliance test.

    The message “HDCP Compliance Test” is shown and then all the tests are shown in sequence.


    Alternatively, you can run the tests using the following command:

```
CPTX:CPTR 46     // specifies that all applicable tests will be run.
```

```
CPTX:CPTU        // Initiates the execution of the test
```

Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.


Another alternative is that you can initiate the tests through the Compliance Controller. Specify the tests you want to run using the check boxes and then click on the **Run Tests** activation button.



16. Monitor the 882E LCD (with release 2.17.x) for a set of prompts during the 3A-01 and 3A-05 tests.

Note: *You will not be prompted as shown below when using releases prior to 2.17.x.*


a. When prompted shown below occurs, power cycle the device under test:



b. Press the button adjacent to the Next! indication after the device under test is back on to continue.

c. When prompted with the screen shown below, examine the video on the display under test and press the appropriate button adjacent to the indication (Yes! or No!) to continue.

Note: *The prompt asks you if the video appearing on the connected display looks good. "Looks good" means that there is a picture and an absence of excessive snow.*



17. (Optional) To run a specific test you can use the command line as shown below:

```
CPTX:CPTR 20      // Selects specific test (e.g. 3A_01) see table below
CPTX:CPTU         // Initiates the execution of the test
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?        // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTU?        // Queries the selected test to run (see table)
```

The following table describes the tests that can be performed.

CPTX:CPTR

Index	Test	Description
20	3A_01 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Regular Procedure: With HDMI Capable Receiver
21	3A_02 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) HDCP Port Access
22	3A_03 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) Verify Bksv

CPTX:CPTR

Index	Test	Description
23	3A_04 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) Verify RO'
24	3A_05 (Repeater Downstream w/Receiver) (Between HDMI Capable Transmitter and DVI Receiver)	Regular Procedure: With DVI Receiver

To run the 3B series HDCP compliance tests on an HDMI repeater:

For the 882E releases prior to 2.17.x, the 3B-01 test is run multiple times for the two read configurations: 1) short read and 2) combined read. For the 2.17.x release, these multiple iterations are handled in the batch mode but you can choose to run them through the command line as well.

Refer to "To run the 3B-01 HDCP compliance test on an HDMI repeater:" on page 725 for procedures on running this test.

1. For the 882E analyzer connect the cables as follows:

   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.

   b. Connect an HDMI cable from the repeater device under test output to the EST HDMI port labeled, “HDMI IN.”


   c. Connect an HDMI cable from a compliant source device output to the input of the repeater device under test.

   d. Connect an HDMI cable from the 882 HDMI Rx 1 port to the EST HDMI port labeled “HDMI OUT.”

   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   f. Connect an HDMI cable from the 882 HDMI Tx 1 port to the HDMI input of the display device (used to monitor the video).

   The following diagram depicts the test setup for the 882EA:




2. For the 882CA connect the cables as follows:

   a. Connect an HDMI cable from the repeater device under test output to the 882 HDMI Rx 1 port."

   b. Connect an HDMI cable from a compliant source device such as a DVD player (shown) to the input of the repeater device under test.

   The following diagram depicts the test setup for the 882CA:



3. Activate the HDMI-H interface on the output port as follows:

   a. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                    CVBS
  HDMI-D               S-VIDEO
  HDMI-H                  SDI
```

   b. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the display is shown below.

```
  VGA                    CVBS
  HDMI-D              S-VIDEO
 *HDMI-H                  SDI
```

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

4. Press the **Interface** key repeatedly until the following menu appears:

```
* HDMI IN 1
  HDMI IN 2
```

5. Choose the HDMI IN 1 by pressing the adjacent soft key.

6. Verify that the repeater is sending in video using the Timing measurement function of the analzyer. Refer to "To view timing information of an external HDMI/DVI source signal on a display:" on page 246 for information on running the timing test.

   Verify that the source is outputting one of the following formats:

   - 640x480p at 59.94/60Hz
   - 720x480p at 59.94/60Hz
   - 720x576p at 50Hz

   Verify that the source is outputing the RGB mode:

   If the 882 cannot detect the incoming video, enter the following command to turn on the EST:

   ```
   QD:PROD:EST          // Turns on the EST
   ```

7. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.

   ```
   EDID              Packets
   Misc                 HDCP
   ```

   Note: *You can set the Product Capabilities Parameters through the Compliance Controller, see instructions in Step 9 below.*

8. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.

   ```
   !CompRpt          EditPCP↖
   ```

9. Select **EditPCP** to define the capabilities of the HDCP device under.


   The following is displayed on the generator's LCD.

   ```
   Source           :DUT Type
   0       :Source_Max_KSV
   1       :Source_Authe_Cnt
   +Source_Out_OnlyRep     ↓
   ```

The following table describes the test parameters and their settings (gray = N/A).

Parameter	Explanation
DUT type	The type of device under test. This can be one of Sink, Source, Repeater, Repeater3AB, or Repeater3C. For this test, select Repeater3AB.
Source Max KSV	Specifies the maximum number of KSVs the source can read. The valid values are 1 through 127.
Source Authentication Control	Specifies the number of times a source DUT attempts authentication before transitioning into the authentication state. The valid values are 1 or greater.
Source Out Only Repeater	Indicates whether the DUT outputs contents to a repeater to which no downstream device is connected. The values are + for yes and - for no.
Sink 1.1 Features Supported	Indicates whether the DUT supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Sink 1.1 Audio Supported	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater 1.1 Features Supported	Indicates whether supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Repeater Audio Support	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater HPD Pulse	Indicates whether the DUT has the capability to output HPD pulse by user operation. The values are + for yes, repeater DUT allows the user to initiate a HPD; and - for no, the repeater DUT does not support a user to manually force of a hot plug pulse.
Repeater Max KSV	Specifies the maximum number of KSVs the repeater can read. The valid values are 2 through 127.
Repeater Out OnlyRep	Indicates whether the DUT outputs content to the downstream repeater that has no downstream device connected. The values are + for yes, the repeater will forward encrypted video to a downstream repeater when there are no other downstream devices; and - for no, the repeater will not forward encrypted video to a downstream repeater when there are no other downstream devices.

Alternatively you can define the PCP parameters through the Compliance Controller. Launch the Compliance Controller using the procedures in “To launch the Compliance Controller:” on page 680. Specify the values using the check box and entry fields using the information in the following steps and then click on the **Use PCP** activation button.



10. Select **Repeater3AB** device by pressing the adjacent soft key to specify that the device under test is a repeater.

    The following is displayed on the generator's LCD.

```
Repeater3AB    :DUT Type
0      :Source_Max_KSV
1      :Source_Authe_Cnt
+Source_Out_OnlyRep    ↓
```

    Alternatively, you can specify the device under test as a repeater for the 3B test using the following commands:

```
CPTX:DUTT 3      // specifies the device under test as a repeater
                    for test 3AB.
```

    You can query the current value of the parameter with:

```
CPTX:DUTT?       // returns the device under test type.
```

11. (Optional) Specify the remaining parameters in the **EditPCP** menu using the table above.

    Alternatively, you can specify the parameters through the command line as follows:


```
CPTX:RPFT 0      // indicates whether DUT (repeater) supports 1.1
                    features such as Advanced Cipher and Enhanced
                    Link Verification. 1 = yes; 0 = no.
CPTX:RKSV 10     // specifies maximum number of downstream devices
                    that can be supported in the repeater's KSV list
CPTX:ROOR 0      // indicates whether DUT (repeater) outputs outputs
                    content to the downstream repeater that does not
                    have any downstream device connected.
                    1 = yes; 0 = no.
CPTX:SRCZ 0      // indicates whether the 880 should use a downstream
                    device count of 0 or the device count as specified
                    by the SKSV command.
                    Note that this parameter is only used for the
                    3B-01 test and this test should be run for both
                    settings: 0 or 1 (use setting of SKSV).
```

12. Press the **Options** key to save the capabilities definition.

    The generator LCD will display the message “Saved”.


13. Press the **Tools** key get back to the Reports menu.

    The generator LCD will display the reports menu as shown below.



14. Select **HDCP** to access the HDCP compliance test menu.

    The following is displayed on the generator’s LCD.



15. Select **!CompRpt** to initiate the HDCP compliance test.

    The message “HDCP Compliance Test” is shown and then all the tests are shown in sequence.


    Alternatively, you can run the tests using the following command:

```
CPTX:CPTR 46     // specifies that all applicable tests will be run.
```

```
CPTX:CPTU        // Initiates the execution of the test
```

Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.


Another alternative is that you can initiate the tests through the Compliance Controller. Specify the tests you want to run using the check boxes and then click on the **Run Tests** activation button.



Monitor the 882E LCD (with release 2.17.x) for a set of prompts during the 3B-01 test.

Note: *You will not be prompted as shown below when using releases prior to 2.17.x.*


a. When prompted shown below occurs, power cycle the device under test:



b. Press the button adjacent to the Next! indication after the device under test is back on to continue.

c. When prompted with the screen shown below, examine the video on the display under test and press the appropriate button adjacent to the indication (Yes! or No!) to continue.

Note: *The prompt asks you if the video appearing on the connected display looks good. "Looks good" means that there is a picture and an absence of excessive snow.*



16. (Optional) To run a specific test you can use the command line as shown below:

```
CPTX:CPTR 25     // Selects specific test (e.g. 3B_01) see table below
CPTX:CPTU        // Initiates the execution of the test
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?       // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTR?       // Queries the selected test to run (see table)
```

The following table describes the tests that can be performed.

CPTX:CPTR


Index	Test	Description
25	3B_01 (Repeater Downstream w/Repeater)	Regular Procedure: With Repeater
26	3B_02 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Timeout of KSV List READY
27	3B_03 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
28	3B_04 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS_EXCEEDED
29	3B_05 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE_EXCEEDED

To run the 3B-01 HDCP compliance test on an HDMI repeater:

For the 882E releases prior to 2.17.x and for the 882CA, the 3B-01 tests are required to be run with 2 different set ups through the command line for both read configurations: 1) short read and 2) long read.

1. For the 882E analyzer connect the cables as follows:
   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.
   b. Connect an HDMI cable from the repeater device under test output to the EST HDMI port labeled, “HDMI IN.”
   c. Connect an HDMI cable from a compliant source device output to the input of the repeater device under test.
   d. Connect an HDMI cable from the 882 HDMI Rx 1 port to the EST HDMI port labeled “HDMI OUT.”
   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”
   f. Connect an HDMI cable from the 882 HDMI Tx 1 port to the HDMI input of the display device (used to monitor the video).

   The following diagram depicts the test setup for the 882EA:



2. Ensure that the 882 settings used for the 3B-0x series described in “To run the 3B series HDCP compliance tests on an HDMI repeater:” on page 716, are maintained during this test. This includes selection of the HDMI interface, selection of the key PCP parameters such as the device type, etc.
3. To run 3B-01 tests using the short read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:CPTU        // Initiates the execution of the test.
```

4. To run 3B-01 tests using the combined read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:CPTU        // Initiates the execution of the test.
```

Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.


To run the 3C-I series HDCP compliance tests on an HDMI repeater:

For the 882E releases prior to 2.17.x, the 3C-I-01 test is run for each of the two read configurations: 1) short read and 2) combined read. For the 2.17.x release, these multiple iterations are handled in the batch mode but you can choose to run them through the command line as well.

Refer to “To run the 3C-I-01 HDCP compliance test on an HDMI repeater:” on page 733 for procedures on running the 3C-I-01 test in both configurations.

1. For the 882E analyzer connect the cables as follows:
   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.
   b. Connect an HDMI cable from the repeater device under test input to the EST HDMI port labeled, “HDMI OUT.”
   c. Connect an HDMI cable from the 882 HDMI Rx 1 port to the HDMI output of the repeater device under test.
   d. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled “HDMI IN.”
   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   The following diagram depicts the test setup for the 882EA:




2. For the 882CA connect the cables as follows:

   a. Connect an HDMI cable from the repeater device under test output to the 882 HDMI Rx 1 port."

   b. Connect an HDMI cable from the 882 HDMI Tx 1 port to the HDMI input of the repeater device under test.

   The following diagram depicts the test setup for the 882CA:



3. Activate the HDMI-H interface on the output port as follows:

   c. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                    CVBS
  HDMI-D               S-VIDEO
  HDMI-H                   SDI
```

   d. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the display is shown below.

```
  VGA                    CVBS
  HDMI-D              S-VIDEO
 *HDMI-H                  SDI
```

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

4. Press the **Interface** key repeatedly until the following menu appears:

```
* HDMI IN 1
  HDMI IN 2
```

5. Choose the HDMI IN 1 by pressing the adjacent soft key.
6. For the 882E when using the EST, verify that the source is sending in video using the timing measurement function of the analzyer. Refer to "To view timing information of an external HDMI/DVI source signal on a display:" on page 246 for information on running the timing test.

   Verify that the source is outputting one of the following formats:

   - 640x480p at 59.94/60Hz
   - 720x480p at 59.94/60Hz
   - 720x576p at 50Hz

   Verify that the source is outputing the RGB mode:

   If the 882 cannot detect the incoming video, enter the following command to turn on the EST:

   ```
   QD:PROD:EST          // Turns on the EST.
   ```

7. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.

   ```
   EDID              Packets
   Misc                 HDCP
   ```

   Note: *You can set the Product Capabilities Parameters through the Compliance Controller, see instructions in Step 9 below.*

8. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.

   ```
   !CompRpt          EditPCP↖
   ```

9. Select **EditPCP** to define the capabilities of the HDCP device under.


   The following is displayed on the generator's LCD.

   ```
   Source           :DUT Type
   0       :Source_Max_KSV
   1       :Source_Authe_Cnt
   +Source_Out_OnlyRep     ↓
   ```

The following table describes the test parameters and their settings (gray = N/A).

Parameter	Explanation
DUT type	The type of device under test. This can be one of Sink, Source, Repeater, Repeater3AB, or Repeater3C. For this test, select Repeater3C.
Source Max KSV	Specifies the maximum number of KSVs the source can read. The valid values are 1 through 127.
Source Authentication Control	Specifies the number of times a source DUT attempts authentication before transitioning into the authentication state. The valid values are 1 or greater.
Source Out Only Repeater	Indicates whether the DUT outputs contents to a repeater to which no downstream device is connected. The values are + for yes and - for no.
Sink 1.1 Features Supported	Indicates whether the DUT supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Sink 1.1 Audio Supported	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater 1.1 Features Supported	Indicates whether supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Repeater Audio Support	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater HPD Pulse	Indicates whether the DUT has the capability to output HPD pulse by user operation. The values are + for yes, repeater DUT allows the user to initiate a HPD; and - for no, the repeater DUT does not support a user to manually force of a hot plug pulse.
Repeater Max KSV	Specifies the maximum number of KSVs the repeater can read. The valid values are 2 through 127.
Repeater Out OnlyRep	Indicates whether the DUT outputs content to the downstream repeater that has no downstream device connected. The values are + for yes, the repeater will forward encrypted video to a downstream repeater when there are no other downstream devices; and - for no, the repeater will not forward encrypted video to a downstream repeater when there are no other downstream devices.

Alternatively you can define the PCP parameters through the Compliance Controller. Launch the Compliance Controller using the procedures in “To launch the Compliance Controller:” on page 680. Specify the values using the check box and entry fields using the information in the following steps and then click on the **Use PCP** activation button.



Select **Repeater3C** device by pressing the adjacent soft key to specify that the device under test is a repeater.

The following is displayed on the generator's LCD.

```
Repeater3C      :DUT Type
0       :Source_Max_KSV
1       :Source_Authe_Cnt
+Source_Out_OnlyRep     ↓
```

Alternatively, you can specify the device under test as a repeater for the 3C test using the following commands:

```
CPTX:DUTT 4     // specifies the device under test as a repeater
                   for the 3C test.
```

You can query the current value of the parameter with:

```
CPTX:DUTT?      // returns the device under test type.
```

1. (Optional) Specify the remaining parameters in the **EditPCP** menu using the table above.

   Alternatively, you can specify the parameters through the command line as follows:


```
CPTX:RPFT 0      // indicates whether DUT (repeater) supports 1.1
                    features such as Advanced Cipher and Enhanced
                    Link Verification. 1 = yes; 0 = no.
CPTX:RKSV 10     // specifies maximum number of downstream devices
                    that can be supported in the repeater's KSV list
CPTX:ROOR 0      // indicates whether DUT (repeater) outputs outputs
                    content to the downstream repeater that does not
                    have any downstream device connected.
                    1 = yes; 0 = no.
```

2. Press the **Options** key to save the capabilities definition.

   The generator LCD will display the message "Saved".


3. Press the **Tools** key get back to the Reports menu.

   The generator LCD will display the reports menu as shown below.



4. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.



5. Select **!CompRpt** to initiate the HDCP compliance test.

   The message "HDCP Compliance Test" is shown and then all the tests are shown in sequence.


   Alternatively, you can run the tests using the following command:

```
CPTX:CPTR 46     // specifies that all applicable tests will be run.
```

```
CPTX:CPTU        // Initiates the execution of the test
```

Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

Another alternative is that you can initiate the tests through the Compliance Controller. Specify the tests you want to run using the check boxes and then click on the **Run Tests** activation button.



(Optional) To run a specific test you can use the command line as shown below:

```
CPTX:CPTR 30     // Selects specific test (e.g. 3C1_01) see
                    table below
CPTX:CPTU        // Initiates the execution of the test
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?       // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTR?       // Queries the selected test to run (see table)
```

The following table describes the tests that can be performed.

CPTX:CPTR

Index	Test	Description
30	3C_I_01 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Regular Procedure: Transmitter – DUT – Receiver
31	3C_I_02 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Regular Procedure: HPD Pulse Output Caused By User Operation
32	3C_I_03 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (First Part of Authentication) New Authentication
33	3C_I_04 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Second Part of Authentication) New Authentication
34	3C_I_05 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Third Part of Authentication) New Authentication
35	3C_I_06 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Second Part of Authentication) Verify Bksv
36	3C_I_07 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and HDMI Capable Receiver)	Irregular Procedure: (Second Part of Authentication) Verify R0'

To run the 3C-I-01 HDCP compliance test on an HDMI repeater:

For the 882E releases prior to 2.17.x, the 3C-I-01 tests are required to be run with 2 different set ups through the command line for both read configurations: 1) short read and 2) long read.

1. For the 882E analyzer connect the cables as follows:

   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.


   b. Connect an HDMI cable from the repeater device under test input to the EST HDMI port labeled, “HDMI OUT.”

   c. Connect an HDMI cable from the 882 HDMI Rx 1 port to the HDMI output of the repeater device under test.

   d. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled “HDMI IN.”

   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   The following diagram depicts the test setup for the 882EA:



2. Ensure that the 882 settings used for the 3C-I-0x series described in “To run the 3C-II series HDCP compliance tests on an HDMI repeater:” on page 735, are maintained during this test. This includes selection of the HDMI interface, selection of the key PCP parameters such as the device type, etc.

3. To run 3C-I-01 tests using the short read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:CPTU        // Initiates the execution of the test.
```

4. To run 3C-I-01 tests using the combined read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:CPTU        // Initiates the execution of the test.
```

   Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.


To run the 3C-II series HDCP compliance tests on an HDMI repeater:

For the 882E releases prior to 2.17.x, the 3C-II-01 test is run for each of the two read configurations: 1) short read and 2) combined read. For the 2.17.x release, these multiple iterations are handled in the batch mode but you can choose to run them through the command line as well.

Refer to “To run the 3C-II-01 HDCP compliance test on an HDMI repeater:” on page 742 for procedures on running the 3C-II-01 test in both configurations.

1. For the 882E analyzer connect the cables as follows:
   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.
   b. Connect an HDMI cable from the repeater device under test input to the EST HDMI port labeled, “HDMI OUT.”
   c. Connect an HDMI cable from the 882 HDMI Rx 1 port to the HDMI output of the repeater device under test.
   d. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled “HDMI IN.”
   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   The following diagram depicts the test setup for the 882EA:




2. For the 882CA connect the cables as follows:

   a. Connect an HDMI cable from the repeater device under test output to the 882 HDMI Rx 1 port."

   b. Connect an HDMI cable from the 882 HDMI Tx 1 port to the HDMI input of the repeater device.

   The following diagram depicts the test setup for the 882CA:



3. Activate the HDMI-H interface on the output port as follows:

   c. Press the **Interface** key. A listing of signal interfaces appears on the generator's display as shown below.

```
* VGA                    CVBS
  HDMI-D               S-VIDEO
  HDMI-H                   SDI
```

   d. Choose the **HDMI-H** item by pressing the adjacent soft key. The interface is activated and the display is shown below.

```
  VGA                    CVBS
  HDMI-D              S-VIDEO
 *HDMI-H                  SDI
```

   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 4          // Activates the HDMI-H interface
ALLU            // Applies the interface setting to the generator
```

4. Press the **Interface** key repeatedly until the following menu appears:

```
* HDMI IN 1
  HDMI IN 2
```

5. Choose the HDMI IN 1 by pressing the adjacent soft key.
6. For the 882E when using the EST, verify that the source is sending in video using the timing measurement function of the analzyer. Refer to "To view timing information of an external HDMI/DVI source signal on a display:" on page 246 for information on running the timing test.

   Verify that the source is outputting one of the following formats:

   - 640x480p at 59.94/60Hz
   - 720x480p at 59.94/60Hz
   - 720x576p at 50Hz

   Verify that the source is outputing the RGB mode:

   If the 882 cannot detect the incoming video, enter the following command to turn on the EST:

   ```
   QD:PROD:EST          // Turns on the EST.
   ```

7. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.

   ```
   EDID              Packets
   Misc                 HDCP
   ```

   Note: *You can set the Product Capabilities Parameters through the Compliance Controller, see instructions in Step 9 below.*

8. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.

   ```
   !CompRpt          EditPCP↖
   ```

9. Select **EditPCP** to define the capabilities of the HDCP device under.


   The following is displayed on the generator's LCD.

   ```
   Source           :DUT Type
   0       :Source_Max_KSV
   1       :Source_Authe_Cnt
   +Source_Out_OnlyRep     ↓
   ```

The following table describes the test parameters and their settings (gray = N/A).

Parameter	Explanation
DUT type	The type of device under test. This can be one of Sink, Source, Repeater, Repeater3AB, or Repeater3C. For this test, select Repeater3C.
Source Max KSV	Specifies the maximum number of KSVs the source can read. The valid values are 1 through 127.
Source Authentication Control	Specifies the number of times a source DUT attempts authentication before transitioning into the authentication state. The valid values are 1 or greater.
Source Out Only Repeater	Indicates whether the DUT outputs contents to a repeater to which no downstream device is connected. The values are + for yes and - for no.
Sink 1.1 Features Supported	Indicates whether the DUT supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Sink 1.1 Audio Supported	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater 1.1 Features Supported	Indicates whether supports Advanced_Cipher mode and Enhanced Link Verification. The values are + for yes and - for no.
Repeater Audio Support	Indicates whether the DUT supports audio output. The values are + for yes and - for no.
Repeater HPD Pulse	Indicates whether the DUT has the capability to output HPD pulse by user operation. The values are + for yes, repeater DUT allows the user to initiate a HPD; and - for no, the repeater DUT does not support a user to manually force of a hot plug pulse.
Repeater Max KSV	Specifies the maximum number of KSVs the repeater can read. The valid values are 2 through 127.
Repeater Out OnlyRep	Indicates whether the DUT outputs content to the downstream repeater that has no downstream device connected. The values are + for yes, the repeater will forward encrypted video to a downstream repeater when there are no other downstream devices; and - for no, the repeater will not forward encrypted video to a downstream repeater when there are no other downstream devices.

Alternatively you can define the PCP parameters through the Compliance Controller. Launch the Compliance Controller using the procedures in “To launch the Compliance Controller:” on page 680. Specify the values using the check box and entry fields using the information in the following steps and then click on the **Use PCP** activation button.



Select **Repeater3C** device by pressing the adjacent soft key to specify that the device under test is a repeater.

The following is displayed on the generator's LCD.

```
Repeater3C      :DUT Type
0       :Source_Max_KSV
1       :Source_Authe_Cnt
+Source_Out_OnlyRep     ↓
```

Alternatively, you can specify the device under test as a repeater using the following commands:

```
CPTX:DUTT 4     // specifies the device under test as a repeater.
```

You can query the current value of the parameter with:

```
CPTX:DUTT?      // returns the device under test type.
```

1. (Optional) Specify the remaining parameters in the **EditPCP** menu using the table above.

   Alternatively, you can specify the parameters through the command line as follows:


```
CPTX:RPFT 0      // indicates whether DUT (repeater) supports 1.1
                    features such as Advanced Cipher and Enhanced
                    Link Verification. 1 = yes; 0 = no.
CPTX:RKSV 10     // specifies maximum number of downstream devices
                    that can be supported in the repeater's KSV list
CPTX:ROOR 0      // indicates whether DUT (repeater) outputs outputs
                    content to the downstream repeater that does not
                    have any downstream device connected.
                    1 = yes; 0 = no.
```

2. Press the **Options** key to save the capabilities definition.

   The generator LCD will display the message "Saved".


3. Press the **Tools** key get back to the Reports menu.

   The generator LCD will display the reports menu as shown below.



4. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.



5. Select **!CompRpt** to initiate the HDCP compliance test.

   The message "HDCP Compliance Test" is shown and then all the tests are shown in sequence.


   Alternatively, you can run the tests using the following command:

```
CPTX:CPTR 46     // specifies that all applicable tests will be run.
```

```
CPTX:CPTU        // Initiates the execution of the test
```

Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

Another alternative is that you can initiate the tests through the Compliance Controller. Specify the tests you want to run using the check boxes and then click on the **Run Tests** activation button.



(Optional) To run a specific test you can use the command line as shown below:

```
CPTX:CPTR 37     // Selects specific test (e.g. 3C2_01) see table
                    below
CPTX:CPTU        // Initiates the execution of the test
```

You can query the complete list of tests to choose from:

```
CPTX:GCTN?       // Queries the list of tests supported
```

You can query the currently selected test to run with:

```
CPTX:CPTR?       // Queries the selected test to run (see table)
```

The following table describes the tests that can be performed.

CPTX:CPTR

Index	Test	Description
37	3C_II_01 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: Transmitter – DUT – Repeater-Receiver
38	3C_II_02 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: HPD After Writing Aksv
39	3C_II_03 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: HPD After Reading R0'
40	3C_II_04 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Regular Procedure: HPD After Starting Third Part of Authentication
41	3C_II_05 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
42	3C_II_06 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) DEVICE_COUNT
43	3C_II_07 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) DEPTH
44	3C_II_08 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS_EXCEEDED
45	3C_II_09 (Repeater Upstream w/Transmitter) (Between HDMI Capable Transmitter and Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE_EXCEEDED

To run the 3C-II-01 HDCP compliance test on an HDMI repeater:

For the 882E releases prior to 2.17.x, the 3C-II-01 tests are required to be run with 2 different set ups through the command line for both read configurations: 1) short read and 2) long read.

1. For the 882E analyzer connect the cables as follows:

   a. Apply power to the Encryption Status Tester (EST) using the power adapter supplied with the EST.


   b. Connect an HDMI cable from the repeater device under test input to the EST HDMI port labeled, “HDMI OUT.”

   c. Connect an HDMI cable from the 882 HDMI Rx 1 port to the HDMI output of the repeater device under test.

   d. Connect an HDMI cable from the 882 HDMI Tx 1 port to the EST HDMI port labeled “HDMI IN.”

   e. Connect an HDMI cable from the 882 HDMI Tx 2 port to the EST HDMI port labeled “HDMI.”

   The following diagram depicts the test setup for the 882EA:



2. Ensure that the 882 settings used for the 3C-II-0x series described in “To run the 3C-II series HDCP compliance tests on an HDMI repeater:” on page 735, are maintained during this test. This includes selection of the HDMI interface, selection of the key PCP parameters such as the device type, etc.

3. To run 3C-II-01 tests using the short read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 0      // Specifies short read.
CPTX:CPTU        // Initiates the execution of the test.
```

4. To run 3C-II-01 tests using the combined read with the encryption enable pulse positioned at the beginning of the vsync pulse, enter the following commands:

```
CPTX:CRIP 1      // Specifies combined read.
CPTX:CPTU        // Initiates the execution of the test.
```

   Refer to “To view the HDCP compliance report:” on page 744 for procedures on how to view the generated report.

To view the HDCP compliance report:


1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.




Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*

2. Choose the **Generated Reports** item. The Generator the provides a list of reports currently available as shown below.



3. Select the HDCP compliance test report from the list. The report then appears in the browser window as shown below. You can then save the report as a web page file for distribution. The following is an example of a report for the HDCP compliance test for a display.



Generator Information

Model =	882CA
Unit Revision =	A
Unit SN =	6050019
Date =	05042006
Firmware =	20.1883502

Unit Under Test Information (PCP Selections)

Unit Under Test Type =	Display
Source_Max_KSV =	0
Source_Authe_Count =	1
Source_Out_OnlyRep =	YES
Sink_1.1Features_Supported =	NO
Sink_Audio_Supported =	YES
Repeater_1.1Features_Supported =	YES
Repeater_Audio_Supported =	YES
Repeater_HPD_Pulse =	YES
Repeater_Max_KSV =	2
Repeater_Out_OnlyRep =	YES

Repeater TESTS Summary (Test 3C1-3C11)

```
Test 3C-1-01: Regular Procedure Transmitter-DUT-Receiver.
Test 3C-1-02: Regular procedure:HPD pulse output caused by user operation
Test 3C-1-03: Irregular procedure.(First part of authentication) New authentication.
Test 3C-1-04: Irregular procedure:(Second part of authentication) New Authentication.
Test 3C-1-05: Irregular Procedure (Third part of authentication) New Authentication.
Test 3C-1-06: Irregular procedure:(Second part of authentication) Verify Bksv
Test 3C-1-07: Irregular procedure:(Second part of authentication) Verify R0'.
Test 3C-11-01: Regular procedure:Transmittter-DUT-Repeater+Receiver.
Test 3C-11-02: Regular procedure:HPD after writing Aksv.
```

The following is an example of a report for the HDCP compliance test for a source (player).



Generator Information

Model =	882CA
Unit Revision =	A
Unit SN =	6050019
Date =	05042006
Firmware =	20.1883502
Unit Under Test Type =	Player

PCP Selections


Source_Max_KSV =	0
Source_Authe_Count =	0
Source_Out_OnlyRep =	NO
Sink_1.1Features_Supported =	NO
Sink_Audio_Supported =	NO
Repeater_1.1Features_Supported =	NO
Repeater_Audio_Supported =	NO
Repeater_HPD_Pulse =	NO
Repeater_Max_KSV =	0
Repeater_Out_OnlyRep =	NO

SOURCE TESTS

est 1A-01

- Starting Test 1A-01
- Timestamp:150.49644 secs., Ri' read (both bytes).
- Timestamp: 2.12720 secs., Hot plug detect timer expired.
- Timestamp: 3.41866 secs., Bstatus read.
- Timestamp: 3.42071 secs., Bcaps read.
- Timestamp: 3.42234 secs., Warning. Video Signal is not HDMI mode and is running an I

The following is an example of a report for the HDCP compliance test for a repeater.



HDCP Compliance Report

quantumdata

enerator Information

Model =	882CA
Unit Revision =	A
Unit SN =	6050019
Date =	05042006
Firmware =	20.1883610

NIT UNDER TEST INFORMATION (PCP SELECTIONS)

Unit Under Test Type =	Repeater
Repeater 1.1 Features Supported =	NO
Repeater Audio Supported =	YES
Repeater HPD Pulse =	YES
Repeater Max KSV =	2
Repeater Out OnlyRep =	YES

epeater TESTS Summary (Test 3C1-3C11)

-1-01: Regular Procedure Transmitter-DUT-Receiver.
-1-02: Regular procedure:HPD pulse output caused by user operation
-1-03: Irregular procedure.(First part of authentication) New authentication.
-1-04: Irregular procedure:(Second part of authentication) New Authentication.
-1-05: Irregular Procedure (Third part of authentication) New Authentication.
-1-06: Irregular procedure:(Second part of authentication) Verify Bksv
-1-07: Irregular procedure:(Second part of authentication) Verify R0'.
-11-01: Regular procedure:Transmittter-DUT-Repeater+Receiver.
-11-02: Regular procedure:HPD after writing Aksv.
_11_03: Regular procedure: HPD after reading R0'
-11-04: Regular procedure: HPD after starting third part of authentication.
-11-05: Irregular procedure:(Second part of authentication)Verify V'.
Test 3C-11-06: Irregular procedure:(second part of authentication) Device count
-11-07: Irregular procedure:(second part of authentication) Depth.
Test 3C-11-08: Irregular procedure:(second part of authentication) MAX_DEVS_EXC

Running the HDCP compliance test for DisplayPort devices

The 882E supports the running of an HDCP compliance test on HDCP-enabled DisplayPort sinks. The HDCP compliance test was developed while working closely with Digital Content Protection.

Note: *The HDCP compliance test is an optional feature. You must purchase the optional license for this feature.*

The HDCP compliance test system enables developers of DisplayPort products to perform a fast and comprehensive HDCP compliance test. Because the 882E can emulate DisplayPort HDCP sources it can perform an HDCP compliance tests on any sink.

The HDCP compliance test can be run entirely through the 882E front panel or through the command line. The HDCP commands enable you to run a specific subset of the tests in the series of tests.

The following table describes the tests that can be performed (gray = not yet supported).

Index	Test	Description
1	1A_01 (Transmitter w/Receiver)	Regular Procedure: With Receiver
2	1A_02 (Transmitter w/Receiver)	Regular Procedure: HPD After Writing Aksv
3	1A_03 (Transmitter w/Receiver)	Regular Procedure: HPD During Link Integrity Check Stage
4	1A_04 (Transmitter w/Receiver)	Irregular Procedure: (First Part of Authentication) Failure to Read Bcaps HDCP_CAPABLE Bit
5	1A_05 (Transmitter w/Receiver)	Irregular Procedure: (First Part of Authentication) Verify Bksv
6	1A_06 (Transmitter w/Receiver)	Irregular Procedure: (First Part of Authentication) Verify R0'
7	1A_07 (Transmitter w/Receiver)	Irregular Procedure: (Link Integrity Check) Link Integrity Failure
8	1A_08 (Transmitter w/Receiver)	Irregular Procedure: SRM
9	1A_09 (Transmitter w/Receiver)	Regular Procedure: Encryption Disable Bootstrapping
10	1B_01 (Transmitter w/Repeater)	Regular Procedure: With Repeater
11	1B_02 (Transmitter w/Repeater)	Irregular Procedure: Spurious CP_IRQ Interrupt
12	1B_03 (Transmitter w/Repeater)	Regular Procedure: HPD After Reading R0'
13	1B_04 (Transmitter w/Repeater)	Irregular Procedure: (Second Part of Authentication) Timeout of KSV List READY
14	1B_05 (Transmitter w/Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'

Index	Test	Description
15	1B_06 (Transmitter w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS EXCEEDED
16	1B_07 (Transmitter w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE EXCEEDED
17	2A_01 (Receiver w/Transmitter)	Regular Procedure: With Transmitter
18	2A_02 (Receiver w/Transmitter)	Irregular Procedure: (First Part of Authentication) New Authentication
19	2A_03 (Receiver w/Transmitter)	Irregular Procedure: (Link Integrity Check) New Authentication
20	2A_04 (Receiver w/Transmitter)	Regular Procedure: Encryption Disable Bootstrapping
21	3A_01 (Repeater Downstream w/Receiver)	Regular Procedure: With Receiver
22	3A_02 (Repeater Downstream w/Receiver)	Irregular Procedure: (First Part of Authentication) Failure to Read Bcaps HDCP_CAPABLE Bit
23	3A_03 (Repeater Downstream w/Receiver)	Irregular Procedure: (First Part of Authentication) Verify Bksv
24	3A_04 (Repeater Downstream w/Receiver)	Irregular Procedure: (First Part of Authentication) Verify R0'
25	3B_01 (Repeater Downstream w/Repeater)	Regular Procedure: With Repeater
26	3B_02 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Timeout of KSV List READY
27	3B_03 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
28	3B_04 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS_EXCEEDED
29	3B_05 (Repeater Downstream w/Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE_EXCEEDED
30	3C_01 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Receiver)	Regular Procedure: Transmitter – DUT – Receiver
31	3C_02 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Receiver)	Regular Procedure: HPD Propagation when an Active Receiver is Disconnected and Reconnected Downstream
32	3C_03 (Repeater Upstream w/Transmitter) (Reconnected Downstream)	Regular Procedure: HPD Propagation when an Active Receiver is Disconnected Downstream
33	3C_04 (Repeater Upstream w/Transmitter) (Downstream)	Regular Procedure: HPD Propagation when an Active Receiver is Connected


Index	Test	Description
34	3C_05 (Repeater Upstream w/Transmitter) (Downstream)	Irregular Procedure: (First Part of Authentication) New Authentication
35	3C_06 (Repeater Upstream w/Transmitter) (Downstream)	Irregular Procedure: (Second Part of Authentication) New Authentication
36	3C_07 (Repeater Upstream w/Transmitter) (Downstream)	Irregular Procedure: (Link Integrity Check) New Authentication
37	3C_08 (Repeater Upstream w/Transmitter) (Downstream)	Irregular Procedure: (Second Part of Authentication) Verify Bksv
38	3C_09 (Repeater Upstream w/Transmitter) (Downstream)	Irregular Procedure: (Second Part of Authentication) Verify R0'
39	3C_10 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Regular Procedure: Transmitter – DUT – Repeater
40	3C_11 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Regular Procedure: HPD After Writing Aksv
41	3C_12 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Regular Procedure: HPD After Reading R0'
42	3C_13 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Regular Procedure: HPD After Starting Third Part of Authentication
43	3C_14 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Irregular Procedure: (Second Part of Authentication) Verify V'
44	3C_15 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Irregular Procedure: (Second Part of Authentication) DEVICE_COUNT
45	3C_16 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Irregular Procedure: (Second Part of Authentication) DEPTH
47	3C_17 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_DEVS_EXCEEDED
48	3C_18 (Repeater Upstream w/Transmitter) (Repeater (DUT) Connected to Transmitter (TE) and Repeater)	Irregular Procedure: (Second Part of Authentication) MAX_CASCADE_EXCEEDED

There are several configurations depending on what type of HDCP device you are testing. Procedures for each are provided below.

To run the 2C series HDCP compliance tests on DisplayPort sinks (receivers):

1. Connect a cable between the DisplayPort Out connector on the generator and the sink device's DisplayPort receiver interface with the HDCP function.

   The following diagram depicts the test setup:



2. Activate the DisplayPort interface by pressing the **Interface** key and choosing the DisplayPort interface as shown below.




   Alternatively, to activate the interface through the command line interface, enter the following commands:

```
XVSI 10         // Activates the DisplayPort interface
ALLU            // Applies the interface setting to the generator
```


3. Press the **Tools** key and choose the **Reports** item by pressing the adjacent soft key.

   The following is displayed on the generator's LCD.




4. Select **HDCP** to access the HDCP compliance test menu.

   The following is displayed on the generator's LCD.



5. Select **EditPCP** to define the capabilities of the HDCP device under.

   Note: *For the sink device tests there are no parameter settings required. You will only need to set the device type to sink.*




The following table describes the test parameters and their settings.

Parameter	Explanation
Device Under Test type	The type of device under test. For this test, select Sink (Receiver).

6. Select **Sink** device by pressing the adjacent soft key to specify that the device under test is a sink.

   The following is displayed on the generator's LCD.



   Alternatively, you can specify the device under test as a sink using the following commands:

```
CPTX:DUTT 0     // specifies device under test as a sink (receiver)
```

7. Specify the remaining parameters in the **EditPCP** menu using the table above.
8. Press the **Enter/Options** key to save the capabilities definition.

   The generator LCD will display the message "Saved".


9. Press the **Tools** key get back to the Reports menu.

   The generator LCD will display the reports menu as shown below.



10. Select **HDCP** to access the HDCP compliance test menu.

    The following is displayed on the generator's LCD.



11. Select **!CompRpt** to initiate the HDCP compliance test.

    The message “HDCP Compliance Test” is shown and then all the tests are shown in sequence.

    Alternatively, you can run the tests using the following command:

    ```
    CPTX:CPTR 48     // specifies that all applicable tests will be run.
    DPRX:CPTU        // Initiates the execution of the test
    ```

    Refer to “To view the DisplayPort HDCP compliance report:” on page 755 for procedures on how to view the generated report.

12. (Optional) To run a specific test you can use the command line as shown below:

    ```
    CPTX:CPTR 17     // Selects specific test (e.g. 2A_01) see table below
    CPTX:CPTU        // Initiates the execution of the test
    ```

    You can query the complete list of tests to choose from:

    ```
    CPTX:GCTN?       // Queries the list of tests supported
    ```

    You can query the list of completed reports with:

    ```
    CPTX:CPTR?       // Queries the list of tests run (see table)
    ```

The following table describes the applicable tests that can be performed.

DPRX: HDCP Index	Test	Description
17	2A_01 (Receiver w/Transmitter)	Regular Procedure: With Transmitter
18	2A_02 (Receiver w/Transmitter)	Irregular Procedure: (First Part of Authentication) New Authentication
19	2A_03 (Receiver w/Transmitter)	Irregular Procedure: (Link Integrity Check) New Authentication
20	2A_04 (Receiver w/Transmitter)	Regular Procedure: Encryption Disable Bootstrapping

To view the DisplayPort HDCP compliance report:

1. Open a Web browser (such as Internet Explorer) and type the generator's IP address in the address entry field. For example, enter the following: http://206.135.215.189/

   The generator home page appears in the browser.




Note: *You can add the page to your list of favorite pages in your Web browser to avoid retyping the IP address each time you want to access the page.*

2. Choose the **Generated Reports** item. The Generator the provides a list of reports currently available as shown below.



Select the HDCP compliance test report from the list. The report then appears in the browser window as shown below. You can then save the report as a web page file for distribution. The following is an example of a report for the HDCP compliance test for a display.



HOME

quantumdata

HDCP Compliance Report

GENERATOR INFORMATION

Model =	882E
Unit Revision =	A
Unit SN =	07120003
Generator Build Date =	12042007
Firmware =	20.1885501

UNIT UNDER TEST INFORMATION (PCP SELECTIONS)

Unit Under Test Type =	Sink
DUT DPCD Revision =	1.1
DUT Maximum Lane Count =	4
DUT Maximum Link Rate =	2.70 Gbps
Enhanced Frame Capable =	Y
Current Lane Count =	4

SINK TEST SUMMARY

- PASS **Test 2A-01: Regular Procedure: With Transmitter**:Verify the Receiver's implementation of the HDCP Transmitter is connected to it.
- PASS **Test 2A-02: Irregular Procedure: (First Part of Authentication) New Authentication**:Verify th authenticates when a new An and Aksv are written by the Transmitter immediately after write of the first Ar part of authentication.
- PASS **Test 2A-03: Irregular Procedure: (Link Integrity Check) New Authentication**:Verify that the Re a new An and Aksv are written by the Transmitter during the link integrity check stage
- PASS **Test 2A-04: Regular Procedure: Encryption Disable Bootstrapping**:Verify that the Receiver corre disable bootstrapping.

20 Using Special Sync Output

Topics in this chapter:

- Overview
- Operating special sync for probe pulse
- Configuring special sync for FS, LS, or CS

Overview

The generator is equipped with a Special Sync BNC connector on the rear of the generator labeled SPECIAL. You can configure the output of this video interface to output frame sync, line sync, composite sync or a special probe pulse.

The probe feature is used with a programmable probe pulse that is available on the Special Sync BNC connector. This pulse is most often used to trigger an oscilloscope or synchronize an inspection camera. The probe feature allows you to position the leading edge of the probe pulse anywhere within the video frame. This feature greatly facilitates troubleshooting by enabling you to focus on specific video signal problems occurring anywhere in the video signal.

Operating special sync for probe pulse

Configuring the probe feature involves positioning the probe pulse in the desired location on the video frame. You can do this using either the generator front panel or the command line interface. The front panel is most convenient if you are near the generator and not using a computer or terminal. Alternatively, you can control the generator through the command line interface either locally or remotely through the serial connection or through a Telnet session.

Probe coordinate numbering

Unlike ITU and SMPTE standards, the Quantum Data standard counts pixels, lines, and coordinates beginning with the number zero (not one) to improve the mapping between video signal specifications and modern computer graphics coordinates. The television standards are accounted for by suppressing any half-active line that appears in an equalizing interval and lengthening (to a full line) any half-active line that begins in the active portion of a field. Vertical counting always begins with the leading edge of blanking of the first field (not vertical sync). The first field is always defined as the field that includes the top line of the displayed picture (Y:0). This definition is always true whether the total number of active lines is odd or even.


With interlaced scanning, lines continue to be numbered sequentially throughout the frame, beginning with the leading edge of blanking of the first field. Therefore, the first two lines of blanking in the first field are numbered L:0 followed by L:1. If you have 525 total lines and 486 of those are active, for example, the first two (blank) lines of the second field would be numbered L:262 and L:263. The Y position continues to follow the visual order of lines going from the top to the bottom of the screen. If the last line of blanking in the first field is L:18, then L:19 corresponds to Y:0, L:20 to Y:2, L:21 to Y:4 and so on. In the second field, L:282 would correspond to Y:1, L:283 to Y:3, L:284 to Y:5 and so on.

Configuring the probe feature

This section describes how to configure the probe feature. Configuring the probe feature entails enabling the probe, configuring the sensitivity for traveling through the frame, and identifying the line(s) on which the probe is present.

To configure the probe feature:

1. Press the **Tools** key. The following menu appears on the generator's display:



2. Choose the **Probe** item by pressing the adjacent soft key. The current probe settings appear on the generator's display as shown below:

```
Left      P:0000    Exp
Right     X:0000      1
Up        L:0000     10
Down      Y:0000    100
```

3. Press the **Settings** key to access the setting for the probe pulse width. The following appears on the generator's display:

```
      Probe Tool
     Probe Width
   PSPW
<-   136
```

4. Set the probe width as follows

   a. Position the blinking cursor on the digit you want to change. To do this, press the soft key adjacent to the arrow by the width value to move the cursor left or right until it appears on the digit you want to change.

   b. Adjust the value of the digit up or down by pressing the + or - keys. Repeat for each you want to change.

5. To save the changes, press the **Enter** (**Options**) key. The following choices appear on the generator's display:

```
     Apply Settings?

                      Back
Yes                     No
```

   To save the changes, choose the **Yes** item by pressing the adjacent soft key.

   To exit without saving the changes, choose the **No** item.

   To return to the previous screen without saving the changes, choose the **Back** item.

6. Press the **Options** key. The options for setting the line or lines on which the probe pulse will occur appears on the generator's display:

```
*OneLine            Exit
 AllActive
 AllLines
                  Visible-
```


7. Press the soft key adjacent to the desired option, as follows:

   - OneLine: Probe pulse occurs once per frame.
   - AllActive: Probe pulse occurs on every active line in the frame.
   - AllLines: Probe pulse occurs on every line in the frame.


8. Enable or disable the visibility setting by pressing the soft key adjacent to the Visible item on the display. A + indicates visibility is enabled; a - indicates it is disabled. Enabling the visibility setting will allow you to see the pulse position on a monitor.

To position the probe pulse in a specific location in the video signal:

1. Press the **Tools** key. The following menu appears on the generator's display:



2. Choose the **Pulse** item by pressing the adjacent soft key. The current probe settings appear on the generator's display as shown below:



3. Select the travel sensitivity of the positioning keys by pressing the soft key adjacent to the desired setting. Refer to the table below.

Setting	Sensitivity
EXP	exponential increase/decrease when +/- keys are pressed
1	increase/decrease by 1 line or pixel when +/- keys are pressed
10	increase/decrease by 10 lines or pixels when +/- keys are pressed
100	increase/decrease by 100 lines or pixels when +/- keys are pressed

4. Set the horizontal position of the probe pulse by pressing the soft key adjacent to the Left or Right item on the generator's display.

   The horizontal position of the probe is simultaneously displayed in two different ways:

   - The horizontal position P:*nnnn* is given in pixels relative to the leading edge of the horizontal sync.
   - If the leading edge of the probe is within the active portion of a line, an alternate horizontal position X:*nnnn* is also displayed, indicating the number of pixels between the start of active video (X:0) and the leading edge of the probe pulse in the horizontal direction.

5. Set the vertical position of the probe pulse by pressing the soft key adjacent to the Up or Down item on the generator's display.

   The vertical position of the probe is simultaneously displayed in two different ways:

   - The vertical position *L:nnnn* is given in whole scan lines relative to the leading edge of blanking of the frame or first field.

- If the probe is within the active portion of the frame, an alternate vertical position *Y:nnnn* is also displayed, indicating the number of lines between the start of active (Y:0) and the leading edge of the probe in the vertical direction.

Controlling the probe using the command line interface

Using the command line interface to control the probe provides more control, enables you to change the polarity and width, and to change the format and image while maintaining the probe pulse parameters.

To configure the probe feature:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See "Establishing a terminal session with the generator" on page 31 or "Establishing a Telnet session with the generator" on page 34.
2. Enable the probe feature by entering the following commands:

```
FSPG 0   // disable the frame sync on special sync output
PSPG 1   // enable the probe pulse
PSPP 1   // set the probe pulse polarity (0 for low or 1 for high)
PSPW 10  // set pulse width to 10 pixels (range: 1 pixel to HTOT - 1)
PSHD 100 // set pulse horizontal position at 100 pixels from leading
         // edge of horiztonal sync pulse, in range from 0 <=
         // PSHD < (HTOT - PSPW - 1)
PSVW 50  // set the pulse vertical position at 50 lines from leading
         // edge of vertical blanking, in range from 0 <=
         // PSVD < (VTOT-1)
ALLU     // apply the settings
```

To set the lines on which the probe pulse occurs:

1. Enter the appropriate command:

Set the probe pulse to occur	Command
Once per frame	`PSPM 0`
Once every active line	`PSPM 1`
Once every line	`PSPM 3`

2. Send the `ALLU` command to apply the setting.


Configuring special sync for FS, LS, or CS

The special sync output can provide frame sync, line sync, or composite sync signals. The output is controlled by setting parameters of these signals using the command line interface. The following commands are used to set the special sync signal:

- FSPG - Frame sync
- PSPG - Probe signal
- LSPG - Line sync
- CSPG - Composite sync

Note: *The special sync output is disabled whenever these parameters are set to zero.*

A frame pulse can be generated and output at the beginning of each frame. In the case of interlaced video, the frame pulse is output at the beginning of the blanking interval (of the first field) that immediately precedes the top line of active video.



To configure frame sync on the special sync output:

1. Establish a session with the generator using either HyperTerminal over a serial connection or Telnet over an Ethernet LAN. See “Establishing a terminal session with the generator” on page 31 or “Establishing a Telnet session with the generator” on page 34.
2. Enable the frame sync by entering the following command:

   ```
   FSPG 1
   ```

   The values of the other parameters (LS? and CSPG) do not matter once FSPG is enabled.

3. Set the frame pulse polarity (either 0 for low or 1 for high) by entering the following command:

```
FSPP 1
```

4. Set the frame pulse pixel width by entering the following command:

```
FSPW 100    // range: 1 pixel to HTOT - 1
```

5. Set the frame pulse delay by entering the following command:

```
FSPD 10     // range: 0 <= FSPD < (VTOT - FSPW - 1); default = 0
```

6. Save these settings by entering the following command:

```
ALLU
```

To configure line sync on the special sync output:

1. Enable the line sync signal by entering the following commands:

```
FSPG 0
PSPG 0
LSPG 1
ALLU
```

   The value of composite sync (CSPG) does not matter once these are set.

2. Set the line sync pulse polarity by entering the following command:

```
LSPP 1     // 1 = high (default)
ALLU
```

To configure composite sync on the special sync output:

1. Enable digital composite sync by entering the following command:

```
SSST 2    //(or 6,11)
```

2. Enable the composite sync signal by entering the following commands:

```
FSPG 0
PSPG 0
LSPG 0
CSPG 1
ALLU
```

3. Set the composite sync pulse polarity by entering the following commands:

```
CSPP 1     // 1 = high (default)
ALLU
```

21 Script SDK

Topics in this chapter:

- Overview
- Creating executable program scripts
- ScriptSDK API functions by category
- ScriptSDK API functions by name
- ScriptSDK commands
- Sample ScriptSDK programs

Overview

The Quantum Data Software Development Kit (SDK) provides Application Programming Interfaces (APIs) for two categories of automation: 1) custom images (Image SDK) and 2) executable scripts (ScriptSDK). Both of these SDKs use the C++ programming language.

The Script SDK API provides a programming interface for executing any set of commands in the 880 series command language. Additional functions allow for program control, user input/output, and debugging. ScriptSDK is a much more powerful alternative to the test sequence feature in the 881/882 generators. By providing full access to the 880 series command language, ScriptSDK allows for a broad range of control and functionality in executable scripts that reside within the generator. The executable program scripts can be executed via the ScriptSDK selection in the 882's TOOLS menu.

The entire ScriptSDK system includes components that reside on the personal computer (PC) and components that reside in the Quantum Data 881/882 generator. The PC components include:

- C++ compiler
- Libraries
- Header files
- Examples
- Templates
- Graphical User Interface

These are automatically downloaded from the Quantum Data website and installed on the PC the first time the Quantum Data SDK is run. The graphical user interface (GUI) program includes the text editor and menus to compile programs and load the executable object files into the generator. The GUI is a Java application that is loaded from the 881/882 generator each time the Quantum Data SDK is run.

The other components of this system lie within the embedded firmware in the Quantum Data 881/882 generator. This includes the Scriptrunner functionality for running the executable program scripts, as well as the proper linkages to allow the custom images to load.

Installation

The Quantum Data SDK can be accessed from the generator's home page beginning with firmware version 2.18.0. It is implemented as a Java application, and the Java Runtime Environment (JRE) is required on the host computer. JRE version 5 is recommended.

The SDK is launched from the Quantum Data SDK list item on the generator's home page. If the SDK is not yet installed, the user will be prompted through the installation process which includes connecting to the Quantum Data website. Therefore, an internet connection is required. If the older command-line version of the Image SDK is already installed on the system, it will be replaced by the Quantum Data SDK. The installation program can save the original SDK on the computer.

For first-time installation, an internet connection is required so that the automatic installation process can retrieve the installation package from the Quantum Data website. If the host computer does not yet have JRE, it can be downloaded from the java.com website, or via a link near the bottom of the generator's home page.

Image programs versus script programs

When the Quantum Data SDK is launched, the user has a choice of Image SDK or ScriptSDK, depending on the type of application to be developed. When the SDK is running, the user can freely switch between Image SDK and Script SDK at any time.

The Image SDK is used to create resolution-independent test patterns and other display images. When an image is loaded from the SDK into the generator via the Load & Execute menu selection, it is displayed immediately. An image load consists of a file transfer and the commands IMGP, IMGL, and IMGU. After loading the image via the SDK, the image is then available to be selected for display via browse mode.

The ScriptSDK is used to create executable programs that can be stored in the generator and run from the SDK menu. A ScriptSDK program can contain any commands in the 880 command language, as well as user menus, responses to key presses, numeric input, and output to the serial port.

Creating executable program scripts

This sections provides information and procedures for using the ScriptSDK application.

Getting Started

The following are the important points to keep in mind when creating executable scripts:

- Naming files
- Return values on exit
- Enabling output
- Softkey functions

These are described in the following subsections.

Naming the file and the executable script

The executable script will have the same base name as the source file. This name must be lower-case, and it should be 8 characters or less in length. This name must be appended to "Script_" to name the function.

For example, for an executable script called "demo" the source file will be demo.cpp. The main function will be Script_demo(), and the resulting object file will be demo.o. The "load & execute" command will send this object file to the generator, and it will be visible in the Scripts menu as "demo."

Returning “true” on exit

The script's main function (e.g., Script_demo()) must return "true" on exit. As in any C or C++ program, it is okay to have multiple return points. Refer to the sample programs for examples.

Enabling output to a serial terminal

By executing the CIOY command sc.Exec("CIOY"); you can enable output to the serial terminal for debugging and/or status output via printf(). You can connect a simple serial terminal (such as Hyperterm running on a PC). Serial port settings default to 9600 baud, 8 bits, no parity, 1 stop bit, no handshake. The required DB-9 null cable is included with all 880 series generators.

Writing to a log file

In some applications you may wish to write data out to a text file for later examination. For example you may want to create a script that measures the timing parameters of an incoming HDMI signal and write them out to a file. Starting in Release 2.19 you can do this. You will need to include three extern declarations at the top of the script:

```
extern int fopen();
extern int fclose();
extern int fprintf();
```

You will also need to include a File* declaration which points to a path where the log file is stored. Examples are shown in this chapter.

Halting a script through the front panel during execution


When a script is executing, the top right soft key on the 882 is assigned to the STOP function. If the STOP key is pressed, the sc.Canceled() method will return true. The script must check this state in order to detect whether the STOP key has been pressed. A script should always return true when exiting. See example programs testapi.cpp and tcan.cpp.

Some scripts may take over the top right soft key so it is not available for the STOP function. The example program testapi is an example of this. Therefore, the generator's OPTIONS key is always available to interrupt scripts that are running. After pressing the OPTIONS key, pressing the bottom left soft key (!Yes) will stop the script.

About the ScriptSDK main window

The Quantum Data SDK GUI is shown below. It is centered around the text editor. The title bar at the top indicates whether the program is currently set for ScriptSDK or ImageSDK. Beneath the title bar is the menu bar, featuring pull-down menu categories of File, Compile, Load&Execute, and Connection. The menu bar also contains a button for toggling between ScriptSDK and ImageSDK modes.

Under the menu bar is the main section of the GUI, the tabbed Editor pane. Multiple files can be edited, and each file has its own tab. Under the Editor pane is the output pane. The two tabs in this pane contain compiler output and connection output. Finally, the status bar at the bottom of the window shows the IP address of the 880 series generator that is currently connected.



ScriptSDK menu summary

Refer to the table below for a list of menu commands.

Menu	Command	Description
File	New	Opens a new empty file in the tabbed editor pane.
	New File from Template	Only active in ScriptSDK mode, this selection presents a dialog for opening a template file from the script_templates folder.
	Open	Presents a dialog for opening an existing source file. In ScriptSDK mode the default folder is scripts; in ImageSDK mode the default folder is examples.
	Close File	Closes the file in the current editor tab.
	Save	Saves the file in the current editor tab.

Menu	Command	Description
	Save as	Presents a dialog for saving the current file, allowing the user to choose a new filename and/or folder.
	Preference	Allows the user to choose between the Quantum Data SDK text editor and another text editor on the host PC
	Exit	Exits the Quantum Data SDK. This will also cause the web browser to immediately terminate, so it is recommended to instead use the web browser's back button to exit the SDK.
Compile	Current File	Compiles the file in the curent editor tab.
	Another File	Presents a dialog for choosing a source file to compile.
Load& Execute	Object File	Presents a dialog for choosing the object file to load to the generator.
Control	Pause	
	Terminate	
Connection	Connect to	Presents a dialog for entering the IP address of the generator to connect to. The dialog defaults to the generator that the application was launched from.
Switch to Image SDK		Allows the user to toggle between ImageSDK and ScriptSDK. This switch changes the default folders on the host PC for source and object files; it also changes the destination path on the generator for storing executable object files.


Starting ScriptSDK

To start ScriptSDK:

1. Connect to the generator through your Web browser. The generator Home page appears.



2. On the generator Home page, click **Script SDK**. The ScriptSDK Home page appears, and then a message appears asking you to choose whether you want to connect to ScriptSDK or ImageSDK.




3. Click **Script SDK**. The ScriptSDK main window appears as shown below.

Creating, compiling, and executing a script

To start a scripting session:


1. With the ScriptSDK main window open, click **Connection**, and then click **Connect to**. The Input dialog box appears.




2. Enter the IP address of the generator you want to connect to. (The default address is the address of the generator from which you launched ScriptSDK.) Click **OK**. ScriptSDK attempts to connect to the generator and displays the message **Successfully Connected to Unit** when connected. Click **OK**.

To open an existing script:

1. Click **File**, and then click **Open**. The Open Script dialog box appears.




2. Select the script you want to open, and then click **Open**. The script appears in the Editor pane. You can have multiple scripts open at the same time. Each script appears as a separate tab in the Editor pane.




To create a new script:

1. Click **File**, and then click **New**. A new tab appears in the Editor pane.

2. Type the script in the Editor pane.




3. When you are finsihed, click **File**, and then click **Save**. The Save Script dialog box appears. In the **Filename** box, type a name for the script, and then click **Save**.



To create a new script using a template:

1. Click **File**, and then click **New File from Template**. The Select Template dialog box appears.
2. Select the template you want to use, and then click **Open**. The template appears in the Editor pane.

3. Modify the template as needed to match your requirements. When you are finsihed, click **File**, and then click **Save**. The Save Script dialog box appears. In the **Filename** box, type a name for the script, and then click **Save**.



To compile a script:


1. To compile a script, click the tab in the Editor Pane that contains the script you want to compile.
2. Click **Current File** from the Compile pull down menu. The file is compiled and any compiler messages appear in the Compile Output pane. The output of the compile process is an executable object file that is placed in Scripts folder, which is in the SDK folder on your 882 generator library directory.

To execute a script from the ScriptSDK GUI:

1. Click **Object File** from the **Load&Execute** pull down menu. A dialog box called Choose Object File dialog box appears.
2. Select the file you want to execute, and then click **Choose**. A message appears telling you if the execution was successful.
3. You can also execute a scrip


To execute a script from the 882 front panel:

1. Press the **Tools** key. The Tools menu appears on the generator's display as shown below.




2. Scroll down until you see the ScriptSDK selection item.

   The list of available scripts is presented.



3. Execute the desired script by pressing the adjacent soft key.

   The script that has been selected and is now running is shown along with an option to stop the script.



To execute a script from the 882 command line:

1. Load the script file that you want to execute by entering the following command.

   ```
   SCRX:LOAD testapi.o //loads script object from current scripts path
   ```

   For a list of scripts, enter the following command:

   ```
   SCRX:LIST?
   ```

2. Execute the script by entering the following command:

   ```
   SCRX:EXEC   // executes currently loaded script
   ```

   To stop a script that is executing enter the following:

   ```
   SCRX:STOP   // stops execution of currently running script
   ```

ScriptSDK API functions by category

The ScriptSDK API functions are all public methods of the QDScriptContext class. They are presented in categories of control, command, response, front panel display, and operators.

Control functions

Command	Description
GetGC	Get the handle of TGC
Canceled	Status of script cancel
Pause	Calibrate generator (using self-calibration circuitry)

Command functions

Command	Description
SetCmdName	Set name of command to execute
GetCmdName	Get name of command to execute
Exec	Execute current command
Append	Append to command string
Reset	Reset the command string
SetDefaultTimeOut	Set default command timeout
GetDefaultTimeOut	Get default command timeout
SetCancelOnError	Set "cancel on error" status
GetCancelOnError	Get "cancel on error" status

Response functions

Command	Description
GetResponse	Get most recent response string
GetIntResponse	Get response as signed int
GetUIntResponse	Get response as unsigned int
GetDoubleResponse	Get response as double
GetRespLineCount	Get number of lines in response
ClearResponse	Reset the response
Failed	Get fail state of most recent command
Succeed	Get response state of most recent command
GetError	Get error value for failed command

Front panel functions

Command	Description
Write	Write a string to front panel display
InputInteger	Get integer user input via front panel
InputFloat	Get float user input via front panel
WaitForKeyPress	Wait for user to press a soft key
ClearLCD	Clear the front panel display

Operator functions

Command	Description
=	Assign name of command to be executed
+=	Append to command to be executed

ScriptSDK API functions by name

This subsections lists the ScriptSDK functions by name and provides details about how to use them.

Append

Class	Command
Description	Adds characters to an existing command string, created with a call to SetCmdName(). Allowable arguments are char pointer, integer, and double-precision float. In the case of an integer argument, the radix for the base of the resulting string can be specified optionally. The default radix is 10.
Command syntax	sc.Append(const char* txt) sc.Append(UINT32 value, UINT32 RADIX=10) sc.Append(double value)
Example	Refer to example programs apndflt.cpp, apndint.cpp, sampseq.cpp, testapi.cpp
Related commands	Exec(), GetCmdName(), Reset(), SetCmdName,

Canceled

Class	Control
Description	Returns script cancel state. A script can be set to cancel state by pressing the STOP (upper right) soft key during execution, or by pressing the OPTIONS key and then the lower-left (!Yes) soft key to confirm. A script can also be set to cancel state if its CancelOnError status is true, and the script encounters an error while executing. To cancel script execution, the script must check the return value of Canceled(); if it is true, the script should immediately return a value of true.
Command syntax	sc.Canceled(void)
Example	Refer to example programs apndflt.cpp, apndint.cpp, sampseq.cpp, tcan.cpp, testapi.cpp
Related commands	Exec(), GetCmdName(), Reset(), SetCmdName

ClearLCD

Class	Front Panel
Description	Clears the entire display on the front panel of the generator
Command syntax	sc.ClearLCD(void)
Example	Refer to example program testapi.cpp
Related commands	Write(), InputInteger(), InputFloat()

ClearReponse

Class	Response
Description	Resets the command response string to a default empty state. This can be used to clear a response after it is queried; therefore the next non-empty response will be a new response.
Command syntax	sc.ClearResponse(void)
Related commands	GetResponse(), GetIntResponse(), GetUIntResponse(), GetDoubleResponse()

Exec

Class	Command
Description	Execute a command. Command can be pre-built using SetCmdName() and Append(), or a pointer to a command string can be passed. Command timeout in milliseconds can be specified optionally.
Command syntax	sc.Exec(void) sc.Exec(UINT32 timeout) sc.Exec(char* cmdString) sc.Exec(char* cmdString, UINT32 timeout)
Return type	UNIT32
Example	Refer to sample programs apnd.cpp, apndflt.cpp, apndint.cpp, sampseq.cpp, tcan.cpp, testapi.cpp
Related commands	SetCmdName( ), Append( ), GetCmdName( ), SetDefaultTimeOut(), GetDefaultTimeOut(), Command Reference in Appendix A of 881/882 Series User Guide

Failed

Class	Response
Description	Returns true if previous command execution failed.
Command syntax	sc.Failed(void)
Return type	bool
Related commands	Exec(), Succeed(), GetError()

GetBoolResponse

Class	Response
Description	Gets the most recent query response string and returns it as a bool. If the first character of the response string is "T" or "t" the return value is "true." If the first character of the response string is "F" or "f" the return value is "false." Otherwise, it will attempt to convert the string to unsigned long via strtoul(). If the result of the conversion is zero, the return value is "false." If the result is not zero, the return value is "true."
Command syntax	sc.GetBoolResponse(void)
Return type	bool
Example	Refer to sample program testapi.cpp
Related commands	GetResponse(), GetIntResponse(), GetUIntResponse(), GetDoubleResponse(), GetRespLineCount(), ClearResponse()

GetCancelOnError

Class	Command
Description	Returns CancelOnError status. Return value of true indicates that an execution error will cause Canceled() to be true. To terminate script execution on error, program code should check the state of Canceled(); if it is true the program should exit via "return true;"
Command syntax	sc.GetCancelOnError(void)
Return type	bool
Related commands	Canceled(), SetCancelOnError(), GetError()

GetCmdName

Class	Command
Description	Returns the current contents of the command string. The command string can be built using SetCmdName(), Append(), =, and +=.
Command syntax	sc.GetCmdName(void)
Return type	const char*
Example	Refer to sample programs apnd.cpp, apndflt.cpp, testapi.cpp
Related commands	SetCmdName(), Exec(), Append(), operator =, operator +=

GetDefaultTimeOut

Class	Command
Description	Returns the current timeout value for commands, in milliseconds.
Command syntax	sc.GetDefaultTimeOut(void)
Return type	UNIT32
Related commands	SetDefaultTimeOut()

GetDoubleResponse

Class	Response
Description	Gets the most recent query response string and returns it as a double-precision floating point value.
Command syntax	sc.GetDoubleResponse(void)
Return type	double
Example	refer to sample program testapi.cpp
Related commands	GetResponse(), GetIntResponse(), GetUIntResponse(), ClearResponse()

GetError

Class	Response
Description	Returns the error value of the previous command.
Command syntax	sc.GetError(void)
Return type	UNIT32
Example	refer to sample program testapi.cpp
Related commands	Exec(), Failed(), Succeed()

GetGC

Class	Control
Description	Returns a pointer to an instance of the graphics core object that provides dynamic linking with internal generator firmware.
Command syntax	GetGC(void)
Return type	TGC*

GetIntResponse

Class	Response
Description	Gets the most recent query response string and returns it as a signed 32-bit integer value.
Command syntax	sc.GetIntResponse(void)
Return type	INT32
Example	refer to sample program testapi.cpp
Related commands	GetResponse(), GetUIntResponse(), GetDoubleResponse(), ClearResponse()

GetRespLineCount

Class	Response
Description	Some query responses can consist of multiple lines of output. This method returns the number of lines of output from the most recent query.
Command syntax	sc.GetRespLineCount(void)
Return type	INT32
Example	refer to sample program testapi.cpp
Related commands	GetResponse(), GetIntResponse(), GetUIntResponse(), GetDoubleResponse, ClearResponse()

InputFloat

Class	Front Panel
Description	Presents a dialog for user input of a floating point value via front panel display and keys. Parameters allow specification of the displayed prompt, number of digits (whole and fractional,) and initial value. The prompt string is required. The whole and frac parameters are optional and both default to 4. The initValue parameter is optional and defaults to zero.
Command syntax	sc.InputFloat(const char*prompt, UINT32 whole, UINT32 frac, double initValue)
Return type	double
Example	refer to example program testapi.cpp.
Related commands	InputInteger(), ClearLCD()

InputInteger

Class	Front Panel
Description	Presents a dialog for user input of an integer value via front panel display and keys. Parameters allow specification of the displayed prompt, number of digits, and initial value. The prompt string is required. The numDigits parameter is optional and defaults to 4. The initValue parameter is optional and defaults to zero.
Command syntax	sc.InputInteger(const char* prompt, UINT32 numDigits, INT32 initValue)
Return type	INT32
Example	refer to example program testapi.cpp.
Related commands	InutFloat(), ClearLCD()

Pause

Class	Control
Description	Forces a delay in program execution, for specified number of milliseconds.
Command syntax	sc.Pause(UINT32 timeValue)
Return type	void
Example	refer to example programs apndflt.cpp, apndint.cpp, sampseq.cpp, tcan.cpp, testapi.cpp.

Reset

Class	Command
Description	Clears the command string; resets it to the default empty state.
Command syntax	sc.Reset(void)
Return type	void
Example	refer to example program testapi.cpp.
Related commands	SetCmdName(), Append(), GetCmdName()

SetCancelOnError

Class	Command
Description	Sets or clears the CancelOnError status. If set (with an argument of true) an error or failure will cause the Canceled() state to be set to true. To terminate script execution on error, program code should check the state of Canceled(); if it is true the program should exit via "return true;"
Command syntax	sc.SetCancelOnError(bool)
Return type	void
Example	refer to example program testapi.cpp.
Related commands	Canceled(), GetCancelOnError(), GetError()

SetCmdName

Class	Command
Description	Sets a command string to be executed later. The command string can be added to with Append(). The command can be executed with Exec().
Command syntax	sc.SetCmdName(const char*)
Return type	void
Example	refer to example programs apnd.cpp, apndflt.cpp. testapi.cpp
Related commands	refer to example programs apnd.cpp, apndflt.cpp. testapi.cpp

SetDefaultTimeOut

Class	Command
Description	Sets the current timeout value for commands, in milliseconds.
Command syntax	sc.SetDefaultTimeOut(UINT32)
Return type	void
Example	sc.SetDefaultTimeOut(5000); // commands will time out in 5 seconds
Related commands	GetDefaultTimeOut()

Succeed

Class	Response
Description	Returns true if previous command execution was successful.
Command syntax	sc.Succeed(void)
Return type	bool
Example	refer to example program testapi.cpp.
Related commands	Exec(), Fail(), GetError()

WaitForKeyPress

Class: Front Panel

Description: Delays program execution until a soft key is pressed. Optional argument indicates desired timeout in milliseconds. Void argument or zero will result in wait for ever. Returns a value representing the key pressed; one of the following:

QD_KEY_LEFT_1

QD_KEY_LEFT_2

QD_KEY_LEFT_3

QD_KEY_LEFT_4

QD_KEY_RIGHT_1

QD_KEY_RIGHT_2

QD_KEY_RIGHT_3

QD_KEY_RIGHT_4

Command syntax: sc.WaitForKeyPress(void)

sc.WaitForKeyPress(UINT32)

Return type: QDKeyId

Example: refer to example program testapi.cpp.

Related commands: Write(), ClearLCD()

Write

Class	Front Panel
Description	Write a string to the generator's front panel display. The display is 20 characters by 4 lines. Allowable values of column are in the range of 0 - 19. Allowable values of row are 0 - 3.
Command syntax	sc.Write(UINT32 column, UINT32 row, char* string)
Return type	void
Example	refer to example programs apndflt.cpp, testapi.cpp
Related commands	ClearLCD(), WaitForKeyPress(), InputFloat(), InputInteger()

Operator =

Class	Operator
Description	Assigns a string to the command string. The command string is represented by the pointer to the script context; sc. This is similar to SetCmdName().
Command syntax	sc = "string"

Example	sc = "SCRX:LOAD";// set the command string
	also refer to example program testapi.cpp.

Related commands	Operator +=, SetCmdName(), Append(), Exec()

Operator +=

Class	Operator
Description	Appends characters to the command string. The argument will be converted to ASCII character string if necessary. The command string is represented by a pointer to the script context; sc. This is similar to Append().
Command syntax	sc += "string" sc += char sc += double sc += UINT32

Example	sc += "testapi.o";// append filename to the command string
	also refer to example program testapi.cpp

Related commands	Operator =, Append(), SetCmdName(), Exec()

ScriptSDK commands

This subsection lists the commands related to the ScriptSDK that can be executed through the 882's command line interface. These can be executed through the serial port, a telnet session or through the command utility available through the 882 home page.

SCRX:LIST?

Class	Scriptrunner
Description	Lists the executable script object files currently residing in the generator
Query syntax	SCRX:LIST?
Query response	list of executable script object files
Example	`SCRX:LIST?  // list executable scripts`

SCRX:PATH

Class — Scriptrunner

Description — Sets the current path for storage of SDK scripts. The query returns the current script path name.

Command syntax — SCRX:PATH <*name*>

name

a valid MS-DOS compatible path and filename (8 characters minus any extension)

Query syntax — SCRX:PATH?

name

returns a valid MS-DOS compatible path and filename for the name of the path

Query response — path name

Example

```
SCRX:PATH /tffs0/Library/Scripts // sets script path to default directory
```

SCRX:EXEC, SCRX:EXEC?

Class	Scriptrunner
Description	Executes the currently loaded script. The query returns the name of the currently executing script.
Command syntax	SCRX:EXEC
Query syntax	SCRX:EXEC?
Query response	path and name of currently executing script object file
Example	`SCRX:EXEC  // execute currently loaded script`

SCRX:LOAD, SCRX:LOAD?

Class Scriptrunner

Description Loads a script object file in preparation for execution. Script object file must already be stored in generator file system. If the load command also includes a directory path, then this command will also change the current scripts path (SCRX:PATH) to the specified path. The query returns the name of the currently loaded script.

Command syntax SCRX:LOAD <*name*>

name

a valid script file, including ".o" extension which can optionally include a fully-qualified path

Query syntax SCRX:LOAD?

Query response name of currently loaded script object file

Example
```
SCRX:LOAD testapi.o //loads script object from current scripts path
SCRX:LOAD /tffs0/library/userdata/testapi.o  //loads script object
                                               testapi.o from specified
                                               path, and also sets
                                               current script path to
SCRX:LOAD?          //returns name of currently loaded script object file
```

SCRX:KILL

Class Scriptrunner

Description Deletes an executable object file from the generator

Command syntax SCRX:KILL name

name

a valid script file, including ".o" extension which can optionally include a fully-qualified path

Example
```
SCRX:KILL testapi.o // deletes script object testapi.o from current
                       scripts path
SCRX:KILL /tffs0/library/userdata/testimg.o // deletes file testimg.o
                                               from specified path
```

SCRX:STOP

Class Scriptrunner

Description Stops the execution of a script

Command syntax SCRX:STOP

Example
```
SCRX:STOP // stops execution of currently running script
```

Sample ScriptSDK programs

This subsections provides some example ScriptSDK scripts to help you understand how to create scripts for specific applications.

apnd.cpp

This example shows how to append text to a command string using the Append function and demonstrates printing debug messages to a serial port.

```
#include <stdio.h>
#include <QDScriptContext.h>
bool Script_apnd( QDScriptContext& sc)
{
// enable printf to serial terminal
    sc.Exec("CIOY");
// create a command to load the DMT0660 timing format
    sc.SetCmdName("FMTL");
    sc.Append("/tffs0/Library/Formats/dmt0660.xml");
// print the entire command string to the serial port
    printf( "%s\n", sc.GetCmdName() );
// invoke the full FMTL command using the previously assigned command
string
    sc.Exec();
// create a command to use the selected timing format
    sc.SetCmdName("FMTU");
// invoke the FMTU command using the previously assigned command string
    sc.Exec();
return true;
}
```

apndflt.cpp

This example shows how to add a floating point numeric value to a command string using the Append function and also demonstrates writing to the 882 front panel display.

```
#include <stdio.h>
#include <QDScriptContext.h>
bool Script_apndflt( QDScriptContext& sc )
{
// For RGB: step the analog video signal swing from 0.1 volts
// to 1.0 volts in steps of 0.10 volts, pausing at each level
    double aswing;
// select a safe format, VGA
    sc.Exec("FMTL /tffs0/Library/Formats/DMT0660.xml");
    // use this selected format
    sc.Exec ("FMTU");
    // select a colorful image for this example
    sc.Exec("IMGL /Cache0/Images/colorbar.img");
    // select RGB video out
    sc.Exec("XVSI 9");
    // enable RGB video
    sc.Exec("AVST 2");
    // apply the above image and interface selections
    sc.Exec("ALLU");
    // step the analog video signal swing from 0.1 volts to 1.0
    // volts in steps of 0.10 volts, pausing at each level
    for(aswing=0.10; aswing<1.01; aswing+=0.10)
    {
        // build the command to set analog video swing
        sc.SetCmdName("AVSS");
        sc.Append(aswing);
// write the command to the bottom of the front-panel display
        sc.Write( 0,3,(char *)sc.GetCmdName() );
// issue the command to set analog video swing
        sc.Exec();
// use the selected format parameters
        sc.Exec("FMTU");
// pause for 10 seconds at each level
        sc.Pause(10000);
// this will cause script to immediately exit if STOP is pressed
        if (sc.Canceled())
return true;
}
    return true;
}
```

apndflt.cpp

This example demonstrates appending an integer to a command string. This example will sequentially test 3 different video interfaces: HDMI, S-video, and composite.

```
#include <stdio.h>
#include <QDScriptContext.h>
bool Script_apndint( QDScriptContext& sc )

    UINT32 formatnum;

    sc.Exec("CIOY");        // enable printf to serial terminal

    // first load an image to use for this example:
    sc.Exec("IMGL /Cache0/Images/colorbar.img");
    // display the image
    sc.Exec("IMGU");

    // step through 3 interfaces: 4=HDMI-H, 5=SVideo, 6=CVBS
    for(formatnum=4; formatnum<=6; formatnum++)
    {
        // build command string to set video output interface
        // XVSI specifies which video output interface to use
        sc.SetCmdName("XVSI ");

        // use Append function to convert formatnum to character
           and insert it into
        // command string.  Base-10 conversion.
        // For this example, it will be either 4, 5, or 6.
        sc.Append(formatnum, 10);

        // print the entire command string to the serial port
        printf( "%s\n", sc.GetCmdName() );
        // execute the completed XVSI command
        sc.Exec();

        // This switch will select a video format that is appropriate
        // for the output interface selected above switch(formatnum)
        {
            case 4:
                printf("Now testing HDMI...\n");
                // load a format that is compatible with HDMI interface
                sc.SetCmdName("FMTL /tffs0/Library/Formats/dmt0660.xml");
                break;

            case 5:
                printf("Now testing SVideo...\n");
                // load a format that is compatible with SVideo interface
                sc.SetCmdName("FMTL /tffs0/Library/Formats/ntsc.xml");
                break;

            case 6:
                printf("Now testing CVBS...\n");
```

```
                // load a format that is compatible with CVBS interface
                sc.SetCmdName("FMTL /tffs0/Library/Formats/ntsc.xml");
            }
            // invoke the selected format
            sc.Exec();

            // use the format that was selected above
            sc.Exec("FMTU");

            // delay for 10 seconds on each interface
            sc.Pause(10000);

            // this will cause script to immediately exit if STOP is pressed
            if (sc.Canceled())
    return true;
        }
        return true;
    }
```

sampseq.cpp

```
// Quantum Data ScriptSDK Demonstration Program

//~~~~~~~~~~~~~~~~~~~~~~~~~~~~

#include <stdio.h>

#include <QDScriptContext.h>

//~~~~~~~~~~~~~~~~~~~~~~

/*********************************************************************

*  Script_sampseq

*********************************************************************

This is a conversion of "Sample Sequence" from chapter 8 of the 881/882 User Guide.
This demonstrates how a sequence can be converted to an SDK script.  Note that
arguments are not always the same as in the sequence XML files, as shown in the XVSG
conversions below.

In ScriptSDK, commands have the same syntax as if they were being entered at a
command prompt.  For full details on command syntax, refer to the Command Reference
in Appendix A of the 881/882 User Guide available at:
http://www.quantumdata.com/downloads/index.asp

Note:  Note: this script (and the sequence that it evolved from) expects you to have
previously selected a compatible interface, such as VGA or HDMI.

*********************************************************************

*  Usage:

Script_sampleseq( QDScriptContext& sc );

*

*  Arguments:

*     sc - the script context being executed on.

*********************************************************************/

bool Script_sampseq( QDScriptContext& sc )

{

//<?xml version="1.0" encoding="UTF-8" ?>

//<DATAOBJ>

   //<HEADER TYPE="SEQ" VERSION="1.0" ></HEADER>

   //<DATA>

   //<MODE>STEP</MODE>
```

```
//<STEP>
//<FMT>/tffs0/Library/Formats/DMT0660.xml</FMT>
sc.Exec("FMTL /tffs0/Library/Formats/DMT0660.xml");
sc.Exec("FMTU");
//<IMG>/Cache0/Images/Acer1.img</IMG>
sc.Exec("IMGL /Cache0/Images/Acer1.img");
sc.Exec("IMGU");
//<DELY>+3.0000000E+00</DELY>
sc.Pause(3000);
//<VERS>0</VERS>
sc.Exec("IVER 0");
//<XVSG>7</XVSG>
sc.SetCmdName("XVSG ");
sc.Append("1 1 1");
sc.Exec();

if (sc.Canceled()) {
   return true;
}
printf("Check Point 1\n");
//</STEP>
//<STEP>
//<IMG>/Cache0/Images/Cubes.img</IMG>
sc.Exec("IMGL /Cache0/Images/Cubes.img");
sc.Exec("IMGU");
//<DELY>+4.0000000E+00</DELY>
sc.Pause(4000);

if (sc.Canceled()) {
   return true;
}
printf("Check Point 2\n");
```

```
//</STEP>
//<STEP>
//<IMG>/Cache0/Images/Linearty.img</IMG>
sc.Exec("IMGL /Cache0/Images/Linearty.img");
sc.Exec("IMGU");
//<DELY>+5.5000000E+00</DELY>
sc.Pause(5500);

if (sc.Canceled()) {
   return true;
}
printf("Check Point 3\n");
//</STEP>
//<STEP>
//<FMT>/tffs0/Library/formats/DMT0860.xml</FMT>
sc.Exec("FMTL /tffs0/Library/Formats/DMT0860.xml");
sc.Exec("FMTU");
//<IMG>/Cache0/Images/RampX.img</IMG>
sc.Exec("IMGL /Cache0/Images/RampX.img");
sc.Exec("IMGU");
//<DELY>+3.0000000E+00</DELY>
sc.Pause(3000);

if (sc.Canceled()) {
   return true;
}
printf("Check Point 4\n");
//</STEP>
//<STEP>
//<XVSG>1</XVSG>
sc.Exec("XVSG 0 0 1");
```

```
    //</STEP>
    //<STEP>
    //<XVSG>2</XVSG>
    sc.Exec("XVSG 0 1 0");

    //</STEP>
    //<STEP>
    //<XVSG>4</XVSG>
    sc.Exec("XVSG 1 0 0");

    //</STEP>
    //<STEP>
    //<XVSG>7</XVSG>
    sc.Exec("XVSG 1 1 1");

    if (sc.Canceled()) {
       return true;
    }
    printf("Check Point 5\n");
    //</STEP>
    //<STEP>
    //<FMT>/tffs0/Library/Formats/DMT1060.XML</FMT>
    sc.Exec("FMTL /tffs0/Library/Formats/DMT1060.xml");
    sc.Exec("FMTU");
    //<IMG>/Cache0/Images/Master.img</IMG>
    sc.Exec("IMGL /Cache0/Images/Master.img");
    sc.Exec("IMGU");
    //<DELY>+5.0000000E+00</DELY>
    sc.Pause(5000);
    return true;
}
```

sampseq.cpp

This example delays and does nothing except waits to be cancelled, then reports to a serial terminal whether it was cancelled.

```
#include <stdio.h>
#include <QDScriptContext.h>
bool Script_tcan( QDScriptContext& sc )
{
    sc.Exec("CIOY");        // enable printf to serial terminal
    printf("Pause for 10 seconds\n");
    sc.Pause( 10000 );                          // pause for 10 seconds

    if (sc.Canceled())
    {
        printf("Script was canceled\n");
    }
    else
    {
        printf("Script completed\n");
    }
    return true;
}
```

testapi.cpp

This example demonstrates the following functions of the API:

- Sending commands and getting responses back
- Pause()
- Multi-line response
- Operators “=” and “+=”
- QDLcd associated API commands: InputInteger(), InputFloat(), and WaitForButtonPress()
- GetUIntResponse()
- GetIntResponse()
- GetDoubleResponse()
- GetBoolResponse()
- Detecting an invalid command

```
#include <QDScriptContext.h>
#include <stdio.h>
bool Script_testapi( QDScriptContext& sc )
{
    // ============================================================
    // Demonstration of sending command and getting response back
    // ============================================================
    // one way to execute a command/query
    sc.Exec("CIOY");        // enable printf to serial terminal
    // another way to execute a command/query
    sc.SetCmdName("VERF?"); // query generator firmware version
    sc.Exec();              // execute the command
    printf("The return value of command \"%s\" is %s\n", sc.GetCmdName(),
sc.GetResponse());
    // ============================================================
    // Demonstration of Pause()
    // ============================================================
    printf("Pause for 5 seconds\n");
    sc.Pause( 5000 );
    if (sc.Canceled()) {
        return true;
    }
    printf("\nWake up from Pause(5000)\n");
    sc.SetCmdName("VERG?"); // query generator gateware versions
    sc.Exec();              // execute the command
    if (sc.Succeed()) {     // was previous command successful?
        printf("\nThe return value of command \"%s\" is %s\n",
sc.GetCmdName(), sc.GetResponse());
    }
```

```
    else
        printf("\nThere is no response.\n");
    // ============================================================
    // Demonstration of multi-line respones
    // ============================================================
    if (sc.Canceled()) {
        return true;
    }
    // query the first 10 test images in the generator
    sc.SetCmdName("IMGQ?");
    sc.Append(" 1 10");
    sc.Exec();
    printf("\nThe response of command \"%s\" has %d lines\n",
sc.GetCmdName(), sc.GetRespLineCount());
    printf("\nThe 9th line of response is %s\n", sc.GetResponse(9));
    for ( UINT32 index=1; index<sc.GetRespLineCount()+1; index++ ) {
        printf("Response line %d is: %s \n", index,
sc.GetResponse(index));
    }
    // ============================================================
    // Demonstration of Operator "=" and "+=" overloading
    // ============================================================
    sc.Reset();
    if (sc.Canceled()) {
        return true;
    }
    sc  = "SCRX:";
    sc += "LIST";
    sc += "?";
    sc.Exec();
    printf("\nThe return value of command \"%s\" is %s\n",
sc.GetCmdName(), sc.GetResponse());
    // ============================================================
    // Demonstration of QDLcd associated APIs, InputInteger() &
InputFloat()
    // ============================================================
    if (sc.Canceled()) {
        return true;
    }
    // Test "InputInteger( const char* prompt )" API
    INT32 test = sc.InputInteger( "My test:" );
    printf("\nThe input of my test is: %d\n", test);
    if (sc.Canceled()) {
        return true;
    }
    test = sc.InputInteger( "Input another one:" );
    printf("\nThe input of second input is: %d\n", test);
    if (sc.Canceled()) {
        return true;
    }
    test = sc.InputInteger( "Test limity:", 3, 300 );
    printf("\nThe input of test limit is: %d\n", test);
    if (sc.Canceled()) {
```

```
        return true;
    }
    double test2 = sc.InputFloat( "Test Float:" );
    printf("\nThe input of Test Float is: %f\n", test2);
    // ============================================================
    // Demonstration of QDLcd associated APIs, WaitForButtonPress()
    // ============================================================
    if (sc.Canceled()) {
        return true;
    }
    sc.ClearLCD();
    sc.Write(1, 1, "Test WaitForButtonPress()");
    sc.Write(0, 3, "<-Yes4");
    sc.Write(16, 3, "No->");
    QDKeyId pressedKey = sc.WaitForKeyPress(5000);
    if ( pressedKey == QD_KEY_LEFT_4 ) {
        printf("\nUser pressed \"Yes\"\n");
    }
    else if ( pressedKey == QD_KEY_RIGHT_4 ) {
        printf("\nUser pressed \"No\"\n");
    }
    else
    {
        printf("\nPressed Invalid Key\n");
    }
// ============================================================
    // Demonstration of GetUIntResponse()
    // ============================================================
    if (sc.Canceled()) {
        return true;
    }
    sc.SetCmdName("DPTR?");
    //sc.ClearScreen();
    sc.Exec();
    if (sc.Succeed()) {
        printf("\nTest GetUIntResponse(): The return value of command
\"%s\" is %d\n", sc.GetCmdName(), sc.GetUIntResponse());
    }
    else
        printf("\nCommand execution failed.\n");
    // ============================================================
    // Demonstration of GetIntResponse()
    // ============================================================
    if (sc.Canceled()) {
        return true;
    }
    sc.SetCmdName("HRES?");
    //sc.ClearScreen();
    sc.Exec();
    if (sc.Succeed()) {
        printf("\nTest GetIntResponse(): The return value of command
\"%s\" is %d\n", sc.GetCmdName(), sc.GetIntResponse());
    }
```

```
    else
        printf("\nCommand execution failed.\n");
    // ========================================================
    // Demonstration of GetDoubleResponse()
    // ========================================================
    if (sc.Canceled()) {
        return true;
    }
    sc.SetCmdName("PRAT?");
    //sc.ClearScreen();
    sc.Exec();
    if (sc.Succeed()) {
        printf("\nTest GetDoubleResponse(): The return value of command
\"%s\" is %f\n", sc.GetCmdName(), sc.GetDoubleResponse());
    }
    else
        printf("\nCommand execution failed. Error is %d\n",
sc.GetError());
    // ========================================================
    // Demonstration of GetBoolResponse()
    // ========================================================
    if (sc.Canceled()) {
        return true;
    }
    sc.SetCmdName("PDAX:RPTG?");
    //sc.ClearScreen();
    sc.Exec();
    if (sc.Succeed()) {
        printf("\nTest GetBoolResponse(): The return value of command
\"%s\" is %d\n", sc.GetCmdName(), sc.GetBoolResponse());
    }
    else
        printf("\nCommand execution failed.\n");
    // ========================================================
    // Demonstration of Pause()
    // ========================================================
    printf("Pause for 6 seconds\n");
        sc.Pause( 6000 );
    if (sc.Canceled()) {
        return true;
    }
    printf("\nWake up from Pause(6000)\n");
    if (sc.Canceled()) {
        return true;
    }
    sc.SetCmdName("VERG?");
    //sc.ClearScreen();
    sc.Exec();

    if (sc.Succeed()) {
        printf("\nThe return value of command \"%s\" is %s\n",
sc.GetCmdName(), sc.GetResponse());
    }
```

```
    else
        printf("\nCommand execution failed.\n");
// =======================================================
    // Demonstration of detecting invalid command
    // =======================================================
    // First, set CancelOnError to be FALSE, the test should continue to
next
    sc.SetCancelOnError( false );
    sc.SetCmdName("VERP?");
    sc.Exec();
    printf("\nThe error status of the invalid command %s is %d\n",
sc.GetCmdName(), sc.GetError());
    if (sc.Canceled()) {
        printf("The test exited because the command is not valid\n");
        return true;
    }
    else
    {
        printf("Script not cancelled.  Execution should continue\n");
    }
    // Then, set CancelOnError to be TRUE, the test should continue to
next
    sc.SetCancelOnError( true );
    sc.SetCmdName("VERP?");
    sc.Exec();
    printf("\nThe error status of the invalid command %s is %d\n",
sc.GetCmdName(), sc.GetError());
    if (sc.Canceled()) {
        printf("The test exited because the command is not valid\n");
        return true;
    }
    else
    {
        printf("Script not cancelled.  Execution should continue\n");
    }
    return true;
}
```

timinglog.cpp

This example demonstrates the ability to output data to a file. It uses the new functions related to file output: fopen(); fclose(); fprint().

```
#include <stdio.h>

#include <QDScriptContext.h>


extern int fopen();

extern int fclose();

extern int fprintf();


// set up delay between timing measurements as 5000 milliseconds

UINT32 delay = 5000;


bool Script_timinglog( QDScriptContext& sc )

{

  INT32 num = 1;


  // open a text file to write to

  FILE* outfile = fopen("/card0/timing_log.txt","w");

  fprintf( outfile, "Start of timing analyzer log\n\n" );

  fprintf( outfile, "Delay between timing measurements: %d milliseconds\n", delay );

  sc.Exec("DATE?");

  fprintf( outfile, "Measurement start date and time: %s, ", sc.GetResponse());

  sc.Exec("TIME?");

  fprintf( outfile, "%s\n\n", sc.GetResponse());

  fprintf( outfile,
"Number\tSCAN\tPRAT\t\t\tHRAT\tVRAT\t\tHTOT\tHRES\tHSPD\tHSPW\tHSPP\tVTOT\tV
RES\tVSPD\tVSPW\tVSPP\tHVPD\n" );

  fprintf( outfile,
"====\t====\t====\t====\t====\t====\t====\t====\t====\t====\t====\t====\t====\n" );


  // infinite loop until you press Stop on top right

  while (true)
```

```
{
  sc.SetCancelOnError( false);

  // measure the incoming signal
  sc.Exec("TMAU");

  // repeat measurement if there is no incoming signal
  while (sc.Failed())
  {
    sc.Pause(delay);
    sc.Exec("TMAU");
  }

  // if Stop is pressed, close the file and end script
  if (sc.Canceled()) {
    sc.Exec("DATE?");
    fprintf( outfile, "\nMeasurement end date and time: %s, ", sc.GetResponse());
    sc.Exec("TIME?");
    fprintf( outfile, "%s\n\n", sc.GetResponse());
    fprintf( outfile, "End of timing analyzer log\n" );
    fclose( outfile );
    return true;
  }

  // query and write measured timing values to the text file
  fprintf( outfile, "%d\t\t", num);
  sc.Exec("TMAX:SCAN?");
  fprintf( outfile, "%s\t", sc.GetResponse());
  sc.Exec("TMAX:PRAT?");
  fprintf( outfile, "%s\t", sc.GetResponse());
  sc.Exec("TMAX:HRAT?");
  fprintf( outfile, "%s\t", sc.GetResponse());
```

```
sc.Exec("TMAX:VRAT?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:HTOT?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:HRES?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:HSPD?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:HSPW?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:HSPP?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:VTOT?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:VRES?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:VSPD?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:VSPW?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:VSPP?");
fprintf( outfile, "%s\t", sc.GetResponse());
sc.Exec("TMAX:HVPD?");
fprintf( outfile, "%s\n", sc.GetResponse());

// increase the measurement number counter
num++;

// hard delay until the next measurement
sc.Pause(delay);

// if Stop is pressed, close the file and end script
```

```
    if (sc.Canceled()) {
      sc.Exec("DATE?");
      fprintf( outfile, "\nMeasurement end date and time: %s, ", sc.GetResponse());
      sc.Exec("TIME?");
      fprintf( outfile, "%s\n\n", sc.GetResponse());
      fprintf( outfile, "End of timing analyzer log\n" );
      fclose( outfile );
      return true;
    }
  }
}
```

A Command Reference

Topics in this appendix:

- Commands by category
- Commands by name

Commands by category

System

Control

Command	Description
BOIT	Initialize generator (without performing self-calibration)
BOOT	Restart generator (without performing self-calibration)
SCAL	Calibrate generator (using self-calibration circuitry)
UI:MODE	Set generator operating mode (Basic or Browse)
NERR?	Get number of errors in error queue
ERRY?	Retrieve most recent error from error queue
ERRC	Clear all errors in error queue
OERR?	Check for error queue overflow
NOTU	Disables ongoing command execution until communication is complete
TOGG	Enable/disable hot plug setting of source format list via EDID function
INIT	Restore generator RAM storage to factory default condition
DATE	Sets generator system date
TIME	Sets generator system time

Parameters

Command	Description
ASSC	Set analog sync swing calibration factor
AVCM	Set analog video calibration method
AVSC	Set analog video swing calibration factor
CALF	Set analog output calibration factors
DVSC	Set TMDS differential swing calibration factor
RATC	Set pixel rate calibration factor
FRGB	Temporarily set image foreground RGB colors
MODE	Set serial port communications parameters

Tools

Command	Description
VERF?	Get generator firmware version number
VERG?	Get gateway version number
FILE:LOAD	Load file (image, format) on generator
FILE:SCREENCAP	Capture currently displayed image to a bitmap file
LCDS?	Get text displayed on generator LCD display
LEDS?	Get status of generator signals
DEVS?	List all devices
LS?	List contents of current directory
CAT?	View contents of a text file
PWD?	Get current directory name
RM	Remove a file from current directory
TASK?	List current tasks

Network

Command	Description
ENET	Get generator's ethernet MAC address
ENET:IP	Set generator's ethernet IP address
ENET:MASK	Set generator's ethernet subnet mask address

User Profile

Command	Description
USRA	Add user profile
USRU	Create new user profile
USRK	Delete user profile

GPIB (IEEE-488.2 standard)

Commands

Command	Description
*CLS	Clear event status register
*ESE	Set event status enable register value
*ESR?	Get event status register value
*IDN?	Get equipment identification string
*OPC	Set OPC bit in event status register
*RST	Reset generator to known condition
*SRE	Set service request enable register value
*STB	Get status byte register value
GPIB	Set GPIB port address

Port control

Command	Description
*DDT	Execute command on generator when triggered
*TRG	Execute/trigger command on generator
*TST	Perform self-text on generator
*WAI	Wait for command completion before sending prompt
SEOS	Set how generator reads strings

Gating Controls

Command	Description
BLUG	Enable/disable blue video output
GRNG	Enable/disable green video output
REDG	Enable/disable red video output
HPBG	Enable/disable reading hot plug formats
OUTG	Enable/disable all video and sync outputs
SVSG	Set output colors
XVSG	Enable/disable output colors

Images

Control

Command	Description
IMGQ?	Get list of images stored in memory
IMGL	Load an image from a file
IMGU	Update generator with current image edit buffer contents
IMGA	Save image edit buffer contents to a specified filename
IMGK	Delete a saved image file
IMGP	Set default image path
ISUB	Enable/disable alternate versions of images
IVER	Set a image version (normal/alternate)
LEVP, LEVP:R	Set image color component (R, G, B) levels
TOBL	Set signal levels relative to blanking (blacker than black)

Edit

Command	Description
IMGN	Create a new image file
IMGB	Begin an image editing session
IMGE	End an image editing session
IMGS	Save a new image to filename specified by IMGN
ANIM?	Determine if image has animation
DELX	Set horizontal shift for each step of SlideG/SlideRGB image
DELY	Set vertical shift for each step of SlideG/SlideRGB image
DWEL	Set number of frames for each step of SlideG/SlideRGB image
ISTP?	Allow contents of custom image to be copied
MSIZ	Set size of light meter boxes in BriteBox image
NOGA	Disables gamma correction in a custom image
OFFX	Set horizontal offset for large patch of Regulate image
OFFY	Set vertical offset for large patch of Regulate image
PENH	Set height variable for line thickness in EeRise, NAWC, and Slider images
PENW	Set width variable for line thickness in EeRise, NAWC, and Slider images

Command	Description
SPAX	Set horizontal spacing
SPAY	Set vertical spacing
UIDN	Set test string in upper portion of SMPTE133 and Cubes images
XRES	Set horizontal scaling factor
YRES	Set vertical scaling factor

Custom Image Draw

Command	Description
ADOT	Draw a single pixel
ANTI	Use anti-aliasing
CENT	Draw a small cross in center
CROS	Draw a large cross in center
FORM	Draw format data block
GRID	Draw a color crosshatch with boxes
GRIH	Draw equally spaced horizontal lines (grill)
GRIV	Draw equally spaced vertical lines (grill)
HATI	Draw inside-out color crosshatch with boxes
HATO	Draw outside-in color crosshatch with boxes
LIMI	Draw nine markers to define active video area
LINE	Draw a line between two points
OVAL	Draw an oval
PAGE	Fill a rectangular area with a repeating character
RECT	Draw a rectangle with sides parallel to axis of active video
SNUM	Draw sequence step number (when using a sequence)
TBOX	Draw information text box
TBXG	Enable/disable display of information text box specified by TBOX
TEXT	Draw text string
TRIA	Draw a triangle

ImageShift utility

Command	Description
ISHG	Enable/disable image shifting function
ISHQ?	Get list of imageshift files stored in memory
ISHL	Load values from an imageshift file
ISHN	Create a new imageshift file
ISHB	Begin an imageshift file editing session
XISH:HINC	Set horizontal shifting increment
XISH:PATH	Set shift path
XISH:SRCN	Set image for shifting
XISH:TINC	Set time shift increment
XISH:TTYP	Set shifting method
XISH:VINC	Set vertical shifting increment
ISHE	End an imageshift file editing session
ISHS	Save a new imageshift file to filename specified by ISHN
ISHU	Update generator with current imageshift file edit buffer contents
ISHA	Save imageshift file edit buffer contents to a specified filename
ISHK	Delete a saved imageshift file
ISHP	Set default imageshift path

Formats

Control

Command	Description
FMTQ?	Get list of formats stored in memory
FMTL	Load a format from a file
FMTU	Update generator with current format edit buffer contents
FMTA	Save format edit buffer contents to a specified filename
FMTG?	Test format edit buffer contents
FMTK	Delete a saved format file
FMTP	Set default format path
FMTZ	Clear format storage memory

Edit

Command	Description
FMTN	Create a new format file
FMTB	Begin a format editing session
FMTE	End a format editing session
FMTS	Save a new format to filename specified by FMTN
JDVI	Set upper and lower pixel clock rate limit for DVI output
JLDI	Set pixel clock rate for LDI output
JRAT	Set pixel clock rate
PELD	Set number of data bits in each active pixel
HSIZ	Set horizontal physical size of image displayed
VSIZ	Set vertical physical size of image displayed
USIZ	Set measurement units for HSIZ and VSIZ

Parameters (Video Signal)

Command	Type	Description
XVSI	Interface	Enable/disable video signal interface output
XVSI:IN	Interface	Enable/disable video signal interface input
SSST	Synchronization	Set display sync signal type
GAMC	Gamma Correction	Enable/disable video gamma correction factor
GAMA	Gamma Correction	Set video gamma correction factor
CXAR	Active Format (HDMI)	Set aspect ratio of source image content
EXAR	Active Format (HDMI)	Set aspect ratio of extended image content
SXAR	Active Format (HDMI)	Set natural aspect ratio of video signal format
EXCX	Active Format (HDMI)	Map source image to extended image
SXCX	Active Format (HDMI)	Map CXAR-shaped image to SXAR-shaped aperture
SXEX	Active Format (HDMI)	Map EXAR-shaped image to SXAR-shaped aperture
XAFD	Active Format (HDMI)	Set parameters to support a given AFD code

Command	Type	Description
PXAR?	Active Format (HDMI)	Get aspect ratio of pixels in active regions of raster image
XBBH	Manual Border (HDMI)	Set bottom border height
XLBW	Manual Border (HDMI)	Set left border width
XRBW	Manual Border (HDMI)	Set right border width
XTBH	Manual Border (HDMI)	Set top border height
PELD	Canvas	Set pixel depth
NPPP	Canvas	Set pixel repetition factor
AVST	Analog Video	Set signal output type
AVSS	Analog Video	Set maximum peak-to-peak swing for analog video output
AVPS	Analog Video	Set analog video black pedestal level
AVPG	Analog Video	Enable/disable analog video set-up pedestal
AVCS	Analog Video	Set color subcarrier type for television output
AVCO	Analog Video	Set mapping of video colors to analog video output
ASSS	Analog Sync	Set maximum peak-to-peak swing for composite sync
ASCT	Analog Sync	Set composite sync type for analog video output
EQUF	Analog Sync	Enable/disable equalization pulses in composite sync
ASBG	Analog Sync Gates	Add composite sync to blue analog video output
TSPG	Analog Sync Gates	Enable/disable tri-level sync pulse
ASSG	Analog Sync Gates	Add composite sync to all three analog video outputs
DVST	Digital Video	Set signal type
DVQM	Digital Video	Set quantizing mode
NCPP	Digital Video	Set number of clocks per pixel
NBPC	Digital Video	Set color depth
LMAX	Digital Video	Set maximum digital quantizing level
LMIN	Digital Video	Set minimum digital quantizing level
NLNK	Digital Video	Set number of links used by LVDI digital outputs

Command	Type	Description
BALG	Digital Video	Enable/disable adding DC balancing to Open LVDI digital output
PREG	Digital Video	Enable/disable pre-emphasis to Open LVDI digital outputs
DVSP	Digital Video	Set signal polarity
DVPT	Digital Video	Set output protocol (DVI or HDMI)
DVSM	Digital Video	Set sampling mode
DVSS (OUT1:DVSS, OUT2:DVSS)	Digital Video	Set TMDS differential swing voltage
DSST	Digital Sync	Set digital separate sync type for digital composite sync output
DSCT	Digital Sync	Set composite sync type for digital composite sync output
HSPP	Digital Sync Polarity	Set digital horizontal sync pulse polarity
VSPP	Digital Sync Polarity	Set digital vertical sync pulse polarity
CSPP	Digital Sync Polarity	Set digital composite sync output polarity
FSPP	Digital Sync Polarity	Set digital frame sync pulse polarity
PSPP	Digital Sync Polarity	Set probe pulse polarity
LSPP	Digital Sync Polarity	Set digital line sync pulse polarity
HSPG	Digital Sync Gates	Enable/disable digital horizontal sync output
VSPG	Digital Sync Gates	Enable/disable digital vertical sync output
CSPG	Digital Sync Gates	Enable/disable all digital composite sync outputs
PSPG	Digital Sync Gates	Enable/disable probe pulse on special sync output
LSPG	Digital Sync Gates	Enable/disable digital horizontal sync output
FSPG	Digital Sync Gates	Enable/disable digital frame sync output
PCPG	Digital Sync Gates	Enable/disable pixel clock pulse

Parameters (Video Timing)

Command	Type	Description
PRAT?	Rates	Get current pixel rate setting
HRAT	Rates	Set line frequency
VRAT?	Rates	Get current vertical (field) rate
FRAT?	Rates	Get current vertical rate setting for frame
HTOT	Horizontal	Set total number of pixels per horizontal line
HRES	Horizontal	Set number of active pixels per line
VTOT	Vertical	Set total number of lines per vertical frame
VRES	Vertical	Set number of active pixels per frame
SCAN	Vertical	Set number of fields scanned per frame
RFLD	Vertical	Enable/disable identical video information output for each field of interlaced format
HSPD	Horizontal Sync	Set horizontal sync pulse delay
HSPW	Horizontal Sync	Set width of horizontal sync pulse
HVPD?	Horizontal Sync	Get pixel delay between horizontal and vertical sync pulses
VSPD	Vertical Sync	Set vertical sync pulse delay
VSPW	Vertical Sync	Set vertical sync pulse width
EQUB	Composite Sync	Set equalization interval before vertical sync pulse
EQUA	Composite Sync	Set equalization interval after vertical sync pulse
HVSA	Composite Sync	Set pixel serration period
FSPD	Frame Sync	Set frame sync pulse delay
FSPW	Frame Sync	Set width of frame sync pulse
PSHD	Probe Sync	Set line delay (in pixels)
PSVD	Probe Sync	Set vertical delay
PSPW	Probe Sync	Set pixel width
PSVW	Probe Sync	Set vertical width
PSPM	Probe Sync	Set lines in frame where probe pulse occurs

Parameters (Audio Signal and Timing)

Command	Type	Description
CAUD	Encoding	Set digital audio clips
DASI	Interface	Set digital audio signal interface

Command	Type	Description
DAST	Encoding	Set digital audio signal type
NDAS	Encoding	Set number of digital audio streams
NDAC	Encoding	Set number of digital audio channels (CC parameter in Audio InfoFrame)
NBPA	Encoding	Set number of bits (SS parameter in Audio InfoFrame)
DAXG	Components	Specify gated speaker locations
DAXA	Components	Specify available speaker locations
SDMG	Mix	Set generator audio source (internal or external)
DADG	Mix	Enable/disable audio signal downmixing (DM_I parameter in Audio InfoFrame)
DALS	Mix	Set level shift value for audio signal downmixing (LVS parameter in Audio InfoFrame)
DACA	Channels	Set active audio channels
DACG	Channels	Set gated audio channels
SAMP	Sinewave	Set amplitude of digital audio stream sinewave output
SMAX?	Sinewave	Get maximum amplitude of digital audio stream sinewave output
SMIN?	Sinewave	Get minimum amplitude of digital audio stream sinewave output
SRAT	Sinewave	Set frequency of digital audio stream sinewave output
ARAT	Digital Audio Timing	Set sampling rate (CT parameter in Audio InfoFrame)
BRAT	Digital Audio Timing	Set bit rate (MBR parameter in Audio InfoFrame)

Test Sequences

Control

Command	Description
SEQQ?	Get list of filenames of stored sequence files
SEQL	Load a sequence from a file
SEQA	Save sequence edit buffer contents to a specified filename

Command	Description
SEQU	Update hardware with current sequence editor contents
SEQK	Delete a saved sequence file
SEQP	Set default sequence path
SMOD	Set sequence mode
DNUM	Enable/display sequence step number display
NSTP?	Get number of sequence steps in the buffer

Edit

Command	Description
SEQN	Create a new sequence file
SEQB	Begin a sequence editing session
STEP	Select a sequence step
SDLY	Set sequence step delay
SEQE	End a sequence editing session
SEQS	Save a new sequence to filename specified by SEQN

Directories

Control

Command	Description
DIRQ?	Get list of directories
DIRL	Copy a directory from memory into directory edit buffer
DIRA	Save current contents of directory edit buffer to a file
DIRU	Install (use) currently loaded directory
DIRK	Delete a directory
DIRP	Set current directory path name

Edit

Command	Description
DIRN	Initialize directory edit buffer
DIRB	Begin a directory editing session
DIRE	End a directory editing session
DIRS	Save contents of directory edit buffer in memory
DIRT	Set directory type to be created
NAMF?	Get index number of file in directory edit buffer
NAMI	Move file to new index position
NAMK	Delete a file from directory edit buffer
NAMQ?	Get list of files in directory edit buffer
NAMY	Delete a file from index position in directory edit buffer

EDID and DDC

Control

Command	Description
DCPG	Enable/disable +5V power signal on output connector
DCPX	Get status of 5V Digital Data Channel (DDC) on output connector
DDCV?	Determine if generator hardware supports VESA DDC communications.
DIDQ	Get list of filenames of stored EDID files

Command	Description
DIDL	Load an EDID from a file
DIDA	Save an EDID to a specified filename
DIDU	Update hardware with current EDID contents
DIDK	Delete a saved EDID file
DIDP	Set default EDID path
EDA	Read/write EDID from/to device connected to HDMI output port
EDID?	Read EDID from connected device
I2CR?	Read EDID data using I2C bus
I2CW	Write EDID data using I2C bus
XDID	Set new EDID structure (DVI/HDMI Analyzer)
EDE	Set HDMI input port with contents of EDID buffer (DVI/HDMI Analyzer)
STRG	Enable/disable SCL low signal stretching (DVI/HDMI Analyzer)

Edit

Command	Description
DIDN	Create a new EDID file
DIDB	Begin an EDID editing session
XDID	Set new EDID structure (DVI/HDMI Analyzer)
DIDE	End an EDID editing session
DIDS	Save a new EDID to filename specified by DIDN

Special Sync Probe Pulse

Command	Description
PSHD	Set line delay (in pixels)
PSPG	Enable/disable probe pulse on special sync output
PSPM	Set lines in frame where probe pulse occurs
PSPP	Set probe pulse polarity
PSPW	Set pixel width
PSVD	Set vertical delay
PSVW	Set vertical width

Color Look-Up Table (LUT)

Command	Description
RGBW	Set RGB levels to within the current lookup table
SLUT	Set colorset for color lookup table

HDMI

Data Island Packet

Command	Description
XACR	Set Audio Clock Regeneration packet
XGDP	Set Generic Control packet
XGCP	Enable/disable Audio/Video Mute (AVMUTE) in general control packet
MUTE	Enable/disable Audio/Video Mute (AVMUTE) feature
DPTG	Set gated packet types
DPTR	Set frequency for General Control packet
DPGU	Update generator with current data island packet content

InfoFrame Packet

Command	Description
XGIF	Set Generic (Vendor-Specific) InfoFrame packet data
XAVI	Set Auxiliary Video Information (AVI) InfoFrame packet data

Command	Description
XSPD	Set Source Product Description InfoFrame packet data
XAUD	Set Audio InfoFrame packet data
XMPG	Set MPEG InfoFrame packet data
DVIC	Sets video identification code in AVI InfoFrame
IFTG	Set gated InfoFrame types
IFTR	Set frequency for InfoFrame types
IFGU	Update generator with current InfoFrame content

DVI/HDMI HDCP

Command	Description
HDCP? (OUT1:HDCP?, OUT2:HDCP?)	Set number of frames to run test on a specific HDMI output port

HDCP Compliance

Command	Description
CPTX:CPTR	Enables running of HDCP compliance tests through the command line.
CPTX:CPTU	Actually initiates the running of an HDCP compliance tests through the command line.
CPTX:CRIP	Indicates whether the HDCP authentication will use long or short reads during the authentication.
CPTX:DUTT	Specifies which type of device that you will run an HDCP compliance test on.
CPTX:GCTN?	Queries the list of HDCP compliance tests that can be run.
CPTX:OESS	Indicates where the encryption enable pulse is positioned in the vsync pulse during the 2C-04 test using the Encryption Status Tester device.
CPTX:RKSV	Specifies the maximum number of KSVs supported by the repeater device under test for an HDCP compliance test.
CPTX:ROOR	Specifies whether a repeater device under test outputs content to the downstream repeater that does not have any downstream devices connected.
CPTX:RPFT	Specifies if the repeater support HDMI 1.1 advanced cipher and enhanced link verification.
CPTX:SDCZ	Specifies whether the 880 uses a downstream device count of 0 or the downstream device count as specified by the SKSV command.
CPTX:SOOR	Specifies the number of downstream devices connected to a repeater that the source device under test can support.
CPTX:SRAC	Specifies the number of times the source device under test tries to authenticate before proceeding to the third part of authentication.

DVI/HDMI Signal Analyzer

Command	Description
TMAU	Launch signal timing analysis measurement
TMAX:RPTG	Enable/disable HTML report of signal timing analysis measurement results
TMAX:SCAN	Get signal timing analysis measurement value
PNSA	Set how often pseudo-random noise pixels are calculated
PNSM	Set pseudo-random noise seed and run-length values
PNSG	Enable/disable pseudo-random noise output
PNSP	Set pseudo-random noise sequence type
PNGU	Update generator with pseudo-random noise generator test
PNAU	Update generator with pseudo-random noise generator test and measure all required parameters
GCET?	Get number of RGB and total pixels errors
GFED?	Get details on first error encountered
GNPT?	Get number of measured pixels after pseudo noise measurement
GPER?	Get pixel error rate after pseudo noise measurement
HPPW	Set assertion pulse width of analyzer's hot plug pulse
PDAX:FRMS	Set number of frames to analyze in pixel data analysis test
PDAX:MXER	Set maximum number of detailed errors to record in pixel data analysis test
PDAX:RPTG	Enable/disable HTML report of pixel data analysis test results
PDAX:REFG	Enable/disable automatic reference frame capturing
PDAX:CAPF	Capture a reference frame for pixel data analysis test
PDAX:ERRQ	Get one or more recorded detailed error records
PDAX:NERR	Get number of errors during a pixel data analysis test
PDAX:PASS	Enble or disable video pass through
PDAU	Run pixel data analysis test
GPEL?	Get pixel color components

HDMI LipSync Generator/Analyzer

Command	Description
LSAX:LSGM	Enable/disable lipsync analyzer testing of source device
LSAX:LSGU	Update hardware with lipsync analyzer settings
LSAX:PLAT?	Get name of first received data stream (audio or video)
LSAX:RPTG	Enable/disable HTML report of lipsync analyzer measurement results
LSAX:TLAT?	Get number of seconds delay between received audio and video
LSGX:LSGM	Enable/disable lipsync testing of display (sink) device
LSGX:LSGU	Update hardware with lipsync generator settings
LSGX:PLAT	Set precedence of data streams from lipsync image
LSGX:TLAT	Set latency (delay) between audio and video data streams in lipsync image

Commands by name

*CLS

Clear Status

Class	GPIB
Description	Clears the Event Status Register, the Status Byte and the output buffer.
Command syntax	*CLS
Related commands	*ESR?, *STB

*DDT

Delay Device Trigger

Class — Trigger

Description — Specifies a command or command string to be executed when the generator is “triggered” with the *TRG command. Only one *DDT command can be pending at a time. The command or query arguments must be enclosed in quotes.

Command syntax — *DDT “*command_1*; *command_2* ... *command_n*”

Example

```
*DDT "imgl flat; imgu"
*TRG   // to invoke the command line in quotes from the *DDT command
```

Related commands — *TRG

*ESE

Event Status Enable

Class GPIB

Description Sets the Event Status Enable register to the given mask value. The bits in the Event Status Enable register function as enable bits for each corresponding bit in the Event Status register. That is, when a bit in the Event Status register goes high, and the corresponding bit in the Event Status Enable register is a 1, it is enabled and will cause the ESB bit in the Status Byte register to go high.

The *ESE? query returns the current value of the Event Status Enable register.

Command syntax *ESE *mask*

mask
0 - 255

Example *ESE 8

Query syntax *ESE?

Query response *mask* NL

Where *mask* is in integer NR1 form.

See also: *CLS, *ESR?

*ESR?

Event Status Register

Class GPIB

Description Returns the current value of the Event Status register. After this command is executed, the Event Status register is cleared. This is the only way of clearing any bit in the Event Status register except by the *CLS command.

Query syntax *ESR?

Returns *registerValue* NL

Where *registerValue* is in integer NR1 form.

Related commands *CLS, *ESE

*IDN?

IDeNtification

Class GPIB

Description Returns an equipment identification string formatted per IEEE-488.2 standards.

Query syntax *IDN?

Returns *Company*,*Model*,*SerialNumber*,*FirmwareVersion*

Company
Always QuantumData.

Model
Product model description.

SerialNumber
Serial number of nonvolatile SRAM module (Dallas chip) in generator.

FirmwareVersion
Version number of currently installed firmware.

Example
```
R:\*idn?
QuantumData,802BT-DVI-AN,7514191,7.38380000
```

*OPC

OPeration Complete

Class GPIB

Description Causes the 882 to set the OPC bit in the Event Status register when all operations have been completed. Since there are no overlapping commands, the *OPC command will set the OPC bit immediately when executed.

The *OPC query will put a 1 in the output buffer when all operations are complete.

Command syntax *OPC

Query syntax *OPC?

Returns NL

*RST

ReSet

Class GPIB

Description Performs a device reset. This places the 882 into a known condition. These conditions are:

- IEEE-488 address set to 15
- Status Byte cleared
- Input queue empty
- Output queue empty

Command syntax *RST

Related commands *CLS

*SRE

Service Request Enable

Class GPIB

Description Sets the Service Request Enable register to the mask value given. The bits in the Service Request Enable register function as enable bits for each corresponding bit in the Status Byte register to enable a condition to request service from the system controller. That is, when a bit in the Status Byte register goes true, and the corresponding bit in the Service Request Enable register is also true, the 882 will request service through the GPIB. The *SRE query returns the current value of the Service Request Enable register.

Command syntax *SRE *mask*

mask
0 - 255

Example *SRE 16

Query syntax *SRE?

Returns *mask* NL

Where *mask* is in integer NR1 form.

Related commands *STB, *ESE

*STB

STatus Byte

Class GPIB

Description Returns the current value of the Status Byte register. The value stored in the Status Byte register is not affected by reading it.

Query syntax *STB?

Returns *statusByte*<NL>

Where *statusByte* is in integer NR1 form.

Related commands *SRE, *ESR?, *CLS

*TRG

TRiGger

Class GPIB port control

Description Triggers the generator programmatically. The *TRG command is used to trigger a command or command string entered with the *TRG command.

Command syntax *TRG

Example
```
*DDT "imgl flat;imgu"
*TRG   // Invoke the command line in quotes from the *DDT command
```

Related commands *DDT

*TST

self TeST

Class GPIB port control

Definition: Causes the 882 to perform a self-test and report the results in a response message. If the self-test fails, an ASCII "1" is placed in the output buffer; otherwise, an ASCII "0" is placed in the output buffer.

Query syntax *TST?

Returns *result*<NL>

Where *result* is in integer NR1 form.

*WAI

WAIt for completion suffix

Class GPIB port control

Description Causes the generator to wait until all processes have been completed before sending the prompt. Normally, the generator returns a prompt immediately after either an FMTU, IMGU, ALLU, BOOT, INIT, or SCAL command is received, even before these commands have finished executing. If the system controlling the generator must know when a command has finished executing, use a semicolon to append the suffix … ;*WAI. .

Command syntax *command*; *WAI

command
FMTU, IMGU, ALLU, BOOT, INIT, or SCAL

Example
```
FMTL vga_m3     // Load a format from memory to buffer
IMGL SMPTE133   // Load the SMPTE RP-133 image to buffer
ALLU; *WAI      // Update hardware to current buffer contents and delay
                // prompt until all done
```

ADOT

draw A single pixel DOT

Class
Custom image primitive

Description
Draws a single pixel dot. A dot is the smallest graphic element that can be drawn. It uses three parameters: the color and the X and Y coordinates.

Command syntax
ADOT *color x y*

color
available colors

x
positive integer number

y
positive integer number

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ADOT White 200 300  // Draw white dot at X = 200 Y = 300
```

ALLE

end ALL Editor sessions

Class	Directory, format, image and sequence editor control
Description	Same as entering all of the DIRE, FMTE, IMGE and SEQE commands.
Command syntax	ALLE

ALLU

ALL Use

Class — System control

Description — Checks the current contents of the format buffer for errors. If no errors are found, it reconfigures the signal generating hardware in accordance with the contents. Next, the current test image is re-rendered using the latest system and format parameter data.

Command syntax — ALLU

Other required commands — This command updates the generator after using the FMTL, IMGL and SEQL commands to load new files from memory. This command also can be used to see the results of work when using commands to edit formats or custom images.

Example

```
FMTL vga_m3  // Load a format from memory to buffer
ALLU         // Update hardware to current buffer contents
```

ANIM?

current test image has ANIMation

Class — Image editor control

Description — Returns a flag indicating if the image currently being displayed is animated.

Query syntax — ANIM? *imageName*

Query response — 0 = Not animated (static image) or the image was not found.

1 = Animated.

Example

```
ANIM? cubes    // to determine if the "cubes" image has animation
1              // response indicates that "cubes" is an animated image
```

ANTI

ANTI-alias

Class	Image drawing primitives
Description	Causes other primitives to be drawn using anti-aliasing on diagonal edges when appearing anywhere in a custom image. This command affects only television formats on 801GX generators. It causes the leading and trailing edges of rectangles to have controlled rise and fall times.
Command syntax	ANTI
Other required commands	The IMGU or ALLU command must be used to redraw the custom image using anti-aliased primitives.

ARAT

Audio sampling RATe

Class — Format parameter setting - Audio signal

Description — Sets the sampling rate of the audio stream output from the generator. This sets the CT parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B, table 20).

Command syntax — ARAT *rate*

rate

- 192.0E3
- 176.4E3
- 96.0E3
- 88.2E3
- 48.0E3 (default)
- 44.1E3
- 32.0E3

Example

```
ARAT 48.0E3
ALLU
```

Related commands — XAUD (SF parameter)

ASBG

Analog Sync on Blue Gating

Class
Format parameter setting - Analog video signal

Description
Enables and disables adding composite sync to the blue analog video outputs when analog sync is selected (see SSST command) and an analog video signal is being generated (see AVST command). The ASBG? query returns the current setting of ASBG.

See the ASSG command description for information on simultaneously controlling red, green and blue sync gating.

Command syntax
ASBG *mode*

mode
0 = OFF

1 = ON

Query syntax
ASBG?

Query response
mode

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ASBG 1  // Enable composite sync on blue in buffer
FMTU    // Update hardware to current buffer contents
```

ASCT

Analog Sync Composite Type

Class — Format parameter setting - Analog video signal

Description — Sets the kind of composite sync added to the analog video outputs when analog sync is enabled (see SSST command) and an analog video signal is being generated (see AVST command). The ASCT? query returns the current setting of ASCT. A setting of zero (0) indicates that the ACS sync selection cannot be activated by the operator.

Command syntax — ASCT *type*

type

0 = none

1 = American HDTV ORed

2 = American ORed

3 = American w/serr

4 = American w/serr & eq

5 = European HDTV ORed

6 = European ORed

7 = European w/serr

8 = European w/serr & eq

9 = American HDTV w/serr

10 = American HDTV w/serr & eq

11 = European HDTV w/serr

12 = European HDTV w/serr & eq

13 = Japanese HDTV ORed

14 = Japanese HDTV w/serr

15 = Japanese HDTV w/serr & eq

Query syntax — ASCT?

Query response — *type*

Other required commands

The SSST mode must be set to 4, 5, 6, or 7 and the AVST type must be set to 1, 2 or 5 in order for the ASCT setting to have any affect on the generator's hardware outputs. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ASCT 2  // Enable Amer ORed comp sync in buffer
SSST 4  // Enable ACS
AVST 2  // Select analog RGB as video type
FMTU    // Update hardware to current buffer contents
```

ASGG

Analog Sync on Green Gating

Class
Format parameter

Description
Enables and disables adding composite sync to the green analog video outputs when analog sync is selected (see SSST command) and an analog video signal is being generated (see AVST command). The ASGG? query returns the current setting of ASGG.

See the ASSG command description for information on simultaneously controlling red, green and green sync gating.

Command syntax
ASGG *mode*

mode
0 = OFF

1 = ON

Query syntax
ASGG?

Query response
mode

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ASGG 1  // Enable composite sync on green in buffer
FMTU    // Update hardware to current buffer contents
```

ASRG

Analog Sync on Red Gating

Class
Format parameter

Description
Enables and disables adding composite sync to the red analog video outputs when analog sync is selected (see SSST command) and an analog video signal is being generated (see AVST command). The ASRG? query returns the current setting of ASRG.

See the ASSG command description for information on simultaneously controlling red, green and red sync gating.

Command syntax
ASRG *mode*

mode
0 = OFF

1 = ON

Query syntax
ASRG?

Query response
mode

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ASRG 1  // Enable composite sync on red in buffer
FMTU    // Update hardware to current buffer contents
```

ASSC

Analog Sync Swing Calibration factor

Class — System calibration settings

Description — Sets the analog video calibration (or scaling) factor that's used to adjust the level set by ASSS. Issuing the command with a single factor sets all three analog video channels to the same value. Issuing the command with three factors sets each of the analog video channels to each of the given values. The actual peak-to-peak swing of the analog composite sync signals at the output connectors equals the product of ASSS multiplied by ASSC. The ASSC? query returns the current settings of ASSC. The default factory setting is 1.000 for this parameter.

Note: *The ASSC parameter is a system level parameter that affects the analog video swing of all formats that are recalled. The ASSC value is retained when the generator is powered down and back up again. Query the current setting of ASSC if you are experiencing problems with low or missing analog composite sync levels. Reinitializing the generator's memory restores the setting to factory default values of 1.000.*

Command syntax — ASSC *red_factor, green_factor, blue_factor*

or

ASSC *common_factor*

factor

min = 0.000 (floating point accepted)

max = 1.000 (floating point accepted)

Query syntax — ASSC?

Query response — *red_factor, green_factor, blue_factor*

Example

```
ASSC .995 .998 1.00  // Reduce red and green sync levels
FMTU                 // Update hardware to current buffer contents
```

ASSG

Analog Sync Signal Gate

Class
Format parameter setting - Analog video signal

Description
Enables and disables adding composite sync to all three analog video outputs when analog sync is selected (see SSST command) and an analog video signal is being generated (see AVST command). This command can take the place of sending all three of the individual ASRG, ASGG, ASBG commands. The ASSG? query returns the current settings of the ASSG?

Command syntax
ASSG *red_mode*, *green_mode*, *blue_mode*

or

ASSG *common_mode*

mode

0 = OFF

1 = ON

(0, 0, 0 or 0, 1, 0 only choices on 801GC-ISA)

Query syntax
ASSG?

Query response
red_mode, *green_mode*, *blue_mode*

Other required commands
The SSST type must be 4, 5, 6 or 7 to output analog sync. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ASSG 0,1,0  // Enable composite sync on green in buffer
FMTU        // Update hardware to current buffer contents
```

ASSS

Analog Sync Signal Swing

Class
Format parameter setting - Analog video signal

Description
Sets the maximum peak-to-peak swing for any composite sync that is added to any of the three analog video channels. The actual peak-to-peak swing of the analog sync signals at the output connectors equals the product of ASSS multiplied by ASSC. The ASSS? query returns the current setting of ASSS.

Command syntax
ASSS *level*

level

min = 0.000 volts (floating point accepted)

max = 0.500 volts (floating point accepted)

Query syntax
ASSS?

Query response
level

Other required commands
One or more ASSG modes must be set to ON and the SSST type must be 4, 5, 6 or 7 to output analog sync. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
ASSS 0.286  // Set sync swing to 286 mV in buffer
FMTU        // Update hardware to current buffer contents
```

AVCM

Analog Video Calibration Method

Class — System calibration setting

Description — Determines how the generator tests and calibrates its analog video outputs. The AVCM? query returns the current setting of AVCM.

Command syntax — AVCM *type*

type

0 = Interpolate

1 = Measure Interpolate

2 = Measure Set Absolute

3 = Test Levels

Query syntax — AVCM?

Query response — *type*

Example

```
AVCM 1  // Select Measure Interpolate
        // type of self cal
```

AVCO

Analog Video COnfiguration

Class — Format parameter setting - Analog video signal

Description — Sets the mapping of the analog video colors to the video output connections. The AVCO? query returns the current setting of AVCO.

Command syntax — AVCO *type*

type

0 = RGB - R to R, G to G, B to B (Normal)

1 = RBG - R to R, B to G, G to B

2 = GRB - G to R, R to G, B to B

3 = GBR - G to R, B to G, R to B

4 = BRG - B to R, R to G, G to B

5 = BGR - B to R, G to G, R to B

Query syntax — AVCO?

Query response — *type*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
AVCO 5  // Output blue on red chan and red on blue chan
FMTU    // Update hardware to current buffer contents
```

AVCS

Analog Video Color subcarrier Selection

Class — Format parameter setting - Analog video signal

Description — Sets the color subcarrier type used for the television outputs on generator models that have television outputs available. The AVCS? query returns the current setting of AVCS.

Command syntax — AVCS *type*

type

0 = No subcarrier

1 = NTSC-M, 3.579545 MHz (American)

2 = NTSC-44, 4.43361875 MHz (conversion format without phase alternation)

3 = PAL, 4.43361875 MHz (with phase alternation)

4 = PAL-Nc, 3.58205625 MHz (Argentina)

5 = PAL-M, 3.57561149 MHz

6 = PAL-60, 3.57561149 MHz

Query syntax — AVCS?

Query response — *type*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
AVCS 1  // Select standard American NTSC encoding
FMTU    // Update hardware to current buffer contents
```

AVPG

Analog Video Pedestal Gate

Class
Format parameter setting - Analog video signal

Description
Enables and disables the analog video set-up pedestal. The AVPG? query returns the current setting of AVPG.

Command syntax
AVPG *mode*

mode
0 = OFF

1 = ON

Query syntax
AVPG?

Query response
mode

Other required commands
Analog video must be enabled with the AVST command in order to output an analog video signal. The pedestal level is set with the AVPS command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
AVPG 1      // Enable use of a black level pedestal
AVPS 7.5    // Set pedestal level to 7.5 IRE
FMTU        // Update hardware to current buffer contents
```

AVPS

Analog Video Pedestal Swing

Class
Format parameter setting - Analog video signal

Description
Sets a black pedestal level between the blanking level (0.0 I.R.E.) and the peak video level (100.0 I.R.E.). The AVPS? query returns the current setting of AVPS.

Command syntax
AVPS *level*

level
min = 0.0 I.R.E.

max = 100.0 I.R.E.

Query syntax
AVPS?

Query response
level

Other required commands
AVPG must be set to ON to enable the use of the pedestal. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
AVPG 1     // Enable use of a black level pedestal
AVPS 7.5   // Set pedestal level to 7.5 IRE
FMTU       // Update hardware to current buffer contents
```

AVSC

Analog Video Swing Calibration factor

Class
System parameter setting

Description
Sets the analog video calibration (or scaling) factor that is used to adjust the level set by AVSS. Issuing the command with a single factor sets all three analog video channels to the same value. Issuing the command with three factors sets each of the analog video channels to each of the given values. The actual peak-to-peak swing of the analog video signals at the output connectors equals the product of AVSS multiplied by AVSC. The AVSC? query returns the current setting of AVSC for each channel. The default factory settings are 1.000 for AVSC.

Note: *The AVSC parameter is a system level parameter that affects the analog video swing of all Formats that are recalled. The AVSC value is retained when the generator is powered down and back up again. Query the current value of the AVSC if you are experiencing low or missing analog video levels.*

Command syntax
AVSC *red_factor, green_factor, blue_factor*

or

AVSC *common_factor*

common_factor
min = 0.000 (floating point accepted)

max = 1.000 (floating point accepted)

Query syntax
AVSC?

Query response
red_factor, green_factor, blue_factor

Other required commands
The FMTU command instructs the generator to use the new setting on the current format.

Example

```
AVSC 1.000 .995 .998 // Reduce green and blue levels
FMTU                 // Apply new factors to current format
```

AVSS

Analog Video Signal Swing

Class
Format parameter setting - Analog video signal

Description
Sets the maximum peak-to-peak swing for all three analog video channels. The actual peak-to-peak swing of the analog video signals at the output equals the product of AVSS multiplied by AVSC. The AVSS? query returns the current setting of AVSS.

Command syntax
AVSS *level*

level
0.000 to 1.000 volts (floating point accepted)

Query syntax
AVSS?

Query response
level

Other required commands
Analog video must be enabled with the AVST command in order to output an analog video signal. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example 1
This example uses the AVSS command changes the output level of the NTSC format from 714mV to 500mV.

```
FMTL NTSC
FMTB
AVSS 0.5
FMTE
FMTA NTSC_1
```

Example 2
This example enables analog video, and sets the video swing.

```
AVST 2          // Select RGB component color video in buffer
AVSS 0.714      // Set to 714 mV in buffer
FMTU            // Update hardware to current buffer contents
```

Example 3
This example changes the sync level from 286mV to 200mV, and sets the video output level at 500mV.

```
FMTL NTSC
FMTB
ASSS 0.2
AVSS 0.7
FMTE
FMTA NTSC_1
```

AVST

Analog Video Signal Type

Class — Format parameter setting - Analog video signal

Description — Establishes the type of signal that appears on the analog video outputs of the generator. The AVST? query returns the current setting of AVST.

Command syntax — AVST *type*

type

0 = none

1 = Analog Y (grayscale)

2 = Analog RGB (color)

3 = CVBS or S-Video grayscale

4 = CVBS or S-Video color

5 = Analog YPrPb (old SMPTE 240M HDTV)

6 = Analog YPrPb ITU BT.601 (ANSI/SMPTE 170M TV)

7 = Analog YPrPb SMPTE RP177 HDTV

8 = YPrPb ITU-R BT.709 HDTV

Query syntax — AVST?

Query response — *type*

Other required commands — DVST must be set to zero when analog video is used. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
DVST 0  // Disable digital video
AVST 2  // Select RGB component color video
ALLU    // Update hardware and redraw test image
```

BALG

dc BALancing Gate

Class — Format parameter setting - Digital video signal

Description — Enables and disables adding DC balancing to the Open LVDI digital outputs on generators that support LVDI outputs. FPD-Link compatible displays use unbalanced (BALG 0), while OpenLDI displays use balanced (BALG 1).

The BALG? query returns the current setting of BALG.

Command syntax — BALG *mode*

mode

0 = OFF

1 = ON

Query syntax — BALG?

Query response — *mode*

Other required commands — FMTU or ALLU

BLUG

BLUe Gate

Class	Video Gate
Description	Toggles the blue video signal gate.
Command syntax	BLUG *mode* *mode* 0 disable 1 enable
Query syntax	BLUG?
Query response	0 or 1
Other required commands	ALLU to invoke the command.
Related commands	GRNG, REDG
Example	`BLUG 0; ALLU  // disable blue video component`

BOIT

BOot and IniTialize

Class	System control
Description	Initializes the generator without going through a self-calibration.
Command syntax	BOIT

BOOT

warm BOOT

Class System control

Description Causes the generator to go through its standard power-up procedure. Self-calibration is not performed. The procedure checks all RAM storage locations for corrupt data. This command is equivalent to turning the generator off and then on.

Command syntax BOOT

BRAT

Bit RATe

Class — Format parameter setting - Digital audio signal

Description — Sets the bit rate (in Hz) for an external compressed audio source. This sets the MBR parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B).

The BRAT? query returns the current compressed digital audio bit rate

Command syntax — BRAT *rate*

rate

0.0 (audio is not compressed)

8000, 16000, 24000 (or higher multiple of 8,000)

Query syntax — BRAT?

Example

```
BRAT 32000
IFGU
```

Related commands — XAUD (MBR parameter)

CALF

analog video CALibration Factors

Class System calibration settings

Description Sets the analog output calibration factors to values other than those set by the generator's own self-calibration function. Each channel is calibrated using two independent zero calibration points, and two independent slope calibration points. Interpolation equations for the different video types are used to set the caldac values that controls the output sync and voltage levels to the correct values.

TV calibration uses two factors for NTSC output, and two factors for PAL output.

Note: *Sending bad calibration factors to the generator via the CALF command can hang the generator. If the generator hangs it will have to be reinitialized.*

Command syntax CALF *zero500R*, *zero50R*, *slope1500R*, *slope1000R*, *zero500G*, *zero50G*, *slope1500G*, *slope1000R*, *zero500B*, *zero50B*, *slope1500B*, *slope1000B*, *ntsc714*, *pal700*, *ntsc_blank*, *pal_blank*

zero500R
Red calibration factor from 0 (most negative) to 4095 (least negative) at -1.0V.

zero50R
Red calibration factor from 0 (most negative) to 4095 (least negative) at -100mV.

slope1500R
Red calibration factor from 0 (maximum swing) to 4095 (minimum swing) at 2.0V.

slope1000R
Red calibration factor from 0 (maximum swing) to 4095 (minimum swing) at 1.4V.

zero500G, zero50G, slope1500G, slope1000R
Green calibration factors.

zero500B, zero50B, slope1500B, slope1000B
Blue calibration factors.

ntsc714
Factor from 0 (maximum swing) to 4095 (minimum swing) for NTSC output level at 714mV. The *ntsc714* and *ntsc_blank* values are interrelated.

pal700
Factor from 0 (maximum swing) to 4095 (minimum swing) for PAL output level at 700mV.

ntsc_blank
Factor from 0 (least negative) to 4095 (most negative) used to set the zero level of the NTSC output at 0.0 IRE.

pal_blank

Factor from 0 (least negative) to 4095 (most negative) used to set the zero level of the PAL output at 0.0 IRE.

Query syntax CALF?

Related commands The AVSC command matches the levels for the three analog video channels. The ALLU command updates the signal generating hardware to the new settings and redraws the test image.

Example

```
CALF 1090, 2590, 1992, 3223, 1149, 2634, 2059, 3278, 1001, 2506, 1993,
3221, 781, 780, 3387, 3513            // Set new factors
ALLU                                  // Use new factors
```

CAT?

Class Tools

Description Lists the contents of a file.

Query syntax CAT? file

file.ext
any valid text file name

Query response Contents of text file

Related commands None

Example
```
CAT?
<?xml version="1.0" encoding="UTF-8" ?>
<DATAOBJ>
  <HEADER TYPE="LIB" VERSION="1.0" >
    <DISPNAME>FormatVESAClassQD</DISPNAME>
  </HEADER>
  <DATA>
    <TYPE>SOURCE</TYPE>
    <NAME>/tffs0/Library/Formats/DMT0659.xml</NAME>
    <NAME>/tffs0/Library/Formats/DMT0660.xml</NAME>
    <NAME>/tffs0/Library/Formats/DMT0672.xml</NAME>
    .
    .
    .
    <NAME>/tffs0/Library/Formats/DMT2060.xml</NAME>
    <NAME>/tffs0/Library/Formats/DMT2075.xml</NAME>
    <NAME>/tffs0/Library/Formats/SMT0660.xml</NAME>
    <NAME>/tffs0/Library/Formats/SMT0660D.xml</NAME>
    <NAME>/tffs0/Library/Formats/SMT0760H.xml</NAME>
    <NAME>/tffs0/Library/Formats/SMT0760V.xml</NAME>
  </DATA></DATAOBJ>
```

CAUD

Compressed AUDio output

Class Audio

Description Enables you to play compressed audio out the 882E HDMI output. You can use this command with any pattern in the generator.

Command syntax CAUD *clip_index*

clip_index

an index representing the audio clip:

1:DTS, 5.1, 48000.00 [dts-48kHz-1509kbps-51ch.wav.pcm]

2:DTS(ES), 6.1, 48000.00 [DTES-ES-48kHz-1509kbps-61ch.wav.pcm]

3:DTS(HDHRA), 7.1, 192000.00 [dtshdhra-48kHz-5376kbps-71ch.wav.pcm]

4:DTS(HDHRA), 5.1, 192000.00 [dtshdhra-48kHz-3840kbps-51ch.wav.pcm]

5:DTS(HDHRA), 7.1, 192000.00 [dtshdhra-96kHz-5760kbps-71ch.wav.pcm]

6:DTS(HDMA), 5.1, 192000.00 [dtshdma-48kHz-VBR-51ch-HDMI_HBR.ba.pcm]

7:DTS(HDMA), 7.1, 192000.00 [dtshdma-48kHz-VBR-71ch-HDMI_HBR.ba.pcm]

8:DOLBY(AC3), 2.0, 48000.00 [2khz2ch-0dB_ac3.pcm]

9:DOLBY(EAC3), 2.0, 192000.00 [1khz2ch-20dB_ec3.pcm]

10:DOLBY(EAC3), 5.1, 192000.00 [1khz51ch-20dB_ec3.pcm]

11:DOLBY(EAC3), 7.1, 192000.00 [1khz71ch-1frame_ec3.pcm]

12:DOLBY(TRUEHD), 7.1, 192000.00 [1khz71ch-20dB_mlp.pcm]

13:DOLBY(TRUEHD), 2.0, 192000.00 [nxt2ch2s.mlp.pcm]

Query syntax CAUD?

list

a list of compressed audio formats is shown

Example 1

```
CAUD? // Sends an AC3 clip named "AC3Clip1" out the HDMI output
1:DTS, 5.1, 48000.00 [dts-48kHz-1509kbps-51ch.wav.pcm]
.
.
.
8:DOLBY(AC3), 2.0, 48000.00 [2khz2ch-0dB_ac3.pcm]
.
.
.
13:DOLBY(TRUEHD), 2.0, 192000.00 [nxt2ch2s.mlp.pcm]
```

Example 2

```
CAUD 8  // Sends a 2 channel Dolby AC3 clip with 192kHz sampling rate
           at 0dB out the HDMI output.
```

CENT

draw video CENTering markers

Class
Custom image primitive

Description
Draws a small cross in the center of active video. If the format has an even number of active pixels, the vertical line is 2 pixels thick. The horizontal line is 2 pixels thick if the format has an even number of active lines. The primitive uses a single parameter, the color of the cross.

Command syntax
CENT *color*

color
available colors

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
CENT red  // Draw a small red cross in center of active video
ALLU      // Update hardware to current buffer contents
```

CPTX:CPTR

Specifies an HDCP compliance test to run

Class
HDCP Compliance

Description
Enables running of HDCP compliance tests through the command line. Tests can be run either individually or one at a time. This command is used for running HDCP compliance test either through the HDMI interface or the DisplayPort interface. The command applies only to the active interface.

Command syntax
CPTX:CPTR *test*

test
the specific test index you wish to run.
For HDMI 0 through 46 where 46 will run all tests.
For DisplayPort 0 through 48 where 48 will run all tests

Other required commands
The CPTX:CPTU command initiates the running of the test.

Query syntax
CPTX:CPTR?

Query response
1 through 46 for HDMI or 1 through 48 for DisplayPort

Example 1
```
CPTX:CPTR 1   // Sets up the generator to run the 1A-01 test
CPTX:CPTU     // Initiates the test specified with the CPRT command
```

Example 2
```
CPTX:CPTR 46  // Sets up the generator to run all HDCP test
CPTX:CPTU     // Initiates the test specified with the CPRT command
```

Example 3
```
CPTX:CPTR?    // Queries for the current test specified
16            // Indicates that test number 16 2C-01 is specified
```

CPTX:CPTU

Initiates the running of an HDCP compliance test

Class HDCP Compliance

Description Actually initiates the running of an HDCP compliance tests through the command line. This command is used with the CPTX:CPTR command which specifies which test should be run.

Command syntax CPTX:CPTU

Other required commands The CPTX:CPTR command specifies which HDCP test to run.

Example 1

```
CPTX:CPTR 1   // Sets up the generator to run the 1A-01 test
CPTX:CPTU     // Initiates the test specified with the CPRT command
```

Example 2

```
CPTX:CPTR 46  // Sets up the generator to run all HDCP test
CPTX:CPTU     // Initiates the test specified with the CPRT command
```

CPTX:CRIP

Indicates short or long read for HDCP authentication

Class HDCP Compliance

Description Indicates whether the HDCP authentication will use long or short reads during the authentication. This is one of the Product Capabilities Parameters (PCP).

Command syntax CPTX:CRIP *read_type*

read_type

0 = short
1 = long

Example 1

```
CPTX:CRIP 1   // Causes the test equipment to use long reads during
                 authentication
```

CPTX:DUTT

Specifies the device type for an HDCP compliance test

Class HDCP Compliance

Description Specifies which type of device that you will run an HDCP compliance test on. This is one of the Product Capabilities Parameters (PCP).

Command syntax CPTX:DUTT *device*

device

0 = Sink
1 = Source
2 = not used
3 = Repeater A/B
4 = Repeater 3C

Query syntax CPTX:DUTT?

Query response 0 through 4

Example
```
CPTX:DUTT 1   // Specifies that an HDCP compliance test on a Source
                 will be run
```

CPTX:GCTN?

Queries the list of HDCP compliance tests

Class HDCP Compliance

Description Queries the list of HDCP compliance tests that can be run.

Query syntax CPTX:GCTN?

1 through 45 for HDMI
1 through 47 for DisplayPort

Example

```
CPTX:GCTN?   // To list out the compliance tests
1A-01 = 1
1A-02 = 2
1A-03 = 3
1A-04 = 4
1A-05 = 5
1A-06 = 6
1A-07 = 7
1A-08 = 8
1A-09 = 9
1B-01 = 10
1B-02 = 11
1B-03 = 12
1B-04 = 13
1B-05 = 14
1B-06 = 15
2C-01 = 16
2C-02 = 17
2C-03 = 18
2C-04 = 19
3A-01 = 20
3A-02 = 21
3A-03 = 22
3A-04 = 23
3A-05 = 24
3B-01 = 25
3B-02 = 26
3B-03 = 27
3B-04 = 28
3B-05 = 29
3C-I-01 = 30
...
3C-II-09 = 45
```

CPTX:OESS

Specifies where the Encryption enable pulse is positioned

Class HDCP Compliance

Description Indicates where the encryption enable pulse is positioned in the vsync pulse during the 2C-04 test using the Encryption Status Tester device.

Command syntax CPTX:OESS *pulse_position*

pulse position

1 = encryption enable pulse is position at the beginning of the vsync pulse
4 = encryption enable pulse is position at the middle of the vsync pulse
5 = encryption enable pulse is position at the end of the vsync pulse

Example 1

```
CPTX:OESS 1   // Causes the test equipment to use long reads during
                 authentication
```

CPTX:RKSV

Specifies number of KSVs supported by device

Class HDCP Compliance

Description Specifies the maximum number of KSVs supported by the repeater device under test for an HDCP compliance test. This is one of the Product Capabilities Parameters (PCP).

Command syntax CPTX:RKSV r*ksv*

rksv

1 through 127

Query syntax CPTX:RKSV?

Query response 1 through 127

Example 1

```
CPTX:RKSV 16  // Specifies that the repeater supports 16 downstream
                 devices connected.
```

Example 2

```
CPTX:RKSV?    // Queries to determine what the RSKV parameter is
                 currently set to.
1             // Indicates that the repeater only supports 1 downstream
                 device.
```

CPTX:ROOR

Specifies number of KSVs supported by device

Class HDCP Compliance

Description Specifies whether a repeater device under test outputs content to the downstream repeater that does not have any downstream devices connected. This is one of the Product Capabilities Parameters (PCP).

```
1 = yes; 0 = no.
```

Command syntax CPTX:ROOR *roor*

roor

0 = No the repeater does not output conent to a repeater that does not have downstream devices connected
1 = Yes the repeater does output conent to a repeater that does not have downstream devices connected

Query syntax CPTX:ROOR?

Query response 0 or 1

Example 1
```
CPTX:ROOR 0   // Specifies that the repeater does not output content to
                 a downstream repeater
```

Example 2
```
CPTX:ROOR?    // Queries to determine if the repeater device outputs
                 content to downstream repeater.
```

CPTX:RPFT

Specifies number of KSVs supported by device

Class HDCP Compliance

Description Specifies if the repeater support HDMI 1.1 advanced cipher and enhanced link verification. This is one of the Product Capabilities Parameters (PCP).

Command syntax CPTX:RPFT *rpft*

rpft

0 = No
1 = Yes

Query syntax CPTX:RPFT?

Query response 0 or 1

Example 1
```
CPTX:RPFT 0  // Specifies that the repeater supports HDMI 1.1 advanced
                cipher features.
```

Example 2
```
CPTX:RPFT?   // Queries to determine what the RPFT parameter is
                currently set to.
1            // Indicates that the repeater supports advanced cipher
```

CPTX:SDCZ

Specifies how generator determines downstream device count

Class HDCP Compliance

Description Specifies whether the 880 uses a downstream device count of 0 or the downstream device count as specified by the SKSV command. This command only applies to the 1B-01 test and the 3B-01 test when testing HDMI HDCP compliance. This is one of the Product Capabilities Parameters (PCP).

Command syntax CPTX:SDCZ *device_count*

device_count

0 = no downstream devices
1 = uses the valued specified by the SKSV parameter

Query syntax CPTX:SDCZ?

Query response 0 or 1

Example 1

```
CPTX:SDCZ 0  // Specifies that there are no downstream devices connected
                for the 1B-01 test and the 3B-01 test.
```

Example 2

```
CPTX:SDCZ?    // Queries how to determine the number of downstream
                 devices.
1             // Indicates that the test will be run using the number
                 of downstream devices specified with the SKSV parameter.
```

CPTX:SOOR

Specifies number of downstream devices SOuRce supports

Class HDCP Compliance

Description Specifies the number of downstream devices connected to a repeater that the source device under test can support. This is one of the Product Capabilities Parameters (PCP) for testing source HDMI devices when a repeater is connected.

Command syntax CPTX:SOOR *devices*

devices

0 = no downstream devices
1 = uses the valued specified by the SKSV parameter

Query syntax CPTX:SOOR?

Query response 0 or 1

Example 1
```
CPTX:SOOR 0   // Specifies that there are no downstream devices connected
                 for the 1B-01 test and the 3B-01 test.
```

Example 2
```
CPTX:SOOR?    // Queries how to determine the number of downstream
                 devices.
1             // Indicates that the test will be run using the number
                 of downstream devices specified with the SKSV parameter.
```

CPTX:SRAC

SouRce identification Count

Class HDCP Compliance

Description Specifies the number of times the source device under test tries to authenticate before proceeding to the third part of authentication. This is one of the Product Capabilities Parameters (PCP) for testing source HDMI devices when a repeater is connected.

Command syntax CPTX:SRAC *count*

count

1 through 126

Query syntax CPTX:SRAC?

Query response 1 through 126

Example 1

```
CPTX:SRAC 2    // Specifies that the source device under test will
                  authenticate two times before transitioning to the third
                  phase of authentication.
```

Example 2

```
CPTX:SRAC?     // Queries for the number of times that the device under
                  test will authenticate before transitioning to the
                  third phase of authentication.
1              // Indicates that the device under test will authenticate
                  one time before transitioning to the third phase of
                  authentication.
```

CROS

draw a centered CROSs

Class
Custom image primitive

Description
Draws a large centered cross that fills the active video area. The vertical line is 2 pixels thick if the format has an even number of active pixels. The horizontal line is 2 pixels thick if the format has an even number of active lines. The primitive uses a single parameter, the color of the cross.

Command syntax
CROS *color*

color
available colors

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
CROS magenta  // Draw a large cross in the center of the active video
ALLU          // Update hardware to current buffer contents
```

CSPG

Composite Sync Pulse Gate

Class
Format parameter setting - Synchronization

Description
Enables and disables all of the digital composite sync outputs when digital composite sync is selected via the SSST command (SSST = 3). The CSPG? query returns the current setting of CSPG.

Command syntax
CSPG *mode*

mode
0 = OFF

1 = ON

Query syntax
CSPG?

Query response
0 or 1

Other required commands
In order to use digital composite sync, it must be selected with the SSST command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
CSPG 1  // Enable dig comp sync in buffer
SSST 2  // Choose digital comp sync type in buffer
FMTU    // Update hardware to current buffer contents
```

CSPP

Composite Sync Pulse Polarity

Class — Format parameter setting - Synchronization

Description — Establishes the logic sense of the digital composite sync output. The CSPP? query returns the current setting of CSPP.

Command syntax — CSPP *polarity*

polarity

0 = active-low (negative going pulse)

1 = active-high (positive going pulse)

Query syntax — CSPP?

Query response — 0 or 1

Other required commands — In order to use digital composite sync, it must be gated on with the CSPG command and selected with the SSST command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
CSPG 1  // Enable dig comp sync in buffer
CSPP 1  // Select active hi in buffer
SSST 2  // Choose digital comp sync type in buffer
FMTU    // Update hardware to current buffer contents
```

CXAR

Content Aspect Ratio

Class Format parameter setting - Active Video

Description Sets the aspect ratio of the source image content.

Command syntax CXAR *aspect_ratio*

aspect_ratio
0.75 to 2.39

The following table provides a listing of established aspect ratios.

Aspect Ratio	Symbol	Description	Examples
0.750	OT or T_{90}	Television Portrait	3x4, 480x640, 600x800, 768x1024, 960x1280, 1200x1600
0.800	OG or G_{90}	Workstation Graphics Portrait	4x5, 1024x1280, 1280x1600
1.000	Q	Quadrate, "Square"	1x1, 512x512, 1024x1024
1.250	G	Workstation Graphics	5x4, 1280x1024, 1600x1280
1.333…	T (A)[1]	SDTV / Silent Film	4x3, 640x480, 800x600, 1024x768, 1280x960, 1600x1200
~1.37	C (B)[1]	Academy[2] "Classic" with sound	~4x3, 0.825x0.602 SMPTE RP40 35mm "C"
1.444…	I	IMAX™	13x9, IMAX™
1.500	V (T)[1]	Vista Vision™	3x2, 1152x768 Apple Computer (uncropped) Vista Vision™
1.555…	M (V)[1]	Mid	14x9, AFD Shoot and Protect (half-way between 4x3 and 16x9)
1.600	D	16 Decimal	16x10, 1728x1080, 1280x800, see VESA CVT 1.0
1.666…	E	European Film, "1.66	5x3, 1200x720, 1280x768, 1800x1080
1.750	Z	Old Film	7x4, Old Metro-Goldwyn-Mayer and Disney Films
1.777…	H	HDTV	16x9, 1280x720,1920x1080
~1.85	A (F)[1]	Film Standard (USA)	~13x7, 1280x692, 1920x1038, 0.825x0.446 SMPTE RP40 35mm "A"
2.000	U	Univisum™	2x1, 1280x640, 1920x960
~2.20	F (M)[1]	"Flat", MPEG "20x9"	"~11x5, 1280x582, 1920x874, 1.912x0.870 SMPTE RP91 70mm
~2.39	B (C)[1]	Anamorphic Cinema, "2.35"[3]	~12x5, 1280x536, 1920x804, 1.650x0.690 SMPTE RP40 35mm "B"

1. The letters in parenthesis are the letters that we used to use, before we updated our aspect ratio symbols for compatibiliity with existing film industry standards (i.e. the symbols defined in SMPTE RP40).
2. In 1932, the shape of film was changed from 1.33:1 to 1.37:1 in order to better accommodate the new optical soundtrack that was added a few years earlier. This slightly wider shape is the true aspect ratio of "classic" film. The aperture is commonly referred to as "Academy" and was the shape of the vast majority of U.S. films produced until the 1950s.
3. Sometimes called "2.35", which was the aspect ratio before it was changed to 2.39:1 in 1971 to keep splices from showing up in the projected image.

Related commands EXAR, SXAR

Example
```
CXAR 1.33 //Sets 4:3 picture aspect ratio for source content
FMTU
```

DACA

Digital Audio Channels Available

Class Format parameter setting - Audio signal

Description Specifies which audio channels are active.

Command syntax DACA *mask*

mask

0 to 3, based on following table.

Channel	1	2
Bit	0	1
Value	1	2

Normally, each type of audio content is assigned to a particular channel and is always output on that channel when present. There is one exception to this rule: rear center (RC) content is switched from channel 5 to 7 whenever rear left (RL) content is simultaneously present. To simplify this, RC content is thus treated as if it were two different types of content: RC5 and RC7. When RL content is not present, RC content is output on channel 5 as RC5 content. When RL content is present, RC content is output on channel 7 as RC7 content.

Setting DACA will automatically set DAXA and XAUD:CA parameters to a corresponding value (see table below).

DACA	3
DAXA	3
XAUD:CA	0

Note: *If DACA is set to a value not found in the table above, then other parameters will not be automatically set and an error will be generated if the format is loaded while this condition exists.*

mask

0 to 255 (based on the value in the table below).**Notes:**

- Setting DACA will automatically set DAXA and XAUD:CA parameters to a corresponding value (see table below). However, in the case of DACA values 243, 247, 251, and 255, two sets of DAXA and XAUD:CA values are possible. In this case, DAXA and XAUD:CA settings will be based on those highlighted (in grey) in the table.
- If DACA is set to a value not found in the table above, then other parameters will not be automatically set and an error will be generated if the format is loaded while this condition exists.

Example

```
DACA 3 //specifies audio channels 1 and 2
DACG 3 //gates audio channels 1 and 2
FMTU
```

Related commands DACG

DACG

Digital Audio Channel Gate

Class — Format parameter setting - Audio signal

Description — Specifies which audio channels are gated (on).

Command syntax — DACG *mask*

mask

0 to 3 (based on the value in the table below).

Channel	1	2
Bit	0	1
Value	1	2

Example

```
DACA 3 //specifies audio channels 1 and 2
DACG 3 //gates audio channels 1 and 2
FMTU
```

Related commands — DACA

DADG

Digital Audio Down-mix Gate

Class — Format parameter setting - Audio signal

Description — Enables or disables downmixing of an audio signal. This sets the DM_I parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B, table 24).

Command syntax — DADG *mode*

mode

1 = enable

0 = disable

Example

```
DADG 1
FMTU
IFGU
```

Related commands — XAUD (DMI parameter), DALS

DALS

Digital Audio Level Shift Value

Class
Format parameter setting - Audio signal

Description
Sets the level shift value (in decibels) for downmixing of the audio signal. This sets the LSV parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B, table 23).

Command syntax
DALS *x*

x
0 - 15 (dB)

Example

```
DALS 5
FMTU
IFGU
```

Related commands
XAUD (LSV parameter), DADG

DASI

Digital Audio Signal Interface

Class — Format parameter setting - Audio signal

Description — Sets the digital audio signal interface.

Command syntax — DASI *interface*

interface

0 = none

1 = SPDIF

Example

```
DASI 1
IFGU
```

DAST

Digital Audio Signal Type

Class — Format parameter setting - Audio signal

Description — Sets the digital audio signal type for an audio signal. This sets the CT parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B, table 19).

Command syntax — DAST *type*

type

0 = void

1 = IEC 60958-3 Consumer LPCM

Example

```
DAST 1
IFGU
```

Related commands — XAUD (CT parameter)

DATE

DATE

Class — System parameter

Description — Sets the system date in the 882.

Command syntax — DATE *mm dd yyyy*

mm
01 - 12

dd
01 - 31

yyyy
2000 -

Query syntax — DATE?

mm dd yyyy

Example 1

```
DATE 09 11 2008
```

Example 2

```
DATE?
01 11 2008
```

Related commands — TIME

DAXA

Digital Audio Content Available

Class — Format parameter setting - Audio signal

Description — Specifies which speaker locations are available (present).

Command syntax — DAXA *mask*

mask

0 to 3 (based on the value in the table below).

Normally, each type of audio content is assigned to a particular channel and is always

Content	FR	FL
Bit	1	0
Value	2	1

output on that channel when present. There is one exception to this rule: rear center (RC) content is switched from channel 5 to 7 whenever rear left (RL) content is simultaneously present. To simplify this, RC content is thus treated as if it were two different types of content: RC5 and RC7. When RL content is not present, RC content is output on channel 5 as RC5 content. When RL content is present, RC content is output on channel 7 as RC7 content.

Setting DAXA will automatically set DACA and XAUD:CA parameters to a corresponding value (see table below). However, this method should not be used to gate channels. Instead, DAXG should be used after all of the available channels have been selected.

DAXA	3
DACA	3
XAUD:CA	0

Note: *If DAXA is set to a value not found in the table above, then other parameters will not be automatically set and an error will be generated if the format is loaded while this condition exists.*

Example

```
DAXA 3 //specifies FR and FL as having audio content
DAXG 3 //gates FR and FL content
FMTU
```

Related commands — DAXG

DAXG

Digital Audio Content Gate

Class — Format parameter setting - Audio signal

Description — Specifies which speaker locations are gated (on).

Command syntax — DAXG *mask*

mask

0 to 3 (based on the value in the table below).

Content	FR	FL
Bit	1	0
Value	2	1

Example

```
DAXA 3 //specifies FR and FL as having audio content
DAXG 3 //gates FR and FL content
FMTU
```

Related commands — DAXA

DCBM

Display Code Bit Mask

Class — Direct processor control

Description — Sets the 4-bit binary bit mask used by the DCRD? query. The mask is entered as the decimal equivalent of a 4-bit binary number. The binary number represents the masking of the individual sense lines from M3 (MSB) to M0 (LSB). The DCBM? query returns the current setting of DCBM.

Command syntax — DCBM *mask*

mask

0 = 0 0 0 0	8 = 1 0 0 0
1 = 0 0 0 1	9 = 1 0 0 1
2 = 0 0 1 0	10 = 1 0 1 0
3 = 0 0 1 1	11 = 1 0 1 1
4 = 0 1 0 0	12 = 1 1 0 0
5 = 0 1 0 1	13 = 1 1 0 1
6 = 0 1 1 0	14 = 1 1 1 0
7 = 0 1 1 1	15 = 1 1 1 1

Query syntax — DCBM?

Query response — *mask*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
DCBM 7  // Set mask to read sense lines 0, 1 and 2 only
FMTU    // Update hardware to current buffer contents
```

DCEX

Display Code EXpected

Class — Format parameter settings

Description — Sets up the display code that is expected from a display connected to the generator. The code is determined by one or more sense lines being connected to ground by the display. Many video controller cards for the Apple Macintosh II and VGA type cards for the IBM-PC sample the status of the display code sense lines. The information then sets up one of several different operating modes to match a particular display. An improper display code may make the controller card or display appear to malfunction.

The DCEX? query first performs a logical AND operation with the display code bit mask and the actual display code that's sensed. The decimal equivalent of the result then is returned. The mask is set with the DCEX command.

The expected setting and the actual result are both shown in the Format test image. They have no effect how a given format generates a set of test signals.

Command syntax — DCEX *code*

code

0 = 0 0 0 0	8 = 1 0 0 0
1 = 0 0 0 1	9 = 1 0 0 1
2 = 0 0 1 0	10 = 1 0 1 0
3 = 0 0 1 1	11 = 1 0 1 1
4 = 0 1 0 0	12 = 1 1 0 0
5 = 0 1 0 1	13 = 1 1 0 1
6 = 0 1 1 0	14 = 1 1 1 0
7 = 0 1 1 1	15 = 1 1 1 1

Query syntax — DCEX?

Query response — *code*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
DCBM 7  // Set mask to read sense lines 0, 1 and 2 only
DCEX 5  // Only lines 0 and 1 should be grounded
FMTU    // Update hardware to current buffer contents
```

DCPG (OUT1:DCPG, OUT2:DCPG, AV:DCPG, VGA:DCPG) Data Channel Power Gate

Class EDID and DDC control

Description Enables and disables the +5V power signal at the specified connector by writing to a latch. The [OUT1|OUT2|AV|VGA]:DCPG? query reads back the latched bit at the specified connector.

Command syntax DCPG *option*

connector:DCPG *option*

option

0 = disable +5V power

1 = enable +5V power

connector

OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 connector

AV = SPDIF/AV connector

VGA = VGA connector

Query syntax *DCPG*

connector:DCPG?

connector

OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 connector

AV = SPDIF/AV connector

VGA = VGA connector

Example 1
```
OUT1:DCPG 0       // disables +5V power on the HDMI output 1
DCPU              // initiates the command
```

Example 2
```
VGA:DCPG 1        // enables +5V power on the VGA output
```

Example 3
```
DCPG 1            // enables +5V power on all connectors
DCPU              // initiates the command
```

Example 4
```
OUT2:DCPG?        // queries +5V power on HDMI output 2
```

Example 5
```
DCPG?             // reads back the logical AND of all connectors
```

Related commands DCPX? (OUT1:DCPX?, OUT2:DCPX, AV:DCPX?, VGA:DCPX?)

DCPX? (OUT1:DCPX?, OUT2:DCPX, AV:DCPX?, VGA:DCPX?) Data Channel Power Overcurrent

Class EDID and DDC control

Description Queries the status of the 5V display data channel (DDC) power level at the specified output connector.

Query syntax DCPX?

connector

OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 ports

AV = SPDIF/AV connector

VGA = VGA connector

Returns 0 or 1

0 = OK

1 = overcurrent (for example, shorted)

Example 1
```
OUT1:DCPX?      // queries the DDC power level of HDMI output connector 1
0
```

Example 2
```
OUT2:DCPX?      // queries the DDC power level of HDMI output connector 2
1
```

Example 3
```
DCPX?           // reads back the logical AND of all connectors
0
```

Related commands DCPG (OUT1:DCPG, OUT2:DCPG, AV:DCPG, VGA:DCPG)

DDCV?

DDC Version supported

Class EDID and DDC control

Description The DDCV? query returns a status flag indicating if the generator hardware supports VESA DDC communications.

Query syntax DDCV?

Query response 0 or 1

0 = no DDC support

1 = DDC supported

Example
```
DDCV?  // Return DDC support information
```

DELX

slider image DELta X

Class — Image editor control

Description — Sets the amount of horizontal shift that occurs for each step of the SlideG and SlideRGB built-in images. The command is also used to set the horizontal size of the white patch used in the Regulate image. The DELX? Query returns the current DELX setting.

Command syntax — DELX *delta_x*

delta_x
horizontal distance in pixels

Query syntax — DELX?

Query response — *delta_x*

Example

```
DELX 8         // Set H shift to 8 pixels per step
DELY 3         // Set V shift to 3 pixels per step
DWEL 2         // Display each step for 2 frames
IMGL "SlideG" // Select Image that uses DELX and DELY
IMGU           // Draw the Image
```

DEVS?

DEViceS?

Class Tools

Description Lists all devices.

Query syntax DEVS?

Query response List of devices

Related commands None

Example

```
DEVS?
drv name
  0 \null
  1 \tyCo\0
  3 \card0
  5 QDEW023:
  6 \vio
  7 \tgtsvr
  3 \ram20K
  3 \ramNV
  3 \tffs0
  2 \pipe\cli
  8 \pty\remote0.S
  9 \pty\remote0.M
```

DELY

slider image DELta Y

Class — Image editor control

Description — Sets the amount of vertical shift that occurs for each step of the SlideG and SlideRGB built-in images. The command is also used to set the vertical size of the white patch used in the Regulate image. The DELY? Query returns the current DELY setting.

Command syntax — DELY *delta_y*

delta_y
vertical distance in pixels

Query syntax — DELY?

Query response — *delta_y*

Example

```
DELX 8          // Set H shift to 8 pixels per step
DELY 3          // Set V shift to 3 pixels per step
DWEL 2          // Display each step for 2 frames
IMGL "SlideG" // Select Image that uses DELX and DELY
IMGU            // Draw the Image
```

DIDA

eDID save As file

Class — EDID and DDC control

Description — Saves an EDID to the filename specified by *filename*.

Command syntax — DIDA *filename*

filename
a valid MS-DOS filename (8 characters minus any extension)

Example — This example loads an EDID file, edits it, and saves the changes under a new filename, *myedid8*.

```
DIDL myedid7      // loads the EDID file named myedid7
DIDB            // begins an edid editing session
XDID 19 A E88A82A0564796240F48 // edits EDID at 19 for 10 (0x0A) bytes
DIDE            // ends an edid editing session
DIDA myedid8    // saves the changes to the filename myedid8
```

Related commands — DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDB

eDID editing Begin

Class EDID and DDC control

Description Marks the beginning of an EDID editing session.

Command syntax DIDB

Example

```
DIDL myedid7      // loads the EDID file named myedid7
DIDB            // begins an edid editing session
XDID 19 A E88A82A0564796240F48 // edits EDID at 19 for 10 (0x0A) bytes
DIDE            // ends an edid editing session
DIDA myedid8    // saves the changes to the filename myedid8
```

Related commands DIDA, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDE

eDID editing End

Class EDID and DDC control

Description Marks the end of an EDID editing session.

Command syntax DIDE

Example

```
DIDL myedid7      // loads the EDID file named myedid7
DIDB            // begins an edid editing session
XDID 19 A E88A82A0564796240F48 // edits EDID at 19 for 10 (0x0A) bytes
DIDE            // ends an edid editing session
DIDA myedid8    // saves the changes to the filename myedid8
```

Related commands DIDA, DIDB, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDK

eDID Kill file

Class
EDID and DDC control

Description
Deletes the EDID file specified by *filename*.

Command syntax
DIDK *path/filename*

path/filename
The directory path and valid MS-DOS filename (8 characters minus any extension) of the file to be deleted. If the file to be deleted is in the default path, then *path/* may be omitted.

Example
This example deletes the file *myedid1* in the */userdata* directory on the generator.

```
DIDK /tffs0/library/userdata/myedid1
```

Related commands
DIDA, DIDB, DIDE, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDL

eDID Load from file

Class
EDID and DDC control

Description
Loads an EDID from a file on the generator.

Command syntax
DIDL *path/filename*

path/filename
The directory path and valid MS-DOS filename (8 characters minus any extension) of the file to be loaded. If the file to be loaded is in the default path, then *path/* may be omitted.

Query syntax
DIDL?

Query response
The name of the file currently in the buffer.

Example
This example loads the EDID from the file *myedid1* in the */userdata* directory.

```
DIDL /tffs0/library/userdata/myedid1
```

Related commands
DIDA, DIDB, DIDE, DIDK, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDN

eDID New file

Class
EDID and DDC control

Description
Creates a new EDID file with the name specified by *filename*.

Command syntax
DIDN *path/filename*

path/filename
The directory path and valid MS-DOS filename (8 characters minus any extension) of the file to be created. If the file is to be created in the default path, then *path/* may be omitted.

Example
This example creates the file *myedid1* in the */userdata* directory on the generator.

```
DIDN /tffs0/library/userdata/myedid1
```

Related commands
DIDA, DIDB, DIDE, DIDK, DIDL, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDP

eDID Path

Class — EDID and DDC control

Description — Sets the default EDID path.

Command syntax — DIDP *path*

path
path to directory containing EDID files

Example — This example sets the default path to the */userdata* directory.

```
DIDP /tffs0/library/userdata
```

Related commands — DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDQ

eDID file Query

Class
EDID and DDC control

Description
Returns EDID filenames from the list of all the EDID filenames stored on the generator, beginning at *startIndex* and ending at *endIndex*. The filenames are kept in alphanumeric order.

Query syntax
DIDQ? *startIndex endIndex*

startIndex
positive integer number

endIndex
positive integer number

Query response
List of filenames.

Example
This example returns the first 10 EDID filenames.in the default directory.

```
DIDQ? 1 10
```

Related commands
DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDS

eDID Save to file

Class — EDID and DDC control

Description — Saves an EDID to the filename given by DIDN.

Command syntax — DIDS

Example — This example loads an EDID file, edits it, and saves the changes to the same filename.

```
DIDL myedid7      // loads the EDID file named myedid7
DIDB            // begins an edid editing session
XDID 19 A E88A82A0564796240F48 // edits EDID at 19 for 10 (0x0A) bytes
DIDE            // ends an edid editing session
DIDS            // saves the changes to myedid7
```

Related commands — DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDU, EDA<port>:GDID, EDA<port>:PDID, XDID

DIDU

eDID Use

Class — EDID and DDC control

Description — Updates hardware with current EDID contents. This command also causes a hot plug pulse on the hot plug detect lead.

Command syntax — DIDU

Query syntax — DIDU?

Query response — The current EDID file in use.

Example — This example edits part of an EDID and updates the hardware with the current buffer contents.

```
XDID 8 3 DE33FF
DIDU
```

Related commands — DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, EDA<port>:GDID, EDA<port>:PDID, XDID

DIRA

DIRectory save As

Class Directory memory management

Description Saves the current contents of the directory edit buffer using the given name.

Command syntax DIRA *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Example

```
DIRN Vesa1      // creates a catalog named Vesa1
DIRT Source     // identifies new catalog as a source catalog
DIRB            // begins a directory editing session
NAMI 1 /tffs0/Library/Formats/DMT0660  // adds DMT0660 to catalog
 .
 .              // add other formats
 .
NAMI 6 /tffs0/Library/Formats/DMT0860  // adds DMT0860 to catalog
DIRE            // ends the directory editing session
DIRA Vesa1      // saves the catalog
```

DIRB

DIRectory editing Begin

Class — Directory memory management

Description — Marks the beginning of a directory editing session. This command does nothing in the current firmware version, but is used for compatibility with future versions of firmware.

Command syntax — DIRB

Other required commands — Use either a DIRL command to load an existing directory or a DIRN command to create a new directory. Use DIRE when ending the editing session.

Example

```
DIRN  // Initialize directory edit buffer
DIRB  // Start directory editing session

      //  One or more directory editing commands ...

DIRE  // End directory editing session
```

DIRE

DIRectory editing End

Class — Directory memory management

Description — Marks the end of a directory editing session. This command does nothing in the current firmware version, but is used for compatibility with future versions of firmware.

Command syntax — DIRE

Other required commands — Use DIRB when starting the editing session. Use DIRS to save changes.

Example

```
DIRB            // Start directory editing session

                // One or more directory editing commands ...

DIRA MYDIR_02   // Save edited directory as MYDIR_02
DIRE            // End directory editing session
```

DIRK

DIRectory Kill

Class
Directory memory management

Description
Deletes a directory by name. The query returns a one if the named directory can be deleted. If directory is read-only or nonexistent, the query returns a zero.

Command syntax
DIRK *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax
DIRK? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response
0 or 1

Example

```
DIRK MY_DIR  // Delete directory called "MY_DIR"
```

DIRL

DIRectory Load

Class — Directory memory management

Description — Copies the directory having a name equal to *name* from directory memory into the directory edit buffer. The query returns a one if the named directory can be loaded; otherwise, a zero is returned.

Note: *Use the FMTP, IMGP and SEQP commands to select which directory is used for the format, image, and sequence selection lists.*

Command syntax — DIRL *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax — DIRL? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response — 0 or 1

Example

```
DIRL MY_DIR  // Load "MY_DIR" directory in edit buffer
```

DIRN

DIRectory New

Class
Directory memory management

Description
Initializes the directory edit buffer. The name *name* is assigned as the directory's name. The query will return the name that has been assigned as the directory's name.

Command syntax
DIRN *name*

name
optional valid MS-DOS filename (8 characters minus any extension)

Query syntax
DIRN?

Example
```
DIRN  // Init edit buffer without assigning a new name
```
or
```
DIRN MY_DIR  // Init edit buffer with name of "MY_DIR"
```

DIRP

DIRectory Path

Class — Directory memory management

Description — Sets the current directory path name. The query will return the current directory path name.

Command syntax — DIRP *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax — DIRP?

Query response — *name*

Example

```
DIRP DIRPTH01  // Set directory path to DIRPTH01
```

DIRQ?

DIRectory Query pointer

Class
Directory memory management

Description
Returns the number directory names from the list of all the directory names stored in directory memory beginning at index. The directories are kept in alphanumeric order.

Query syntax
DIRQ? *index number*

index
positive integer number

number
positive integer number

Query response
List of specified directory names

Example
```
DIRQ? 1 5     // List the first five directories in memory
```
or
```
DIRQ? 1 9999  // List all directories in memory
```

DIRS

DIRectory Save

Class Directory memory management

Description Saves the current directory edit buffer contents into directory memory using the current name of the directory in the edit buffer.

Example

```
DIRN NTSCFMT      // creates a catalog named NTSCFMT
DIRT Source       // identifies new catalog as a source catalog
DIRB              // begins a directory editing session
NAMI 1 /tffs0/Library/Formats/NTSC     // adds NTSC to catalog
DIRE              // ends the directory editing session
DIRS              // saves the catalog
```

DIRT

DIRectory Type

Class — Directory memory management

Description — Specifies a directory (catalog) type that is being created.

Command syntax — DIRT *type*

Command response — *type*

Directory type such as: Source, SourceLib, Content, ContentLib

Query syntax — DIRT?

Query response — *type*

The current directory type defined such as: Source, SourceLib, Content, ContentLib

Example

```
DIRN NTSCFMT      // creates a catalog named NTSCFMT
DIRT Source       // identifies new catalog as a source catalog
DIRB              // begins a directory editing session
NAMI 1 /tffs0/Library/Formats/NTSC     // adds NTSC to catalog
 .
 .                // add other formats
 .
NAMI 6 /tffs0/Library/Formats/NTSC-J   // adds NTSC-J to catalog
DIRE              // ends the directory editing session
DIRS              // saves the catalog
```

DIRU

DIRectory Use

Class — Directory memory management

Description — Uses (installs) the currently loaded directory (library).

Command syntax — DIRU *directory*

Command response — Not applicable

Related commands — DIRL

Example

```
DIRN NTSCFMT      // creates a catalog named NTSCFMT
DIRT Source       // identifies new catalog as a source catalog
DIRB              // begins a directory editing session
NAMI 1 /tffs0/Library/Formats/NTSC         // adds NTSC to catalog
DIRE              // ends the directory editing session
DIRS /tffs0/Library/FormatLib/NTSCFMT      // saves the catalog
DIRL /tffs0/Library/FormatLib/NTSCFMT      // loads the catalog
DIRU                                       // installs the catalog
```

DNUM

Display sequence step NUMbers

Class
Sequence editor commands

Description
Enables and disables the addition of the sequence step number to the displayed test image when running a sequence.

Command syntax
DNUM *mode*

mode
0, 1 or 2

Query syntax
DNUM?

Query response
mode

Example
```
DNUM 1  // Enable the displaying of the sequence step #
```

DPGU

Data Island Packet Generator Use

Class Data Island Packet

Description Updates the hardware with content of the current Data Island packet.

Command syntax DPGU

Related Commands DPTG

Example 1 Turn mute on:

```
XGCP 1 0
DPTG 7
DPTR 1
DPGU
```

Example 2 Read mute status:

```
R:MUTE?
R:1
```

Example 3 Turn mute off:

```
XGCP 0 1
DPTG 7
DPTR 1
DPGU
```

Example 4 Read mute status:

```
R:MUTE?
R:0
```

Example 5 Change the N value to 6000, and let hardware determine CTS value:

```
XACR 6000
DTPG 7
DPGU
// You can read N and CTS value at the reciever for verification.
```

Example 6 Change the N value to 6000, and CTS to 8000:

```
XACR 6000 8000
DTPG 7
DPGU
// You can read N and CTS value at the reciever for verification.
```

Example 7 Turn audio off:

```
DPTG 3
DPGU
```

Example 8 Turn audio on:

```
DPTG 7
DPGU
```

DPTG

Data Island Packet Type Gate

Class: Data Island Packet

Description: Gates on or off the assigned packet type (Audio Sample, Audio Clock Regeneration, or General Control Packet) to be updated by the hardware and sent to the receiver.

Gating Audio Sample packets on and off also enables and disables the audio output from the transmitter. The mask value is a value ORed with the current setting.

Command syntax: DPTG *mask*

mask

1 = General Control Packet (GCP)

2 = Audio Clock Regeneration (ACR)

4 = Audio Sample

8 = Generic Data Packet (GDP)

Related commands: DPGU, DPTR

Example: This example gates off the audio (the current value is 7):

DPTG 3; DPGU

See DPGU for other examples.

DPTR

Data Island Packet Type Repeat Mask

Class: Data Island Packetr

Description: Specifies if a General Control packet is sent with every frame or sent once.

Note: *Audio Sample and ACR packets are always enabled (and thus cannot be changed).*

Command syntax: DPTR *mask*

mask

1 = General Control Packet (GCP)

8 = Generic Data Packet (GDP)

Example: See DPGU for examples.

DSCT

Digital Sync Composite Type

Class — Format parameter setting - Digital video signal

Description — Establishes the type of composite sync that appears at the digital composite sync outputs when digital composite sync is selected via the SSST command. The DSCT? query returns the current setting of DSCT. A setting of zero (0) indicates that digital composite sync cannot be activated by the operator.

Command syntax — DSCT *type*

type

- 0 = none
- 2 = American HDTV w/serrations & equalization
- 3 = American HDTV w/serrations
- 4 = American HDTV w/double serrations
- 5 = Austrailian AS 493.1-200X CS serrations
- 6 = European HDTV ORed
- 7 = European HDTV w/single serrations
- 8 = European HDTV w/double serrations

Query syntax — DSCT?

Query response — *type*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
DSCT 2  // Select simple Amer ORed in buffer
FMTU    // Update hardware to current buffer contents
```

DSST

Digital Sync Separate Type

Class — Format parameter setting - Digital video signal

Description — Establishes the type of digital separate sync that appears at the digital HS and VS outputs of the generator when digital composite sync is selected via the SSST command and the outputs are gated on via the HSPG and VSPG commands. The only difference between EIA and CCIR digital separate syncs is that, in the case of CCIR, the width of the vertical sync pulse is 0.5 line shorter than the width specified via the VSPW command. In the EIA case, the width of the vertical sync pulse is as programmed.

After sending the DSST command, send the FMTU or ALLU command.

Command syntax — DSST *type*

type

0 = none

1 = American separate

2 = American HDTV separate

3 = European HDTV separate

4 = Japanese HDTV separate

5 = European separate

Query syntax — DSST?

Query response — Returns the current setting of DSST. A setting of zero (0) indicates that separate digital H&V sync cannot be activated by the operator.

Example

```
DSST 1
FMTU  // Update hardware to current buffer contents
```

DVIC

Digital Video Identification Code

Class InfoFrame Packet

Description Writes the specified Video Identification Code (VIC) into the AVI InfoFrame.

Command syntax DVIC *code*

code

0 = unestablished format

1 - 34 = DVIC code corresponding to a format defined in EIA/CEA-861-C standard (Section 4). See table below for DVIC codes.

For detailed information on these timings refer to the CEA-861-C specification.

DVIC	Format Name	NCPP[1]	HRES[2]	VTOT[3]
1	DMT0659	1	640	525
1	DMT0660	1	640	525
2	480p59	1	720	525
2	480p60	1	720	525
2	480p59LH	1	720	525
2	480p60LH	1	720	525
3	480p59SH	1	720	525
3	480p60SH	1	720	525
4	720p59	1	1280	750
4	720p60	1	1280	750
5	1080i29	1	1920	1125
5	1080i30	1	1920	1125
6	480i2x29	2	720	525
6	480i2x30	2	720	525
6	480i2xL1	2	720	525
6	480i2xL2	2	720	525
7	480i2xS1	2	720	525
7	480i2xS2	2	720	525
8	240p2x_1	2	720	262
8	240p2x_2	2	720	262
8	240p2x_3	2	720	263
8	240p2x_4	2	720	263
8	240p2xL1	2	720	262
8	240p2xL2	2	720	262
8	240p2xL3	2	720	263
8	240p2xL4	2	720	263
9	240p2xS1	2	720	262

DVIC	Format Name	NCPP[1]	HRES[2]	VTOT[3]
9	240p2xS2	2	720	262
9	240p2xS3	2	720	263
9	240p2xS4	2	720	263
10	480i4x29	1	2880	525
10	480i4x30	1	2880	525
10	480i4xL1	1	2880	525
10	480i4xL2	1	2880	525
11	480i4xS1	1	2880	525
11	480i4xS2	1	2880	525
12	240p4x_1	1	2880	262
12	240p4x_2	1	2880	262
12	240p4x_3	1	2880	263
12	240p4x_4	1	2880	263
12	240p4xL1	1	2880	262
12	240p4xL2	1	2880	262
12	240p4xL3	1	2880	263
12	240p4xL4	1	2880	263
13	240p4xS1	1	2880	262
13	240p4xS2	1	2880	262
13	240p4xS3	1	2880	263
13	240p4xS4	1	2880	263
14	480p2x59	2	720	525
14	480p2x60	2	720	525
14	480p2xL1	2	720	525
14	480p2xL2	2	720	525
15	480p2xS1	2	720	525
15	480p2xS2	2	720	525
16	1080p59	1	1920	1125
16	1080p60	1	1920	1125
17	576p50	1	720	625
17	576p50LH	1	720	625
18	576p50SH	1	720	625
19	720p50	1	720	750
20	1080i25	1	1920	1125
21	576i2x25	2	720	625
21	576i2xLH	2	720	625
22	576i2xSH	2	720	625
23	288p2x_1	2	720	312
23	288p2x_2	2	720	313
23	288p2x_3	2	720	314
23	288p2xL1	2	720	312
23	288p2xL2	2	720	313
23	288p2xL3	2	720	314
24	288p2xS1	2	720	312

DVIC	Format Name	NCPP[1]	HRES[2]	VTOT[3]
24	288p2xS2	2	720	313
24	288p2xS3	2	720	314
25	576i4x25	1	2880	625
25	576i4xLH	1	2880	625
26	576i4xSH	1	2880	625
27	288p4x_1	1	2880	312
27	288p4x_2	1	2880	313
27	288p4x_3	1	2880	314
27	288p4xL1	1	2880	312
27	288p4xL2	1	2880	313
27	288p4xL3	1	2880	314
28	288p4xS1	1	2880	312
28	288p4xS2	1	2880	313
28	288p4xS3	1	2880	314
29	576p2x50	1	720	625
29	576p2xLH	1	720	625
30	576p2xSH	1	720	625
31	1080p50	1	1920	1125
32	1080p23	1	1920	1125
32	1080p24	1	1920	1125
33	1080p25	1	1920	1125
34	1080p29	1	1920	1125
34	1080p30	1	1920	1125
35	480p4x59	1	2880	525
35	480p4xL1	1	2880	525
35	480p4x60	1	2880	525
35	480p4xL2	1	2880	525
36	480p4xL2	1	2880	525
36	480p4xS2	1	2880	525
37	576p4x50	1	2880	625
37	576p4xLH	1	2880	625
38	576p4xSH	1	2880	625
39	108Oi25_	1	1920	1250
40	1080i50	1	1920	1125
41	720p100	1	1280	750
42	576p100	1	720	625
42	576p100L	1	720	625
43	576p100S	1	720	625
44	576i2x50	2	720	625
44	576i2xL1	2	720	625
45	576i2xS1	2	720	625
46	1080i59	1	1920	1125
46	1080i60	1	1920	1125
47	720p119	1	1280	750

DVIC	Format Name	NCPP[1]	HRES[2]	VTOT[3]
47	720p120	1	1280	750
48	480p119	1	720	525
48	480p119L	1	720	525
48	480p120	1	720	525
48	480p120L	1	720	525
49	480p119S	1	720	525
49	480p120S	1	720	525
50	480i2x59	2	720	525
50	480i2x60	2	720	525
50	480i2xL3	2	720	525
50	480i2xL4	2	720	525
51	480i2xS3	2	720	525
51	480i2xS4	2	720	525
52	576p200	1	720	625
52	576p200L	1	720	625
53	576p200S	1	720	625
54	576i2x_1	2	720	625
54	576i2xL2	2	720	625
55	576i2xS2	2	720	625
56	480p239	1	720	525
56	480p239L	1	720	525
56	480p240	1	720	525
56	480p240L	1	720	525
57	480p239S	1	720	525
57	480p240S	1	720	525
58	480i2x_1	2	720	525
58	480i2x_2	2	720	525
58	480i2xL5	2	720	525
58	480i2xL6	2	720	525
59	480i2xS5	2	720	525
59	480i2xS6	2	720	525

1. The generator treats double-clocking and pixel repetition as two totally separate items. NCPP controls the number of clocks per pixel, while NPPP controls pixel repetition factor. All library formats set pixel repetition factor NPPP to zero (i.e. OFF) by default. Double-clocking and pixel repetition cannot be applied simultaneously due to AVI:RP field constraints. Therefore, double-clocked formats do not support pixel repetition. Pixel repetition is only applicable to the "4x" formats, where HRES remains at 2880-pixels as the pixel repetition factor NPPP is varied between 1 and 10 - thereby varying the effective resolution.
2. Double-clocked formats have the same horizontal resolution as single-clocked formats - the horizontal active (as we define it), is not doubled in the double-clocked case. Some formats are distinguished by a horizontal active that is 4-times the normal value of 720. Here, pixel repetition may be applied, by a special "PixelRep" test image, after the format has loaded. The "PixelRep" test image allows the number of pixels-per-pixel (NPPP) to be varied and an image with repeated pixels to be rendered for test purposes.
3. Some formats are distinguished by having a slightly different vertical line total.

Related commands XAVI (see VIC parameter),

Example
```
DVIC 23
FMTU
```

DVPT

Digital Video Protocol Type

Class — Format parameter setting - Digital video signal

Description — Controls the output protocol. Setting the DVPT parameter to 2 and issuing a FMTU (or ALLU) command causes the output signal protocol to switch to HDMI, while setting DVPT to 1 causes a DVI compatible protocol to be output. All of the formats in the format library set DVPT to 0. This is a default setting, which lets the output protocol be determined, on a global basis, by the type of hardware that is present.

Command syntax — DVPT *type*

type

0 = default (based on hardware present)

1 = DVI 1.0

2 = HDMI 1.0

Example

```
DVPT 2
FTMU
```

DVQM

Digital Video Quantization Mode

Class — Format parameter setting - Digital video signal

Description — Controls the range of digital signals per the EIA/CEA-861-C standard.

The DVQM? query returns the current DVQM mode.

Command syntax — DVQM *mode*

mode

Use the following table to determine the proper mode (0, 1, or 2).

DVQ Mode	Components	NBPC=8 ranges		NBPC=10 ranges		NBPC=12 ranges	
		LMIN	LMAX	LMIN	LMAX	LMIN	LMAX
0	RGB	0	255	0	1023	0	4095
	YC_bC_r	0	255	0	1023	0	4095
1	RGB	1	254	4	1019	16	4079
	YC_bC_r	1	254	4	1019	16	4079
2	RGB	16	235	64	940	256	3760
	YC_bC_r	16	240	64	960	256	3840

Notes:

- Computer (for example, DMT and CVT) formats set DVQM=0 for full range.
- DVQM can be set to 1 to test the undershoot/overshoot signal code margins (for example, see SMPTE 296M section 7.12).
- Television formats (for example, 1080i29) set DVQM=2 for reduced range required by various television standards (for example, EIA/CEA-861-C).

Query syntax — DVQM?

Example

```
DVQM 1  // Sets the quantizing mode to 1.
FMTU    // Applies the format change
```

Related commands — LMIN, LMAX, NBPC

DVSC

Digital Video Swing Calibration factor

Class
System calibration setting

Description
Sets the TMDS differential swing calibration factor for the digital video signal (HDMI and DVI). The DVSC query returns the current value.

Command syntax
DVSC *factor*

factor
0.0 to 1.1

Query syntax
DVSC?

Related commands
DVSS (OUT1:DVSS, OUT2:DVSS)

Examples
```
DVSC 0.9   // sets the digital video swing calibration to 0.9
ALLU
```

DVSM

Digital Video Sampling Mode

Class — Format parameter setting - Digital video signal

Description — Controls how the color difference components (CbCr) are sampled when YCbCr signal type is selected. Set DVST to a signal type that supports the sampling mode specified by DVSM.

Command syntax — DVSM *mode*

mode

0 = RGB 4:4:4 (default)

2 = 4:2:2 (color difference components are sampled at half the pixel rate; luminance is sampled at full pixel rate)

4 = 4:4:4 (both luminance and color difference components are sampled at the pixel rate)

Related commands — NBPC, DVST

Examples

```
DVST 10   // Selects RGB digital video type
DVSM 0    // Specifies default condition
FMTU      // Applies the format change


DVST 14   // Selects YCbCr digital video type
DVSM 2    // Specifies 4:2:2 sampling mode
FMTU      // Applies the format change
```

DVSP

Digital Video Signal Polarity

Class — Format parameter setting - Digital video signal

Description — Establishes the logic sense of the digital video outputs. The DVSP? query returns the current setting of DVSP.

Command syntax — DVSP *polarity*

polarity

0 = active-low (negative going video)

1 = active-high (positive going video)

Query syntax — DVSP?

Query response — *polarity*

Other required commands — To use the digital video outputs, digital video must be enabled with the DVST command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
AVST 0  // Deselect analog video in buffer
DVST 5  // Select 3 bit color in buffer
DVSP 1  // Select active high video in buffer
FMTU    // Update hardware to current buffer contents
DVSS 1.25      // set digital video swing to 1.25 volts on HDMI output 1
ALLU
```

DVSS (OUT1:DVSS, OUT2:DVSS)
Digital Video Signal Swing

Class
Format parameter setting - Digital video signal

Description
Sets the TMDS differential swing voltage for the digital video signal. For generators with two HDMI ports, the OUT1:DVSS or OUT2:DVSS syntax sets the voltage for the corresponding connector. The DVSS query returns the current value.

The DV_Swing image can also be used to adjust the digital swing.

Command syntax
connector:DVSS *voltage*

connector
OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 connector

voltage
0.0 to 2.0 volts differential peak-to-peak (nominally 1.000, 0.150 to 1.560 range guaranteed)

Query syntax
OUT1:DVSS?
or
DVSS?

Related commands
DVST, DVSC

Example 1
```
DVSS 1.25        // sets the digital video signal swing voltage to 1.25
volts on HDMI output 1
ALLU
```

Example 2
```
OUT1:DVSS 1.00   // sets the digital video signal swing voltage to 1.0
volts on HDMI output 1
ALLU
```

Example 3
```
OUT2:DVSS 0.50   // sets the digital video signal swing voltage to 0.5
volts on HDMI output 2
ALLU
```

Example 4
```
OUT2:DVSS?      // queries the current value of HDMI output 2
+0.500E+00
ALLU
```

DVST

Digital Video Signal Type

Class — Format parameter setting - Digital video signal

Description — Establishes the kind of video signal that exits the digital video signal outputs of the generator.

The DVST? query returns the current setting of DVST.

Command syntax — DVST *type*

type

0 = none

9 = YYY follows the sRGB (per ITU-R BT.709)

10 = RGB

13 = YCbCr (per SMPTE 260M-1999, Table 1)

14 = YCbCr (per ITU-R BT.601-5 Table 3, Item 7)

15 = YCbCr (per ITU-R BT.709-5 Part 1, Section 6.10)

16 = Reserved

17 = xvYCC ITU-R BT.601 HDTV

18 = xvYCC ITU-R BT.709 HDTV

Query syntax — DVST?

Related commands — AVST must be set to zero when digital video is used. Use the ALLU or FMTU command, after the DVST command, to update the hardware with the new settings.

Example

```
AVST 0   // Deselect analog video in buffer
DVST 10  // Select digital RGB
FMTU     // Update hardware to current buffer contents
```

DWEL

slider image DWELl time

Class — Image Control – System Level

Description — Sets the how long each step of the SlideG and SlideRGB built-in images is displayed before the image is updated. The delay is based on the number of vertical frame refreshes that must occur for the currently loaded video format. The command is also used to set how long each step of the Regulate image is displayed. The DWEL? query returns the current DWELL setting.

Command syntax — DWEL *delay*

delay
integer representing number of video frames

Query syntax — DWEL?

Query response — *delay*

Example

```
DELX 8         // Set H shift to 8 pixels per step
DELY 3         // Set V shift to 3 pixels per step
DWEL 2         // Display each step for 2 frames
IMGL "SlideG" // Select Image that uses DELX and DELY
IMGU           // Draw the Image
```

EDA<*port*>:GDID

Get EDID from device

Class
EDID and DDC control

Description
Reads an EDID from a device connected to the specified HDMI out port. Requires firmware release 2.3.0 or higher.

Command syntax
EDA*port*:GDID

port

1 = HDMI out port 1

2 = HDMI out port 2

Example
This example reads an EDID from the device connected to HDMI out port 1.

```
EDA1:GDID
```

Related commands
DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:PDID, XDID

EDA<*port*>:PDID

Put EDID to Device

Class
EDID and DDC control

Description
Writes current EDID to a device connected to the specified HDMI out port. Requires firmware release 2.3.0 or higher.

Command syntax
EDA*port*:PDID

port

1 = HDMI out port 1

2 = HDMI out port 2

Example
This example writes an EDID to the device connected to HDMI out port 1.

```
EDA1:PDID
```

Related commands
DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:PDID, XDID

EDE<*port*>:DIDU
EDID Use

Class
EDID and DDC control

Description
Updates hardware with current EDID contents. Requires firmware release 2.3.0 or higher.

Command syntax
EDE*port*:DIDU

port
the HDMI IN port (1 or 2) to be configured with the contents of the EDID buffer

Query syntax
EDE*port*:DIDU?

port
the HDMI IN port (1 or 2) to be read

Example
This example edits part of an EDID and updates the HDMI IN port 1 with the current buffer contents.

```
XDID 8 3 DE33FF
EDE1:DIDU
```

Related commands
DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, XDID

EDID?

EDID read

Class EDID and DDC control

Description Reads all bytes in the base EDID and up to seven extensions from a DDC compliant display connected to the transmitter on the generator. The data is returned in raw ASCII hex format.

Query syntax EDID?

Query response ASCII hex test string

Related commands I2CR? (OUT1:I2CR?, OUT2:I2CR?, VGA:I2CR?)

Example This example reads a four block E-EDID.

```
R:\edid?
00FFFFFFFFFFFF004489B200050000000D0C010380502D780A0DC9A05747982712484C200
000010101010101010101010101010101011D8018711C1620582C2500C48E2100009E8C
0AD08A20E02D10103E9600138E21000018000000FC0048444D492054560A2020202020000
000FD003B3D0F2E08000A2020202020200306F00202000000000000000000000000000000
000000000000000000000000000000000000000000000000000000000000000000000000
000000000000000000000000000000000000000000000000000000000000000000000000
000000000000000000000000000000000000000000000000000000000000000000000000
C02031CF14985040802010614121623090707830100006503OC001000011D007251D01E20
6E285500C48E2100001ED60980A020E02D1010602200128E210000188C0AD090204031200
C405500C48E21000018011D80D0721C1620102C2580C48E2100009E8C0AA01451F0160026
7C4300138E2100009800000000000000000A4020308F1431113158C0AD090204031200C4
05500138E21000018011D00BC52D01E20B8285540C48E2100001E8C0AA02051201810187E
2300C48E2100009800000000000000000000000000000000000000000000000000000000
000000000000000000000000000000000000000000000000000000000000000000000000
71
```

ENET

Reads EtherNET address

Class	Tools
Description	Retrieves the Ethernet (MAC) address of the generator.
Query syntax	ENET?
Query response	ASCII hex test string
Related commands	None
Example	`ENET?` `00:07:AA:00:20:00`

ENET:IP

Sets IP address for EtherNET port

Class
Tools

Description
Sets the IP address of the Ethernet port of the generator.

Command syntax
ENET:IP *IP*

IP
in the format: www.xxx.yyy.zzz

Query syntax
ENET:IP?

Query response
IP address in format: www.xxx.yyy.zzz

Related commands
None

Example
```
ENET:IP 192.168.254.222
```

ENET:MASK

Sets IP address subnet MASK for EtherNET port

Class — Tools

Description — Sets the IP address of the Ethernet port of the generator.

Command syntax — ENET:MASK *mask*

mask
in the format: www.xxx.yyy.zzz

Query syntax — ENET:MASK?

Query response — subnet mask in format: www.xxx.yyy.zzz

Related commands — None

Example — `ENET:MASK 255.255.255.000`

EQUA

EQUalization interval After vertical sync pulse

Class
Format parameter setting - synchronization

Description
Establishes the width of the equalization interval after the vertical sync pulse in each field whenever a serrated and equalized sync type is selected via either ASCT or DSCT commands and selected via the SSST command. If the type specified for the selected sync signal is one of the CCIR types, then the actual equalization interval output by the generator will be 0.5 lines shorter than the whole number specified. The EQUA? query returns the current setting of EQUA.

Command syntax
EQUA *lines*

lines
min = 0

max = number of lines after vertical sync before video

Query syntax
EQUA?

Query response
lines

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
EQUA 3  // Set post-equalization to 3 lines in buffer
FMTU    // Update hardware to current buffer contents
```

EQUB

EQUalization interval Before vertical sync pulse

Class
Format parameter setting - synchronization

Description
Establishes the width of the equalization interval before the vertical sync pulse in each field whenever a serrated and equalized sync type is selected via either ASCT or DSCT commands and selected via the SSST command. If the type specified for the selected sync signal is one of the CCIR types, then the actual equalization interval output by the generator will be 0.5 lines shorter than the whole number specified. The EQUB? query returns the current setting of EQUB.

Command syntax
EQUB *lines*

lines
min = 0

max = number of lines after video and before vertical sync

Query syntax
EQUB?

Query response
lines

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
EQUB 3  // Set pre-equalization to 3 lines in buffer
FMTU    // Update hardware to current buffer contents
```

EQUF

EQUalization Flatten

Class — Format parameter setting - synchronization

Description — Determines if composite sync will have all equalization pulses removed in the vertical sync front porch (delay) period as required by certain military HOBO and Maverik video formats. The EQUF? query returns the current setting of EQUF.

Command syntax — EQUF *mode*

mode

0 = OFF

1 = ON

Query syntax — EQUF?

Query response — *mode*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
EQUF 0; ALLU  // This is the default
```

ERRC

ERRor queue Clear

Class	System error control
Description	Clears all errors waiting to be reported in the error queue.
Command syntax	ERRC

ERRQ?

ERRor Queue

Class System error control

Description Returns number errors from the list of all errors in the error queue beginning at index. The ERRQ? query does not remove the errors from the queue.

Command syntax ERRQ? *index number*

index
Positive integer number

number
Positive integer number

Query response List of specified range of errors in the error queue.

Examples:
```
ERRQ? 1 5     // List the first five errors in the queue
```
or
```
ERRQ? 1 9999  // List all errors in the queue
```

ERRY?

Yank ERRor from queue

Class	Format parameter setting - synchronization
Description	Returns the most recent error added to the error queue and removes it from the queue.
Query syntax	ERRY?
Query response	Error

EXAR

EXtended Aspect Ratio

Class — Format parameter setting - active video

Description — Sets the aspect ratio of the extended image content.

Note: *If the source image content was shot for a single screen shape, then this parameter will be the same as the CXAR parameter. Alternatively, if the source image content was shot for two different shaped screens (using a "shoot and protect" technique), then this parameter will be different than the CXAR parameter.*

Command syntax — EXAR *aspect_ratio*

aspect_ratio
0.75 to 2.39

Note: *For a listing of established aspect ratios, see the table on page 915 (CXAR command).*

Related commands — CXAR, SXAR

Example —
```
EXAR 1.77 // Sets 16:9 picture aspect ratio for extended image content
FMTU
```

EXCX

Extended-From-Content Aperture Map

Class Format parameter setting - active video

Description Maps CXAR-shaped image content into the extended EXAR-shaped aperture.

Command syntax EXCX *code*

code

0 to 131071 (in decimal)

The mapping code is made up of three binary field codes as follows:

- Bits 0-2 are the *Squeeze/Stretch* (“S”) field code
- Bits 3-9 are the *Letterbox/Pillar* (“L”) field code
- Bits 10-16 are the *Safe Area* (“K”) field code

To determine the proper mapping code, follow these steps:

1. Using the table below, determine the proper “S” field code for bits 0-2.

	“S” Field Code			
	Undo	**Non-Linear**	**Squeeze**	
Squeeze/Stretch Method	**Bit 2**	**Bit 1**	**Bit 0**	**Symbol**
Disabled (scaling is uniform)	0	0	0	
Linear Squeeze (anamorphise)	0	0	1	S

2. Using the table below, determine the proper “L” field code for bits 3-9.

Letterbox/Pillar Mode	“L” Field Code							Symbol
	Undo	Bars	BarContents		Position		Shrink	
	Bit 9	Bit 8	Bit 7[1]	Bit 6[1]	Bit 5	Bit 4	Bit 3	
Disabled	0	0	0	0	0	0	0	
Centered shrink w/black bars top & bottom	0	1	0	0	0	0	1	Lcbb
Centered shrink w/gray bars top & bottom	0	1	0	1	0	0	1	Lcgb
Centered shrink w/white bars top & bottom	0	1	1	0	0	0	1	Lcwb
Centered protected shrink w/shot surround	0	0	0	0	0	0	1	Lcsp
Top shrink w/single black bar at bottom	0	1	0	0	0	1	1	Ltbb
Top shrink w/single gray bar at bottom	0	1	0	1	0	1	1	Ltgb
Top shrink w/white bar at bottom	0	1	1	0	0	1	1	Ltwb

1. Bits 6 and 7 are used to sequence redundant AFD codes.

In the case of pixel repetition (NPPP not equal to 0), the color of the (extended) bars on the left and right sides of the image are filled in accordance with the settings of bits 6 and 7—even when the letterbox/pillar fitting method is disabled (bit 3 = 0).

3. Use the following table to determine the proper “K” field code for bits 10-16.

(Keep) Safe Area Mode	“K” Field Code							Symbol
	Undo	Bars	BarContents		Source	Save Area		
	Bit 16	Bit 15	Bit 14	Bit 13	Bit 12	Bit 11	Bit 10	
None (w/safe area markers)	0	0	0	0	0	0	0	
Shrink coded frame to action area with opaque black bar surround	0	1	0	0	0	0	1	Kabb
Shrink coded frame to action area with opaque gray bar surround	0	1	0	1	0	0	1	Kagb
Shrink coded frame to action area with opaque white bar surround	0	1	1	0	0	0	1	Kawb
Coded frame has shot-protected action area without graticules or bars	0	0	0	0	0	0	1	Kasp
Coded frame has shot-protected action area with action graticules without bars	0	0	0	1	0	0	1	Kaspa
Coded frame has shot-protected action area with title graticules without bars	0	0	1	0	0	0	1	Kaspt
Coded frame has shot-protected action area with action and title graticules without bars	0	0	1	1	0	0	1	Kaspb
Shrink coded frame to title area with opaque black bar surround	0	1	0	0	0	1	0	Ktbb
Shrink coded frame to title area with opaque gray bar surround	0	1	0	1	0	1	0	Ktgb

(Keep) Safe Area Mode	"K" Field Code							Symbol
	Undo	Bars	BarContents		Source	Save Area		
	Bit 16	Bit 15	Bit 14	Bit 13	Bit 12	Bit 11	Bit 10	
Shrink coded frame to title area with opaque white bar surround	0	1	1	0	0	1	0	Ktwb
Coded frame has shot-protected title area without graticules or bars	0	0	0	0	0	1	0	Ktsp
Coded frame has shot-protected title area with action graticules without bars	0	0	0	1	0	1	0	Ktspa
Coded frame has shot-protected title area with title graticules without bars	0	0	1	0	0	1	0	Ktspt
Coded frame has shot-protected title area with action and title graticules without bars	0	0	1	1	0	1	0	Ktspb
Coded frame has shot-protected custom area without graticules or border	0	0	0	0	0	1	1	Kcsp
Coded frame has shot-protected custom area with action graticules without border	0	0	0	1	0	1	1	Kcspa
Coded frame has shot-protected custom area with title graticules without border	0	0	1	0	0	1	1	Kcspt

The following table provides mapping codes used by AFD (see XAFD).

Method	Binary Field Code	Decimal Code	Symbol
Natural aspect ratio	00000000000000000	0	N0
	00000000000010000	16	N1
	00000000000100000	32	N2
Squeeze (anamorphise)	00000000000000001	1	S
Centered protected shrink with shot surround	00000000000001000	8	Lcsp
Centered shrink with black bars top and bottom	00000000100001000	264	Lcbb
Top shrink with single black bar at bottom	00000000100011000	280	Ltbb
Shrink coded frame to title area w/ opaque black bar surround	01000100000000000	34816	Ktbb

Related commands CXAR, EXAR, SXCX, SXEX

Example
```
EXCX 8 // Use centered protected shrink w/shot surround mode
FMTU
```

FILE:LOAD

FILE:LOAD

Class
Tools

Description
Loads and uses a file such as an image or format.

Command syntax (flash memory/ PC card)
FILE:LOAD *filename*

filename
Any file in a generator library directory.

Command syntax (file server)
FILE:LOAD *server_name/filename*

server_name
Valid hostname (no forward slash before name, and colon after name)

filename
Any file in a file server library directory.

Related commands
None

Example
```
FILE:LOAD barsmpte.o // Loads file from generator

FILE:LOAD Host1:/barsmpte.o // Loads file from file server "Host1".
```

FILE:SCREENCAP

FILE:SCREENCAP

Class Tools

Description Captures an image currently rendered on the display to a bit map.

Command syntax FILE:SCREEN f*ilename.bmp*

filename.bmp

Related commands None

Example `FILE:SCREENCAP diamond.bmp`

FMTA

ForMaT save As

Class — Format memory management

Description — Saves the current contents of the format edit buffer using the given name

Command syntax — FMTA *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Example

```
FMTA MY_FMT  // Save with the name "MY_FMT"
```

FMTB

ForMaT editing Begin

Class — Format editor control

Description — Marks the beginning of a format editing session.

Command syntax — FMTB

Other required commands — Use either an FMTL command to load an existing image or an FMTN command to create a new format. Use FMTE when ending the editing session.

Example

```
FMTN  // Initialize format edit buffer
FMTB  // Start format editing session

      // One or more format editing commands ...

FMTE  // End format editing session
```

FMTE

ForMaT editing End

Class — Format editor control

Description — Marks the end of a format editing session.

Command syntax — FMTE

Other required commands — Use FMTB when starting the editing session. Use FMTA or FMTS to save changes.

Example

```
FMTB           // Start format editing session

               // One or more format editing commands ...

FMTA My_fmt1   // Save edited format as My_fmt1
FMTE           // End format editing session
```

FMTG?

ForMaT in buffer Good

Class — Format memory management

Description — Tests the format in the format buffer for errors. If no errors are found, FMTG? returns zero. Otherwise, if one or more errors exist, the number of the first error encountered is returned. To test formats residing in format memory, use the FMTT? query.

Query syntax — FMTG?

Query response — Returns 0 if no errors are found; otherwise, returns the number of the first error encountered.

Example

```
FMTG?  // Return format error status
```

FMTK

ForMaT Kill from memory by name

Class
Format memory management

Description
Erases the named format from memory. The FMTK? query checks to see if the named format can be erased. The RAM location number is returned if it can be erased. Otherwise, a zero is returned.

Command syntax
FMTK *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax
FMTK? *name*

name
valid MS-DOS filename (8 characters minus any extension)

Query response
0 or location

Example

```
FMTK my_fmt1  // Erase format called my_fmt1
```

FMTL

ForMaT Load from memory by name

Class
Format memory management

Description
Assigns a format to the current step of a sequence while between a set of SEQB and SEQE commands. The FMTL command is context sensitive. The FMTL? query returns the name of the format currently assigned to the step.

Outside of the sequence editor, the FMTL command reads the format having a name equal to name from format memory (or EPROM) into the format. FMTL does not reconfigure the signal generating hardware. This feature allows you to work on the contents of any format memory location, while continuing to output a signal based on a previously used format (see FMTU command). The FMTL? query returns the location location in which a format having a name equal to name is found. If multiple formats exist having name *name*, then the lowest numbered location containing a format with a matching name *name* is returned. The format memory (RAM) is always searched first. If a format with name *name* cannot be found anywhere in the format memory, then the industry-standard formats located in EPROM (negative locations) are searched next.

The FMTL? query returns zero if a format with a name equal to name cannot be found in either format space.

Command syntax
FMTL *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax
FMTL? *name*

Query response
location (returns 0 if not found)

Other required commands
The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
FMTL VGA_m3  // Load format called VGA_m3
ALLU         // Update hardware and redraw image
```

FMTN

ForMaT New

Class Format memory management

Description Initializes the format editing buffer. Sending this one command is equivalent to sending all of the following commands:

ASBG 0	GAMA 2.2
ASCT 1	GAMC 0
ASGG 1	HRAT 0
ASSG 0, 1, 0	HRES 0
ASSS 0.286	HSIZ 280
AVPG 0	HSPD 0
AVPS 0.0	HSPG 1
AVSB 0.0	HSPP 0
AVSS 0.714	HSPW 0
AVST 0	HTOT 0
XVSG 1, 1, 1	SCAN 1
CSPG 1	SSST 1
CSPP 0	USIZ 2
DCBM 0	VRES 0
DSEX 0	VSIZ 210
DSST 1	VSPD 0
DVSP 0	VSPG 1
DVST 0	VSPP 0
EQUA 0	VSPW 0
EQUB 0	VTOT 0

This should be the first command sent to the generator when creating a new format. The command only resets to a known state. The command does not create a usable format. The FMTN? query returns the current name of the format in the buffer.

Command syntax FMTN *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax FMTN?

Query response *name*

Example

```
FMTN  // Initialize format buffer
```

or

```
FMTN Narf  // Initialize format buffer and name the format "Narf"
```

FMTP

ForMaT Path

Class — Format memory management

Description — Sets the current format path name to a given medium. The query will return the current format path name.

Command syntax — FMTP *name*

name
a valid MS-DOS path and filename (8 characters minus any extension)

Query syntax — FMTP?

Query response — *name*

Example

```
FMTP /tffs0/Library/Formats // sets format path to flashmen directory
```

FMTQ?

ForMaT Query pointer

Class
Format memory management

Description
Returns number format names from the list of all the formats stored in format memory beginning at index. The formats are kept in alphanumeric order. The generator maintains internal variables for the current index and number values. The value of index is automatically incremented by number after the query is executed. Sending the query with just an index parameter returns the same number of names as the last time, starting at the given index. Sending the query with no parameters, returns the next set of names.

Query syntax
FMTQ? [*index* [*number*]]

index
positive integer number

number
positive integer number

Query response
List of specified format names

Example

```
FMTQ? 1 9999  // List all formats in memory
```

or

```
FMTQ? 1 10    // List the first ten formats in memory
FMTQ? 21 10   // List the 21st through the 30th FMTes in memory
FMTQ? 31 1    // List the 31st through the 40th FMTes in memory
```

FMTS

ForMaT Save

Class Format memory management

Description Saves the current format edit buffer contents into format memory using the current name of the format in the edit buffer.

Command syntax FMTS

Example

```
FMTL DMT0660  // Loads a format for editing
FMTB          // Begins and editing session
HRES 654      // Sets the horizontal resolution to 654 pixels
.
.             // other format parameters
.
HTOT 720      // Sets the horizontal total to 720 pixels
FMTE          // Ends the format editing session
FMTS          // Saves format
```

FMTU

ForMaT Use

Class — Format memory management

Description — Checks the current contents of the format buffer for errors; if no errors are found, it reconfigures the signal generating hardware in accordance with the contents. It does not redraw the previously displayed test image. In some cases this may distort the old image.

The FMTU? query returns either a format memory location *location* or zero. If the signal format currently being output by the signal generating hardware matches that originally loaded (using the FMTL command) from a format memory location, then the matching format memory location *location* is returned. Otherwise, if the format contents have been used to update the signal generating hardware since either an FMTR or FMTL command has been issued, then FMTU? query returns zero.

Command syntax — FMTU

Query syntax — FMTU?

Query response — location or 0

FMTZ

ForMat Zap

Class — Format memory management

Description — Clears format storage memory starting at first and ending at last. The cleared locations are then tagged as being empty. If no last parameter is given, only the first location is cleared. The FMTZ? query is used to determine if a location contains a format or is empty.

Command syntax — FMTZ *first last*

Query syntax — FMTZ? *location*

FORM

draw FORMat data block

Class
Custom image primitive

Description
Displays basic information about the format driving the display. The first line shows the number of horizontal active pixels and vertical active lines. The last number on the line is the number of fields per frame (1 for non-interlaced and 2 for interlaced). The second and third lines show the horizontal and vertical rates, respectively. Text is on a black rectangular background with a single pixel border.

FORM uses three (3) parameters. The first is the color of the text and border. The next two are the X and Y coordinates for the top left corner of the block of text.

Command syntax
FORM *color x y*

color
available colors

x
positive integer number

y
positive integer number

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
FORM blue 30 200  // Display format information
                  // in blue beginning at X=30, Y=200
ALLU              // Update hardware to current buffer contents
```

FRAT?

Frame RATe Query

Class	Format parameter setting - Video resolution
Description	Returns the current frame (vertical) rate setting.
Query syntax	FRAT?
Query response	frame rate
Example	`FRAT?` `25.0000`
Related commands	TMAU

FRGB

Foreground Red, Green and Blue levels

Class System parameter settings

Description Temporarily sets the portions of an image drawn with a color selection of foreground to the given red, green and blue values. All three colors can be set to the same level using a single parameter. The color selection for one or more primitives in a custom image must be set to foreground in order to see the affect of this command on a custom image. The setting is not global and is not saved. The FRGB? query returns the current red, green and blue settings of FRGB.

Command syntax FRGB *red_level green_level blue_level*

or

FRGB *common_gray_level*

level

min = 0 (full off)

max = 255 (full on)

Example

```
FRGB 255 128 0  // Set foreground color to orange
```

or

```
FRGB 128   // Set foreground color to a mid-gray level
```

FSPD

Frame Sync Pulse Delay

Class — Format parameter setting - Synchronization

Description — Sets the delay of the frame sync pulse relative to the last line of active video in the current format. The FSPD? query returns the current FSPD setting.

Command syntax — FSPD *delay*

delay

min = 0 lines

max = (VTOT/SCAN) line

Query syntax — FSPD?

Query response — *delay*

Other required commands — To get a pulse, frame sync must first be enabled with the FSPG command. The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
FSPG 1      // Enable Frame Sync
FSPP 1      // Set for positive going pulse
FSPW 20     // Make the pulse 20 pixels wide
FSPG 300    // Pulse to occur 300 lines after
            // the last line of active video
FMTU        // Update hardware to new settings
```

FSPG

Frame Sync Pulse Gate

Class
Format parameter setting - Synchronization

Description
Enables and disables the digital horizontal sync output. The FSPG? query returns the current FSPG mode.

Command syntax
FSPG *mode*

mode
0 = OFF

1 = ON

Query syntax
FSPG?

Query response
0 or 1

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
FSPG 1      // Enable Frame Sync
FMTU        // Update hardware to new settings
```

FSPP

Frame Sync Pulse Polarity

Class — Format parameter setting - Synchronization

Description — Establishes the logic sense of the digital frame sync output. Setting polarity to one (1) causes the leading edge of frame sync to be a low-to-high transition. Setting polarity to zero (0) causes the leading edge of frame sync to be a high-to-low transition. The FSPP? query returns the current polarity of FSPP.

Command syntax — FSPP *polarity*

polarity

0 = active-low (negative going pulse)

1 = active-high (positive going pulse)

Query syntax — FSPP?

Query response — 0 or 1

Other required commands — To get a pulse, frame sync must first be enabled with the FSPG command. The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
FSPG 1      // Enable Frame Sync
FSPP 1      // Set for positive going pulse
FSPW 20     // Make the pulse 20 pixels wide
FSPG 300    // Pulse to occur 300 lines after
            // the last line of active video
FMTU        // Update hardware to new settings
```

FSPW

Frame Sync Pulse Width

Class — Format parameter setting - Synchronization

Description — Establishes the width of the frame sync pulse. The FSPW? query returns the current setting of FSPW.

Command syntax — FSPW *pixels*

pixels

min = 1

max = HTOT - 1

Query syntax — FSPW?

Query response — *pixels*

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
FSPG 1    // Enable Frame Sync
FSPP 1    // Set for positive going pulse
FSPW 20   // Make the pulse 20 pixels wide
FSPG 300  // Pulse to occur 300 lines after the last line of active video
FMTU      // Update hardware to new settings
```

GAMA

GAMmA correction factor

Class
Format parameter setting - Digital video signal

Description
Establishes the current video gamma correction factor. The GAMA? query returns the current setting of the gamma correction factor.

Command syntax
GAMA *factor*

factor

min = 0.1 (floating point accepted)

max = 10.0 (floating point accepted)

For HDMI video signals GAMA is always 2.222

Query syntax
GAMA?

Query response
factor

Other required commands
Gamma correction must be enabled with the GAMC command in order to use the gamma correction factor. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
GAMC 1    // Enable gamma correction in buffer
GAMA 2.2  // Set correction factor in buffer
FMTU      // Update hardware to current buffer contents
```

GAMC

GAMma Correction mode

Class — Format parameter setting - Digital video signal

Description — Enables or disables application of the video gamma correction factor. The GAMC? query can be used to determine if the gamma correction factor is currently being applied.

Command syntax — GAMC *mode*

mode

0 = disable (don't correct)

1 = enable (correct)

Query syntax — GAMC?

Query response — 0 or 1

Other required commands — The value used for gamma correction is set with the GAMA command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
GAMC 1    // Enable gamma correction in buffer
GAMA 2.2  // Set correction factor in buffer
FMTU      // Update hardware to current buffer contents
```

GCET?

Get Component Error Tallies

Class DVI/HDMI Signal Analyzer

Description Reads the number of errors in the red, green, and blue components along with the total number of bad pixels.

Query syntax GCET?

Query response R, G, B, and bad pixels

Example

```
PNAU      //Pseudo-random noise generated
CR        //Stop pseudo-random noise
GCET?
0,21,0,21 //Returns 21 Green pixel errors and a total of 21 bad pixels
```

Related commands PNAU

GFED?

Get First Error Data

Class DVI/HDMI Signal Analyzer

Description Returns information about the first error encountered during the signal analyzer test.

Query syntax GFED?

Query response expected value followed by the errant value (in hex)

Example

```
PNAU  //Pseudo-random noise generated
CR    //Stop pseudo-random noise
GFED? //Returns expected (40018C) and errant (FFFFFF) value of first
        errored pixel
40018C,FFFFFF
```

Related commands PNAU

GNPT?

Get Number of Pixel Tested

Class — Signal analyzer - Pixel data

Description — Returns the number of pixels being measured in billions after a pseudo noise measurement has finished execution (that is, completed the PNAU command).

Query syntax — GNPT?

Query response — zero (0) or positive number for the number of pixels tested in billions; -1 indicates an error No Signal Detected or TMDS failure.

Example

```
PNAU //Pseudo-random noise generated

CR //Carriage return stops pseudo-random noise

GNPT? //Returns number of pixels in billion
4.255
```

Related commands — PNAU

GPEL?

Get PixEL color components

Class — Signal analyzer - Pixel data

Description — Takes the (x, y) coordinates address of a pixel and returns the red, green, and blue color components of the pixel at that address.

Query syntax — GPEL? *x y*

Query response — R, G, B

Possible errors — Should this info be integrated into the Query response area, instead of creating a new label?The GPEL? query may respond back with one of the following errors in case of a parameter is not set correctly (or in case the setup is not correct).

PNSeedExceedsLimit	2800
PNLengthExceedsLimit	2801
PNNotSupported	2802
NoInputSupported	2803
XcoordOutOfRange	2804
YcoordOutOfRange	2805

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
GPEL? 128 256 //read RGB color components at pixel address 128,256
0,255,0
```

Related commands — PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:FRMS, PDAU

GPER?

Get Pixel Error Rate

Class — Signal analyzer - Pixel data

Description — Returns the pixel error rate in errors per billion after a pseudo noise measurement has finished execution (that is, completed the PNAU command).

Query syntax — GPER?

Query response — zero (0) or positive number representing errors per billion pixels; -1 indicates an error No Signal Detected or TMDS failure.

Example

```
PNAU   //Pseudo-random noise generated

CR     //Carriage return tops pseudo-random noise

GPER?  //Returns pixel error rate
0.88
```

Related commands — PNAU

GPIB

GPIB address

Class GPIB port control

Description Sets the address of the generator on the GPIB port. The address change takes affect as soon as the command is issued. The new address setting will be maintained until 1) the address is changed another GPIB command, 2) the unit is re-initialized with an INIT command or 3) the unit is re-initialized because the power-up self-test found corrupted data in battery backed system memory. In cases 2 and 3, the GPIB address will revert to the address set on the GPIB address switches, if the unit has them. The address reverts to 15 if the unit does not have GPIB address switches. The GPIB? query returns the current GPIB address of the unit.

Command syntax GPIB *address*

address
integer, 0-30

Query syntax GPIB?

Query response *address*

Example
```
GPIB 5  // Set GPIB address to 5
```

GRID

draw a centered GRID

Class
Custom image primitive

Description
Draws a crosshatch of a given color and forms a given number of boxes in each direction. All lines are 1 pixel thick. All of the lines in a given direction are equally spaced. Any remaining pixels are distributed as equally as possible around the perimeter of the grid. This may cause the first and last lines in each direction not to be at the very edges of video.

Command syntax
GRID *color horizontal_boxes vertical_boxes*

color
available colors

horizontal_boxes
number of horizontal boxes (half of number of pixels)

vertical_boxes
number of vertical boxes (half of number of lines)

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
GRID gray75 14 10  // Draw a gray75 grid with 14 horizontal
                   // and 10 vertical boxes
ALLU               // Update hardware to current buffer contents
```

GRIH

draw a GRIII pattern of Horizontal lines

Class
Custom image primitive

Description
Draws equally spaced horizontal lines that form a grill over the entire active video area. The primitive uses three parameters. The first is the color of the lines, the second is the thickness of the lines, and the third is the thickness of the space between the lines.

Command syntax
GRIH *color line_width space_width*

color
available colors

line_width
number of pixels in line

space_width
number of pixels in space

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
GRIH green 4 6  // Draw green grid with 4-pixel lines and 6-pixel spaces
ALLU            // Update hardware to current buffer contents
```

GRIV

draw a GRIll pattern of Vertical lines

Class
Custom image primitive

Description
Draws equally spaced vertical lines that form a grill over the entire active video area. The gaps are not touched and will show any previously drawn primitives. The primitive uses three parameters. The first is the color of the lines, the second is the thickness of the lines, and the third is the thickness of the space between the lines.

Command syntax
GRIV *color line_width space_width*

color
available colors

line_width
number of pixels in line

space_width
number of pixels in space

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
GRIV cyan 16 16  // Draw cyan grill with 16-pixel lines
                 // and 16-pixel spaces
ALLU             // Update hardware to current buffer contents
```

GRNG

GRNe Gate

Class: Video Gate

Description: Toggles the green video signal gate.

Command syntax: GRNG *mode*

mode
0 = disable
1 = enable

Query syntax: GRNG?

Query response: 0 or 1

Other required commands: ALLU to invoke the command.

Related commands: BLUG, REDG

Example:
```
GRNG 0; ALLU  // disable green video component
```

HATI

draw a centered crossHATch from the Inside out

Class
Custom image primitive

Description
Draws a crosshatch from the inside-out of a given color and forms a given number of boxes in each direction. The primitive has center lines that divide the active video exactly in half in each direction. The vertical center line is 2 pixels thick if the format has an even number of active pixels. The horizontal center line is 2 pixels thick if the format has an even number of active lines. All other lines are 1 pixel thick. If you enter an odd number of boxes, a half box is placed at each end of the crosshatch. All lines in a given direction are spaced equally. Any remaining pixels are distributed as equally as possible around the perimeter of the grid. This may cause the first and last lines in each direction not to be at the very edges of video. In turn, this may cause any half boxes to be slightly larger.

Command syntax
HATI *color horizontal_boxes vertical_boxes*

color
available colors

horizontal_boxes
number of horizontal boxes (half of number of pixels)

vertical_boxes
number of vertical boxes (half of number of lines)

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HATI green 15 9  // Draw a green grid with 15 horizontal
                 // and 9 vertical boxes
ALLU             // Update hardware to current buffer contents
```

HATO

draw a centered crossHATch from the Outside in

Class — Custom image primitive

Description — Draws a crosshatch from the outside-in of a given color and forms a given number of boxes in each direction. All lines are 1 pixel thick. The first and last lines in each direction are at the very edges of active video. All the lines in a given direction are spaced equally. Any remaining pixels are added to the boxes along the horizontal and vertical centers of the image.

Command syntax — HATO *color horizontal_boxes vertical_boxes*

color
available colors

horizontal_boxes
number of horizontal boxes (half of number of pixels)

vertical_boxes
number of vertical boxes (half of number of lines)

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HATO yellow 15 9  // Draw a yellow grid with 15 horizontal
                  // and 9 vertical boxes
ALLU              // Update hardware to current buffer contents
```

HDCP? (OUT1:HDCP?, OUT2:HDCP?)
HDCP

Class HDCP

Description: The HDCP query is used to control HDCP tests.

Query syntax *connector*:HDCP? *[frames]*

frames
The number of frames to be tested. The default is 512.

connector
OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 connector

Example
```
OUT1:HDCP? 2000          // run test with production keys for 2000 frames
```

For additional examples, see “Testing DisplayPort sinks with HDCP” on page 672.

HPBG

Hot Plug Bypass Gate

Description: The Hot Plug Bypass gate is used to enable and disable the hot plug bypass. Hot plug bypass will cause the generator to output an HDMI or DVI signal even if the hot plug is not detected. The HPBG? query returns the current status of the Hot Plug Gate.

Command syntax: HPBG *mode*

mode integer

0 = Disable

1 = Enable

Query syntax: HPBG?

Query response: 0 or 1

Other required commands: There are no other commands required.

Related commands: There are no other related commands.

Example:

```
HPBG 1      // Enables hot plug bypass
HPBG?       // Queries the current status of the hot plug bypass
```

HPPW

Hot Plug Pulse Width

Description: The Hot Plug Pulse Width command is used to set the assertion pulse width of the analyzer's hot plug pulse.

Command syntax: HPPW *value*

value (milliseconds) in the range of 100 to 4000

Query syntax: HPPW?

Query response: *value*

Other required commands: There are no other commands required.

Related commands: There are no other related commands.

Example

```
HPPW 175    // sets the hot plug assertion pulse width to 175ms
HPPW?      // queries the current value for the hot plug pulse assertion
```

HRAT

Horizontal RATe

Class — Format parameter setting - Video resolution

Description — Sets the line frequency. Pixel rate is equal to HTOT multiplied by HRAT. Frame rate is equal to HRAT divided by VTOT. Field rate is equal to SCAN multiplied by the frame rate. The HRAT? query returns the current horizontal frequency setting.

Command syntax — HRAT *frequency*

frequency

typical min = 1000 Hz (floating point accepted)

typical max = 130000 Hz (floating point accepted)

Query syntax — HRAT?

Query response — frequency in Hz (floating point returned)

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HRAT 32768  // Set 32.768 kHz rate in buffer
FMTU        // Update hardware to current buffer contents
```

or

```
HRAT 32.768E3  // Set a 32.768 kHz rate
FMTU           // Update hardware to current buffer contents
```

HRES

Horizontal RESolution

Class — Format parameter setting - Video resolution

Description — Establishes the number of active pixels per line. The HRES? query returns the current setting of HRES.

Command syntax — HRES *pixels*

pixels

min = 16

max depends on VRES and model of generator

Query syntax — HRES?

Query response — *pixels*

Other required commands — The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
HRES 480  // Set 480 active pixels line in buffer
ALLU      // Configure hardware and redraw image
```

HSIZ

Horizontal SIZe

Class — Format parameter setting - Video resolution

Description — Establishes the horizontal physical size of the image on the display. Units expected (or returned) vary according to the last mode set with USIZ command. The HSIZ command is context sensitive and must appear between begin and end commands FMTB and FMTE. The HSIZ? query returns the current setting of HSIZ.

Note: *Make sure that the USIZ parameter is properly set before using the HSIZ command. Changing the USIZ setting after entering HSIZ will convert the size to match the new unit of measure.*

Command syntax — HSIZ *physical_size*

physical_size
positive value (floating point accepted)

Query syntax — HSIZ?

Query response — Returns physical size (floating point returned)

Other required commands — The units of measure must be properly set by USIZ before entering HSIZ. The ALLU command updates hardware to the new setting and redraws the test image, taking the new size into account.

Example

```
FMTB        // Begin editing session One or more format editing commands
            // ...
USIZ 1      // Select inches as unit of measure in buffer
HSIZ 10.4   // Set width to 10.4 in buffer
VSIZ 7.8    // Set height to 7.8 in buffer
ALLU        // Test the new settings
            // more format editing commands
            // ...
FMTE        // End of editing session
```

HSPD

Horizontal Sync Pulse Delay

Class — Format parameter setting - Synchronization

Description — Establishes the delay between the leading edge of blanking and the leading edge of the horizontal sync pulse. The HSPD? query returns the current setting of HSPD.

Command syntax — HSPD *pixels*

pixels

min = 1

max = HTOT - HRES - HSPW

Query syntax — HSPD?

Query response — *pixels*

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HSPD 16  // Set 16 pixel pulse delay in buffer
FMTU     // Update hardware to current buffer contents
```

HSPG

Horizontal Sync Pulse Gate

Class
Format parameter setting - Synchronization

Description
Enables and disables the digital horizontal sync output. The HSPG? query returns the current HSPG mode.

Command syntax
HSPG *mode*

mode
0 = OFF

1 = ON

Query syntax
HSPG?

Query response
0 or 1

Other required commands
To use digital horizontal sync, digital separate H and V sync must be selected with the SSST command. The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HSPG 1  // Enable H sync output in buffer
FMTU    // Update hardware to current buffer contents
```

HSPP

Horizontal Sync Pulse Polarity

Class — Format parameter setting - Synchronization

Description — Establishes the logic sense of the digital horizontal sync outputs. Setting polarity to 1 causes the leading edge of horizontal sync to be a low-to-high transition. Setting polarity to 0 causes the leading edge of horizontal sync to be a high-to-low transition. The HSPP? query returns the current polarity of HSPP.

Command syntax — HSPP *polarity*

polarity

0 = active-low (negative going pulse)

1 = active-high (positive going pulse)

Query syntax — HSPP?

Query response — 0 or 1

Other required commands — To use digital horizontal sync, it must be gated on with the HSPG command and digital separate H and V sync must be selected with the SSST command. The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HSPP 0  // Set active low H sync in buffer
HSPG 1  // Enable H sync output in buffer
SSST 1  // Select H&V sync type in buffer
FMTU    // Update hardware to current buffer contents
```

HSPW

Horizontal Sync Pulse Width

Class — Format parameter setting - Synchronization

Description — Establishes the width of the horizontal sync pulse. The HSPW? query returns the current setting of HSPW.

Command syntax — HSPW *pixels*

pixels

min = 1

max = HTOT - HRES - HSPD

Query syntax — HSPW?

Query response — *pixels*

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HSPW 32  // Set pulse width to 32 pixels in buffer
FMTU     // Update hardware to current buffer contents
```

HTOT

Horizontal TOTal pixels per line

Class — Format parameter setting - Video resolution

Description — Establishes the total number of pixels per horizontal line. The HTOT? query returns the current setting of HTOT.

The pixel rate is equal to HRAT multiplied by HTOT.

Note: *The current version of the firmware does not allow you to directly enter a specific pixel rate when setting up a format. If your test specifications call for a specific pixel or dot clock rate, enter suitable values for HRAT and HTOT to give you the desired pixel rate.*

Command syntax — HTOT *pixels*

pixels

Query syntax — HTOT?

Query response — *pixels*

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HTOT 800  // Set total to 800
FMTU      // Update hardware to current buffer contents
```

HVPD?

Horizontal Vertical Sync Pulse Delay

Class Format Parameter Setting - Synchronization

Description Returns the pixel delay between the horizontal and vertical sync pulses.

Query syntax HVPD?

Query response number of pixels

Example
```
HVPD? // read pixel delay between HSYNC and VSYNC pulses
1     // one pixel delay
```

Related commands None

HVSA

Horizontal Vertical Sync Adjustment

Class
Format parameter setting - Synchronization

Description
Lengthens the serration period a given number of pixels from the format's nominal default value as required by certain military STANAG video formats. The HVSA? query returns the current setting of HVSA.

Command syntax
HVSA *pixels*

pixels
integer, 0 and less than HSPW

Query syntax
HVSA?

Query response
pixels

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
HVSA 30;
ALLU
```

I2CR? (OUT1:I2CR?, OUT2:I2CR?, VGA:I2CR?)
I2C port Read

Class — EDID and DDC control

Description — Automatically reads data using a specified I2C protocol. This command reads data from the specified connector, bus and device using the I^2C bus. If no connector is specified, the query defaults to OUT1 or VGA depending on the active output. All numeric parameters are given in ASCII HEX.

> ***Note:*** *EDID-compatible receivers use EPROMs with single-byte or double-byte addresses. The I2CR? query uses different parameters depending on the EPROM type. To determine which EPROM type is used, try both syntaxes until you can read data from the EPROM.*

Query syntax (EPROM with single-byte addresses) — *connector*:I2CR? bus_name *i2c_address offset #_of_bytes*

Query syntax (EPROM with double-byte addresses) — *connector*:I2CR? eprom1 *i2c_address offset #_of_bytes*

Query syntax (device protocol) — *connector*:I2CR? *bus_name i2c_address offset #_of_bytes*

connector
OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 connector

VGA = VGA connector

bus_name (optional - text)
device queried(eprom, eprom1, TV, DT, HT, HR)

i2c_address (hex)
i^2c bus address (A0, A1,...)

offset (hex)
address offset (in bytes)

#_of_bytes (hex)
number of bytes

Example 1 — This example reads 10 bytes of E-EDID data, using the I2C e_ddc protocol.

```
R:\>i2cr? eprom a0 80 10
02031A764785020304060701230907O7
```

Example 2 This command reads four register bytes values from the transmitter TV chip of the generator

```
i2cr? tv 89 00 04
82021402
```

Example 3 This command reads the HDCP Bksv value from a receiver

```
i2cr? 74 00 05
07BE05CEA9
```

Example 4 This command reads two bytes of register values from the transmitter (output 1) HDMI chip of the generator

```
i2cr? HT1 7a 00 02
0002
```

Related commands EDA<port>:GDID, I2CW (OUT1:I2CW, OUT2:I2CW, VGA:I2CW)

I2CW (OUT1:I2CW, OUT2:I2CW, VGA:I2CW)
I2C port Write

Class
EDID and DDC control

Description
Writes raw binary data data using a specified I2C protocol. This command writes data to the specified connector, bus and device using the I^2C bus. If no connector is specified, the query defaults to OUT1 or VGA depending on the active output. All numeric parameters are given in ASCII HEX.

Note: *EDID-compatible receivers use EPROMs with single-byte or double-byte addresses. The I2CW command uses different parameters depending on the EPROM type.*

Important: *When writing data with this command, ensure you send only 8 bytes of data at a time. This is necessary since most EPROMs do not have a larger memory buffer.*

Command syntax (EPROM with single-byte addresses)
connector:I2CW bus_name *i2c_address offset data*

Command syntax (EPROM with double-byte addresses)
connector:I2CW eprom1 *i2c_address offset #_of_bytes data*

Command syntax (device protocol)
connector:I2CW *bus_name i2c_address offset data*

connector
OUT1, OUT2 = HDMI OUT 1 or HDMI OUT 2 connector

VGA = VGA connector

bus_name (optional - text)
device queried (eprom, eprom1, TV, DT, HT1, HR)

i2c_address (hex)
i^2c bus address (A0, A1,...)

offset (hex)
address offset (in bytes)

data (hex)
the data that you want to send to the register

Example 1
This example writes two bytes of E-EDID data, using the I2C e_ddc protocol.

```
i2cw eprom a0 80 2 FFFF
```

Example 2 This command writes four register bytes values from the transmitter TV chip of the generator.

```
i2cw tv 89 00 04 FFFFFFFF
```

Related commands XDID, I2CR? (OUT1:I2CR?, OUT2:I2CR?, VGA:I2CR?)

IFGU

InfoFrame Generator Use

Class InfoFrame Packet

Description Updates hardware with current InfoFrame contents.

Command syntax IFGU

Example
```
IFTG 14
IFGU
```

Related commands IFTG, IFTR, XGIF, XAVI, XSPD, XAUD, XMPG

IFTG

InfoFrame Type Gate

Class InfoFrame Packet

Description Gates the InfoFrames by type. The mask value is a value ORed with the current setting.

Note: *For more information about the InfoFrame structure, see the EIA Standard EIA/CEA-861-B (Section 6).*

Command syntax IFTG *mask*

mask

A bit mask based on these InfoFrame type values.

Type	Value
GIFA	1
AVI	2
SPD	4
AUD	8
MPG	16
GIFB	32

Example This example enables AUD (8), SPD (4), and AVI (2) InfoFrames (but not MPG and GIF InfoFrames). The MPG, GIFA and GIFB InfoFrames are gated off, and loaded with zeros.

```
IFTG 14
IFGU
```

Related commands IFGU, IFTR

IFTR

InfoFrame Type Repeat Mask

Class InfoFrame Packet

Description Specifies if an InfoFrame type is to be sent once (after the IFGU command is executed), or sent in every vertical blanking period (frame).

Note: *For more information about the InfoFrame structure, see the EIA Standard EIA/CEA-861-B (Section 6).*

Command syntax IFTR *mask*

mask

A bit mask based on these InfoFrame type values.

Type	Value
GIFA	1
AVI	2
SPD	4
AUD	8
MPG	16
GIFB	32

Example This example specifies that AUD (8) and AVI (2) InfoFrames should be repeated with every frame, and other InfoFrame types should be sent once.

```
IFTR 10
IFGU
```

Related commands IFTG, IFGU

IMGA

IMaGe save As

Class Image memory management

Description Saves the current contents of the image edit buffer using the given name.

Command syntax IMGA *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Example
```
IMGA MY_IMG  // Save with the name "MY_IMG"
```

IMGB

IMaGe editing Begin

Class — Image editor control

Description — Marks the beginning of an image editing session.

Command syntax — IMGB

Other required commands — Use either an IMGL command to load an existing image or an IMGN command to create a new image. Use IMGE when ending the editing session.

Example

```
IMGN  // Initialize image edit buffer
IMGB  // Start image editing session

      // One or more image editing
      // commands ...

IMGE  // End image editing session
```

IMGE

IMaGe editing End

Class — Image editor control

Description — Marks the end of an image editing session.

Command syntax — IMGE

Other required commands — Use IMGB when starting the editing session. Use IMGA or IMGS to save changes.

Example

```
IMGB            // Start image editing session

                // One or more image editing commands ...

IMGA MYIMG_02   // Save edited image as "MYIMG_02"
IMGE            // End image editing session
```

IMGK

IMaGe Kill

Class — Image memory management

Description — Deletes an image by name. The query returns a 1 if the named image can be deleted. If the image is read-only or nonexistent, the query returns a 0.

Command syntax — IMGK *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax — IMGK? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response — 0 or 1

Example

```
IMGK MY_IMG  // Delete dir called "MY_IMG"
```

IMGL

IMaGe Load

Class
Image memory management

Description
Assigns an image to the current step of a sequence while between a set of SEQB and SEQE commands. The IMGL command is context sensitive. The IMGL? query returns the name of the image currently assigned to the step.

Outside of the sequence editor, the IMGL command copies the image having a name equal to name from image memory into the image edit buffer. The query returns a one (1) if the named image can be loaded, otherwise a zero (0) is returned.

Command syntax
IMGL *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax
IMGL? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response
0 or 1

Other required commands
An ALLU or IMGU command must be executed after the IMGL command to cause the image in the edit to draw on the unit under test.

Example

```
IMGL MY_IMG  // Load "MY_IMG" dir in edit buffer
IMGU         // Draw contents of buffer
```

IMGN

IMaGe New

Class
Image editor control

Description
Initializes the image edit buffer. The name *name* is assigned as the image's name. The query will return the name that has been assigned as the image's name.

Command syntax
IMGN *name*

name
optional valid MS-DOS filename (8 characters minus any extension)

Query syntax
IMGN?

Query response
name

Example

```
IMGN         // Init edit buffer without assigning a new name
```

or

```
IMGN MY_IMG  // Init edit buffer with name of "MY_IMG"
```

IMGP

IMaGe Path

Class
Image memory management

Description
Sets the current image path name to a given directory. The query will return the current image path name.

Command syntax (flash memory/PC card)
IMGP *path name*

path name
a valid MS-DOS filename (8 characters minus any extension)

Command syntax (file server)
IMGP *server name:*

server name
valid hostname (no forward slash before name, and colon after name)

Query syntax
IMGP? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response
name

Example
```
IMGP FINAL  // Sets image pathname to a directory called "FINAL".

IMGP hostname1:  // Sets image pathname to "HOSTNAME1" file server.
```

IMGQ?

IMaGe Query pointer

Class
Image memory management

Description
Returns number image names from the list of all the images stored in image memory beginning at index. The images are kept in alphanumeric order.

Query syntax
IMGQ? *index number*

index
positive integer number

number
positive integer number

Query response
List of specified image names

Example
```
IMGQ? 1 5     // List the first five images in memory
```
or
```
IMGQ? 1 9999  // List all images in memory
```

IMGS

IMaGe Save

Class — Image memory management

Description — Saves the current contents of the generator's custom image edit buffer back to the memory location from which it was originally read.

Command syntax — IMGS

IMGU

IMaGe Use

Class Image memory management

Description Draws an image based on the current contents of the image. The IMGU? query returns the image memory location *location* from which the current contents of the image were read.

Command syntax IMGU

Query syntax IMGU?

Query response *location*

location
-1 through -26 (EPROM)

Example
```
IMGL BriteBox  // Select the BriteBox test image
IMGU           // Draw the selected test image
```

INIT

INITialize to factory default settings

Class — Direct processor control

Description — Restores the contents of all of the generator's RAM storage locations to factory-default conditions. The generator then goes through a complete self-test and self-calibration procedure.

Important: *The INIT command permanently and irreversibly removes all user-created formats, custom images, test sequences, and directories from memory.*

Command syntax — INIT

ISHA

ImageSHift save As

Class

Description — Saves the current contents of the imageshift edit buffer using the specified name.

Command syntax — ISHA *filename*

filename
a valid MS-DOS filename (8 characters minus any extension)

Example

```
ISHA Myshift1   // Saves with the name Myshift1
```

Related commands — ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHB

ImageSHift edit Begin

Class

Description — Marks the beginning of an imageshift editing session.

Command syntax — ISHB

Other required commands — Use either an ISHL command to load an existing imageshift file or an ISHN command to create a new imageshift file. Use ISHE when ending the editing session.

Example

```
ISHB   // Begin imageshift editing session
```

Related commands — ISHA, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHE

ImageSHift edit End

Class

Description — Marks the end of an imageshift editing session.

Command syntax — ISHE

Other required commands — Use ISHS when starting the editing session. Use ISHS or ISHA to save changes.

Example

```
ISHE   // End imageshift editing session
```

Related commands — ISHA, ISHB, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHG

ImageSHift Gate

Class

Description — Enables and disables the image shifting function. The ISHG? query returns the current ISHG mode.

Command syntax — ISHG *mode*

mode

0 = OFF

1 = ON

Query syntax — ISHG?

Query response — 0 or 1

Example

```
ISHG 1  //Enables the image shifting function.
```

Related commands — ISHA, ISHB, ISHE, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHK

ImageSHift Kill

Class

Description Deletes the specified imageshift file.

Command syntax ISHK *path/filename*

path/filename
The directory path and valid MS-DOS filename (8 characters minus any extension) of the file to be deleted. If the file to be deleted is in the default path, then *path/* may be omitted.

Example
```
ISHK Myshift1   // Deletes the imageshift file named Myshift1
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHL

ImageSHift Load

Class

Description Loads the values from the specified imageshift file.

Command syntax ISHL *path/filename*

path/filename
The directory path and valid MS-DOS filename (8 characters minus any extension) of the file to be loaded. If the file to be loaded is in the default path, then *path/* may be omitted.

Example
```
ISHL Myshift1   // Loads the imageshift file named Myshift1
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHN

ImageSHift New file

Class

Description Creates a new imageshift file with the name specified by *filename*.

Command syntax ISHN *filename*

filename
a valid MS-DOS filename (8 characters minus any extension)

Example This example creates the file *Myshift1* in the */imageshifts* directory on the generator.

```
ISHN Myshift1  //Creates an imagefile named Myshift1
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHP

set ImageSHift Path

Class

Description — Sets the default imageshift path.

Command syntax — ISHP *path*

path
path to directory containing imageshift files

Query syntax — ISHP?

Query response — *path*

Example 1 — This example sets the default path to the */imageshifts* directory.

```
ISHP /tffs0/library/imageshifts
```

Example 2 — This example queries the generator for the current imageshift path setting.

```
ISHP?   //Query for the current imageshift path
/tffs0/library/imageshifts  //current path
```

Related commands — ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHQ?

ImageSHift Query pointer

Class

Description Returns a list of up to 5 imageshift filenames from the list of all the imageshift files in a directory. Quering repeatedly will eventually exhaust the list of filenames.

Query syntax ISHQ?

Query response List of imageshift filenames.

Example
```
ISHQ?   //List the first 5 imageshift filenames.
ISHQ?   //List the nezt 5 imageshift filenames.
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHS

ImageSHift Save

Class

Description — Saves the current imageshift values to the filename established using the ISHN command. If no ISHN command has been issued, then the values are saved to the default filename Shift1.xml.

Command syntax — ISHS

Example

```
ISHN Newshift  //Creates a new imageshift file named NEWSHIFT
ISHB           //Begins an imageshift editing session
XISH:SRCN cache0/images/SMPTEBar  //selects the SMPTEBar image
XISH:PATH 0,0 150,20  //Sets the imageshift path x,y coordinates
XISH:TTYP 1   //Sets the trace type to Repeat (1)
ISHE          //Ends the imageshift editing session
ISHS          //Saves the values to the NEWSHIFT file
```

Related commands — ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISHU

ImageSHift Use

Class

Description Applies the current imageshift file values to the hardware.

Command syntax ISHU

Example

```
ISHL Newshift  //Loads the imageshift file named NEWSHIFT
ISHU           //Applies NEWSHIFT values to the hardware
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

ISTP?

Image STep

Class	Image editor control
Description	Allows the contents of user created custom images to be copied out of a generator. The contents of the firmware-based, built-in test images cannot be read out since they are not created as a set of primitives.
Query syntax	ISTP? returns the number of steps in the custom image in the edit buffer. or ISTP? *step_number* returns the contents of the given step in the custom image in the edit buffer as a space delimited text string.
Other required commands	A custom image must have been loaded with the IMGL command and editing must have been started with the IMGB command

ISUB

Image Step Button

Class
System parameter settings

Description
Determines if the Image Step key is on or off to allow activation of alternate versions of test images that have alternate versions.

The ISUB? query returns the current setting of ISUB.

Command syntax
ISUB *mode*

mode

0 = OFF

1 = ON

Query syntax
ISUB?

Query response
0 or 1

Example

```
IMGL SlideBox   // Load image
ISUB 1          // Enable alternate versions
IVER 1          // Load version 1
IMGU            // Update display
```

IVER

Image VERsion

Class
System parameter settings

Description
Determines which version of an image is used for the current step of a sequence while between a set of SEQB and SEQE commands. The IVER command is context sensitive. The IVER? query returns the version currently assigned to the step.

Outside of the sequence editor, the IVER command selects which version of the current image is drawn when either an ALLU or IMGU command is executed. The IVER? query returns the current setting of IVER.

Command syntax
IVER *mode*

mode

0 = Normal

1 = Invert or display alternate version

Query syntax
IVER?

Query response
0 or 1

Other required commands
The IMGU command redraws an image using the new setting. The ALLU command updates hardware and redraws the test image with the new setting.

Example

```
IMGL Text_9  // Select image with white text on black
IVER 1       // Select inverted with black on white
IMGU         // Draw the image as selected
```

JDVI

Justify pixel clock rate for DVI formats

Class
Format editor control

Description
Enables setting of the upper and lower bound for the pixel rate of the HDMI-D and HDMI-H outputs. The command takes two parameters: 1) upper frequency parameter and 2) lower frequency parameter. You can set either values or both values but you have to enter the first parameter if you want to set the second parameter value. The default values for HDMI-H and HDMI-D are 165MHz for the upper limit and 25MHz for the lower limit.

Command syntax
`JDVI upper_pixel_rate lower_pixel_rate`

upper_pixel_rate lower_pixel_rate
floating point number equal to the desired pixel in MHz

Query syntax
`JDVI?`

Query response
upper_pixel_rate lower_pixel_rate

Other required commands
The ALLU command updates hardware to the new settings and redraws the test image.

Examples

```
JDVI 165E06 20E06   // sets the lower limit pixel rate to 20MHz
ALLU
JDVI 170E06 25E06   // sets the upper limit pixel rate to 170MHz
ALLU
JDVI 175E06 23E06   // sets the upper limit pixel rate to 175MHz and
                       the lower limit to 23MHz
ALLU
JDVI?
+175.000E+06, +23.000E+06
```

JLDI

Justify pixel clock rate for LDI formats

Class
Format editor control

Description
Scales the horizontal timing parameters of the format currently in the edit buffer. (For the 801LD used in digital mode, the default is set at 224 MHz.) The parameters are scaled to produce the given pixel rate while keeping the horizontal scan rate as close as possible to its original value. The following parameters are scaled: horizontal total pixels, horizontal active pixels, horizontal sync delay in pixels, and horizontal sync pulse width in pixels. The parameters are scaled so that their periods, in microseconds, are as close as possible to their original values.

Command syntax
JLDI *pixel_rate*

pixel_rate
floating point number equal to the desired pixel in MHz

Query syntax
JLDI?

Query response
pixel_rate

Other required commands
The ALLU command updates hardware to the new settings and redraws the test image.

JRAT

Justify pixel clock RATe

Class
Format editor control

Description
Scales the horizontal timing parameters of the format currently in the edit buffer. The parameters are scaled to produce the given pixel rate while keeping the horizontal scan rate as close as possible to its original value. The following parameters are scaled: horizontal total pixels, horizontal active pixels, horizontal sync delay in pixels, and horizontal sync pulse width in pixels. The parameters are scaled so that their periods, in microseconds, are as close as possible to their original values.

Command syntax
JRAT *pixel_rate*

pixel_rate
floating point number equal to the desired pixel in MHz

Other required commands
The ALLU command updates hardware to the new settings and redraws the test image.

Example

```
JRAT 202.000E6 // Adjust timing to a 202.000 MHz clock
FMTU           // Update hardware to current buffer contents
```

LCDS?

LCD Status

Class System parameter settings

Description Returns text displayed on LCD of the generator.

Query syntax LCDS?

Example
```
LCDS?  // Return text similar to text below
       // H32 15=VGA_m3 crlf
       // V60 51=SMPTE133
```

LEDS?

LED Status

Class System parameter settings

Description Returns the current status of the generator's signal generating hardware as a single decimal number. The number corresponds to the status of the lighted key on the generator in normal operation. The easiest way to interpret the number is to first convert it to an 8-digit binary number. A 1 in a given position, from MSB to LSB, corresponds to the following hardware settings:

Master output control gated ON (MSB)

Digital Separate (HS&VS) Sync selected

Digital Composite Sync selected

Analog Composite Sync selected

Blue video enabled

Green video enabled

Red video enabled

Alternate image version selected (LSB)

Query syntax LEDS?

Query response decimal number from 0 to 255

Example

```
LEDS?
// Returns the following number when the outputs are gated ON, separate
// HS & VS is selected, the red, green and blue video channels are
// enabled and the primary version of an image is selected.

206  // Binary equivalent = 11001110
```

LEVP

Increment LEVels Per color component

Class — Image memory management

Description — Enables you to increment the color component (R,G,B) levels in any increment.

Command syntax — LEVP *value*

value
an interger number that is a percent in increments of 1

Query syntax — LEVP?

Query response — Returns an interger value representing a percent from 0 to 100

Example 1

```
LEVP 33      // Sets the color component values for R,G,B to 33%
                of maximum color
```

Example 2

```
LEVP?        // Returns a value representing a percent of color
                component values
45           // Indicates that the color component value is 45% of maximum
```

LEVP:R

Increment LEVels Per individual color component

Class — Image memory management

Description — Enables you to increment the color component (R,G,B) values in any increment (1 to 100) for each component color individually.

Command syntax — LEVP:*color value*

color
a color component either R, G, B

value
an interger number that is a percent in increments of 1

Query syntax — LEVP:*color*?

color
a color component either R, G, B

Query response — Returns an interger value representing a percent from 0 to 100

Example 1
```
LEVP:R 33   // Sets the red color component values to 33%
               of maximum color
```

Example 2
```
LEVP:G 90   // Sets the green color component values to 33%
               of maximum color
```

Example 3
```
LEVP:B?     // Returns a value representing a percent of color
               value for the blue component
45          // Indicates that the color component value is 45% of maximum
```

LIMI

draw video LIMIts markers

Class
Custom image primitive

Description
Places nine markers that define the active video area. An L-shaped marker is placed at each corner. T-shaped markers are centered along each edge of video, and a small cross is placed at the center of video. The primitive uses a single parameter: color.

Command syntax
LIMI *color*

color
available colors

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
LIMI white  // Place white markers that define active video area
ALLU        // Update hardware to current buffer contents
```

LINE

draw a LINE

Class
Custom image primitive

Description
Draws a line between any two points. The line is 1 pixel thick. The primitive uses five parameters: the color and x,y coordinates for both endpoints.

Command syntax
LINE *color x_start y_start x_end y_end*

color
available colors

x_start, y_start, x_ end, y_end
positive integer number

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
LINE yellow 20 5 320 240
      // Draw yellow line from X=20, Y=5 to X=320, Y=240

ALLU  // Update hardware to current buffer contents
```

LMAX

Digital Video Maximum quantizing Level

Class — Format parameter setting - Digital video signal

Description — Sets the maximum quantizing level of the component video signal for white. The default varies depending on the number of bits per color component. Some applications may require that the maximum level be set lower than the maximum permissible. The query reads the current setting for the maximum level.

Command syntax — LMAX *video_level*

video_level
unsigned integer from 59 to 63 when NBPC is 6 gamuts; 235 to 255 when NBPC is 8 gamuts; 940 to 1023 when NBPC is 10 gamuts; 3760 to 4095 when NBPC is 12 gamuts.

Query syntax — LMAX?

Example — LMAX 254 // To set the maximum digital quantizing level to 254

Related commands — LMIN, NBPC, DVQM

LMIN

Digital Video Minimum quantizing Level

Class — Format parameter setting - Digital video signal

Description — Sets the minimum quantizing level of the component video signal for black. The default is 0 for black; however, some applications may require that the minimum level be set higher. The query reads the current setting for the minimum level.

Command syntax — LMIN *video_level*

video_level
unsigned integer from 0 to 4 when NBPC is 6 gamuts; 0 to 16 when NBPC is 8 gamuts; 0 to 64 when NBPC is 10 gamuts; 0 to 256 when NBPC is 12 gamuts

Query syntax — LMIN?

Example — LMIN 16 // To set the minimum digital quantizing level to 16

Related commands — LMAX, NBPC, DVQM

LS?

Class Tools

Description Lists the contents of the current directory.

Query syntax LS?

Query response List of file names is presented.

Related commands None

Example
```
LS?
barpulse.o
boxquart.o
diamond.o
tceburst.o
barsmpte.o
```

LSAX:LSGM

LipSync Analyzer Enable/Disable

Class LipSync Generator/Analyzer

Description Enable or disable LipSync analyzer for HDMI auto lipsync correction testing.

Command syntax LSAX:LSGM *boolean*

boolean

0 = disable

1 = enable

Query syntax LSAX:LSGM?

Query response 0 or 1

Example

```
LSAX:LSGM 1      // Enable LipSync testing
LSAX:LSGU        // Update hardware to new settings
```

LSAX:LSGU

LipSync Analyzer Use

Class LipSync Generator/Analyzer

Description Updates hardware with current LipSync analyzer setup values and restarts the image.

Command syntax LSAX:LSGU

Example
```
LSAX:LSGM 1      // Enable LipSync analyzer testing
LSAX:LSGU        // Update hardware to new settings
```

LSAX:PLAT?

LipSync Analyzer Data Stream Order

Class LipSync Generator/Analyzer

Description Queries which data stream (audio or video) is received first by lipsync analyzer.

Query syntax LSAX:PLAT?

Query response 0 = video is received first

1 = audio is received first

Example
```
LSAX:PLAT?      // Returns data stream received first
```

LSAX:RPTG

LipSync Analyzer Measurement Report

Class LipSync Generator/Analyzer

Description Generates lipsync analyzer measurement report.

Command syntax LSAX:RPTG *boolean*

boolean

0 = disable

1 = enable

Query syntax LSAX:RPTG?

Query response 0 or 1

Example

```
LSAX:RPTG 1      // Generates lipsync analyzer measurement report
LSAX:LSGU        // Update hardware to new settings
```

LSAX:TLAT?

LipSync Analyzer Audio/Video Latency

Class LipSync Generator/Analyzer

Description Queries latency (delay) between audio and video received by lipsync analyzer.

Query syntax LSAX:TLAT?

Query response number of seconds delay

Example
```
LSAX:TLAT?      // Returns latency between audio and video data streams
```

LSGX:LSGM

LipSync Generator Enable/Disable

Class LipSync Generator/Analyzer

Description Enable or disable LipSync generator for HDMI auto lipsync correction testing.

Command syntax LSGX:LSGM *boolean*

boolean

0 = disable

1 = enable

Query syntax LSGX:LSGM?

Query response 0 or 1

Example

```
LSGX:LSGM 1      // Enable LipSync testing
LSGX:LSGU        // Update hardware to new settings
```

LSGX:LSGU

LipSync Generator Use

Class LipSync Generator/Analyzer

Description Updates hardware with current LipSync generator setup values and restarts the image.

Command syntax LSGX:LSGU

Example
```
LSGX:LSGM 1      // Enable LipSync testing
LSGX:LSGU        // Update hardware to new settings
```

LSGX:PLAT

LipSync Generator Data Stream Order

Class LipSync Generator/Analyzer

Description Determines which data stream (audio or video) is transferred (sent) first for lipsync test image.

Command syntax LSGX:PLAT *boolean*

boolean

0 = video is transferred first (indicating that video takes longer to process–audio is delayed).

1 = audio is transferred first (indicating that audio takes longer to process–video is delayed).

Query syntax LSGX:PLAT?

Query response 0 or 1

Example

```
LSGX:PLAT 1      // Audio is sent first for lipsync test image
LSGX:TLAT 0.5    // Latency between audio and video in lipsync test image
LSGX:LSGU        // Update hardware to new settings
```

LSGX:TLAT

LipSync Generator Audio/Video Latency

Class LipSync Generator/Analyzer

Description Sets latency (delay) between audio and video for lipsync test image.

Command syntax LSGX:TLAT *delay*

delay
0.0 to 0.5 seconds

Query syntax LSGX:TLAT?

Query response *delay*

Example
```
LSGX:PLAT 1      // Audio is sent first for lipsync test image
LSGX:TLAT 0.5    // Latency between audio and video in lipsync test image
LSGX:LSGU        // Update hardware to new settings
```

LSPG

Line Sync Pulse Gate

Class
Format parameter settings

Description
Enables and disables the digital horizontal sync output. The LSPG? query returns the current LSPG mode.

Command syntax
LSPG *mode*

mode integer
0 = OFF

1 = ON

Query syntax
LSPG?

Query response
0 or 1

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
LSPG 1      // Enable Line Sync
FMTU        // Update hardware to new settings
```

LSPP

Line Sync Pulse Polarity

Class — Format parameter setting - Synchronization

Description — Establishes the logic sense of the digital line sync output. Setting polarity to 1 causes the leading edge of line sync to be a low-to-high transition. Setting polarity to 0 causes the leading edge of line sync to be a high-to-low transition. The LSPP? query returns the current polarity of LSPP.

Command syntax — LSPP *polarity*

polarity

0 = active-low (negative going pulse)

1 = active-high (positive going pulse)

Query syntax — FSPP?

Query response — 0 or 1

Other required commands — In order to get a pulse, line sync must first be enabled with the LS? command. The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Example

```
LSPG 1      // Enable Line Sync
LSPP 1      // Set for positive going pulse
LSPW 20     // Make the pulse 20 pixels wide
LSPG 300    // Pulse to occur 300 lines after
            // the last line of active video
FMTU        // Update hardware to new settings
```

MODE

communications MODE

Class System parameter settings

Description Sets the serial port communications parameters of a stand-alone model generator. The changes take effect as soon as the command is entered. The factory default settings are 9600 baud, no parity, 8 data bits, no stop bits, no handshake (handshake), and no protocol.

Command syntax MODE *baud parity data stop handshake protocol*

baud rate
300, 600, 1200, 2400, 4800, 9600, 19200, 38400, 57600, or 115200 bits/sec

parity
N = None, E = Even or O = Odd

data
number of data bits: 7 or 8

stop
number of stop bits: 1 or 2

handshake
N = None

H = Hardware (CTS/RTS)

protocol
N = None

Y=Y-Modem

Example
```
MODE 9600 N 8 1 H N  // Set a stand alone generator to
                     // communicate at 9600 Baud, No parity, 8 data bits,
                     // 1 stop bit, RTS//CTS handshaking and No protocol
```

or

```
MODE 2400  // Change only the baud rate
```

MSIZ

light Meter SIZe

Class
System parameter settings

Description
Establishes the physical size of the light meter boxes displayed in the BriteBox test image. The unit of measure used is based on the current setting of the system level USIZ command. It also affects the size of the cursor boxes in the Persist image. Changing the size will not change the currently displayed image. The MSIZ? query returns the current settings of MSIZ based on the current setting of the system level USIZ command.

Command syntax
MSIZ *width height*

or

MSIZ *common_size*

size
positive floating point number

common_size
square box

Query syntax
MSIZ?

Query response
width, *height*

Other required commands
The correct unit of measure should be selected with the USIZ command prior to setting the size.

Example

```
USIZ 1          // Select inches for units
MSIZ 2.0        // Set size to 2.0 inches
IMGL BriteBox   // Select BriteBox image
IMGU            // Draw selected image using new size
```

MUTE

Audio/Video Mute

Class — Parameters (Audio Signal and Timing)

Description — Enables and disables the HDMI Audio/Video Mute (AVMUTE) feature. When enabled, audio and video are muted by the generator.

Command syntax — MUTE *flag*

flag

0 = disable (AVMUTE_clear_flag sent repeatedly)

1 = enable (AVMUTE_set_flag sent repeatedly)

Query syntax — MUTE?

Query response — 0 or 1

Example — To enable AVMUTE:

```
MUTE 1
MUTE?
```

Use the MUTE? to continuously check until the AVMUTE state is changed (may not take place right away).

NAMF?

NAMe Find

Class — Directory editor control

Description — Returns the index number of the entry with name *name* in the directory edit buffer. The first name in the buffer has an index value of 1. If name is not found, a value of 0 is returned.

Query syntax — NAMF? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response — *index*

Example

```
NAMF? VGA_m4  // Return position of VGA_m4 in directory
```

NAMI

NAMe Insert

Class Directory editor control

Description Moves all the names with index values equal to or greater than *index* to the next higher index value in the directory edit buffer, and then inserts the name *name* in the directory edit buffer at position *index*. A negative number or a 0 used for *index* will put *name* at index position 1. Using a number for *index* beyond the last name in the buffer will add *name* to the index position just beyond the last name. The command does not check if a file called *name* is stored in the generator.

Command syntax NAMI *index name*

name
a valid MS-DOS filename (8 characters minus any extension)

Example 1 This example inserts the DMT0660A format on the knob list at location 1:

```
DIRL FMT
DIRB
NAMI 1 DMT0660A
DIRE
DIRS
```

Example 2
```
NAMI 5 FOCUS1  // Put FOCUS1 in fifth position
```

Example 3
```
NAMI -6 BARS  // Put BARS at beginning of dir
```

Example 4
```
NAMI 999999 HATCH  // Put HATCH at end of dir
```

NAMK

NAMe Kill

Class Directory editor control

Description Deletes the given name from the directory edit buffer. All names with index values greater than the index of the deleted name are moved to the next lower index value in the buffer. Nothing happens if name is not found in the buffer.

Command syntax NAMK *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Example
```
NAMK VGA_m4  // Remove VGA_m4 from dir
```

NAMQ?

NAMe Query

Class
Directory editor control

Description
Returns number names from the list of names in the directory edit buffer beginning at *index*. The generator maintains internal variables for the current *index* and *number* values. The value of *index* is automatically incremented by *number* after the query is executed. Sending the query with just an index parameter, will return the same number of names as the last time, starting at the given index. Sending the query with no parameters will return the next set of names in the directory buffer.

Query syntax
NAMQ? *index number*

index
positive integer number

number
positive integer number

Query response
List of specified entry names from directory edit buffer.

Example 1
```
NAMQ? 1 9999  // List the entire buffer
```

Example 2
```
NAMQ? 1 10   // List the first ten names in the buffer
NAMQ? 21     // List the 21st through the 30th names in the buffer
NAMQ?        // List the 31st through the 40th names in the buffer
```

NAMY

NAMe Yank

Class Directory editor control

Description Deletes the name at the given index number from the directory edit buffer. All names with index values greater than the index of the deleted name are moved to the next lower index value in the buffer. Nothing happens if index is beyond the index number of last name in the buffer.

Command syntax NAMY *index*

Example
```
NAMY 2  // Remove second item from dir
```

NBPA

Number Bits Per Audio sample

Class — Format parameter setting - Audio signal

Description — Sets the number of bits per audio sample for an audio signal. This sets the SS parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B, table 20).

Command syntax — NBPA *bits*

bits

0 (let incoming external audio stream determine the number of bits per sample)

16

20 (882E only)

24 (882E only)

Example

```
NBPA 16
IFGU
```

Related commands — XAUD (SS parameter), SAMP

NBPC

Number Bits Per Component

Class — Format parameter setting - Digital video signal

Description — Sets the number of bits per color component (color depth).

Command syntax — NBPC *bits*

bits

6, 8, 10, or 12 depending on output.

Output	NBPC
DVI	8
TV	12
LVDS	6 (18-bit encoding) or 8 (24-bit encoding)
HDMI Digital RGB or YCbCr 4:4:4 output	8
HDMI YCbCr 4:2:2 output	8, 10, or 12.
SDI HD-SDI 4:2:2	8 or 10

Example

```
NBPC 10
FMTU
```

Related commands — DVSM, DVQM

NCPP

Number Clocks Per Pixel

Class
Format parameter setting - Digital video signal

Description
Specifies the number of clocks per pixel (double-clocking factor for whole line). Some industry standard formats (e.g. 480i) have pixel rates that are below the minimum pixel rate restriction (of 25 MHz) required by the TMDS interface. In these cases, a feature known as “double-clocking” is used to raise the TMDS clock rate to an acceptable frequency.

Double-clocking is controlled by the NCPP format parameter. When NCPP is set to 1 (normal single-clocked), each pixel, output by the generator, is paired with one clock pulse. In this case, the pixel rate is equal to the TMDS clock rate. By setting NCPP to 2 (double-clocked), two clocks are send during each pixel period and the TMDS clock rate is raised to 2 times the pixel rate.

Note that double clocking with NCPP and pixel repetition (NPPP) cannot be applied at the same time.

Command syntax
NCPP *factor*

factor
1 or 2

Related commands
NBPA, NPPP

Example

```
NCPP 2
FMTU
```

NDAC

Number Digital Audio Channels

Class
Format parameter setting - Audio signal

Description
Sets the number of digital audio channels for an audio signal. This sets the CC parameter of the Audio InfoFrame (as specified in EIA/CEA-861-B, table 20).

Command syntax
NDAC *channels*

channels
2 or 8

Example

```
NDAC 2
ALLU
```

Related Commands
XAUD (CC parameter)

NDAS

Number Digital Audio Streams

Class — Format parameter setting - Audio signal

Description — Sets the number of digital audio streams.

Note: *Currently, only one audio stream is supported.*

Command syntax — NDAS *streams*

streams
1 (default)

Example

```
NDAS 1
IFGU
```

NERR?

Number of ERRors in queue

Class	System memory management
Description	Returns the number of errors waiting to be reported in the error queue.
Query syntax	NERR?
Query response	number of errors

NLNK

Number of digital LiNKs

Class
Format parameter setting - Digital video signal

Description
Determines the number of links used by the LVDI digital outputs on generators that support LVDI outputs. The NLNK? query returns the current setting of NLNK.

Command syntax
NLNK *links*

links integer

0 = Default, let the generator decide

1 = Single link

2 = Dual link

Query syntax
NLNK?

Query response
links

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
NLNK 2; FMTU
```

NOGA

use NO GAmma correction

Class Custom image primitive

Description Temporarily disables any gamma correction that may be selected in a format. All color intensity levels in all parts of the custom image are output without gamma correction. Gamma correction is disabled only for as long as the image is displayed.

Command syntax NOGA

NOTU

NOT Until communication is complete

Class	System Level
Description	Temporarily holds-off any ongoing command execution until communication is complete and ALLU is invoked.
Command syntax	NOTU
Query syntax	NOTU?
Query response	0 if not enabled non-zero when enabled
Other required commands	Disabled by ALLU.

NPPP

Number Pixels Per Pixel

Class — Format parameter setting - Digital video signal

Description — Specifies repetition factor for active portion of line.

Command syntax — NPPP *factor*

factor

0 to disable repetition mode (removes extra left and right repetition bars)

1 to 10 enables pixel repetition mode (inserts extra left and right repetition bars)

Related commands — NCPP

Example — `NPPP 4; FMTU`

NSTP?

Number of STePs in sequence

Class	Sequence editor control
Description	Returns the number of steps in a sequence in the buffer.
Query syntax	NSTP?
Query response	steps

OERR?

ERRor queue Overflow

Class: System memory management

Description: Checks for overflow in the error queue. Overflow occurs when an attempt is made to add more errors to the queue than it can hold.

Query syntax: OERR?

Query response: overflow status

0 = No Overflow

1 = Overflow

OFFX

image OFFset X

Class — Image editor control

Description — Sets the horizontal offset used for the large patch in the Regulate test image. It may also control other images. The OFFX? query returns the current OFFX setting.

Command syntax — OFFX *x_offset*

x_offset integer
number of pixels

Query syntax — OFFX?

Query response — X offset

Example — `OFFX 20`

OFFY

image OFFsetY

Class — Image editor control

Description — Sets the vertical offset used for the large patch in the Regulate test image. It may also control other images. The OFFY? query returns the current OFFY setting.

Command syntax — OFFY *y_offset*

y_offset integer
number of pixels

Query syntax — OFFY?

Query response — Y offset

Example — `OFFY 20`

OUT1|OUT2|AV|VGA DCPG, DCPX?, DVSS, I2CR

Description See the following commands:

DCPG (OUT1:DCPG, OUT2:DCPG, AV:DCPG, VGA:DCPG)

DCPX? (OUT1:DCPX?, OUT2:DCPX, AV:DCPX?, VGA:DCPX?)

DVSS (OUT1:DVSS, OUT2:DVSS)

I2CR? (OUT1:I2CR?, OUT2:I2CR?, VGA:I2CR?)

OUTG

OUTputs Gate

Class — System parameter settings

Description — Gates all video and sync outputs of the generator ON and OFF. Gating the outputs OFF forces all outputs to be turned off. Gating the outputs ON turns on all outputs whose individual gating settings are turned ON. The OUTG? query returns the current status of the outputs of the generator.

Command syntax — OUTG *mode*

mode

0 = OFF

1 = ON

Query syntax — OUTG?

Query response — *mode*

Example

```
OUTG 0
ALLU
```

OVAL

draw an OVAL

Class
Custom image primitive

Description
Draws an oval whose axes are parallel to the vertical and horizontal axes of displayed video. The size and position of the oval are defined by its framing rectangle. The framing rectangle is a rectangle whose sides are both tangent to the oval at four points and are parallel to the vertical and horizontal axis of video. It is not drawn as part of the primitive. OVAL uses six parameters. The first is *color*. The next two are the pixel *width* and *height* of the framing rectangle in pixels. The fourth and fifth parameters are the *x, y* coordinates for the top left corner of the framing rectangle. The last parameter is the *fill*.

Command syntax
OVAL *color width height x y fill*

color
available colors

width
total number of horizontal pixels

height
total number of lines

x, y
positive integer numbers

fill
available fill patterns

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
OVAL red 240 150 20 10 GrayPat0  // Draw a red oval 240 pixels wide
                                 // by 150 pixels high. Start framing
                                 // rectangle at X=20, Y=10.
                                 // Fill = none
```

PAGE

draw PAGE of repeating characters

Class
Custom image primitive

Description
Fills a rectangular area (page or block) with a character that repeats horizontally and vertically. The *color* parameter sets the color used to draw the character. The *width* and *height* parameters determine the size of the block to be filled. The *x* and *y* parameters determine the top left corner of the block. The *font* parameter selects which font is used to draw the character. The *character* parameter selects a specific character (by number). For full alphanumeric fonts, the character number is the same as the character's ASCII code number. The spacing between the characters is fixed by the character block size in the font and cannot be changed. Partial characters are not drawn to completely fill the rectangular area; rather, the largest possible block of full characters is centered in the rectangular area.

Command syntax
PAGE *color width height x y font character*

color
available colors

width
width of page in pixels

height
height of page in lines

x
position of left edge of page in pixels

y
position of top edge of page in pixels

font
available fonts

character
min = 0

max = 255

Example

```
PAGE blue 40 30 10 10 opix9 69
// Draw a small block of blue E characters in the upper left corner
```

PCPG

Pixel Clock Pulse Gate

Class
Format parameter settings

Description
Enables and disables the pixel clock pulse output on generators that have a pixel clock output available. The pixel clock output appears on the special sync BNC connector. The PCPG? query returns the current setting of PCPG.

Command syntax
PCPG *mode*

mode
0 = OFF

1 = ON

Query syntax
PCPG?

Query response
mode

Other required commands
FMTU or ALLU

Example

```
PCPG 1  // Enable pixel clk output in buffer
FMTU    // Update hardware with format data
```

PDAU

Pixel Data Analyzer Use

Class Signal analyzer - Pixel data

Description Uses (runs) the pixel data analzyer test.

Command syntax PDAU

Example

```
PDAX:FRAMS 100 //sets the number of frames to analyze in the pixel
                 data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                 data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                 data analysis test
PDAX:REFG 1    //enables auto reference capturing for the pixel
                 data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                 data analysis test
PDAU           //runs the pixel data analysis test
```

Related commands PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:CAPF

PDAX:FRMS

Pixel Data Analyzer for number of FRaMes

Class — Signal analyzer - Pixel data

Description — Determines how many frames to analyze.

Command syntax — PDAX:FRMS *frames*

frames
number of frames analyzed in a range from 1 to 1,000,000

Query syntax — PDAX:FRMS?

Query response — *frames*

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 1    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:          //runs the pixel data analysis test
```

Related commands — PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:CAPF, PDAU

PDAX:MXER

Pixel Data Analyzer MaXimum number of ERrors

Class — Signal analyzer - Pixel data

Description — Determines the maximum number of detailed errors to record during the pixel analzyer test.

Command syntax — PDAX:MXER *records*

records
number of errors to record for the pixel analysis test (0 - 1000)

Query syntax — PDAX:MXER?

Query response — *records*

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the pixel
                data analysis test
PDAX:REFG 1    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:          //runs the pixel data analysis test
```

Related commands — PDAX:FRMS, PDAX:RPTG, PDAX:REFG, PDAX:CAPF, PDAU

PDAX:PASS

Pixel Data Analyzer PASS Thru

Class — Signal analyzer - Pixel data

Description — Enables or disables video passthru.

Command syntax — PDAX:PASS *enable*

enable
0 to disable passthru; 1 to enable video passthru; 2 to enable non-HDCP passthru

Query syntax — PDAX:PASS?

Query response — *1, 2 or 3*

Example

```
PDAX:PASS 0        // Disables passthru mode
PDAX:PASS?         // Returns 0, 1, or 2 to indicate the status
```

Related commands — PDAX:FRMS, PDAX:RPTG, PDAX:REFG, PDAX:CAPF, PDAU

PDAX:RPTG

Enable or disable RePoRT Generation for the Pixel Data Analyzer test

Class
Signal analyzer - Pixel data

Description
Enable or disable the generation of an HTML report for the results of the pixel data analysis test.

Command syntax
PDAX:RPTG *boolean*

boolean
0 (disable), 1 (enable) report generation

Query response
PDAX:RPTG?

Query response
boolean

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:          //runs the pixel data analysis test
```

Related commands
PDAX:MXER, PDAX:FRMS, PDAX:REFG, PDAX:CAPF, PDAU

PDAX:REFG

Pixel Data Analyzer auto REFerence Gate

Class — Signal analyzer - Pixel data

Description — Enable or disable automatic reference frame capturing. If this parameter is disabled you have to manually capture a reference frame.

Command syntax — PDAX:REFG *boolean*

boolean
0 (disable), 1 (enable) auto capturing of a reference frame

Query response — PDAX:REFG?

Query response — *boolean*

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:          //runs the pixel data analysis test
```

Related commands — PDAX:MXER, PDAX:RPTG, PDAX:FRMS, PDAX:CAPF, PDAU

PDAX:CAPF

Pixel Data Analyzer CAPture Frame

Class Signal analyzer - Pixel data

Description Manually captures a reference frame for the pixel data analysis test.

Command syntax PDAX:CAPF

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:          //runs the pixel data analysis test
```

Related commands PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:FRMS, PDAU

PDAX:ERRQ

Pixel Data Analyzer ERRor Query

Class
Signal analyzer - Pixel data

Description
Retrieves one or more of the recorded detailed error records. The count is persistent in that the last entered count will be used in subsequent queries if a count value is not specified. If the start is not specified then the query will start where the previous query left off.

Query syntax
PDAX:ERRQ? *start count*

start
The starting index of the error count. Default is 1.

count
The maximum number of errors to report. The initial count is 10.

Query response
frame, x y mr mg mb rr rg rb

frame
The number of the frame that the error occurred in.

x, y
The coordinate that the error occurred on.

mr
The measured red component value.

mg
The measured red component value.

mb
The rmeasured red component value.

rr
The reference expected red component value.

rg
The reference expected green component value.

rb
The reference expected blue component value.

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
```

```
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                 data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                 data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                 data analysis test
PDAU:                //runs the pixel data analysis test
PDAX:ERRQ? 10 100    //retrieves 100 errors starting at the 10th error
                       in the index.
PDAX:ERRQ?           //retrieves 100 errors starting at the 110th error
                       in the index.
```

Related commands PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:FRMS, PDAX:ERRQ, PDAU

PDAX:NERR

Pixel Data Analyzer Number of ERRors query

Class Signal analyzer - Pixel data

Description Retrieves the number of errors that occurred during the pixel data analysis test.

Query syntax PDAX:NERR?

Query response *number*

number
The number of errors that occurred.

Example
```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:               //runs the pixel data analysis test
PDAX:ERRQ? 10 100    //retrieves 100 errors starting at the 10th error
                       in the index.
PDAX:NERR?          //retrieves number of errors that occurred.
```

Related commands PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:FRMS, PDAX:ERRQ, PDAU

PDAX:VIEW

Pixel Data Analyzer View Data

Class Signal analyzer - Pixel data

Description Output captured image during pixel data analysis test to HDMI output ports.

Command syntax PDAX:VIEW

Example

```
PDAX:FRMS 100 //sets the number of frames to analyze in the pixel
                data analysis test to 100
PDAX:MXER 1000 //sets the maximum number of errors to record in pixel
                data analysis test to 1000
PDAX:RPTG 1    //enables the generation of reports for the ppixel
                data analysis test
PDAX:REFG 0    //enables auto reference capturing for the pixel
                data analysis test
PDAX:CAPF      //captures a frame of pixel data for the pixel
                data analysis test
PDAU:          //runs the pixel data analysis test
PDAX:VIEW      //output captured image from HDMI OUT ports
```

Related commands PDAX:MXER, PDAX:RPTG, PDAX:REFG, PDAX:FRMS, PDAU

PELD

PixEL Depth

Class — Format parameter settings

Description — Establishes the number of data bits that represent each active pixel in video memory (frame buffer). The PELD? query returns the current setting of PELD.

Command syntax — PELD *depth*

depth integer

0 = use generator default

4 = 4 bits-per-pixel (16 colors)

8 = 8 bits-per-pixel (256 colors)

32 = 24 bits-per-pixel (16,777,216 colors)

Query syntax — PELD?

Query response — *depth*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
PELD 8  // Select 8 bits-per pixel
ALLU    // Configure hardware and redraw image
```

PENH

PEN Height

Class — Image editor control

Description — Sets a variable used establish line thicknesses to draw EeRise, NAWC, and Slider test images.

Command syntax — PENH *height*

height integer

Query syntax — PENH?

Query response — *height*

Example

```
PENH 4
```

PENW

PEN Width

Class — Image editor control

Description — Sets a variable used to establish line thicknesses to draw EeRise, NAWC and Slider test images.

Command syntax — PENW *width*

width integer

Query syntax — PENW?

Query response — *width*

Example

```
PENW 4
```

PNAU

Measure Pseudo Noise

Class Signal Analyzer - Pseudo-random noise

Description Loads the hardware required to generate the pseudo noise and measures all the related required parameters.

Command syntax PNAU

Example

```
PNST 1 //Pseudo-random noise signal type set to QDI-BCM
PNSA 1 //Pseudo-random noise signal advance set to ACTIVE PIXELS
PNSM 0 //Pseudo-random noise signal mode set to AUTO
PNSP 0 //Pseudo-random noise signal procedure set to CONTINUOUS
PNAU   //Pseudo-random noise generated

GPER?  //Returns the pixel error rate (in errors per billion)
0.88

GNPT?  //Returns the number of pixels measured (in billions)
4.255

GCET?  //Returns the total number of errors detected on the red, green,
and blue components along with the total number of bad pixels
0,21,0,21

GFED?  //Returns data related to any error (first error only)
40018C,FFFFFF
```

Related commands GPER?, GNPT?, GCET?, GFED?

PNGU

Pseudo Noise Generator Use

Class — Signal Analyzer - Pseudo-random noise

Description — Loads the hardware required to generate pseudo-random noise (per the latest pseudo-random noise signal settings).

Command syntax — PNGU

Example 1

```
PNSF 1 //Pseudo-random noise signal format set to CURRENT (internal)
PNST 1 //Pseudo-random noise signal type set to QDI-BCM
PNSA 1 //Pseudo-random noise signal advance set to ACTIVE PIXELS
PNSM 0 //Pseudo-random noise signal mode set to AUTO
PNSP 0 //Pseudo-random noise signal procedure set to CONTINUOUS
PNSG 1 //Pseudo-random noise signal gate set to ON
PNGU   //Output Pseudo-random noise using latest parameters
```

Example 2 — To stop pseudo-random noise output:

```
PNSG 0 //Pseudo-random noise signal gate set to OFF
PNGU
```

Related commands — PNSG

PNSA

Pseudo Noise Signal Advance

Class — Signal Analyzer - Pseudo-random noise

Description — Controls how often pseudo-random noise pixels are calculated.

Command syntax — PSNA *value*

value

0 = every pixel clock

1 = every active pixel clock

Query syntax — PNSA?

Query response — 0 or 1

Example

```
PNSA 1 //Set calculation to pixel every clock
PNGU
```

Related commands — PNGU

PNSG

Pseudo Noise Signal Gate

Class: Signal Analyzer - Pseudo-random noise

Description: Gates on or off the output of pseudo-random noise.

Command syntax: PNSG *gate*

gate

0 = Pseudo-random noise is not output (the selected image is output)

1 = Pseudo-random noise is output (replacing the selected image output)

Query syntax: PNSG?

Query response: 0 or 1

Example:

```
PNSG 1 //Output pseudo-random noise from the generator
PNGU
```

Related commands: PNGU

PNSM

Pseudo Noise Signal Mode

Class — Signal Analyzer - Pseudo-random noise

Description — Determines how the pseudo-random noise sequence seed and run-length are determined.

Command syntax — PNSM *mode*

mode

0 = Auto mode. The sequence seed and run-length parameters are set automatically. The seed is automatically set to 0x08000001. Noise values are advanced according to the current setting of the PNSA parameter. If PNSA is set to 0 (every pixel), the sequence length is automatically set to the total number of pixels (per frame) minus one. Alternately, if PNSA is set to 1, noise is advanced every active pixel, and the length is set to the size of the HRES*VRES active area (per frame) minus one.

1 = Manual mode. The sequence seed and run-length must be manually set using the PNSL and the PNSS commands.

Query syntax — PNSM?

Query response — 0 or 1

Example

```
PNSM 0 //set pseudo-random noise seed and run-length values automatically
PNGU
```

Related commands — PNGU

PNSP

Pseudo Noise Signal Procedure

Class — Signal Analyzer - Pseudo-random noise

Description — Selects the procedure used when making pseudo-random noise measurements.

PNSP *procedure*

procedure

0 = CONTINUOUS (stop after key press, knob turn, or any I/O). In this mode, noise testing continues until either a key-press, a knob-turn, or serial/GPIB/host I/O port activity is detected. To stop the CONTINUOUS mode remotely via the I/O ports, a “\r” is recommended.

1 = SINGLE SHOT (stop after one run-length). In this mode, a single run-length is executed before the pseudo-random noise measurement is stopped.

n = MULTI SHOT (stop after *n* run-length shots). In this mode, a number of run-lengths (*n*) are executed before pseudo-random noise measurement is stopped and results become available.

Query syntax — PNSP?

Query response — 0 - 2

Example —

```
PNSP 23 // run 23 sequences of the pseudo-random noise measurement
PNGU
```

Related commands — PNGU

PRAT?

Pixel RATe query

Class	Format parameter setting - Video resolution
Description	Returns the current pixel rate setting.
Query syntax	PRAT?
Query response	pixel rate
Example	`PRAT?` `+25.1752E+06`
Related commands	TMAU

PREG

PRE-emphasis Gate

Class — Format parameter settings

Description — Enables and disables adding pre-emphasis to the Open LVDI digital outputs on generators that support LVDI outputs. The PREG? query returns the current setting of PREG. Pre-emphasis is used to add compensation for signal loss in long cables.

Command syntax — PREG *mode*

mode

0 = Pre-emphasis OFF

1 = Pre-emphasis ON

Query syntax — PREG?

Query response — *mode*

Other required commands — FMTU or ALLU

PSHD

Probe Sync Pulse Horizontal Delay

Class
Special Sync Probe Pulse

Description
Sets the delay (in pixels) of the line(s) on which the probe pulse occurs on the special sync output. The PSHD? query returns the current PSHD value.

Command syntax
PSHD *width*

width integer
0=PSVD(HTOT - PSPW-1)

Query syntax
PSHD?

Query response
width

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands
PSPG, PSPW, PSPP, PSVW, PSPM

Example

```
PSPG 1      // Enables probe pulse on special sync
PSPP 1      // Sets probe pulse polarity to positive
PSPW 10     // Sets probe pulse width to 10 pixels
PSHD 200    // Sets probe pulse horizontal delay to 200 pixels
PSVD 300    // Sets probe pulse vertical delay to 300 pixels
ALLU        // Applies the settings
```

PSPG

Probe Sync Pulse Gate

Class — Special Sync Probe Pulse

Description — Enables and disables the probe pulse on the special sync output. The PSPG? query returns the current PSPG mode.

Command syntax — PSPD *mode*

mode integer

0 = OFF

1 = ON

Query syntax — PSPG?

Query response — 0 or 1

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands — PSPP, PSPW, PSHD, PSVW, PSPM

Example

```
FSPG 0      // Disables frame sync
PSPG 1      // Enables probe pulse on special sync
ALLU        // Applies the settings
```

PSPM

Probe Sync Pulse Mode

Class — Special Sync Probe Pulse

Description — Determines what lines in the frame or field the probe pulse occurs on the special sync output. The PSPM? query returns the current PSPM value.

Command syntax — PSPM *mode*

mode integer

0 = once per frame

1 = every active line in frame

3 = every line in frame

4 = custom pulse for specifying vertical pulse across multiple lines

Query syntax — PSPM?

Query response — 0, 1, 3 or 4

Other required commands — The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands — PSPG, PSPP, PSPW, PSHD, PSVW

Example

```
PSPG 1      // Enables probe pulse on special sync
PSPP 1      // Sets probe pulse polarity to positive
PSPW 10     // Sets probe pulse width to 10 pixels
PSHD 200    // Sets probe pulse horizontal delay to 200 pixels
PSVD 300    // Sets probe pulse vertical delay to 300 pixels
PSPM 1      // Sets probe pulse to occur on each active line in a frame
ALLU        // Applies the settings
```

PSPP

Probe Sync Pulse Polarity

Class
Special Sync Probe Pulse

Description
Sets the polarity of the probe pulse on the special sync output. The PSPG? query returns the current PSPP value.

Command syntax
PSPP *polarity*

polarity integer
0 = negative

1 = positive

Query syntax
PSPP?

Query response
0 or 1

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands
PSPG, PSPW, PSHD, PSVW, PSPM

Example

```
PSPG 1      // Enables probe pulse on special sync
PSPP 1      // Sets probe pulse polarity to positive
ALLU        // Applies the settings
```

PSPW

Probe Sync Pulse Width

Class
Special Sync Probe Pulse

Description
Sets the width in pixels of the probe pulse on the special sync output. The PSPW? query returns the current PSPW value.

Command syntax
PSPW *width*

width integer
1 pixel to (HTOT - 1))

Query syntax
PSPW?

Query response
width

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands
PSPG, PSPP, PSHD, PSVW, PSPM

Example

```
PSPG 1      // Enables probe pulse on special sync
PSPP 1      // Sets probe pulse polarity to positive
PSPW 100    // Sets probe pulse width to 100 pixels
ALLU        // Applies the settings
```

PSVD

Probe Sync Pulse Vertical Delay

Class
Special Sync Probe Pulse

Description
Sets the line in the frame or field that the probe pulse occurs on the special sync output. The PSVD? query returns the current PSVD value.

Command syntax
PSVD *line*

line integer
0 = PSVD(VTOT-1)

Query syntax
PSVD?

Query response
line

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands
PSPG, PSPW, PSPP, PSHD, PSPM

Example

```
PSPG 1      // Enables probe pulse on special sync
PSPP 1      // Sets probe pulse polarity to positive
PSPW 10     // Sets probe pulse width to 10 pixels
PSVD 300    // Sets probe pulse vertical delay to 300 pixels
ALLU        // Applies the settings
```

PSVW

Probe Sync Pulse Vertical Width

Class
Special Sync Probe Pulse

Description
Sets the width in lines of the probe pulse on the special sync output. The PSVW? query returns the current PSVW value. To enable the setting of the pulse in number of lines you must specify custom for probe pulse mode (PSPM=4), the probe pulse horizontal delay to 0 (PSHD=0) and the horizontal pulse width (HSPW) to HTOT -1.

Command syntax
PSVW *width*

width integer
1 line to (VTOT - 1))

Query syntax
PSVW?

Query response
width

Other required commands
The FMTU command instructs the generator to use the new settings. The ALLU command updates the hardware to the new settings and redraws the test image.

Related commands
PSPG, PSPP, PSHD, PSVW, PSPM, PSPW

Example

```
PSPG 1      // Enables probe pulse on special sync
PSPP 1      // Sets probe pulse polarity to positive
PSPM 4      // set pulse to custom to enable vertical length in lines
PSHD 0      // set horizontal pulse delay to 0
PSPW 639    // set horizontal pulse delay to HTOT-1
PSVW 100    // Sets probe pulse vertical width to 100 lines
ALLU        // Applies the settings
```

PWD?

Print Working Directory

Class	Tools
Description	Lists the current directory.
Query syntax	PWD?
Query response	List of the directory
Related commands	None
Example	`PWD?` `\tffs0\generator\images`

PXAR?

Pixel Aspect Ratio Query

Class	Format parameter setting - HDMI active video
Description	Reads the aspect ratio of pixels in active regions of the raster image.
Query syntax	PXAR?
Query response	aspect ratio
Related commands	NCPP
Example	`PXAR?` `+1.00000E+00`

RATC

pixel RATe Calibration factor

Class — System parameter settings

Description — Sets an internal multiplication factor used in setting the pixel clock frequency. The multiplication factor can be set to compensate for the frequency error of the internal reference crystal. Having to use a factor outside of the typical range may indicate a failure of generator's hardware. Reinitializing the generator's memory sets the calibration factor to a factory-default setting of 1.00000.

Note: *The RATC parameter is a system level parameter that will affect the pixel clock frequency of all formats that are recalled. The RATC value will be retained when the generator is powered down and back up again. Query the current setting of RATC if you are experiencing problems with the pixel clock or scan rate being off in frequency.*

Command syntax — RATC *factor*

factor

floating point number equal to calibration factor

typical min = 0.99990

typical max = 1.00010

Query syntax — RATC?

Query response — *factor*

Example

```
RATC 1.00007  // Increases pix clk by factor of 1.00007
```

RECT

draw a RECTangle

Class
Custom image primitive

Description
Draws a rectangle whose sides are parallel to the vertical and horizontal axes of displayed video. It uses six parameters. The first is the *color* of the line. The next two parameters are the pixel *width* and *height* of the rectangle. The fourth and fifth parameters are the *x* and *y* coordinates for the top left corner of the rectangle. The last parameter is the *fill*.

Command syntax
RECT *color width height x y fill*

color
available colors

width
total number of horizontal pixels

height
total number of lines

x, y
positive integer numbers

fill
available fill patterns

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
RECT gray50 15 20 50 40 GrayPat50
// Draw a 50% gray rectangle 15 pixels wide and 20 pixels high
// with top left corner at X=50, Y=40 Fill with 50% active pixels

ALLU  // Update hardware to current buffer contents
```

REDG

RED Gate

Class	Video Gate
Description	Toggles the red video signal gate.
Command syntax	REDG *mode* *mode* 0 = disable 1 = enable
Query syntax	REDG?
Query response	0 or 1
Other required commands	ALLU to invoke the command.
Related commands	BLUG, GRNG
Example	`REDG 0; ALLU  // disable red video component`

RFLD

Repeat FieLD

Class — Format parameter setting - Video resolution

Description — Determines if identical video information is output for each field of an interlaced (SCAN = 2) format. The RFLD? query returns the current setting of RFLD.

Command syntax — RFLD *mode*

mode

0 = disabled

1 = enabled

Query syntax — RFLD?

Query response — 0 or 1

Other required commands — FMTU or ALLU

Example

```
SCAN 2  // Set Interlaced scanning
RFLD 1  // Enable repeat field buffer
FMTU    // Update hardware with format data
```

RGBW

RGB Write

Class LUT Management

Description Writes RGB levels to the slot location specified within the current lookup table buffer when a lookup table editing session is active, and writes the levels directly to the LUT hardware when a lookup table editing session is not active.

Command syntax RGBW *slot red_level green_level blue_level*

slot integer

0 to 15 when PELD = 4

0 to 255 when PELD = 8

red_level, green_level, blue_level integer

min = 0

max = LMAX setting (255 nominal)

Related commands RGBQ?

Example

```
IMGL RASTER
IMGU
SLUT 0                                  // clears the look up table
LINE RED 100 100 500 400                // creates red line
RECT GREEN 200 200 300 200 GRAYPAT100   // creates green rectangle
OVAL BLUE 200 200 100 100 GRAYPAT100    // creates blue oval
RGBW 1 255 255 0                        // changes red line to yellow
RGBW 2 255 0 255                        // changes green rect. to magenta
RGBW 3 0 255 255                        // changes blue oval to cyan
```

RM

ReMove

Class Tools

Description Removes a file that resides in the current directory.

Command syntax RM *filename*

Command response *filename*
Any file in a generator or file server library directory.

Related commands None

Example
```
RM hello.o
```

SAMP

Digital Audio Sinewave Amplitude

Class — Parameters (Audio Signal and Timing)

Description — Sets the amplitude in decibels of the audio stream sinewave output by the generator.

Command syntax — SAMP *amplitude* (sets all channels)

amplitude

-96.3 to 0 (if NBPA is 16-bits)

-120.4 to 0.0 (if NBPA is 20-bits)

-144.5 to 0.0 (if NBPA is 24-bits)

Query syntax — SAMP?

Query response — *amplitude*

Example —

```
SAMP -60.0                    // Sets all channels to -60 amplitude
FMTU
```

Related commands — SRAT, SMIN?, SMAX?

SCAL

Self CALibrate

Class System calibration setting

Description Causes a generator equipped with self-calibration circuitry to go through its self-calibration cycle.

Command syntax SCAL

SCAN

SCAN fields per frame

Class — Format parameter setting - Video resolution

Description — Establishes the number of fields scanned per frame. Set to 1 for progressive (non-interlaced) scan and 2 for interlaced scan. The SCAN? query returns the current setting of SCAN.

Command syntax — SCAN *fields*

fields

1 = progressive (non-interlaced)

2 = interlaced

Query syntax — SCAN?

Query response — *fields*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
SCAN  2// Select interlace in buffer
FMTU   // Update hardware to current buffer contents
```

SDLY

Sequence step DeLaY

Class
Sequence editor control

Description
Sets how long a sequence step will pause before advancing to the next step in the auto run mode. A sequence step will use the last value set by the SDLY command. The SDLY? query returns the current setting of SDLY.

Command syntax
SDLY *delay* | *-frames*

delay
Delay time in seconds as a floating point number.

frames
Delay in frames. Type minus (-) character before integer.

min = 0.0 seconds; -1 frame

max = 1.70E38 seconds (infinite)

Query syntax
SDLY?

Query response
delay

Other required commands
SMOD setting must be equal to 3 in order for the SDLY setting to have any affect on sequence operation.

Example

```
SDLY 5.0  // Set delay to five seconds per step
SDLY -3   // Set delay to three frames per step
```

SDMG

Sonic Data Mixer Gate

Class Parameters (Audio Signal and Timing)

Description Configures the generator to use either an internal or external audio source.

Note: *Setting the mask "external" bit to 1 causes the SPDIF audio signal to be passed through the generator. In this case, the Audio InfoFrame CT, CC, SF, and SS parameters are set to 0, indicating that the stream header should be used to determine audio coding type, channel type, sampling frequency, and sample size, respectively. If both "external" and "sdg" bits are set to 1 simultaneously, then an error is generated as the generator's sonic data mixer does not currently support proportional mixing of internal and external sources.*

Important: *Restarting the generator does not change this setting.*

Command syntax SDMG *mask*

mask

1 = sdg (internal)

2 = external

Example 1

```
SDMG 1   // causes the generator allow the SPDIF audio signal to be
            passed through
FMTU
```

SEOS

Set End Of String

Class GPIB port control

Description Controls how a generator reads strings, when reading multi-line responses. In GPIB communication both the sender and receiver first have to agree on end-of-string parsing. The SEOS command enables users to determine if the generator should use line feed for end-of-string parsing.

Command syntax SEOS *integer*

integer

0 = Configures the generator to not test end-of-strings, and to send EOI only on the last character of the entire response. Use this option to receive an entire multi-line response in a single read operation. Leave the VISA “Enable Termination Character” option set to FALSE.

1 = Use end-of-string testing (default).

Query syntax SEOS?

SEQA

SEQuence save As

Class — Sequence memory management

Description — Saves the current contents of the sequence edit buffer using the given name.

Command syntax — SEQA *name*

name
A valid MS-DOS filename (8 characters minus any extension)

Example

```
SEQA MY_SEQ  // Save with the name "MY_SEQ"
```

SEQB

SEQuence editing Begin

Class — Sequence editor control

Description — Marks the beginning of a sequence editing session.

Command syntax — SEQB

Other required commands — Use either a SEQL command to load an existing sequence or a SEQN command to create a new sequence. Use SEQE when ending the editing session.

Example

```
SEQN  // Initialize sequence edit buffer
SEQB  // Start sequence editing session

      // One or more sequence editing commands ...

SEQE  // End sequence editing session
```

SEQE

SEQuence editing End

Class — Sequence editor control

Description — Marks the end of a sequence editing session.

Command syntax — SEQE

Other required commands — Use SEQB when starting the editing session. Use SEQA or SEQS to save changes.

Example

```
EQB             // Start sequence editing session

                // One or more sequence editing commands ...

SEQE            // End sequence editing session
SEQA MYSEQ_02   // Save edited sequence as "MYSEQ_02"
```

SEQK

SEQuence Kill

Class — Sequence memory management

Description — Deletes a sequence by name. The query returns a 1 if the named sequence can be deleted. If sequence is read-only or non-existent, the query returns a 0.

Command syntax — SEQK *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax — SEQK? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response — 0 or 1

Example

```
SEQK MY_SEQ  // Delete seq called "MY_SEQ"
```

SEQL

SEQuence Load

Class
Sequence memory management

Description
Copies the sequence having a name equal to *name* from sequence memory into the sequence edit buffer. The query returns a 1 if the named sequence can be loaded; otherwise, a 0 is returned.

Command syntax
SEQL *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax
SEQL? *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query response
0 or 1

Other required commands
An SEQU command must be executed after the SEQL command to start running the sequence.

Example

```
SEQL MY_SEQ  // Load "MY_SEQ" dir in edit buffer
SEQU         // Start running the sequence in the buffer
```

SEQN

SEQuence New

Class
Sequence editor control

Description
Initializes the sequence edit buffer. The name *name* is assigned as the sequence's name. The query will return the name that has been assigned as the sequence's name.

Command syntax
SEQN *name*

name
optional valid MS-DOS filename (8 characters minus any extension)

Query syntax
SEQN?

Query response
name

Example
```
SEQN         // Init edit buffer without assigning a new name
```
or
```
SEQN MY_SEQ  // Init edit buffer with name of "MY_SEQ"
```

SEQP

SEQuence Path

Class — Sequence memory management

Description — Sets the current sequence path name to a given directory. The query will return the current path name.

Command syntax — SEQP *name*

name
a valid MS-DOS filename (8 characters minus any extension)

Query syntax — SEQP?

Query response — Current sequence path name.

Example

```
SEQP BURN  // Sequences in BURN directory will be listed
```

SEQQ?

SEQuence Query pointer

Class
Sequence memory management

Description
Returns number sequence names from the list of all the sequence names stored in sequence memory beginning at *index*. The directories are kept in alphanumeric order. The generator maintains internal variables for the current *index* and *number* values. The value of *index* is automatically incremented by *number* after the query is executed. Sending the query with just an *index* parameter, will return the same number of names as the last time, starting at the given index. Sending the query with no parameters will return the next set of names in the directory buffer.

Query syntax
SEQQ? *index number*

index
positive integer number

number
positive integer number

Query response
List of specified sequence names.

Example 1
```
SEQQ? 1 9999  // List the names of all sequences stored in memory
```

Example 2
```
SEQQ? 1 10  // List names of the first ten sequences stored in memory
SEQQ? 21    // List names of the 21st through the 30th sequences
SEQQ?       // List names of the 31st through the 40th sequences
```

SEQS

SEQuence Save

Class — Sequence memory management

Description — Saves the current contents of the generator's sequence edit buffer back to the memory location from which they were originally read.

Command syntax — SEQS

SEQU

SEQuence Use

Class: Sequence memory management

Description: Runs the sequence currently stored in the sequence edit buffer. The SEQU? query returns the sequence name currently set in the sequence edit buffer.

Command syntax: SEQU

Query syntax: SEQU?

Query response: name

Other required commands: The sequence in the edit buffer must have a non-zero SMOD setting to run.

Example:

```
SEQL MY_SEQ  // Load "MY_SEQ" dir in edit buffer
SEQU         // Start running the sequence in the buffer
```

SLUT

Set Look-Up Table

Class LUT Management

Description Sets up the color look-up-table (LUT) for rendering and displaying selected colors from defined sets. This command is made available for testing low-level drawing firmware and is not intended for use by end users.

Command syntax SLUT *colorset*

colorset integer
Bit mask indicating desired color sets

Example 1
```
SLUT 65536  // Setup for HUERGB colorset
```

Example 2
```
SLUT 0      // clears look up table
```

SMAX?

Digital Audio Sinewave Maximum

Class	Parameters (Audio Signal and Timing)
Description	Returns the maximum amplitude of the digital audio sinewave output from the generator.
Query syntax	SMAX?
Query response	maximum amplitude (0 - 65,535)
Related commands	SRAT, SAMP, SMIN?

SMIN?

Digital Audio Sinewave Minimum

Class	Parameters (Audio Signal and Timing)
Description	Returns the minimum amplitude of the digital audio sinewave output from the generator.
Query syntax	SMIN?
Query response	minimum amplitude (0 - 65,535)
Related commands	SRAT, SAMP, SMAX?

SMOD

Sequence operating MODe

Class
Sequence editor control

Description
Sets the sequence mode. The SMOD? query returns the current setting of SMOD.

Command syntax
SMOD *mode*

mode

0 = disable

1 = enable manual step mode that stops at last step

2 = enable manual step mode that wraps to first step after last step

3 = enable continuous auto stepping

Query syntax
SMOD?

Query response
mode

Other required commands
The SEQL command loads the sequence and SEQU starts to run it.

Example

```
SEQL MY_SEQ  // Load "MY_SEQ" in edit buffer
SEQU         // Start running the sequence in the buffer
SMOD 3       // Set the sequence mode
```

SNUM

draw sequence Step NUMber

Class
Custom image primitive

Description
Displays the sequence step number to an image when drawn as part of a test sequence. The number, along with the word “Step,” appears in a small box. The SNUM command uses three parameters. The first is the *color* used for the text and box border. The next two parameters are the *x* and *y* coordinates for the position of the box.

Command syntax
SNUM *color x y*

color
available colors

x, y
positive integer numbers

Other required commands
The displaying of sequence step numbers must be enabled with the DNUM command, and the custom image must have been loaded as part of a sequence in order for this primitive to be drawn.

Example

```
SNUM white 50 50  // Display seq. num. in box with top left corner at
                  // X=50, Y=50
```

SPAX

slider image SPAcing X

Class Image editor control

Description Sets the horizontal spacing of certain elements in some built-in test images. The SPAX? query returns the current SPAX setting.

Command syntax SPAX *x_spacing*

x_spacing integer
number of pixels

Query syntax SPAX?

Query response *x_spacing*

Example
```
SPAX 20
```

SPAY

slider image SPAcing Y

Class — Image editor control

Description — Sets the vertical spacing of certain elements in some built-in test images. The SPAY? query returns the current SPAY setting.

Command syntax — SPAY *y_spacing*

y_spacing integer
number of pixels

Query syntax — SPAY?

Query response — *y_spacing*

Example — `SPAY 20`

SRAT

Digital Audio Sinewave Rate

Class — Parameters (Audio Signal and Timing)

Description — Sets the frequency of the audio sinewave from the generator.

Command syntax — SRAT *rate*

rate
20.0 to 20.0E3 (Hz)

Query syntax — SRAT?

Query response — *rate*

Example —
```
SRAT 10.0E3
FMTU
```

Related commands — SAMP, SMAX?, SMIN?

SSST

Select Sync Signal Type

Class — Format parameter setting - Synchronization

Description — Selects the type of sync signal used to synchronize the display. In general, any one of three different types of sync can be selected to synchronize the display. The availability of different sync types is specified using the ASCT, DSCT, and DSST commands. Some displays may not accept one (or more) types of sync. For example, a digital video monitor cannot accept analog composite sync because analog signal transmission is not used. Also, a PGA display cannot accept digital separate HS and VS because only one sync wire is provided in the cabling. In these cases, one (or more) of the sync types (ASCT, DSCT, or DSST) is set to 0, indicating that they are not supported. If a non-supported sync type is selected using the SSST command, then the corresponding sync outputs of the generator will remain disabled. The SSST? query returns the type of sync (if any) that is currently selected.

Command syntax — SSST *type*

type

0 = no sync

1 = digital separate horizontal and vertical sync (DHS & DVS)

2 = digital separate sync (DSS)

3 = digital separate composite sync (DCS)

4 = analog composite sync (ACS)

5 = DSS and ACS

6 = DCS and ACS

7 = DSS, DCS, and ACS

8 = DPMS-OFF (DSS)

9 = DPMS-SUSPEND (DSS)

10 = DPMS-STANDBY (DSS)

11 = DCS & DSS

Query syntax — SSST?

Query response — *type*

Other required commands

The desired sync type selected must not be set to void with the ASCT, DSCT, or DSST commands. To actually output the selected sync signal, it must be gated on with the appropriate ASSG, ASBG, ASGG, ASRG, CSPG, HSPG, and VSPG settings.

Example

```
DSST 1  // Set Amer. H&V in buffer
HSPG 1  // Enable H sync in buffer
VSPG 1  // Enable V sync in buffer
SSST 1  // Select sep H&V sync in buffer
FMTU    // Update hardware to current buffer contents
```

STRG

STRetchinG SCL Low Signal

Class
EDID and DDC control

Description
Enables a stretching capability for the receiver of the HDMI analyzer. Each time a host accesses the I2C receiver bus (for example, to read the EDID), the receiver stretches the SCL low signal for 5 ms.

Enable stretching for testing purposes only.

Command syntax
STRG *value*

value

0 = deactivate stretching

1 = activate stretching of SCL low signal for 5 ms

Query syntax
STRG?

Query response
0 or 1

Example

```
STRG 1
DIDU
```

Related commands
DIDU

STEP

sequence STEP number

Class
Sequence editor control

Description
Selects a step in the sequence edit buffer. It is context sensitive. While editing a sequence (between SEQB and SEQE commands), the STEP command selects a step to be edited. Outside of the sequence editor and while running a sequence, the command selects a step to be executed.

The STEP? query returns the current setting of STEP.

Command syntax
STEP *step*

step
min = 1

max = See description

Query syntax
STEP?

Query response
step

Other required commands
When running a sequence, the SEQU command must be executed after the STEP command to load the format and display the image selected in the step.

Example

```
STEP 5  // Select fifth step in current sequence
SEQU    // Load format and draw image in current step
```

SVSG

Single Video Signal Gating

Class Video Gate

Description Determines which output colors are enabled. The SVSG? query returns the current SVSG setting.

Command syntax SVSG *gate_mask*

gate_mask

Gate Mask	Red	Green	Blue
0	Off	Off	Off
1	Off	Off	On
2	Off	On	Off
3	Off	On	On
4	On	Off	Off
5	On	Off	On
6	On	On	Off
7	On	On	On

Query syntax SVSG?

Query response *gate_mask*

Example

```
SVSG 7
```

SXAR

Signal Aspect Ratio

Class — Format parameter setting - active video

Description — Sets the natural aspect ratio of the video signal format (or “coded frame”) that transports images to the display.

Command syntax — SXAR *aspect_ratio*

aspect_ratio
0.75 to ˜2.39

Note: *For a listing of established aspect ratios, see the table on page 915 (CXAR command).*

Related commands — CXAR, EXAR

Example

```
SXAR 1.33 // Sets 4:3 video signal aspect ratio for source content
FMTU
```

SXCX

Signal-From-Content Aperture Map

Class — Format parameter setting - active video

Description — Sets the proper parameters to values necessary to fit CXAR-shaped image content to the SXAR-shaped aperture of the signal interface timing format.

Upon executing this command, the following actions are performed:

1. The EXAR value is set to the CXAR value (EXAR=CXAR).
2. The EXCX value is set to 0 (EXCX=0).
3. The SXEX value is set to value entered for this command (SXEX=SXCX).

Command syntax — SXCX *code*

code
0 to 131071 (in decimal)

Note: *For help in determining the proper mapping code, follow the procedure on page 991 (EXCX command).*

Related commands — SXEX, EXAR, EXCX, CXAR, SXCX, SXAR

Example

```
SXCX 264 //Use centered shrink w/black bars top & bottom
FMTU
```

SXEX

Signal-From-Extended Aperture Map

Class — Format parameter setting - active video

Description — Maps EXAR-shaped image content into the SXAR-shaped signal interface.

Command syntax — SXEX *code*

code

0 to 131071 (in decimal)

The mapping code is made up of three binary field codes as follows:

- Bits 0-2 are the *Squeeze/Stretch* (“S”) field code
- Bits 3-9 are the *Letterbox/Pillar* (“L”) field code
- Bits 10-16 are the *Safe Area* (“K”) field code

Note: *For help in determining the proper mapping code, follow the procedure on page 991 (EXCX command).*

Related commands — EXAR, SXAR, EXCX, SXCX

Example

```
SXEX 264 //Use centered shrink w/black bars top & bottom
FMTU
```

TASK?

Class Tools

Description Lists the current tasks.

Query syntax TASK?

Query response Tabular list of tasks

Related commands None

Example

```
TASK?
NAME         ENTRY        TID    PRI   STATUS      PC       SP     ERRNO  DELAY
---------- ------------ -------- --- ---------- -------- -------- ------- -----
tExcTask   excTask        f549d8   0 PEND         415e84   f548f8       0     0
tLogTask   logTask        f52050   0 PEND         415e84   f51f78       0     0
tDcacheUpd dcacheUpd      f2d7d0   1 READY        39fd44   f2d748   3006c     0
tCShell    1849d0         e393a8   1 PEND         39ba74   e38eb8       0     0
tCShell0   1849d0         d2b5f8   1 READY        3a0780   d2b100       0     0
tPcmciad   pcmciad        f50550   2 PEND         415e84   f50470       0     0
tWdbTask   392880         e3b6e0   3 PEND         39ba74   e3b5f8       0     0
tSerRxTx   RxTxTaskEntr   d95580   7 READY        39fd44   d954f8       0     0
cioPipeDraiDrainPipe__8   ffeb98   8 PEND         39ba74   ffea38  3d0002     0
appMain    appMain__Fv    da5798  10 READY        39fd44   da55e0       0     0
tNetTask   netTask        e69e28  50 READY        39ba74   e69d70       0     0
tWebUI     AcceptTaskEn   d77088  50 PEND         39ba74   d76ef0       0     0
tTelnetd   telnetd        e40fa8  55 PEND         39ba74   e40e08       0     0
tFtpdTask  1c890c         e3f9b8  55 PEND         39ba74   e3f850       0     0
GPIB       MonitorEntry   d8db68  55 READY        39c170   d8dac8  3d0004     0
tTelnetOutTtelnetOutTas   d265c0  55 READY        39ba74   d262e8       0     0
tTelnetInTatelnetInTask   d25020  55 READY        39b8d0   d24cf8       0     0
tSeqTask   RunEntry__15   d71db8  90 PEND         39ba74   d71d00       0     0
tTffsPTask flPollTask     f2a268 100 READY        39fd44   f2a1e0       0     0
tPortmapd  portmapd       e42570 100 PEND         39ba74   e423f0      16     0
tHTTPd     3dac04         e22ee0 200 PEND         39ba74   e22da8       0     0
value = 0 = 0x0
```

TBOX

draw information Text BOX

Class Custom Image Primitive

Description Renders an information text box that can be added to custom images. This command allows color, position, information, and box type to be customized.

Command syntax TBOX *color %x %y info type*

color
valid color name

%x
0.0 to 1.0 normalized positioning of box center in the x direction

%y
0.0 to 1.0 normalized positioning of box center in the y direction

info
0 = format, image, line-rate, and frame-rate (default =

1 = format

2 = image

3 = sequence

4 = step number

5 = format and image

6 = sequence and step

7 = line-rate and HRES X VRES

8 = pixel-rate and HRES X VRES

9 = format, image, sequence, and step

10 = format, image, HRES X VRES, and pixel rate

11 = line-rate, frame-rate, sequence, and step

12 = pixel-rate, HRES X VRES, sequence, and step

13 = line-rate, frame-rate, pixel-rate, and HRES X VRES

14 = format, image, line-rate, frame-rate, sequence, and step

15 = format, image, HRES X VRES, pixel-rate, sequence and step

type

0 = text only

1 = text w/ border

2 = text w/ black background

3 = text w/ border and black background

Query syntax TBOX?

Query response *color %x %y info type*

Other required commands TBXG

Example

```
TBOX white 0.5 0.5 8 3
```

TBXG

Text BoX Gating

Class

Description — Enables and disables the displaying of the text box defined by the TBOX command. The TBXG? query returns the current TBXG mode.

Command syntax — TBXG *mode*

mode integer
0 = OFF

1 = ON

Query syntax — TBXG?

Query response — *mode*

Other required commands — TBOX

Example

```
TBXG 1
```

TIME

Class
System parameter setting

Description
Sets the system time in the 882.

Command syntax
TIME *hh mm ss*

hh
00 - 23

mm
00 - 59

ss
00 - 59

Query syntax
TIME?

hh:mm:ss

Example 1
```
TIME 13 44 48
```

Example 2
```
TIME?
13:44:48
```

Related commands
DATE

TEXT

draw TEXT string

Class
Custom image primitive

Description
Draws a user-defined text string. It uses five parameters. The first is *color*. The next two are the *x* and *y* coordinates for the upper left corner of the starting position of the string. The fourth parameter selects the *font*. The last parameter is the *text* string. If the string is longer than one word, it must be contained inside quotation marks.

All of the characters in the text string must have matching characters in the font selected by font name.

Command syntax
Text *color x y font "text "*

color
available colors

x, y
coordinates of top left corner of page in pixels

font
available fonts

text
approximately 30 characters (must be enclosed by quotes)

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
TEXT red 50 40 opix9 "HELLO WORLD"
     // Draw red "HELLO WORLD" at x=50 y=40 in opix9 font
```

TMAU

Timing Measurement Analyzer Use

Class DVI/HDMI Signal Analyzer

Description Initiates a measurement of the timing received from an external DVI/HDMI source (via the HDMI Input connector).

Command syntax TMAU

Example

```
TMAU       // Measure external signal's timing format parameters
TMAX:HTOT? // Read external signal's total number of horizontal pixels
              800
TMAX:HRES? // Read external signal's total number of active horizotan
              pixels 640
```

TMAX:RPTG

Timing Measurement Analyzer RePorT Gate

Class DVI/HDMI Signal Analyzer

Description Enable or disable the generation of an HTML report for the analysis results.

Command syntax TMAX:RPTG *boolean*

boolean
0 (disable) reporting, 1 (enable) reporting

Example
```
TMAU        // Measure external signal's timing format parameters
TMAX:RPTG 1 // Enables reporting of the timing measurements
```

TMAX:SCAN

Timing Measurement Analyzer parameter query

Class DVI/HDMI Signal Analyzer

Description Retrieves the measured value of the parameters queried of the last timing test run. The timing parameters can be read back via queries using the following commands

SCAN?	Returns the scan type
PRAT?	Returns the pixel rate (in Hz)
VRAT?	Returns the vertical (field) rate (VRAT = FRAT * SCAN)
HTOT?	Returns the horizontal total (in pixels)
HRES?	Returns the horizontal active (in pixels)
HSPD?	Returns the horizontal sync pulse delay (in pixels)
HSPW?	Returns the horizontal sync pulse width (in pixels)
HSPP?	Returns the horizontal sync pulse polarity
VTOT?	Returns the vertical total (in lines)
VRES?	Returns the vertical active (in lines)
VSPD?	Returns the vertical sync pulse delay (in lines)
VSPW?	Returns the vertical sync pulse width (in lines)
VSPP?	Returns the vertical sync pulse polarity
HVPD?	Returns the pixel delay between the H and V sync pulses

Query syntax TMAX:*parameter?*

parameter
The parameter name (see table above)

Example
```
PNSF 1  // Pseudo-random noise signal format set to MEASURED
PNST 1  // Pseudo-random noise signal type set to QDI-BCM
TMAU       // Measure external signal's timing format parameters
TMAX:SCAN? // Queries for the SCAN parameter that was measured
TMAX:HRAT? // Queries for the HRAT parameter that was measured
```

TOBL

set levels relative TO BLanking

Class Custom image primitive

Description Temporarily changes how the signal levels are determined for a given color intensity level. The default method uses black as the 0% reference level and peak video as the 100% level. Inserting TOBL moves the 0% reference point to the blanking (blacker than black) pedestal level. The reference point remains shifted only for as long as the image is displayed.

Command syntax TOBL

TOGG

TOGGle Hot Plug (enable/disable)

Class System

Description Enables or disables reading EDID from sink to set the Source list to hot plug formats. When enabled, only EDID formats will be shown in the Source list.

Command syntax TOGG *mode*

mode

1

Enable reading of EDID from sink. This is equivalent to pressing the Sink->Options key sequence and enabling EDID formats.

0

Disable read of EDID from sink. This is equivalent to pressing the Sink->Options key sequence and disabling EDID formats.

Query syntax TOGG?

Query response *mode*

Example
```
TOGG 0 // disables EDID formats
TOGG 1 // enables EDID formats
```

TRIA

draw a TRIAngle

Class
Custom image primitive

Description
Draws a triangle defined by its three end points. The primitive uses eight parameters. The first is line *color*. The next three pairs of parameters are the *x* and *y* coordinates for the three points. The last parameter is the *fill*. More complex filled polygons can be built up using a series of joined filled triangles.

Command syntax
TRIA *color x1 y1 x2 y2 x3 y3 fill*

color
available colors

x1, y1, x2, y2, x3, y3
positive integer number

fill
available fill pattern

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
TRIA red50 10 5 10 25 40 15 GrayPat50
     // Draw a red50 triangle at x=10,
     // y=5; x=10, y=25; x=40, y=15 with
     // 50% active pixel fill


ALLU // Update hardware to current
     // buffer contents
```

TSPG

Tri-level Sync Pulse Gate

Class Format parameter setting - Synchronization

Description Enables and disables the tri-level sync pulse. This command affects only tri-level analog composite sync types (ASCT = 1, 11, 12, 13, 14, or 15). The exact function of the TSPG command depends on the analog sync composite type selected, as shown below.



Command syntax TSPG *mode*

mode

0 = OFF

1 = ON

Query syntax TSPG?

Query response *mode*

Other required commands

The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
TSPG 1  // Enable tri-level sync pulse in buffer
FMTU    // Update hardware to current buffer contents
```

UI:MODE

Operational mode

Class — System control

Description — Sets generator operational mode

Command Syntax — UI:MODE *mode*

mode

0 = Basic mode

1 = Browse mode

Query syntax — UI:MODE?

Query response — *mode*

Example

```
UI:MODE 1  // Set operational mode to Browse mode
```

UIDN

User IDeNtification

Class
System parameter settings

Description
Sets up the text string that is placed in the upper portions of the SMPTE133 and Cubes images. The command can be used to add a company name or other identification to the images. The command will not change the text in a currently displayed image; it must be redrawn to use the new text. The factory default string is “Quantum Data.” The UIDN? query returns the current text string.

Command syntax
UIDN *string*

string
text string 80 characters in length

Query syntax
UIDN?

Query response
string

Other required commands
The IMGU command redraws the last selected test image. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
UIDN "XYZ Monitor Mfg."  // Change text string
IMGL SMPTE133            // Select image that uses the text string
IMGU                     // Draw the image using new string
```

USIZ

Unit of measure used for physical SIZes

Class
System control

Description
Sets the units of measure assumed by HSIZ and VSIZ commands to establish the physical size of the image that appears on the CRT (context sensitive; see FMTB and FMTE). The USIZ? query returns the current setting of USIZ.

Note: *Changing the USIZ parameter between inches and millimeters will convert the current HSIZ and VSIZ values to match the new unit of measure. For example, if USIZ is in inches and the current HSIZ is 10 (inches), changing USIZ from inches to mm will change HSIZ to 25.4 (mm). The USIZ command should be sent before specifying physical sizes in format command files.*

Command syntax
USIZ *units*

units

0 = sizes not given (use default)

1 = inches

2 = mm

Query syntax
USIZ?

Query response
units

Other required commands
The ALLU command updates hardware to the new setting and redraws the test image, taking the new units into account.

Example

```
FMTB        // Begin editing session

            // One or more format editing commands ...

USIZ 1      // Select inches as unit of measure in buffer
HSIZ 10.4   // Set width to 10.4 in buffer
VSIZ 7.8    // Set height to 7.8 in buffer
ALLU        // Test the new settings

            // One or more format editing commands ...

FMTE        // End editing session
```

USRA

Add USeR

Class Tools

Description Adds a user profile.

Command syntax USRA *username*

username
A name with 8 alphanumeric characters.

Example
```
USRA janedoe
USRU janedoe
```

USRK

Delete a USeR

Class Tools

Description Deletes a user profile.

Command syntax USRK *username*

username
An existing user name

Example `USRK janedoe`

USRU

Create USeR

Class Tools

Description Creates a user profile.

Command syntax USRU *username*

username
A name with 8 alphanumeric characters.

Query syntax USRU?

Query response *username*

Example
```
USRA janedoe
USRU janedoe
```

VERF?

VERsion Firmware

Class — Miscellaneous system parameters

Description — Returns the firmware version number for the runtime code and the boot code. The digits to the left of the decimal point represent the major release level. The digits to the right of the decimal point represent the revision number of the release. A second decimal point followed by more digits indicates the revision is at a given beta test level.

Query syntax — VERF?

Query response — *version runtime code: version boot code*

Example

```
VERF?
20.0882002,01.03.03
```

VERG?

VERsion Gateware

Class Miscellaneous system parameters

Description Returns the gateware version number for the programmable devices. The digits to the left of the decimal point represent the major release level. The digits to the right of the decimal point represent the revision number of the release. A second decimal point followed by more digits indicates the revision is at a given beta test level.

Query syntax VERG?

Query response *product code, revision, date code: product code, revsion, date code: product code, revsion, date code*

Example
```
VERG?
255C,39,3232006:253F,75,4252006:253A,7,4252006
```

VRAT?

Vertical RATe Query

Class — Format parameter setting - Video resolution

Description — Returns the current vertical (field) rate. This is equal to the product of the FRAT (frame rate) and SCAN (scan type) settings (FRAT * SCAN).

Query syntax — VRAT?

Query response — vertical field rate

Example

```
VRAT? //read the product of FRAT and SCAN settings
50.0000
```

Related commands — FRAT?

VRES

Vertical RESolution

Class — Format parameter setting - Video resolution

Description — Establishes the number of active lines per frame. The VRES? query returns the current setting of VRES.

Command syntax — VRES *lines*

lines

min =

- 1 (when SCAN = 1) or
- 2 (when SCAN = 2)

max = the lesser of

- VTOT-1 (when SCAN = 1) or
- VTOT-3 (when SCAN = 2)

Must be an even number when SCAN = 2.

Query syntax — VRES?

Query response — *lines*

Other required commands — The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
VRES 480  // Set 480 active lines in buffer
ALLU      // Configure hardware and redraw image
```

VSIZ

Vertical SIZe

Class
Format parameter setting - Video resolution

Description
Establishes the vertical physical size of the image on the display. Units expected (or returned) vary according to the last mode set with USIZ command. The VSIZ command is context sensitive and must appear between begin and end commands FMTB and FMTE. The VSIZ? query returns the current setting of VSIZ.

Note: *Make sure that the USIZ parameter is properly set before using the VSIZ command. Changing the USIZ setting after entering VSIZ will convert the size to match the new unit of measure.*

Command syntax
VSIZ *size*

size
physical size; positive value (floating point accepted)

Query syntax
VSIZ?

Query response
size

Other required commands
The units of measure must be properly set by USIZ before entering VSIZ. The ALLU command updates hardware to the new setting and redraws the test image, taking the new size into account.

Example

```
FMTB        // Begin editing session

            // One or more format editing commands ...

USIZ 1      // Select inches as unit of measure in buffer
HSIZ 10.4   // Set width to 10.4 in buffer
VSIZ 7.8    // Set height to 7.8 in buffer
ALLU        // Test the new settings

            // One or more format editing commands ...

FMTE        // End editing session
```

VSPD

Vertical Sync Pulse Delay

Class
Format parameter setting - Synchronization

Description
Establishes the delay between leading edge of blanking in the first (or even) field and the leading edge of the vertical sync pulse. When interlacing, delay between end of video and leading edge of vertical sync before second (or odd) field is 0.5 line shorter than the whole-line delay specified. The VSPD? query returns the current setting of the vertical sync pulse delay.

Command syntax
VSPD *lines*

lines

min =0 (when SCAN = 1) or 1 (when SCAN = 2)

max = VTOT-VRES-VSPW (when SCAN = 1) or [(VTOT-VRES-1) /2]-VSPW (when SCAN = 2)

Query syntax
VSPD?

Query response
lines

Other required commands
The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
VSPD 11  // Set V sync delay to 11 lines in buffer
FMTU     // Update hardware to current buffer contents
```

VSPG

Vertical Sync Pulse Gate

Class
Format parameter setting - Synchronization

Description
Enables and disables the digital vertical sync output. The VSPG? query returns the current mode of VSPG.

Command syntax
VSPG *mode*

mode
0 = OFF

1 = ON

Query syntax
VSPG?

Query response
0 or 1

Other required commands
To use digital vertical sync, digital separate H and V sync must be selected with the SSST command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
VSPG 1  // Enable V sync output in buffer
FMTU    // Update hardware to current buffer contents
```

VSPP

Vertical Sync Pulse Polarity

Class — Format parameter setting - Synchronization

Description — Establishes the logic sense of the digital vertical sync outputs. Setting polarity to 1 causes the leading edge of vertical sync to be a low-to-high transition. Setting polarity to 0 causes the leading edge of vertical sync to be a high-to-low transition. The VSPP? query returns the current polarity of VSPP.

Command syntax — VSPP *polarity*

polarity

0 = high-to-low transition

1 = low-to-high transition

Query syntax — VSPP?

Query response — 0 or 1

Other required commands — In order to use digital vertical sync, it must be gated on with the VSPG command and digital separate H and V sync must be selected with the SSST command. The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
VSPP 1  // Set active hi V sync in buffer
VSPG 1  // Enable V sync output in buffer
SSST 1  // Select H&V sync type in buffer
FMTU    // Update hardware to current buffer contents
```

VSPW

Vertical Sync Pulse Width

Class — Format parameter setting - Synchronization

Description — Establishes the width of the vertical sync pulse in lines. If the type specified for the selected sync signal (see SSST, ASCT, DSCT, or DSST commands) is one of the CCIR types, then the actual sync pulse width output by the generator will be 1/2 line shorter than the whole number specified. The VSPW? query returns the current setting of VSPW.

Command syntax — VSPW *lines*

Query syntax — VSPW?

Query response — *lines*

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
VSPW 3  // Set V sync width to 3 lines in buffer
FMTU    // Update hardware to current buffer contents
```

VTOT

Vertical TOTal lines per frame

Class — Format parameter setting - Video resolution

Description — Establishes the total number of lines per frame. When interlacing (SCAN=2), VTOT must be odd. The VTOT? query returns the current setting of VTOT.

The frame or picture refresh rate is equal to HRAT divided by VTOT.

The field or vertical rate is equal to the frame rate when SCAN = 1 (non-interlaced operation).

The field or vertical rate is equal to twice the frame rate when SCAN = 2 (non-interlaced operation).

Note: *The current version of the firmware does not allow you to directly enter a specific field or frame rate when setting up a format. If your test specifications call for a specific field, frame or vertical refresh rate, enter suitable values for HRAT, SCAN and VTOT to give you the desired rate.*

Command syntax — VTOT *lines*

lines

must be an odd number when SCAN = 2

min =

- 2 @ SCAN=1
- 5 @ SCAN=2

max =

- 801GC-ISA = 4096 @ SCAN=1; 4097 @ SCAN=2
- 801GF-ISA = 4096 @ SCAN=1; 8191 @ SCAN=2
- 801GP = 2048
- 801GC, GX = 4096 @ SCAN=1; 4097 @ SCAN=2
- 801GF = 4096 @ SCAN=1; 8191 @ SCAN=2

Query syntax — VTOT?

Query response — *lines*

Other required commands

The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
VTOT 525  // Set total lines//frame to 525 in buffer
FMTU      // Update hardware to current buffer contents
```

XACR

Audio Clock Recovery Data

Class — Parameters (Audio Signal and Timing)

Description — Sets the N value, and optionally sets the CTS value.

The XACR command takes effect (the new N and CTS values are encoded and transmitted to the receiver) after the packet is gated on (DPTG command) and the hardware has been updated (DPGU command).

Command syntax — XACR *n cts*

n
value of audio clock regeneration

cts
Cycle Time Stamp. If not specified, the hardware will calculate the CTS value.

Related Commands — DPTG, DPGU

XAFD

AFD Mode Setting

Class — Format parameter setting - active video

Description — Sets the SXCX, SXEX, EXAR, EXCX, and CXAR parameters to values necessary to support a given AFD code.

Command syntax — XAFD *afd_code*

afd_code
0 to 15

The following table provides a listing of AFD codes and corresponding parameter settings.

Note: *This command will not change the value of SXAR (which remains fixed by the current format). Therefore, the range of allowed AFD values are determined by the value of SXAR in the current format.*

AFD Code	SXAR	CXAR[1]	EXCX[1]	EXAR	SXEX[1]
2	1.33	1.77	0	CXAR	280
	1.77	1.77	0	CXAR	16
3	1.33 or 1.77	1.55	0	CXAR	280
4	1.33 or 1.77	> 1.77	0	CXAR	264
8	1.33	1.33	0	CXAR	0
	1.77	1.33	0	CXAR	0
9	1.33	1.33	0	CXAR	16
	1.77	1.33	0	CXAR	264
10	1.33	1.77	0	CXAR	264
	1.77	1.77	0	CXAR	32
11	1.33	1.55	0	CXAR	264
	1.77	1.55	0	CXAR	264
13	1.33	1.55	0	CXAR	8
	1.77	1.55	8	1.33	264
14	1.33	1.55	8	1.77	264
	1.77	1.55	0	CXAR	8
15	1.33	1.33	8	1.77	264
	1.77	1.33	0	1.33	8

1. Compound maps involving the EXAR extended aperture and both mapping methods SXEX & EXCX are shown in bold. In these cases, an EXCX–L_{csp} operation is first used to place CXAR-shaped content into the EXAR-shaped extended aperture. This operation is then followed by a SXEX-L_{cbb} operation which finally places the EXAR-shaped extended aperture into the SXAR-shaped output signal aperture.

Related Commands SXCX, SXEX, EXAR, EXCX, CXAR

Example
```
XAFD 11 //set parameters for AFD code 11
FMTU
```

XAUD

Audio InfoFrame Data

Class — InfoFrame Packet

Description — Writes Audio InfoFrame packet data.

Command syntax (individual parameter) — XAUD:*audparameter value*

Command syntax (complete packet) — For uncompressed audio coding type:

XAUD *type version length* [*CC* [1 [*SS* [*SF* [*CA* [*LSV* [*DMI*]]]]]]]

For compressed audio coding types:

XAUD *type version length* [*CC* [*CT* [*SS* [*SF* [*MBR* [*CA* [*LSV* [*DMI*]]]]]]]

type
4

version
1

length (bytes)
10

The remaining are Audio Infoframe data parameters (*audparameter*) as specified in EIA/CEA-861-B standard, Section 6.3:

VERS (same as *Version*)
Infoframe version

CC
Channel count (see EIA/CEA-861-B standard, Table 19 for settings)

CC2	CC1	CC0	Audio channel count
0	0	0	Refer to Stream Header
0	0	1	2ch
0	1	0	3ch
0	1	1	4ch
1	0	0	5ch
1	0	1	6ch
1	1	0	7ch
1	1	1	8ch

CT

Audio coding type (see EIA/CEA-861-B standard, Table 19 for settings)

CT3	CT2	CT1	CT0	Audio Coding Type
0	0	0	0	Refer to Stream Header
0	0	0	1	IEC60958 PCM [26, 27]
0	0	1	0	AC-3
0	0	1	1	MPEG1 (Layers 1 & 2)
0	1	0	0	MP3 (MPEG 1 Layer 3)
0	1	0	1	MPEG2 (multichannel)
0	1	1	0	AAC
0	1	1	1	DTS
1	0	0	0	ATRAC

SS

Sample size (see EIA/CEA-861-B standard, Table 20 for settings)

SS1	SS0	Sample Size
0	0	Refer to Stream Header
0	1	16 bit
1	0	20 bit
1	1	24 bit

SF

Sampling frequency (see EIA/CEA-861-B standard, Table 20 for settings)

SF2	SF1	SF0	Sampling Frequency
0	0	0	Refer to Stream Header
0	0	1	32 kHz
0	1	0	44.1 kHz (CD)
0	1	1	48 kHz
1	0	0	88.2 kHz
1	0	1	96 kHz
1	1	0	176.4 kHz
1	1	1	192 kHz

MBR

Maximum bit rate (this setting multiplied by 8KHz represents the maximum bit rate of the audio stream)

CA

Channel assignment code (see EIA/CEA-861-B standard, Table 22 for settings)

Note: *Setting the XAUD:CA value will automatically set both* DACA *and* DAXA *to corresponding values. See the table on page 925 to view these settings.*

CA								Channel Number							
7	6	5	4	3	2	1	0	8	7	6	5	4	3	2	1

CA								Channel Number							
0	0	0	0	0	0	0	0	-	-	-	-	-	-	FR	FL
0	0	0	0	0	0	0	1	-	-	-	-	-	LFE	FR	FL
0	0	0	0	0	0	1	0	-	-	-	-	FC	-	FR	FL
0	0	0	0	0	0	1	1	-	-	-	-	FC	LFE	FR	FL
0	0	0	0	0	1	0	0	-	-	-	RC	-	-	FR	FL
0	0	0	0	0	1	0	1	-	-	-	RC	-	LFE	FR	FL
0	0	0	0	0	1	1	0	-	-	-	RC	FC	-	FR	FL
0	0	0	0	0	1	1	1	-	-	-	RC	FC	LFE	FR	FL
0	0	0	0	1	0	0	0	-	-	RR	RL	-	-	FR	FL
0	0	0	0	1	0	0	1	-	-	RR	RL	-	LFE	FR	FL
0	0	0	0	1	0	1	0	-	-	RR	RL	FC	-	FR	FL
0	0	0	0	1	0	1	1	-	-	RR	RL	FC	LFE	FR	FL
0	0	0	0	1	1	0	0	-	RC	RR	RL	-	-	FR	FL
0	0	0	0	1	1	0	1	-	RC	RR	RL	-	LFE	FR	FL
0	0	0	0	1	1	1	0	-	RC	RR	RL	FC	-	FR	FL
0	0	0	0	1	1	1	1	-	RC	RR	RL	FC	LFE	FR	FL
0	0	0	1	0	0	0	0	RRC	RLC	RR	RL	-	-	FR	FL
0	0	0	1	0	0	0	1	RRC	RLC	RR	RL	-	LFE	FR	FL
0	0	0	1	0	0	1	0	RRC	RLC	RR	RL	FC	-	FR	FL
0	0	0	1	0	0	1	1	RRC	RLC	RR	RL	FC	LFE	FR	FL
0	0	0	1	0	1	0	0	FRC	FLC	-	-	-	-	FR	FL
0	0	0	1	0	1	0	1	FRC	FLC	-	-	-	LFE	FR	FL
0	0	0	1	0	1	1	0	FRC	FLC	-	-	FC	-	FR	FL
0	0	0	1	0	1	1	1	FRC	FLC	-	-	FC	LFE	FR	FL
0	0	0	1	1	0	0	0	FRC	FLC	-	RC	-	-	FR	FL
0	0	0	1	1	0	0	1	FRC	FLC	-	RC	-	LFE	FR	FL
0	0	0	1	1	0	1	0	FRC	FLC	-	RC	FC	-	FR	FL
0	0	0	1	1	0	1	1	FRC	FLC	-	RC	FC	LFE	FR	FL
0	0	0	1	1	1	0	0	FRC	FLC	RR	RL	-	-	FR	FL
0	0	0	1	1	1	0	1	FRC	FLC	RR	RL	-	LFE	FR	FL
0	0	0	1	1	1	1	0	FRC	FLC	RR	RL	FC	-	FR	FL
0	0	0	1	1	1	1	1	FRC	FLC	RR	RL	FC	LFE	FR	FL

LSV

Level shift value (see EIA/CEA-861-B standard, Table 23 for settings)

LSV3	LSV2	LSV1	LSV0	Level Shift Value
0	0	0	0	0dB
0	0	0	1	1dB
0	0	1	0	2dB
0	0	1	1	3dB
0	1	0	0	4dB
0	1	0	1	5dB
0	1	1	0	6dB
0	1	1	1	7dB
1	0	0	0	8dB
1	0	0	1	9dB
1	0	1	0	10dB
1	0	1	1	11dB
1	1	0	0	12dB

LSV3	LSV2	LSV1	LSV0	Level Shift Value
1	1	0	1	13dB
1	1	1	0	14dB
1	1	1	1	15dB

DMI

Down-mix inhibit (see EIA/CEA-861-B standard, Table 24 for settings)

DM_INH	Describes whether the down mixed stereo output is permitted
0	Permitted or no information about any assertion of this
1	Prohibited

Query syntax XAUD:*audparameter*?

Query response *value*

Example 1 The following example sets the number of audio channels (*CC* parameter) to 2 in the Audio Infoframe.

```
XAUD:CC 2
IFGU
```

Example 2 The following example sets an Audio InfoFrame with these properties:

- Seven channels (*CC* parameter)
- MPEG1 coding type (*CT* parameter)
- 16-bit sample size (*SS* parameter)
- 88.2KHz frequency (*SF* parameter)
- 72KHz maximum bit rate (*MBR* parameter)
- All but channel 3 (LFE) are allocated (*CA* parameter)
- 10dB attenuation during source device down-mixing (*LSV* parameter)
- Down-mixing permitted (*DMI* parameter)

```
XAUD 4 1 10 6 3 1 4 9 18 10 0;IFGU
```

Example 3 The following example reports the current setting for the Member Bit Rate parameter in the Audio Infoframe.

```
XAUD:MBR?
```

Related commands IFTR, IFTG, IFGU, DAXA, DACA

XAVI

Auxiliary Video Information InfoFrame Data

Class — InfoFrame Packet

Description — Writes Auxiliary Video Information (AVI) InfoFrame packet data.

Command syntax (individual parameter) — XAVI:*aviparameter value*

Command syntax (complete packet–version 1) — XAVI *type version length* [*S* [*B* [*A* [*Y* [*R* [*M* [*C* [*SC* [*ETB* [*SBB* [*ELB* [*SRB*]]]]]]]]]]]

Command syntax (complete packet–version 2) — XAVI *type version length* [*S* [*B* [*A* [*Y* [*R* [*M* [*C* [*SC* [*ETB* [*SBB* [*ELB* [*SRB* [VIC [PR [RGB [EC [ITC]]]]]]]]]]]]]]]]

type
2

version
1 = version 1
2 = version 2

length (bytes)
13

The remaining are AVI Infoframe data parameters (*aviparameter*) as specified in EIA/CEA-861-B standard, Section 6.1:

VERS (same as *Version*)
Infoframe version:
1 = version 1
2 = version 2

S
Scan information (see EIA/CEA-861-B standard, Table 8 for settings)

S1	S0	Scan Information
0	0	No Data
0	1	Overscanned (television)
1	0	Underscanned (computer)
1	1	Future

B

Bar information (see EIA/CEA-861-B standard, Table 8 for settings)

B 1	B 0	Bar Information
0	0	Bar data not valid
0	1	Vertical Bar info valid
1	0	Horizontal Bar info valid
1	1	Vertical & Horizontal Bar info valid

A

Active Format Information (AFD) present (see EIA/CEA-861-B standard, Table 8 for settings)

A 0	Active Format Information Present
0	No data
1	Active format information valid

Y

Video type (see EIA/CEA-861-B standard, Table 8 for settings)

Y 1	Y 0	RGB or YCbCr
0	0	RGB (default)
0	1	YCbCr 4:2:2
1	0	YCbCr 4:4:4
1	1	Future

R

Active Format Aspect Ratio (AFD value) (see EIA/CEA-861-B standard, Table 9 for settings)

R 3	R 2	R 1	R 0	Active Format Aspect Ratio
1	0	0	0	Same as picture aspect ratio
1	0	0	1	4:3 (Center)
1	0	1	0	16:9 (Center)
1	0	1	1	14:9 (Center)
other values				Per DVB AFD active_format field

M

Picture Aspect Ratio (see EIA/CEA-861-B standard, Table 9 for settings)

M 1	M 0	Picture Aspect Ratio
0	0	No data
0	1	4:3
1	0	16:9

M 1	M 0	Picture Aspect Ratio
1	1	Future

C

Colorimetry (see EIA/CEA-861-B standard, Table 9 for settings)

C 1	C 0	Colorimetry
0	0	No data
0	1	SMPTE 170M ITU601
1	0	ITU709
1	1	Future

SC

Non-uniform Picture Scaling (see EIA/CEA-861-B standard, Table 11 for settings)

SC 1	SC 0	Non-Uniform Picture Scaling
0	0	No known non-uniform scaling
0	1	Picture has been scaled horizontally
1	0	Picture has been scaled vertically
1	1	Picture has been scaled horizontally and vertically

ETB

Line number of end of top bar representing the last line of a horizontal letterbox bar area at the top of the picture (0 = no horizontal bar present at top of picture).

SBB

Line number of start of bottom bar representing the first line of a horizontal letterbox bar area at the bottom of the picture.

ELB

Pixel number of end of left bar representing the last horizontal pixel of a vertical pillar-bar area at the left side of the picture (0 = no vertical bar present at left of picture).

SRB

Pixel number of start of right bar representing the first horizontal pixel of a vertical pillar-bar area at the left side of the picture.

VIC

Video Format Identification Codes (see DVIC for settings).

PR

Pixel repetition for “2x” and “4x” formats (see EIA/CEA-861-B standard, Table 14 for settings) This field is set automatically based on settings for NCPP and NPPP.

PR 3	PR 2	PR 1	PR 0	Pixel Repetition for Optional (2880)
0	0	0	0	No Repetition (i.e. pixel sent once)

PR 3	PR 2	PR 1	PR 0	Pixel Repetition for Optional (2880)
0	0	0	1	Pixel sent 2 times (i.e. repeated once)
0	0	1	0	Pixel sent 3 times
0	0	1	1	Pixel sent 4 times
0	1	0	0	Pixel sent 5 times
0	1	0	1	Pixel sent 6 times
0	1	1	0	Pixel sent 7 times
0	1	1	1	Pixel sent 8 times
1	0	0	0	Pixel sent 9 times
1	0	0	1	Pixel sent 10 times

RGB

RGB Quantization Range (see EIA/CEA-861-D standard, Table 11 for settings)

Q 1	Q 0	RGB Quantization Range
0	0	Default (depends on video format)
0	1	Limited range
1	0	Full range
1	1	Reserved

EC

Extended Colorimetry (see EIA/CEA-861-D standard, Table 11 for settings)

EC 2	EC 1	EC 0	Extended Colorimetry
0	0	0	xvYCC601 (IEC 61966-2-4 with standard definition primaries)
0	0	1	xvYCC709 (IEC 61966-2-4 with high definition primaries)
-	-	-	Reserved

ITC

IT Content (see EIA/CEA-861-D standard, Table 11 for settings)

ITC	IT Content
0	No data (DVIC of the format is neither 0 or 1)
1	IT content (DVIC of the format is either 0 or 1)

Query syntax XAVI:*aviparameter*?

Query response *value*

Example 1 The following example sets the scan information (*S* parameter) to overscanned in the AVI Infoframe.

```
XAVI:S 1
IFGU
```

Example 2 The following example sets the AFD flag (*A* parameter) to not present and the picture aspect ratio (*M* parameter) to 4:3 in the AVI Infoframe.

```
XAVI:A 0; M 1;IFGU
```

Example 4 The following example reports the current settings for the following AVI Infoframe parameters:

- Video Type
- Active Format Information present
- Bar information present
- Scan information
- Colorimetry

```
XAVI:Y?
XAVI:A?
XAVI:B?
XAVI:S?
XAVI:C?
```

Related commands DVIC, NPPP, IFTR, IFTG, IFGU

XBBH

Arbitrary Bottom Border Height

Class — Format parameter setting - active video

Description — Establishes the first line of a horizontal letterbox bar area at the bottom of the image.

Command syntax — XBBH *line_number*

line_number
0 to 65535 (in decimal)

Related commands — XISH:TTYP, XRBW, XTBH

Example

```
XBBH 769
FMTU
```

XDID

EDID data write

Class
EDID and DDC control

Description
Writes new EDID structure for DVI Analyzer receiver.

Command syntax
XDID *offset bytes data*

offset (hex)
address offset (in bytes)

bytes
number of bytes (hex)

data
data (hex)

Example 1
To change the first 3 bytes of the EDID structure (after the header):

```
XDID 8 3 DE33FF
DIDU
```

Example 2
To write at offset 256 (start of block 2):

```
XDID 100 8 1122334455667788
XDID 108 8 8899AABBCCDDEEFF
DIDU
```

Related commands
DIDA, DIDB, DIDE, DIDK, DIDL, TASK?, DIDP, DIDQ, DIDS, DIDU, EDA<port>:GDID, EDA<port>:PDID

XGCP

General Control Parameter Data

Class — Data Island Packet

Description — Enables and disables the HDMI Audio/Video Mute (AVMUTE) feature. When enabled, audio and video are muted by the generator.

Important: *You can set either the AVMUTE set flag (to turn mute on) or the AVMUTE clear flag (to turn mute off) to 1 (but not both).*

Note: *The status of the mute is changed only after the packet is gated ON* (DPTG)*, the repeat mode has been set* (DPTR)*, and the hardware has been updated* (DPGU) *(see example below).*

Command syntax — XGCP *AVMUTE_set_flag*

AVMUTE_set_flag

0 = off

1 = on

Related commands — MUTE, DPTG, DPGU

Example 1 — To enable AVMUTE:

```
DPTG 7
DPTR 1
XGCP 1
DPGU
```

Once executed, use the MUTE? to continuously check until the AVMUTE state is changed (may not take place right away).

Example 2 — To disable AVMUTE:

```
DPTG 7
DPTR 1
XGCP 0
DPGU
```

Again, use the MUTE? command to continuously check until the AVMUTE state is changed.

XGDP

Generic Data Packet Data

Class — Data Island Packet

Description — Writes a generic data packet for sourcing highly-customized arbitrary data.

Command syntax (individual parameter) — XGDP:*gdpparameter value*

Command syntax (complete packet) — XGDP *data*

*data (*ASCII)
hexidecimal payload data in the form of ASCII characters (“0” through “F”)—each representing one 4-bit nibble of data (if less than 60 ASCII characters, which is less than 30 bytes of data, are specified, then the remaining bytes are set to zero)

The following are data island packet parameters (*gdpparameter*) as specified in HDMI specification, Section 5.3.

hb0
Packet type (see HDMI specification, Section 5.3.1 through 5.3.6 for settings)

hb1
Packet-specific data (see HDMI specification, Section 5.3.1 through 5.3.6 for settings)

hb2
Packet-specific data (see HDMI specification, Section 5.3.1 through 5.3.6 for settings)

pb0 – pb27
InfoFrame packet data (see HDMI specification, Section 5.3.5 for settings)

Example
```
XGDP 03AABBCC
DPGU
```

You will have to gate on the general data packet with DPTG and DPGU

XGIF

Generic InfoFrame Data

Class — InfoFrame Packet

Description — Writes generic InfoFrame packet data. This allows you to emulate any InfoFrame type (including vendor-specific).

Note: *The HDMI specification (section 5.2.3.2) requires that an HDMI packet must be transmitted at least every two VSYNC periods, or the receiver will drop out of HDMI mode. A Generic InfoFrame packet can be used for this purpose by enabling its repeat bit (see the IFTR command).*

Command syntax (individual parameter) — XGIF:*gifparameter value*

Command syntax (complete packet) — XGIF *type version length* [VERS[LEN[TYPE[INFO]]]]

type
1

version
1

length (bytes)
27

The remaining are GIF Infoframe data parameters (*gifparameter*) as specified in EIA/CEA-861-D standard, Section 6.1:

VERS (same as *version*)
Infoframe version

LEN (same as *length*)
Infoframe length (in bytes)

TYPE (same as *type*)
Infoframe type

INFO
hexidecimal payload data in the form of ASCII characters—each representing one 4-bit nibble of data. If less than 50 ASCII characters are specified, the remaining bytes are set to zero.

Query syntax — XGIF:*gifparameter* ?

Query response — *value*

Example The following example writes 10 bytes of generic InfoFrame data. The remaining bytes 11-25 will be set to zero.

```
XGIF INFO 1122EE4455BB77FF99AA
IFGU
```

Related commands IFTR, IFTG, IFGU

XISH:HINC

Image SHift Horizontal INCrement

Class ImageShift

Description Establishes the horizontal shifting increment value. The value must be less than or equal to the active horizontal resolution of the current video format, which can be queried with HRES?. If an imageshift editing session is in progress (the ISHB command was issued), the value will be changed, but not applied to the hardware until the ISHE and ISHU commands are issued. Otherwise, the command will take effect immediately.

Command syntax XISH:HINC *increment*

increment
positive integer number

Query syntax XISH:HINC?

Query response Current horizontal shifting increment value.

Example 1
```
XISH:HINC 4  //Sets the horizontal shifting increment to 4.
```

Example 2
```
XISH:HINC?  //Queries for current horizontal shifting increment.
4
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

XISH:PATH

Image SHift Path

Class ImageShift

Description Establishes two points along which the image will be shifted. The points are defined by two sets of x,y coordinates. The default coordinates are 0,0 and 100,100. The x coordinates must be less than or equal to the active horizontal resolution of the current video format, which can be queried with HRES?. The y coordinates must be less than or equal to the active vertical resolution of the current video format, which can be queried with VRES?. If an imageshift editing session is in progress (the ISHB command was issued), the path will be changed, but not applied to the hardware until the ISHE and ISHU commands are issued. Otherwise, the command will take effect immediately.

Command syntax XISH:PATH x_*start,y_start x_end,y_end*

x_start,y_start x_end,y_end
positive integer numbers

Query syntax XISH:PATH?

Query response *x_start,y_start x_end,y_end*

Example 1
```
XISH:PATH 0,0 150,20  //Sets the start point to 0,0 and the end point to
                      //150,20
```

Example 2
```
XISH:PATH?  //Queries for current path.
0,0 150,20
```

Related commands ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:SRCN, XISH:TINC, XISH:TTYP, XISH:VINC

XISH:SRCN

Image SHift SouRCe Name

Class — Image Shift

Description — Establishes the image file or bitmap file that will be used for image shifting. The default file is /Cache0/Images/Ramp. If an imageshift editing session is in progress (the ISHB command was issued), the image source will be changed, but not applied to the hardware until the ISHE and ISHU commands are issued. Otherwise, the command will take effect immediately.

Command syntax — XISH:SRCN *path/filename*

path/filename
The directory path and valid MS-DOS filename (8 characters minus any extension) of the image or bitmap file to be used for image shifting. If the file to be used is in the default path, then *path/* may be omitted.

Query syntax — XISH:SRCN?

Query response — *path/filename*

Example —
```
XISH:SRCN Master  //Selects the Master image as the current image to
                  //shift
```

Related commands — ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:TINC, XISH:TTYP, XISH:VINC

XISH:TINC

Image SHift Time INCrement

Class — Image Shift

Description — Establishes the time shift increment value, which is the number of frames to pause before shfiting the image. If an imageshift editing session is in progress (the ISHB command was issued), the value will be changed, but not applied to the hardware until the ISHE and ISHU commands are issued. Otherwise, the command will take effect immediately.

Command syntax — XISH:TINC *increment*

increment
positive integer number 0 – 999

Query syntax — XISH:TINC?

Query response — Current time shift increment value.

Example 1
```
XISH:TINC 2  //Sets the time shift increment to 2.
```

Example 2
```
XISH:TINC?  //Queries for current time shift increment.
2
```

Related commands — ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TTYP, XISH:VINC

XISH:TTYP

Image SHift Trace TYPe

Class — Image Shift

Description — Establishes the way in which image shifting will occur. A repeating trace type causes the image to shift between the start and end points, and then restart at the start point. A reverse trace type causes the image to shift between the start and end points, and then from the end point to the start point. If an imageshift editing session is in progress (the ISHB command was issued), the trace type will be changed, but not applied to the hardware until the ISHE and ISHU commands are issued. Otherwise, the command will take effect immediately.

Command syntax — XISH:TTYP *type*

type

1 = Repeat

2 = Reverse

Query syntax — XISH:TTYP?

Query response — 1 or 2

Example 1

```
XISH:TTYP 1  //Sets the trace type to 1, Repeat.
```

Example 2

```
XISH:TTYP?  //Queries for current trace type.
1
```

Related commands — ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:VINC

XISH:VINC

Image SHift Vertical INCrement

Class
Image Shift

Description
Establishes the vertical shifting increment value. The value must be less than or equal to the active vertical resolution of the current video format, which can be queried with VRES?. If an imageshift editing session is in progress (the ISHB command was issued), the value will be changed, but not applied to the hardware until the ISHE and ISHU commands are issued. Otherwise, the command will take effect immediately.

Command syntax
XISH:VINC *increment*

increment
positive integer number

Query syntax
XISH:VINC?

Query response
Current vertical shifting increment value.

Example 1
```
XISH:VINC 4  //Sets the vertical shifting increment to 4.
```

Example 2
```
XISH:HINC?  //Queries for current vertical shifting increment.
4
```

Related commands
ISHA, ISHB, ISHE, ISHG, ISHK, ISHL, ISHN, ISHP, ISHQ?, ISHS, ISHU, XISH:HINC, XISH:PATH, XISH:SRCN, XISH:TINC, XISH:TTYP

XLBW

Arbitrary Left Border Width

Class — Format parameter setting - active video

Description — Establishes the last horizontal pixel of a vertical pillar-box bar area at the left side of the image.

Command syntax — XLBW *pixel_number*

pixel_number
0 to 65535 (in decimal)

Related commands — XBBH, XRBW, XTBH

Example

```
XLBW 64
FMTU
```

XMPG

MPEG InfoFrame Data

Class — InfoFrame Packet

Description — Writes MPEG InfoFrame packet data.

Command syntax (individual parameter) — XMPG: *mpgparameter value*

Command syntax (complete packet) — XMPG *type version length* [*MB* [*MF* [*FR*]]]

type
5

version
1

length (bytes)
10

The remaining are MPEG Infoframe data parameters (*mpgparameter*) as specified in EIA/CEA-861-B standard, Section 6.4:

VERS (same as *Version*)
Infoframe version

MB
MPEG bit rate (Enter rate in Hertz [Hz])

MF
MPEG frame (see EIA/CEA-861-B standard, Table 26 for settings)

FR
Field repeat (see EIA/CEA-861-B standard, Table 26 for settings)

Query syntax — XMPG:*mpgparameter*?

Query response — *value*

Example The following example sets the data rate of the MPEG transmission in the MPEG InfoFrame data to 44.1kHz.

```
XMPG:MB 44100
IFGU
```

Related commands IFTR, IFTG, IFGU

XRBW

Arbitrary Right Border Width

Class
Format parameter setting - active video

Description
Establishes the first horizontal pixel of a vertical pillar-bar area at the right side of the image.

Command syntax
XRBW *pixel_number*

pixel_number
0 to 65535 (in decimal)

Related commands
XISH:TTYP, XTBH, XBBH

Example

```
XRBW 961
FMTU
```

XRES

X axis RESolution for custom images

Class
Image editor control

Description
Sets the width factor used to scale horizontal size and position parameters in the primitives of a custom image in the image editor buffer. The XRES? query returns the current XRES setting.

Command syntax
XRES *width*

width integer
16 to 65,536

Query syntax
XRES?

Query response
width

Example

```
XRES 1600  // Set horizontal scaling factor to 1600
YRES 900   // Set vertical scaling factor to 900
```

XSPD

Source Product Description InfoFrame Data

Class
InfoFrame Packet

Description
Writes Source Product Description InfoFrame packet data.

Command syntax (individual parameter)
XSPD: *spdparameter value*

Command syntax (complete packet)
XSPD *type version length* [*VNS* [*PDS* [*SDI*]]]

type
3

version
1

length (bytes)
25

The remaining are Source Product Description Infoframe data parameters (*spdparameter*) as specified in EIA/CEA-861-B standard, Section 6.2:

VERS (same as *Version*)
Infoframe version

VNS
Vendor name string

PDS
Product description string

SDI
Source device information (see EIA/CEA-861-B standard, Table 17 for settings)

Query syntax
XSPD:*spdparameter*?

Query response
value

Example
The following example sets the vendor name string (*VNS* parameter) to “QDI” in the Source Product Description Infoframe.

```
IFGU
XSPD:VNS QDI
```

Example 2 The following example specifies a Source Product Description InfoFrame with these properties:

- Vendor name is QDI
- Product description is HDMI-Analyzer
- Source device is Digital STB (1)

```
XSPD 3 1 25 QDI HDMI-Analyzer 1
```

Example 3 The following example reports the current setting for the Product Description parameter in the Source Product Description Infoframe.

```
XSPD:PDS?
```

XTBH

Arbitrary Top Border Height

Class — Parameters (Video Signal)

Description — Establishes the last line of a horizontal letterbox bar area at the top of the image.

Command syntax — XTBW *line_number*

line_number
0 to 65535

Related commands — XISH:TTYP, XRBW, XBBH

Example

```
XTBH 15
FMTU
```

XVSG

Video Signal Gating

Class — Format parameter settings

Description — Determines which video outputs are active when the format is selected. The same command controls both the analog and digital video outputs.

Command syntax — XVSG *red_mode, green_mode, blue_mode*

red_mode, green_mode, blue_mode

0 = OFF

1 = ON

Other required commands — The FMTU command instructs the generator to use the new setting. The ALLU command updates hardware to the new setting and redraws the test image.

Example

```
XVSG 1 1 1  // Enable all color channels
FMTU        // Update hardware to current buffer contents
```

XVSI

Video Signal Interface

Class
Format video signal

Description
Enables the specified video signal interface output for the analyzer.

Command syntax
XVSI *interface*

or

XVSI:OUT *interface*

interface

1 = DVI-A (analog)

2 = DVI-D (digital)

3 = HDMI-D (DVI)

4 = HDMI-H (HDMI)

5 = SVIDEO

6 = CVBS

7 = SDI, HD-SDI

9 = VGA

10 = DisplayPort

Query syntax
XVSI?

or

XVSI:OUT?

Query response
interface

Other required commands
The ALLU command updates hardware to the new setting and redraws the test image.

Example 1

```
XVSI 1   // Enable DVI for analog output
ALLU     // Update hardware to current buffer contents

XVSI 3   // Enable HDMI interface for DVI output
ALLU     // Update hardware to current buffer contents

XVSI:OUT 4   // Enable HDMI interface for HDMI output
ALLU         // Update hardware to current buffer contents
```

Example 2

```
XVSI?    //Queries for the currently-enabled video signal interface output
4        //HDMI-H output is currently enabled
```

Related commands XVSI:IN

XVSI:IN

Video Signal Interface INput

Class — Format video signal

Description — Enables the specified video signal interface input for the analyzer.

Command syntax — XVSI:IN *interface*

interface

0 = no interface selected

1 = HDMI-1

2 = HDMI-2

Query syntax — XVSI:IN?

Query response — *interface*

Other required commands — The ALLU command updates hardware to the new setting and redraws the test image.

Example 1

```
XVSI:IN 1   // Enable HDMI-1 input connector for the analyzer
ALLU        // Update hardware to current buffer contents
```

Example 2

```
XVSI:IN?   //Queries for the currently-enabled video signal interface
           //input
2          //HDMI-2 is currently enabled
```

Related commands — XVSI

YRES

Y axis RESolution for custom images

Class
Image editor control

Description
Sets the height factor used to scale vertical size and position parameters in the primitives of a custom image in the image editor buffer. The YRES? query returns the current YRES setting.

Command syntax
YRES *height*

height integer
16 to 65,536

Query syntax
YRES?

Query response
height

Example

```
XRES 1600  // Set horizontal scaling factor to 1600
YRES 900   // Set vertical scaling factor to 900
```

Example

```
dirn mydir      // create a directory named mymap
dirb            // begin directory context
nami 1 smpte133 // insert the name smpte133 at index 1
nami 2 flat     // insert the name flat at index 2
nami 3 raster   // insert the name raster at index 3
dire            // end directory context
dirs            // save map named mymap
dirl mydir      // load directory mydir into edit buffer
dirb            // begin directory context
namq? 1 10      // list mydir names
namy 2          // yank name at index 2
nami 1 colorbar // insert new name at index 1
dire            // end directory context
dira newdir     // save modified mydir as newdir
dirq? 1 10      // list available directories
                // (up to 10 maps starting with the 1st)
```

B Image Reference


Topics in this appendix:

- Standard image descriptions

Standard image descriptions


Acer1

Description Special test image developed per customer specifications. Consists of two sets of color bars and five blocks of “#” characters on a white crosshatch with a black background.




Acer2

Description Special test image developed per customer specifications. Consists of colorbars, lines of “#” characters, and a green border.




Acer3, Acer4, Acer5 and Acer6

Description Special test images developed per customer specifications. Consists of large and small white circles centered on either a yellow (Acer3), magenta (Acer4), cyan (Acer5), or white (Acer6) crosshatch on a black background. The Acer3 image is shown below.



Acer7 and Acer8

Description Special test image developed per customer specifications. In the primary version, five blocks of either white “#” (Acer7) or “H” (Acer8) characters on a black background are displayed. A secondary version displays black characters on a white background. The Acer7 image is shown below.



Acer9

Description Special test image developed per customer specifications. In the primary version, a mostly white field is displayed with two rows of color bars at the bottom. A secondary version displays a black field with the two rows of color bars at the bottom.




AFDtest

Description Used to test HDMI content mapping using different EIA/CEA-861-B formats. There are 10 different versions of this image. For more information, see “Testing with Active Format Description (AFD) (882 only)” on page 384.


AnsiGray

Description The primary version displays a white background with a small black pixel in the center fills the active video area. A secondary version displays a black background with a small white pixel in the center.




AnsiLght

Description The primary version displays a white background with a small black pixel in the center fills the active video area. A secondary version displays a black background with a small white pixel in the center.



Apple1

Description Special test image developed per customer specifications. A secondary version shows reverse (black characters on white background).




Audio LR, AudioLRf, AudioRAT, Audio_L, Audio_Lf, Audio_R, Audio_Rf

Description Used to configure HDMI audio output signal. The AudioLR is shown below. For more information, see “Testing HDMI audio” on page 367.

BarBlack

Description Special test image developed per customer specifications.


A secondary version shows reverse (black lines on white background).



BLU_EM, GRN_EM, RED_EM, WHT_EM, MEME1111, MEMESony, MESony_B, MESony_G, and MESony_R

Description In the primary version, the screen is filled with blue (BLU and B), green (GRN and G), red (R), or white (WHT, MEME1111, MEMEPlus, and MEMESony) EM character blocks on a black background. Only the white character has a secondary version. It is drawn with black characters on a white background.

A bitmap of a single character block is shown here. The BLU_EM image is shown below.




Test Focus

Purpose This pattern is specified by some display manufacturers for checking and adjusting focus one color at a time.

BLU_EM+, GRN_EM+, RED_EM+, WHT_EM+, MEMEPlus, MEPlus_B, MEPlus_G, and MEPlus_R

Description In the primary version, the screen is filled with blue (BLU and B), green (GRN and G), red (R), or white (WHT and Sony) EM character blocks on a black background. Only the white character has a secondary version. It is drawn with black characters on a white background.

A bitmap of a single character block is shown here. The BLU_EM+ image is shown below.



Test Focus

Purpose This pattern is specified by one or more display manufacturers for checking and adjusting focus one color at a time.

BLU_PIC, GRAY_PIC, GRN_PIC, RED_PIC, WHT_PIC

Description A solid blue (BLU), gray, green (GRN), red, or white (WHT) box fills the active video area. Only the white fill has a secondary version. It can be changed to a black fill by pressing the **Step** key. The BLU_PIC image is shown below.



Test Purity adjustment

Purpose To produce correct colors in a displayed image, the electron beams from each of the three (3) guns in the CRT should strike only their matching phosphors. A white image shows patches of various colors on a monitor with bad purity. The purity adjustment(s) should be performed before doing any brightness or color tests. In some cases, purity adjustments involve loosening and repositioning the yoke, in which case purity should be adjusted prior to doing any geometry tests.

Method The methods used for adjusting purity on a color monitor depend on the type of monitor and CRT (for example; Delta, In-Line or Single Gun). In most cases, the first step is to degauss the CRT.

Note: *For a Delta Gun CRT, turn on only the red output. A solid uniform field of red should appear. If the color is not uniform, adjust the yoke and the Purity Tabs assembly.*

If purity cannot be corrected to acceptable limits, the monitor may not have been properly degaussed or there may be a defect in the CRT or purity assembly.


Test Shadow mask warping


Purpose The purity characteristics of your CRT can change over time if you leave it on with a lot of video being displayed. This may be due to the CRT's electron beams striking its shadow mask with enough energy to cause the mask to heat. This internal heating may be enough to cause the shadow mask to warp and give bad purity.

Method Set the purity image to white and allow the monitor to run for a few minutes. Any mask warping shows up as a change in purity. You can use a color meter to measure the change. The BriteBox pattern may also be useful for measuring shadow mask warping.

Bosch

Description Special test image developed per customer specifications. This image has 6 versions.






Box_50mm, Box_64mm, Box100mm, Box150mm, Box200mm, Box250mm

Description The primary version has a solid white box in the center of the active video. Depending on the image selected, the box is sized by square millimeters. If there is room, information on the current format appears below and to the left of the box. This shows the number of active pixels and lines as well as the horizontal and vertical scan rates. A forward slash (*/*) after the number of active lines indicates the format is interlaced.

Note: *The box will be the correct size only if the correct physical active video size is set in the format.*

The Box_50mm image is shown below. The secondary version draws a black box and black text on a white background.




Test Brightness control adjustment

Purpose The wrong brightness setting may cause other tests such as Contrast, Focus, and Beam Size to be invalid. An accurate brightness setting helps give repeatable measurements throughout other tests.

Method Center your light meter probe within the center square and adjust the monitor's brightness control to obtain the required light meter reading.

BriteBox

Description The primary version has a single white box in the center of active video. The box size is controlled by the MSIZ system parameter. The secondary version adds four boxes in the corners of active video.



Test Brightness control adjustment

Purpose The wrong brightness setting may cause other tests such as Contrast, Focus, and Beam Size to be invalid. An accurate brightness setting helps give repeatable measurements throughout other tests.

Method Center your light meter probe within the center square and adjust the monitor's brightness control to obtain the required light meter reading.


Test Brightness uniformity

Purpose The light output of most picture tubes varies slightly when measured across the CRT face. This test can be used to verify that the light output variation is within your specification limits.

Method Select the inverted version and perform the Brightness Control Adjustment test on the center box. Then, center the light meter probe in each of the corner squares and note the reading you get for each square. The deviation between each of the corner readings and the center reading should be within your specification limits.

Burst (TV formats only)

Description The left side starts with reference white (+100 IRE) and black (+7.5 IRE) levels. This is followed by six bursts of sine waves. Each burst is at a different frequency, forming vertical lines of various widths. The frequencies, going from left to right, are 0.5, 1, 2, 3, 3.58, and 4.43 MHz.



Test Frequency response


Method When viewed on a TV screen, the peak intensities of all of the bursts should match the white reference level. The darkest portions between the peaks should match the black reference level.

The image can also be used with a TV waveform analyzer to check the frequency response of a video system. One scan line of the image, as it would appear on a waveform analyzer, is shown at the top of the next page . High frequency roll-off (loss) would show up as a decrease in the peak-to-peak swings on the right side of the waveform. Low frequency roll-off would show up as a decrease in the peak-to-peak swings on the left side of the waveform.

Some waveform analyzers can be set to detect and display the amplitude of the peaks. A typical amplitude waveform for a good system is shown at the bottom of the next page.


BurstTCE

Description Fills screen with a 0.5 MHz frequency. This can be increased in 0.5 MHz increments by pressing the Contents key and then the Options key. You then enable More and use the +/- increment keys.



Check511

Description — Consists of five small boxes in the corners and at the center of the active video. The boxes are on a black background. Each box consists of alternating black and white pixels that form a very fine checkerboard. The secondary version inverts the image, creating a white background. The colors of the individual pixels in the boxes also are inverted.



Test — Verify monitor resolution


Purpose — The resolution of your monitor should meet or exceed the design specifications.

Method — First adjust the brightness, contrast, and focus to their correct settings. You should be able to see individual and distinct pixels in each of the boxes. Failure to see distinct pixels may indicate you have a defective video amplifier, focus correction circuit, or picture tube.

Note: *If multi-colored areas appear on a mask-type color picture tube, you may have a problem with convergence or you may be exceeding the resolution of the picture tube.*

CheckBy3

Description The active video area is equally divided into a 3x3 checkerboard of black and white boxes. The primary version has four white boxes as shown in the image below. The secondary version has five white boxes (reverse).




Test Contrast ratio

Purpose The pattern is based on a proposed ANSI method of measuring the contrast ratio of video projection systems.

Method Using a light meter probe, measure and record the light-level reading (in foot lamberts) in the center of each of the black and white boxes. The contrast ratio is expressed as the average of all of the white readings divided by the average of all of the black readings.

Check_02

Description Primary version is shown below. The secondary version has reverse (black lines on white background).



Check_11

Description In the primary version, the active video area is filled with alternating black and white pixels that form a very fine checkerboard, as shown below. The secondary version inverts the colors in the image. The inverted image looks almost the same as the non-inverted version.



Test Verify monitor resolution


Purpose The resolution of your monitor should meet or exceed the design specifications.

Method Adjust the brightness, contrast, and focus to their correct settings first. You should be able to see individual and distinct pixels in each of the boxes. Failure to see distinct pixels may indicate you have a defective video amplifier, focus correction circuit, or picture tube.

Note: *If multi-colored areas appear on a mask-type color picture tube, you may have a problem with convergence, or you may be exceeding the resolution of the picture tube.*

CirclesL


Description Special test image developed per customer specifications. In the primary version (shown below), the image consists of five large white circles on a black background. The circles are positioned in the center and in the corners of the active video area. The secondary version inverts the image to black circles on a white background.



Purpose This pattern is specified by some monitor manufacturers for checking and adjusting video scan size, linearity, and over scanning.

CirclesS

Description Special test image developed per customer specifications. In the primary version (shown below), the image consists of eight small white circles on a black background. The circles are positioned in the corners of the active video area and centered on each edge of the active video area. The secondary version inverts the image to black circles on a white background.




Purpose This pattern is specified by some monitor manufacturers for checking and adjusting video scan size, linearity, and over scanning.

ColorBar

Description The primary version (shown below) has 16 full-height vertical color bars. The secondary version splits the field into a top and bottom half. The bars in the bottom half of the screen are in reverse order.

Note: *When outputting digital video, 33% Gray changes to 50% Gray, and 67% Gray becomes either Black or some gray level depending on how the display interprets the video information.*




Test Verify that all video channels are functional

Purpose To verify that none of the video channels are bad or connected incorrectly.

Method Compare the sequence of color bars with the table. Missing bars may indicate a dead or unconnected channel. The transition between the bars should be sharp and distinct. Each bar should also be uniform in color and intensity across its entire width. Non-uniformity may indicate problems with the response of the video amplifiers. If all the bars are present but in the wrong order, one or more inputs may be swapped.


ComFocus

Description Special test image developed per customer specifications.



Cubes


Description This is an animated image consisting of one small multicolored cube orbiting around a larger multicolored cube. Each cube also is spinning on its own axis. The default text string is *Quantum Data*, which can be changed using commands. The primary version (shown below) has a black background and a thick green border. The secondary version uses a white background.



Purpose Can be used for show demonstrations with your own text.

Diamond1


Description Special test image developed per customer specifications.



Dot1606, Dot1610, Dot1612, Dot1615, Dot1812, Dot1815, Dot2016

Description The primary version has white pixel dots on a black background. The secondary version has black pixel dots on a white background.

The primary version of the Dot2016 image is shown below.



Dot_10, Dot_12, Dot_24


Description

The active video area is filled with multiple rows of white, single pixel dots. The dots define the corners of what would appear to be square boxes if all connecting pixels were lit. The number of rows of boxes and the number of boxes per row depends on which version of the image is selected and the screen aspect ratio of the currently-loaded format. The number in the image's name refers to the number of boxes that will be formed along the minor axis for most aspect ratios. The generator calculates the ratio and then finds the closest match from the following table.

Aspect Ratio		**Dot_10**		**Dot_12**		**Dot_24**	
W : H	Decimal	Number of Rows	Boxes per Row	Number of Rows	Boxes per Row	Number of Rows	Boxes per Row
16 : 9	1.777 É	10	16	10	16	18	32
5 : 3	1.666 É	10	16	10	16	18	30
4 : 3	1.333 É	10	14	12	16	24	32
1 : 1	1.000	10	10	12	12	24	24
3 : 4	0.750	14	10	16	12	32	24

The primary version has white pixel dots on a black background. A secondary version has black pixel dots on a white background.

The primary version of the Dot_24 image is shown below.



Purpose

To accurately produce an image on a color monitor, the three electron beams in the CRT must meet (converge) at the same location at the same time. Small dots displayed on a misconverged monitor appear as a group of multi-colored dots.

Method The convergence adjustments of most color monitors fall into two main categories. The first set of adjustments, usually called Static Convergence, aligns the three beams in the center of the display. This method involves turning on all three guns and adjusting the various magnets on the convergence assembly to produce all white dots in the center of the display. The convergence assembly is located on the neck of the CRT. Different monitors and CRT types may each require their own magnet-adjustment sequence.

After the center of the display is properly converged, the outer areas are adjusted by using the monitor's Dynamic Convergence controls. The number of controls, the area of the screen they affect, and their adjustment procedure depends on the monitor under test.

Test Focus adjustments

Purpose An out-of-focus monitor displays fuzzy pixels which, in turn, result in poorly formed and hard-to-read characters.

Method On monitors with a single (static) focus adjustment, adjust the control for the best average focus over the entire screen. The focus at certain locations should be within specified limits.

Some monitors have a static and one or more dynamic focus controls. The sequence for adjusting them and the areas of the screen they affect depend on the monitor under test.

DV_Swing

Description This image is only available with DVI and HDMI. The DV_Swing image is used to temporally change the digital video swing (DVSS format parameter) between 90 and 1620 mVp-p of the HDMI and DVI digital output for the active format. This image displays the current video swing value over a graduated (ramp) background. This image is supported by HDMI boards (revision F or later), and DVI boards with FPGA F1 or later.


Note: *The DVSC command can be used to set the swing value between 150 and 1500 mVp-p.*



Method To adjust the swing in 6 mV increments, press the Contents key and then the Options key. You then enable More and use the +/- increment keys to proceed through the subimages.

Dyna

Description This image has multiple versions that display different sizes of the same pattern. Version 0 is shown below.




EdidData

Description Displays EDID from the display connected with the generator. For more information, see page 589.


Elbit

Description Special test image developed per customer specifications. This image has 19 versions.




EMITest1, EMITest2, EMITest3, EMITest4, EMITest5

Description Special test images used for electro-magnetic interference (EMI) testing of displays. The entire active video area is filled with an “H” character. The primary versions of these images draw white characters on a black background. The secondary versions draw black characters on a white background. The EMITest1 image is shown below.




The EMITest2 image is the same as EMITest1, but with the bottom row of characters constantly drawn left-to-right and then cleared.

The EMITest3 image is the same as EMITest1, but with a larger version of the “H” character.



The EMITest4 image is the same as EMITest3, but with the bottom row of characters constantly drawn left-to-right and then cleared.

The EMITest5 image is shown below.




Flat, Flat07, Flat13, Flat20, Flat27, Flat33, Flat40, Flat47, Flat53, Flat60, Flat67, Flat73, Flat80, Flat87, Flat93, FlatGray, Flat_01, Flat_02, Flat_03, Flat_04, Flat_05, Flat_06, Flat_07, Flat_08, Flat_09, Flat_10, Flat_11, Flat_12, Flat_13, Flat_14, Flat_15, Flat_16

Description The entire active video area is filled with a shade of gray. Each image displays a different shade of gray. The FlatGray image is shown below.




Flat_B, Flat_G, Flat_R

Description The screen is filled with blue (B), green (G) or red (R). The Flat_B image is shown below.




Focus20

Description Primary version shown below. The secondary version has black characters on a white background.




FocusC14

Description Primary version shown below.The secondary version has black characters on a white background.




FocusCCx

Description Primary version shown below. The secondary version has black characters on a white background.




FocusEM

Description Primary version shown below. The secondary version has black characters on a white background.



FocusEMP

Description Primary version shown below. The secondary version has black characters on a white background.




FocusM00 - FocusM15

Description The FocusM00 image is shown below.



Focus_@6, Focus_@7, Focus_@8, Focus_@9

Description In the primary versions, the screen is filled with white "@" characters on a black background. The secondary versions are drawn with black characters on a white background. The primary version of the Focus_@6 image is shown below.



Test Focus adjustments


Purpose An out-of-focus monitor displays fuzzy graphic images and poorly formed, hard-to-read text characters.

Method On monitors with a single (static) focus adjustment, adjust the control for the best average focus over the entire screen. The focus at certain locations of the screen should be within specified limits.

Some monitors have a static and one or more dynamic focus controls. The sequence for adjusting them and the areas of the screen that they affect depend on the monitor under test.

Focus_Cx

Description In the primary version (shown below), the screen is filled with white Cx characters on a black background. The secondary version is drawn with black characters on a white background.



Test Focus adjustments


Purpose An out-of-focus monitor displays fuzzy graphic images and poorly formed, hard-to-read text characters.

Method On monitors with a single (static) focus adjustment, adjust the control for the best average focus over the entire screen. The focus at certain locations of the screen should be within specified limits.

Some monitors have a static and one or more dynamic focus controls. The sequence for adjusting them and the areas of the screen that they affect depend on the monitor under test.

Focus_H

Description In the primary version (shown below), the screen is filled with white H characters on a black background. The secondary version is drawn with black characters on a white background.



Test Focus adjustments)


Purpose An out-of-focus monitor displays fuzzy graphic images and poorly formed, hard-to-read text characters.

Method On monitors with a single (static) focus adjustment, adjust the control for the best average focus over the entire screen. The focus at certain locations of the screen should be within specified limits.

Some monitors have a static and one or more dynamic focus controls. The sequence for adjusting them and the areas of the screen that they affect depend on the monitor under test.


Focus_MM

Description In the primary version (shown below), the screen is filled with white M characters on a black background. The secondary version is drawn with black characters on a white background.



Focus_Oo

Description In the primary version (shown below), the screen is filled with white Oo characters on a black background. The secondary version is drawn with black characters on a white background.



Test Focus adjustments

Purpose An out-of-focus monitor displays fuzzy graphic images and poorly formed, hard-to-read text characters.


Method On monitors with a single (static) focus adjustment, adjust the control for the best average focus over the entire screen. The focus at certain locations of the screen should be within specified limits.

Some monitors have a static and one or more dynamic focus controls. The sequence for adjusting them and the areas of the screen that they affect depend on the monitor under test.

Format


Description A listing of the data contained in any format. The primary image lists the settings of the format driving the display. The secondary image can be used to list the contents of any stored format (via the Location field).

This pattern works best at display resolutions of at least 640 pixel by 480 lines.



Geom_1 - Geom_5

Description The primary version of the Geom_1 image is shown below. Secondary version is drawn with black lines on a white background.




Gray25, Gray40

Description The Gray25 image is shown below.



GrayBar

Description The primary version (shown below) has 16 full-height vertical graybars. The intensity of the bars is shown below. The secondary version splits the field into a top and bottom half. The bars in the bottom half of the screen are in reverse order.



Test Video color tracking (color monitors)

Purpose To verify that a color monitor accurately reproduces colors at all intensities.

Method Perform the Brightness Control Adjustment and Brightness Uniformity tests first.

Changes in brightness from bar to bar should be uniform. All of the bars should appear as an untinted gray at all levels.

Test Video gain linearity (monochrome monitors)

Purpose To check the video linearity (grayscale modulation)

Method Perform the Brightness Control Adjustment and Brightness Uniformity tests first.

Changes in brightness from bar to bar should be visible and uniform.

GrayL1, GrayL3


Description The GrayL1 image is shown below.



Grays5, Grays9, Grays11, Grays16, Grays32, Grays64

Description These images have the designated number of full-height vertical graybars.

The Grays11 image is shown below.



GraysAll


Description Contains 256 grayscale versions, from 0 (full black) to 255 (full white).



Grill_11, Grill_15, Grill_22, Grill_33, Grill_44

Description The entire active video area is filled with alternating black and white stripes. The stripes are drawn at different resolutions. Each of the stripes is four (4) pixels wide in the Grill_44 image and three (3) pixels wide in the Grill_33 image. Each of the stripes is two (2) pixels wide in the Grill_22 image and one (1) pixel wide in the Grill_11 image.

The primary versions draw vertical stripes. The secondary versions draw horizontal stripes. The primary version of the Grill_44 image is shown below.



Test Verify monitor resolution


Purpose The resolution of your monitor should meet or exceed the design specifications.

Method First adjust the brightness, contrast, and focus to their correct settings. You should be able to see individual and distinct stripes in all areas of the display at all four resolutions. Failure to see distinct lines at the highest resolution (Grill_11) may indicate you have a defective video amplifier or picture tube.

Note: *If multi-colored lines appear on a mask-type color picture tube, you may have a problem with convergence or you may be exceeding the resolution of the picture tube.*


HalfArea

Description Primary version shown below. Secondary version is drawn with black boxes and white background.




HalfClk

Description




Hat1606, Hat1610, Hat1612, Hat1615

Description Primary version of Hat1606 is shown below. Secondary version is inversed.




Hat1606A, Hat1610A, Hat1612A, Hat1615A

Description Primary version of Hat1606A is shown below. Secondary version is inversed.




Hat1812, Hat1815

Description Primary version of Hat1812 is shown below. Secondary version is inversed.




Hat1812A, Hat1815A

Description Primary version of Hat1812A is shown below. Secondary version is inversed.




Hat2016

Description Primary version is shown below. Secondary version is inversed.



Hat2016A

Description Primary version is shown below. Secondary version is inversed.




Hatch_6, Hatch_10i, Hatch_10o, Hatch_12i, Hatch_12o, Hatch_24i, Hatch_24o, Hatch_24s, Hatch_G, Hatch_M, GRN_HTCH, and MAGENTA

Description The primary versions consist of a white, green (G and GRN), or magenta (M) crosshatch drawn on a black background. The lines form square boxes. A single pixel dot is located in the center of each crosshatch box. The number of boxes formed depends on the version of the image selected and the screen aspect ratio of the currently loaded format. The number in the image's name refers to the number of boxes that are formed along the minor axis for most aspect ratios. The generator calculates the ratio and then finds the closest match from the table on the next page. Version names indicate the drawing method, as follows:

- Versions ending in "i" draw from the inside (center) out. Any partial boxes are placed around the perimeter of the image.
- Versions ending in "o" draw from the outside in. Any partial boxes are placed along the centerlines of the image.
- Versions ending in "s" are the "i" version plus a 1-pixel thick border.

The secondary versions invert the images to black lines and dots on a white background. Hatch_G, Hatch_M, GRN_HTCH and Magenta do not have secondary versions.

The primary version of the Hatch_10i image is shown below.



Aspect Ratio		Dot_10		Dot_12		Dot_24	
W : H	Decimal	Boxes Vertically	Boxes Horizon-tally	Boxes Vertically	Boxes Horizon-tally	Boxes Vertically	Boxes Horizon-tally
16 : 9	1.777 É	10	16	10	16	18	32
5 : 3	1.666 É	10	16	10	16	18	30
4 : 3	1.333 É	10	14	12	16	24	32
1 : 1	1.000	10	10	12	12	24	24
3 : 4	0.750	14	10	16	12	32	24

Test Convergence adjustment (color monitors only)


Purpose To accurately produce an image on a color monitor, the three electron beams in the CRT must meet (converge) at the same location at the same time. Lines displayed on a misconverged monitor appear as several multi-colored lines, and the transitions between different colored areas contain fringes of other colors.

Method The convergence adjustments of most color monitors fall into two main categories. The first set of adjustments, usually called Static Convergence, aligns the three beams in the center of the display. This method involves turning on all three guns and adjusting the various magnets on the convergence assembly to produce all white dots in the center of the display. The convergence assembly is located on the neck of the CRT. Different monitors and CRT types may each require their own magnet adjustment sequence.

After the center of the display is properly converged, the outer areas are adjusted by using the monitor's Dynamic Convergence controls. The number of controls, the area of the screen they affect, and their adjustment procedure depend on the monitor under test.


Hatch_16, Hatch_20

Description The primary version of the Hatch_16 image is shown below. The secondary versions draw black lines on a white background.



Hatch20

Description Primary version...The secondary version draws black lines on a white background.




Hatch4x3, Hatch5x4 and Hatch8x8

Description

These are different versions of a crosshatch pattern that may be called for by some display manufacturers' test procedures. The primary version consists of white crosshatch and circles on a black background. The secondary version inverts the image to black lines on a white background.

The primary version of the Hatch4x3 image is shown below.




Purpose

This is a general purpose test image that can be used to check and adjust video scan linearity and geometry and color convergence.

Hatch64W

Description This is a crosshatch pattern that may be called for by some manufacturers' test procedures. The primary version (shown below) consists of an 8x8 white crosshatch on a black background. A white rectangular patch is added in the center. The secondary version inverts the image to black lines and box on a white background.



Purpose


Method This is a general purpose test image that can be used to check and adjust video scan linearity and geometry, and color convergence. The large white rectangle also allows for checking a display's high voltage regulation. This is done by observing the vertical lines at the left and right edges of the image. They should be fairly straight and not pull in the area of the white rectangle.

HdcpA1B1, HdcpA1B2, HdcpA2B1, HdcpA2B2, HdcpProd

Description Used with HDCP feature. For more information, see Chapter 19, "Testing HDCP on HDMI and DisplayPort."


Hitachi1

Description Special test image developed per customer specifications. The image consists of a 2x2 cluster of Microsoft Windows® screen simulations using Japanese characters.




HSVnRGB

Description



Imex1

Description




InFocus1

Description Special test image developed per customer specifications.




InFocus2

Description Special test image developed per customer specifications.



KanjiKAN


Description In the primary version (shown below), the screen is filled with white Japanese Kan characters on a black background. The secondary version is drawn with black characters on a white background.



Test Focus adjustments


LGLCDTVB, LGLCDTVG, LGLCDTVR, LGLCDTVW

Description Special test image developed per customer specifications. Each image has three versions. The primary version of the LGLCDTVB image is shown below.



LGRamp

Description Special test image developed per customer specifications. The image provides a grayscale of two objects. The secondary version of the LGRamp image is shown below.




Linearty (Linearity)

Description This image has three parts. The first part consists of six (6) white circles. A large circle is drawn in the center of the screen. Its diameter equals the lesser of the video height or width of the display. A smaller circle is drawn at half the diameter and concentric with the larger circle. A circle also is drawn in each of the corners of the screen. The diameter of the corner circles equals one-fifth of the display width.

The second part of the image consists of a white crosshatch. The number of boxes in the crosshatch depends on the physical size of the display.

The last part of the image consists of white tic marks on the horizontal and vertical center lines of the image. The marks are one pixel thick at every other pixel location. Every fifth mark is slightly longer. The color of the pattern can be changed with the individual video output controls.



Test Linearity adjustment

Purpose To present an undistorted display, the horizontal and vertical sweeps of the electron beam across the face of the CRT should be at uniform speeds. Any non-uniformity in the sweep causes portions of an image to stretch while other portions are compressed. Non-linearity in a monitor shows up in several ways. It may be present across the entire screen, in a large portion of the screen, or localized in a very small area.

Method The circles in the image can be used to do a general adjustment of a monitor's linearity controls. Adjust the controls to form perfectly round circles. The crosshatch image can be used to measure linearity and to make finer control adjustments. All the full boxes in the crosshatch should be identical in size. Measure them with a ruler or a gauge made for the monitor under test. Any deviation should be within your specification limits. Use the tic


marks and a ruler or gauge to measure linearity over a small portion of the display. Compare the number of tic marks per unit of measure with an adjacent or overlapping area.

LinFocus

Description This image has several parts. The first part consists of a large circle in the center of the screen. Its diameter equals the lesser of the video height or width of the display.

The second part is a 10x10 box crosshatch. The crosshatch is drawn in from the outside edges, with any extra pixels in the boxes placed along the vertical and horizontal axis. The vertical centerline is two pixels thick if the format has an even number of active pixels per line. The horizontal centerline is two pixels thick if the format has an even number of active lines per frame. A smaller box is added at the center of the image. The box is one-half the height and two-fifths the width of one of the crosshatch boxes. Current format data is shown in the lower left quadrant of the image. It shows the number of active pixels (H) and lines (V) as well as the vertical and horizontal scan rates.

The primary version (shown below) consists of a white pattern on a black background. The secondary version has a black pattern on a white background.



The image also includes blocks of focus-checking characters at various locations. The blocks are positioned inside the crosshatch boxes and are up to 3x3 characters in size. The size of the blocks is limited by the number of characters that can fit in one box.

Test Linearity adjustment

Method Please see the Linearity test image on “Linearty (Linearity)” on page 1317 for information on measuring linearity.

Test Focus adjustment

Purpose An out-of-focus monitor displays fuzzy graphic images and poorly formed, hard-to-read characters when text is displayed on the screen.


Method On monitors with a single (static) focus adjustment, adjust the control for the best average focus over the entire screen. The focus at certain locations of the screen should be within specified limits.

Some monitors have a static and one or more dynamic focus controls. The sequence for adjusting them and the areas of the screen they affect depend on the monitor under test.

LipSync


Description The lipsync image enables you to test for synchronization between HDMI video and audio. The image enables you to select between a range of intervals. You can access the subimages to control the interval of each video/audio synchronization event through the Content->Options menu and incrementing with the +/- keys. There are 255 distinct settings (different intervals) available.

When you first select the Lipsync image, the interval is set at 0.66733 sec per audio event (shown below) for progressive formats and 1.333333 sec for interlaced formats. When you enable subimages with Content->Option, the default inital screen at image rendition 0 is one sync event per 1.101100 sec for progressive formats and 2.2 sec for interlaced formats. You can increase this up to 8.475133 sec at image rendition 254 which is one video/audio synchronization event per 8.46666 seconds for progressive formats and 16.933332 for interlaced formats.



Master


Description



MEMEPlus, MEPlus_B, MEPlus_G, and MEPlus_R

Description In the primary version, the screen is filled with blue (BLU and B), green (GRN and G), red (R), or white (WHT and Sony) EM character blocks on a black background. Only the white character has a secondary version. It is drawn with black characters on a white background.

A bitmap of a single character block is shown here. The BLU_EM+ image is shown below.




Test Focus


Purpose This pattern is specified by one or more display manufacturers for checking and adjusting focus one color at a time.

MoireX, MoireX33, MoireY, MoireY33

Description The MoireX and MoireY images consist of black lines on a white background across the active video area. MoireX provides vertical lines; MoireY provides horizontal lines. The MoireX image is shown below.




The primary version of the MoireX33 and MoireY33 images provide a black frame around the black lines. The secondary version draws a white frame around black lines. The primary version of the MoireX33 image is shown below.




Monoscop

Description




MSony7, MSony8

Description Special test image developed per customer specifications. Primary version of the MSony7 image is shown below. The secondary version draws white boxes and characters with a black background.




MulBurst

Description



Orion

Description This image provides a color bar that rotates (shifts) the bars to the right on an incremental basis.




The color bars are shifted to the right at 3 second intervals. After pressing the Contents key and then the Options key you then enable More and use the +/- increment keys to proceed through the subimages to adjust the interval between 3, 10, 30 and 60 seconds.


Outline0, Outline1, Outline2, Outline3

Description The primary version of the Outline0 image consists of a rectangular white border on a black background. The border is one (1) pixel wide and defines the active video area. Two (2) diagonal lines join the opposite corners. A-full size cross is centered in the image. The horizontal line of the cross is one (1) pixel thick for formats with an odd number of active lines and two (2) pixels thick for formats with an even number of active lines. The vertical line of the cross is one (1) pixel thick for formats with an odd number of active pixels per line and two (2) pixels thick for formats with an even number of active pixels.


The secondary version of these images draw black lines on a white background.




In the Outline1 version, the two diagonal lines are removed and short marker lines are added to the border lines near to where the cross lines meet the border lines. The markers appear at both sides of the cross lines. The distance between the marker lines and the cross lines is the greater of either two (2) pixels or one (1) millimeter.



In the Outline2 version, the two diagonal lines are removed and short marker lines are added to the corners, and where cross lines meet and end.



In the Outline3 version, the two diagonal lines are removed, cross lines are shortened, and short marker lines are added.



Test Yoke tilt correction

Purpose The horizontal axis of a displayed image should line up with the horizontal axis of your monitor. Any tilt is likely due to the yoke being rotated on the neck of the CRT. A rotated yoke makes any displayed image appear rotated.

Method Place your monitor on a flat surface so the face of the CRT is perpendicular to the surface. Use a ruler or gauge to measure the height of each end of the image's horizontal center line from the surface. The difference between the two readings should be within specification for the monitor. If it is out of specification, the yoke must be adjusted. Loosen the hardware that clamps the yoke to the neck of the CRT and rotate the yoke until the line is horizontal. Tighten the yoke-clamp hardware.

Test Yoke winding orthogonality check

Purpose The horizontal and vertical deflection coils on the yoke should have their axes cross at exactly 90 degrees. Improper orientation of the windings causes displayed rectangles to look more like nonorthogonal parallelograms. This type of defect is almost impossible to correct with adjustments. It is usually easier to replace the defective yoke.

Method First, perform the yoke tilt correction described above. The vertical center line of the image should be perpendicular to the work surface. If the deviation is beyond specification, the monitor should be rejected and sent back for repair, rather than trying to magnet a defective yoke.

Test Display size correction

Purpose A too-large active video size adjustment on a monitor may cause information to be lost around the edges of the screen. A too-small active video size adjustment may make some displayed information hard to read. The correct size is needed to obtain the correct aspect ratio. You need the correct aspect ratio to get round circles and square squares.

Method First, determine the correct physical size of the active video area for the display. This information usually is given in a display's specification sheet or service manual. The size should match the sizes in the format you are using. The size setting of the current format can be checked using the Format test image.

Place a ruler or gauge along the horizontal line of the image and adjust the monitor's horizontal size control until the distance between the end points matches the specified value.

Move the ruler or gauge to the vertical line and adjust your monitor's vertical size control until the distance between the end points matches the specified value.

Test Parallelogram distortion check

Purpose Parallelogram distortion is very difficult to correct with magnets because the correction often causes barrel distortion. Therefore, you should decide early whether your monitor meets this specification. The problem usually can be traced to the improper winding of the yoke coils. If the problem is not too severe, it may be corrected by adding or adjusting magnets on the yoke. However, if the distortion is excessive, it may be an indication of a defective yoke which cannot be corrected with magnets.

Method Measure the lengths of the two (2) diagonal lines. Any difference is an indication of parallelogram distortion. The difference in readings should be within the specifications of the monitor.

If the difference in the readings is too far beyond specification, the monitor should be rejected and sent back for repair, rather than trying to magnet a defective yoke.

Test Trapezoid distortion correction

Purpose This image gives you a way to measure trapezoid distortion in your monitor. If the distortion is not too severe, you may be able to correct it by adding or adjusting magnets on the yoke.

Method Perform the yoke winding orthogonality check and parallelogram distortion check first to avoid wasting time on a monitor with a defective yoke.

Measure the width of the image at the top and bottom of the display. Any difference in readings should be within the specification limits. Measure the height of the image at both sides of the display. Again, any difference in readings should be within specification limits. If either of the differences is out of specification, the trapezoid distortion of the monitor is out of specification.

Add or adjust magnets on the yoke to correct the problem. The pin and barrel distortion correction should be repeated to make sure that it is still in specification.

Test Pin and barrel distortion correction

Purpose If perfectly linear sweep signals are sent to a perfectly wound deflection yoke mounted on a perfect CRT, you would not necessarily get a perfectly formed raster. Instead you would likely get a raster that had its corners stretched away from the center, resembling a pin cushion. This distortion occurs because the geometry of the deflected electron beam does not match the geometry of the tube face plate. Also, imperfections in the yoke or CRT may affect this problem. In some cases one or more corners may be pulled towards the center of the raster causing it to look like a barrel. Uncorrected raster distortion carries over as distortion of the displayed image.


Method A slot gauge may be used to determine if the amount of pincushion or barrel distortion is within limits. A basic slot gauge may consist of a piece of opaque film with at least two (2) transparent slots in it. One slot is used for top and bottom distortion and the other is used for the sides. By positioning the correct slot over each portion of the border line, the entire line should be visible. If this cannot be done at all four sides, the monitor requires correcting.

There are two main ways of correcting pincushion distortion. The first involves placing or adjusting magnets on the yoke. This is a trial-and-error method. However, skilled operators develop a feel for how strong a magnet to use and how to place it in order to get the desired correction. If any correction is performed, the trapezoid distortion correction should be repeated.

The other correction method involves adding correction signals to the deflection signal driving the yoke. This method is usually found in color monitors, where adding magnets to the yoke would cause problems with convergence and purity. The type and number of adjustments depends on the monitor being tested.


P1

Description This image is a 6x6 white crosshatch without a border on a black background.




P2

Description This image is a 4x4 white crosshatch with a border on a black background.




P3

Description This image is a 4x4 white crosshatch with a border and a small, centered white patch on a black background.




P4

Description This image is an 8x8 white crosshatch with a border on a black background.




P5

Description This image is an 8x8 white crosshatch with a border and a small, centered white patch on a black background.




P6

Description 16x12 pixel white crosshatch with a border on a black background.




P6_Sony

Description 6x12 pixel white crosshatch with a border on a black background.



P7

Description 16x12 white crosshatch with a border and a small, centered white patch on a black background.




P8

Description This image is an all black active video area. The secondary version draws an all white video area.




P9

Description This image is an all white active video area. The secondary version draws an all black video area.



P10

Description Special test image developed per customer specifications. There are four versions of this image.



After pressing the Contents key and then the Options key you then enable More and use the +/- increment keys to proceed through the subimages to select up to 4 different versions of this image.

PacketRx


Description Displays the InfoFrame data received by HDMI receiver. For more information, see “Testing HDMI transmit device InfoFrame capability” on page 305.

PacketTx

Description Displays the InfoFrame data transmitted from the HDMI transmitter. For more information, see “Viewing InfoFrame contents (882 only)” on page 380.


PdsCrt1

Description Special test image developed per customer specifications.



PdsCrt2

Description Special test image developed per customer specifications.



Persist

Description In the primary version, 15 small white boxes move back and forth between diagonal guide lines. The lines form 15 side-by-side tracks. The size of each box is scaled to the light meter box size set by the MSIZ system parameter. The image does the following:


- The box in the center track (marked “1X”) moves one scan line vertically and one pixel horizontally for each vertical frame of refresh.
- The seven boxes to the right of the center track (marked “2X” through “8X”) move 2, 3, 4, 5, 6, 7, and 8 pixels and lines per frame, respectively.
- The seven boxes to the left of the center track (marked “/2” through “/8”) move one scan line vertically and one pixel horizontally for every 2, 3, 4, 5, 6, 7, and 8 vertical frames of refresh, respectively. These boxes are at the bottom of the tracks.

In cases where the next move would cause the box to move beyond the end of its track, it immediately reverses and moves the correct distance in the opposite direction for the next frame.

A continuously-running counter appears in the upper left corner of the image. The number shown is the number of vertical frame refreshes that have occurred since the generator was first powered up.

The secondary version draws a black image on a white background.

An example of the primary version of the Persist image is shown below:



Test Phosphor persistence


Purpose The phosphors on the face of most CRTs continue to glow for a short period of time after the electron beam has stopped energizing them. This phenomenon is called persistence. A certain amount of persistence is desirable in most applications. It prevents a flickering of a displayed image that most users would find objectionable. On the other hand, a CRT with an overly long persistence time causes moving objects to leave a blurred trail.

Method A flickering in the slower moving boxes indicates that the combination of refresh rate and phosphor persistence is not suitable for long-term viewing.

A fading tail left behind by the faster moving boxes indicates that the display may not be suitable for viewing animated images.


PgBar64H, PgBar64V

Description Special test image developed per customer specifications. The PgBar64H image is shown below.




PgCB, PgCG, PgCR, PgCW, PgCWrgb

Description Special test image developed per customer specifications. Primary version of PgCB is shown below. The secondary versions draw all white over the last bar.




The PGCWrgb is shown below.



Philips1

Description Special test image developed per customer specifications.



PixelRep

Description Used to test HDMI pixel repetition. There are 10 different versions of this image to support the different pixel repetition settings. For more information, see “Testing HDMI video pixel repetition (882 only)” on page 363.

PRN24bit

Description This image displays pseudo-random noise using 24-bits-per-pixel color depth.

PRN_5, PRN_9

Description Used with analyer to verify the analyzer's pseudo-random noise analysis capability. The PRN_5 image introduces 5 pixel errors per color component, while the PRN_9 image introduces 9 pixel errors per color component.

The PRN_5 image is shown below.



PulseBar

Description This image is intended for TV formats, but can be displayed with any format up to 100 MHz. The image looks like two vertical lines followed by a wide vertical bar on a display's screen. The first line is a sine-squared modulated pulse that fades from black to red and

back to black. The pulse is 20 T for PAL and 12.5 T for NTSC formats. The second narrower line is a 2 T white sine-squared pulse. T = 100 nSec for PAL and 125 nSec for NTSC formats. The wide bar is white with sine-squared edges.




Test Video system testing

This multi-purpose pattern can be used with other instruments to check television K factors. The modulated pulse can be used to check chrominance-to-luminance delay and gain. The narrow white line can be used to measure short term linear distortion (K2T).

QuartBox

Description — The primary version (shown below) has a single white box in the center of active video. The size of the box is one-half the width and height of the active video area (a quarter of the entire active video area). The secondary version draws a black box on a white background.



Test — Brightness control adjustment

Purpose — The wrong brightness setting on your monitor may cause other tests such as Contrast, Focus, and Beam Size to be invalid. An accurate brightness setting helps give repeatable measurements throughout other tests. This version of the brightness box should be used if the display's specifications call for the brightness to be set with one-fourth of the screen lit.

Method — Place your light meter probe within the center box and adjust the monitor's brightness control to obtain the required light meter reading.

Notes — The color of the center box is a special color, named foreground. The FRGB command can be used to change the default color of foreground to any RGB value.

```
IMGL quartbox: ALLU     // loads QuartBox image
FRGB 122 122 122        // sets RGB color of box
```

After loading a different format, send the FRGB command again to set the box fill color.

If you want to draw your own box, use foreground as the fill color, and then use the FRGB command to define the color of "foreground." For example:

```
IMGL raster; ALLU     // clears display
RECT foreground 100 100 100 100 dither100
FRGB 128 128 0
FRGB 192 192 64
```

```
FMTL DMT0660; ALLU
FRGB 192 192 64
```

Ramp

Description This image provides an active video area starting from full black (+7.5 IRE) at one edge of the screen to full white (+100 IRE) at opposite end of the screen.

There are 4 versions of this image—one for each edge of the display.

When selected, this image is displayed.



After pressing the Contents key and then the Options key. You then enable More and use the +/- increment keys to proceed through the subimages to change the image starting point to left, right, top, or bottom.

RampX

Description This image provides a ramp image that continuously sweeps (moves) to the right on an adjustable time basis.

When selected, this image is displayed.



After pressing the Contents key and then the Options key you then enable More and use the +/- increment keys to adjust the speed.

Ramp_B, Ramp_G, and Ramp_R

Description The active video area goes from full black (+7.5 IRE) at the left edge of the screen to full blue (_B), green (_G), or red (_R) at the right edge. The Ramp_B image is shown below.



Test Video gain linearity

Method When viewed on a TV screen, the full range of grays should be visible. There should be no color shifts visible.

Raster

Description The primary version shows a totally black display (nothing being displayed). The secondary version shows a totally white display.



Test Raster centering

Purpose Many monitor applications require that the displayed image or text fit completely within a bezel that surrounds the CRT. This usually requires that you first center the blank raster on the face of the CRT, and then center the image within the raster. Use this image for centering the raster on the CRT.

Method Turn up your monitor's brightness control until the raster is just visible. Adjust the raster's position and size using the size and raster centering controls. The raster centering adjustment for many monochrome monitors consists of moving magnetic rings on the deflection yoke.

Regulate

Description The image cycles between two (2) patterns. In the primary version, the first pattern is a white outline that defines the edges of displayed video. The other pattern has the same outline plus a solid white rectangle in the center. The size of the solid rectangle equals 95% of the height and width of displayed video. The speed of the cycle cannot be changed. The secondary version has a thick white frame with a black center for the first pattern and a solid white active video area for the other pattern.

The first pattern of the primary version is shown below.




Test High voltage regulation

Method The size of the border should not change for each half of the image. The change in border size between the two images should be within the specification limits of the monitor.

Samsung1, Samsung2


Description Special test images developed per customer specifications. The image consists of three small simulations of Microsoft Windows® screens on a blue background (Samsung1) or black background (Samsung2). A border and centered cross are formed with repeating

groups of the characters “e” and “m”. The repeating characters are also used to form a rectangular patch in the upper left hand corner and a circular area in the center of the image. The secondary version of Samsung2 draws a white background.




Samsung3

Description Special test image developed per customer specifications.



Samsung4

Description Special test image developed per customer specifications.



Samsung5

Description Special test image developed per customer specifications.


Samsung6

Description Special test image developed per customer specifications.




SamsungB

Description Special test image developed per customer specifications.




SamsungT

Description Special test image developed per customer specifications. There are four versions of this image. When selected, the following image is displayed.



SlideBox

Description This image displays a 16x9 white crosshatch with a large white patch moving across the screen.



To change the animation speed:


1. Load the SlideBox image.
2. Establish a terminal session with the generator (see page 32).
3. Enter the following commands:

```
ISUB 1
IVER 1
IMGU
DELX 10;
IMGU
DELX 20;
IMGU
```

SMPTE133

Description This image is based on a recommended practice (RP-133) test pattern designed by the Society of Motion Picture and Television Engineers (SMPTE). The original application was used in testing and evaluating medical imaging monochrome displays. The image now is

used in many different display applications. The image is self-scaling as to the number of active pixels and active lines used. Some of the image's elements have minor differences from the original SMPTE specification.



These differences are noted in descriptions of the individual elements.

- The image is drawn on a reference background having a 50% intensity level. The background covers the entire active video area.
- **Crosshatch** – There are 10 boxes vertically. The number of horizontal boxes is based on the physical aspect ratio determined by the HSIZ and VSIZparameters in the currently loaded format. The boxes are perfectly square with any fractional spaces placed around the outside edges of the image. The vertical lines are two (2) pixels thick while the horizontal lines are two (2) scan lines thick. Small crosses indicate the intersection of the horizontal and vertical lines when they are covered by other parts of the image. All parts of the crosshatch are normally drawn using a 70% intensity level. A 75% level is used in the secondary version.
- **Resolution patch** – The patch is made up of six (6) smaller boxes that are each about 6.25% of the height of the display. The boxes are made of alternating intensity (0 and 100%) stripes. The stripes run vertically and horizontally. The stripes may be one (1), two (2) or three (3) pixels wide each. Details of the patch are shown in the lower half of the following illustration. The patches are located in each corner of the main image and in the center. They are oriented with the highest resolution and contrast boxes closest to the outside corners. The 48%-53%, 48%-51% and 50%-51% level patches are omitted in the secondary version.
- **Grayscale boxes** – Twelve (12) boxes at eleven (11) intensity levels are clustered around the center of the main image. They start at 0% and increase in 10% steps to

100% with two (2) boxes at a 50% level. All of the grayscale boxes are omitted in the secondary version.

- **Gamma check dither box** – A small box is drawn inside the right-hand 50% grayscale box. The box is half the width and height of the larger box. The box consists of a checkerboard of alternate one-on and one-off pixels. The alternate pixels have levels of 0 and 100%. This smaller box is not part of the original SMPTE specification and is omitted in the secondary version.
- **Contrast boxes** – Two (2) boxes are drawn adjacent to the grayscale boxes. They are at 0 and 100% levels. There are smaller boxes drawn inside each box at 5 and 95% levels. The contrast boxes are omitted in the secondary version.
- **Black and white windows** – Two (2) horizontal bars are located above and below the grayscale boxes. Their height equals 8% of the display height. There are half-size bars centered in the larger bars. In the primary version, the dark portion of the windows is at a 5% level and the bright portion is at a 95% level. Zero and 100% levels are used in the secondary version.
- **Border** – A border line is drawn around the image. It is set in from the edges of displayed video a distance equal to 1% of the displayed height and has a thickness equal to 0.5% of the displayed height. The intensity level is the same as that of the crosshatch lines.
- **Circle** – A large circle is centered in the image. It touches the top and bottom of the active video area when the aspect ratio is wider than it is high (landscape-type display). The circle touches the left and right sides of active video when the aspect ratio is taller than it is wide (portrait-type display). The intensity level is the same as that of the crosshatch lines. The circle is not part of the original SMPTE specification.
- **Resolution data** - The number of active pixels per line and the number of active lines is shown as text below the lower black and white window. The pixel depth also is shown. The intensity level of the text is the same as that of the crosshatch lines. The displaying of the data is not part of the original SMPTE specification.

  The secondary version adds a row of six (6) color bars above and below the black-and-white windows. The order of the colors, from left to right, is red, green, blue, cyan (g+b), magenta (r+b) and yellow (r+g). The top row is drawn at 100% intensity levels and the bottom row is drawn at 50% intensity levels. Color bars are not part of the original SMPTE specification.

Test Deflection linearity

Method If the overall height and width of the display's active video area match the sizes in the format, the large circle should be perfectly round. Each box in the crosshatch pattern should be the same size and shape. For more information on testing linearity, refer to the Linearty test image on page 1317.

Test High contrast resolution

Method All the 0 and 100% level stripes in all the resolution patches should be separate and distinct.

Test Low contrast resolution and noise

Method All the mid-level 2 on - 2 off stripes in all the resolution patches should be visible and distinct. This is a sensitive test for noise in the display's video amplifiers.

Test Quick gamma check

Method The average brightness level of the small gamma dither box should match the brightness of the larger surrounding box. This is a visual check to see if the display's gamma correction is producing the correct mid-level response.

Test Video gain linearity and gamma

Method The individual grayscale boxes all should be at their indicated levels. A small aperture photometer is usually required to get accurate and repeatable readings.

Test Contrast and brightness check

Method On a display with properly adjusted brightness and contrast controls, both the 5% and 95% contrast boxes should be clearly visible inside their larger surrounding 0% and 100% boxes.

Test Video amplifier stability

Method The two black-and-white windows should show sharp transitions between the smaller box and the surrounding window. Streaking may be an indication of undershoot or overshoot while ghost images may indicate a ringing problem.

Test Excessive overscan and off-center alignment

Method The entire border should be clearly visible on the face of the tube and not be hidden by the edge of the glass or by any bezel.

Test Interlace flicker

Method The horizontal 1 on - 1 off stripes in the resolution boxes should not have objectionable flicker when shown with an interlaced format. Excessive flicker indicates that the combination of the display's CRT persistence and frame scan rate is below the persistence time of the human eye.

SMPTEbar

Description This image is based on an engineering guideline (EG1-1990) test signal specified by the Society of Motion Picture and Television Engineers (SMPTE). The SMPTE pattern, in turn, is derived from an EIA standard test pattern (RS-189-A). The image, is set up to be generated by an 801GX generator as an encoded TV output. It is designed for adjusting the color settings of a television monitor by eye. It can also be used with a TV waveform analyzer and vectorscope for testing video signal processors and color decoders. The image is available on all models as a component RGB signal. Some of the image's elements have some differences from the original SMPTE specification.

These differences are given in descriptions of the individual elements.

- The upper 67% of the image consists of a series of color bars. These bars match the order of the bars in the SMPTE and EIA patterns. They are similar to the 801GX's TVBar_75 image without the last black bar.
- The left side of the lower 25% of the image contains isolated -I and Q color difference signals that match the original EIA and SMPTE patterns. The -I signal appears as a bluish-gray bar and the Q signal appears as a purple bar on a TV monitor. The bars are separated by a white (+100 IRE) bar.
- The right side of the lower 25% of the image contains a narrow 12.5 IRE gray bar. Due to a hardware limitation on the 801GX, this portion of the pattern does not match the original EIA and SMPTE patterns. The original patterns had +3.5 (blacker than black) and +11.5 IRE bars separated by a +7.5 IRE (black) bar.

- The remaining central 8% of the image contains a row of chroma set bars. These bars are part of the SMPTE pattern but are not in the EIA pattern. The order of the alternating color and black bars matches those in the SMPTE pattern.



Test Color video performance

Purpose This general purpose pattern can be used to check the video handling capabilities of most parts of a television system.

Method When viewed on a TV screen, all of the upper color bars should be correct and in the order shown. The hue and intensity of each bar should be uniform over the entire bar.

The image can be used with a TV waveform analyzer to check the performance of a video system. The upper color bars, as they would appear on a waveform analyzer, are shown on a previous page.

Test Color decoder performance

Purpose The image can used with a TV vectorscope to check for proper operation of a video color decoder. Vectorscope signatures of the upper and lower portions of the image using NTSC encoding can be found on the previous page.

Method The vectorscope signature for the color bars should hit the target test point for each color on the vectorscope's graticule. If you are using PAL encoded video, the signature will be similar to the one shown for the TVBar_75 test image on page page 1362.

The three "legs" of the vectorscope signature for the -I and Q color difference signals should match the Burst, -I and Q reference lines on the vectorscope's graticule.

The following tests are based on the original SMPTE guideline:

Test Visual chroma gain adjustment

Method To perform this test, you must have a way of turning off the red and green guns in the monitor under test. Turning off the red and green video components of the 801GX generator's video output will not work for this test.

This test uses the upper and central color bars. Switch off the red and green guns on the monitor. This will produce four blue bars, separated by black bars. Adjust the chroma gain so that the brightness of each outer blue bar is uniform over the entire bar. The gain is correct when the bottom 10% of each bar is the same brightness as the rest of the bar.

Test Visual chroma phase adjustment

Method In order to perform this test, you must have a way of turning off the red and green guns in the monitor under test. Turning off the red and green video components of the 801GX generator's video output will not work for this test.


This test uses the upper and central color bars. Switch off the red and green guns on the monitor. This will produce four blue bars, separated by black bars. Adjust the chroma phase so that the brightness of each of the two central blue bars is uniform over the entire bar. The phase is correct when the bottom 10% of each bar is the same brightness as the rest of the bar.

Test Visual black level adjustment

Method This test uses the lower right hand portion of the image. Reduce the black level until the gray bar disappears. Slowly increase the black level until the bar just becomes clearly visible.


Sony6

Description Special test image developed per customer specifications.



Sony6WLC

Description Special test image developed per customer specifications.



sRGBflat

Description

For testing color response per Microsoft's WinColorKit standard. This standard was developed by Microsoft to standardize methods relating to the matching of colors appearing on various displays (go to *http://www.microsoft.com/whdc/hwdev/tech/color/ColorTest.mspx* for more details). There are 38 different versions of this image to support this feature.

When selected, a flat image appears with a color that is remembered from the last time the image was set up. The example below shows version 8 (Red1) of the sRGBflat image:



A small label in the upper left corner of the image indicates the Microsoft name for the color that is currently being displayed (for example, "sRGB-Gray5"). Note that some of the names that appear conflict with generator color names (for example, "sRGB-Gray5" is not the same as the generator color "Gray5").

After pressing the Contents key and then the Options key. You then enable More and use the +/- increment keys to select up to 38 different versions of this image. Each image displays another WinColorKit color.

Note: *For more information of generator support for Microsoft WinColorKit, go to http://www.quantumdata.com/support/kb/article.asp?kbid=100152.*

Staircas, Stairs20

Description

The active video area goes from full black at the left edge of the screen to full white at the right edge. There are six (6) steps (Stairs20) or sixteen (16) steps (Staircas).

The Stairs20 image is shown below.



Test Video gain linearity


Method When viewed on a monitor's screen, a black bar plus five (5) gray bars should be visible. There should be no color shifts, and each of the bars should be uniform in color.

The image also can be used with an oscilloscope or TV waveform analyzer to check the gain linearity and gamma correction of a video system.

Strokes0, Strokes1

Description This image may cited by some display manufacturers' test procedures. The Strokes0 version consists of multiple groups of separated red, green and blue horizontal lines drawn on a black background. The Strokes1 version consists of multiple groups of separated red, green and blue diagonal lines drawn on a black background.

The Strokes0 image is shown below.



Purpose These images are special-purpose test patterns used in test and alignment procedures specified by some display manufacturers.

Text_9, Text_9T, Text_11, Text_12T, Text_16

Description In the primary versions, the screen is filled with random paragraphs of white text on a black background. The amount of text is determined by the size of the font used and the horizontal and vertical resolution of the format. The Text_16 image uses a larger font than the Text_9 image. The secondary versions use black text on a white background.

The primary version of the Text_9 image is shown below.




Test Word processor simulation

Purpose If your monitor is used in word processor workstations or other applications that call for large amounts of text to be displayed, you can use this image to simulate actual user conditions.

Method Select a suitable font size and text color. Adjust your monitor's brightness and contrast controls to obtain the best image. The characters in all areas of the display should be well formed and in focus.

TAARamp

Description The TAARamp pattern is shown below.




TintAlign

Description




Toshiba

Description Special test image developed per customer specifications. There are two sub images, the secondary image is depicted below. The top half of the image has three small boxes (red, green, blue) with the upper left half at 92.7% luminence and the upper right half at 50% luminence. There is a series of 11 small boxes of increasing luminence left to right with the luminence identified in text. The lower left quarter of the image is 28.5% luminence and the lower right is magenta at 44.3 IRE.



TPVAOC1 and TPVAOC2


Description The TPVAOC1 pattern is shown below.



TVBar100 & TVBar_75 (TV formats only)

Description The image consists of seven vertical bars that fill the entire active video area. The color and order of the bars is shown in the figure below. The TVBar100 image has a peak video level of 100 IRE and the TVBar_75 image has a peak video level of 75 IRE.

The TVBar100 image is shown below.




Test Color video performance

Purpose This general purpose pattern can be used to check the video handling capabilities of most parts of a television system.

Method When viewed on a TV screen, all of the colors should be correct and in the order shown. The hue and intensity of each bar should be uniform over the entire bar.

The image can be used with a TV waveform analyzer to check the performance of a video system. Individual scan lines of each image, as they would appear on a waveform analyzer, are shown on the following page.

The image is quite effective when used with a TV vectorscope to see how a video system handles an encoded color signal.The image consists of a white crosshatch on a black background. The lines form square boxes when the display's active video area has a 4:3 aspect ratio. The vertical lines are made using sine-squared (2 T) pulses (T = 125 nSec for NTSC and T = 100 nSec for PAL).




Test Convergence adjustment

Purpose To accurately produce an image on a color monitor, the three electron beams in the CRT must meet (converge) at the same location at the same time. Lines displayed on a mis-converged monitor will appear as several multi-colored lines, and the transitions between different colored areas will contain "fringes" of other colors.

Method The convergence adjustments of most color monitors can be divided into two main categories. The first set of adjustments, usually called "Static Convergence," calls for aligning the three beams in the center of the display. This method involves turning on all three guns and adjusting the various magnets on the convergence assembly to produce all white lines and dots in the center of the display. The convergence assembly is located on the neck of the CRT. Different monitors and CRT types may each require their own magnet adjustment sequence.

After the center of the display is properly converged, the outer areas can be adjusted by using the monitor's "Dynamic Convergence" controls. The number of controls, the area of the screen that they affect and their adjustment procedure is dependent upon the monitor under test.

Test Sweep linearity adjustment



Purpose To present an undistorted display, the horizontal and vertical sweeps of the electron beam across the face of the CRT should be at uniform speeds. Any non-uniformity in the sweep will cause portions of an image to be stretched while other portions will be compressed. Non-linearity in a monitor can show up in several ways. It may be present across the entire screen, a large portion of the screen, or it may be localized in a very small area.


Method Adjust the display's linearity controls so that all of the boxes in the crosshatch are identical in size. You can measure the boxes with a ruler or with a gauge made for the monitor under test. Any deviation should be within your specification limits.

Taffeta

Description


TVoutLin

Description Equivalent to Outline1 image but it uses anti-aliasing for vertical bars and double horizontal lines, which reduces flickering.



TVSplBar

Description Special test image developed per customer specifications.



C Error Messages

Topics in this appendix:

- Error code descriptions

Error code descriptions

0000-0099 General errors

0001 No such command

The generator encountered an invalid command error condition.

0002 No such query

The generator encountered an invalid command query error condition.

0003 Too many arguments

The generator encountered too many arguments for the executed command.

0004 Invalid argument count

The generator encountered an invalid argument count for the executed command.

0005 Invalid argument value

The generator encountered an invalid argument value for the executed command.

0006 Invalid file

The generator encountered an invalid file error condition.

0007 Invalid file type

The generator encountered an invalid file type error condition.

0008 Invalid file data

The generator encountered an invalid file data error condition.

0099 Internal error

The generator encountered an internal error condition.

2000-2999 Format errors

2030 Number of fields per frame less than 1

A valid video format must have at least one (1) vertical filed of video per frame.

2040 Number of fields per frame greater than 2

The generator hardware configuration does not support interlaced video formats having more than two (2) vertical fields per frame.

2041 Can not repeat field if progressive

Repeat field operation is only supported in interlaced video formats.

2050 Horizontal total too small

The video format's total (active + blanked) number of pixel clock cycles per horizontal scan line is below the minimum number supported by the generator hardware configuration.

2059 Invalid Mode

The video format setting is incompatible with the interface selected.

2060 Horizontal total too large

The video format's total (active + blanked) number of pixel clock cycles per horizontal scan line is greater than the maximum number supported by the generator hardware configuration.

2061 Invalid pixel repetition value

The value specified by the NPPP (number of pixels per pixel) to set the repetition factor for active lines is invalid.

2062 Invalid pixel and clock values

The value specified by the NCPP (number of clocks per pixel) to set the number of clocks per pixel is invalid.

2063 Invalid embedded aspect ratio

The value specified by the EXAR (extended aspect ratio) parameter is invalid.

2064 HDMI 5V pin is bad

The 5V pin of the HDMI connectors (Pin 18) is monitored by the generator. If the generator does not detect the 5V on this pin it will issue this error.

2065 Invalid specified border

The value specified for XLBW (left border width), XRBW (right border width), XTBH (top border height), or XBBH (bottom border height) is invalid.

2066 Invalid XAFD value

The value specified for the active format descriptor (XAFD) parameter was out of range.

2067 Invalid SXEX value

The value specified by the signal from extended aperture map is invalid.

2068 TMDS 5V pin is bad

The 5V pin of the DVI connectors is monitored by the generator. If the generator does not detect the 5V on this pin it will issue this error.

2071 Pixel rate too high

The video format's total (active + blanked) number of pixel clock cycles per horizontal scan line multiplied by the horizontal scan rate exceeds the maximum pixel clock frequency supported by the generator hardware configuration for the format's video type.

2072 Pixel clock rate too high for pixel depth

The video format's pixel depth combined with the total (active + blanked) number of pixel clock cycles per horizontal scan line and horizontal scan rate exceeds the maximum internal video data bit rate supported by the generator hardware configuration. The pixel depth and/or total number of pixels per line need to be reduced in order to keep the current horizontal scan rate.

2073 Pixel rate justification too high

The target pixel clock rate selected for justification of the video format exceeds the generator hardware configuration.

2074 Pixel depth not supported

The video format's pixel depth is not supported by the generator hardware configuration.

2075 Analog composite sync type not supported

The video format's analog video composite sync type selection is not supported by the generator hardware configuration.

2076 Digital sync composite type not supported

The video format's digital composite sync type selection is not supported by the generator hardware configuration.

2077 Number of digital links not allowed

The number of serial digital video data links in the video format exceeds the number of links supported by the current firmware.

2078 Digital sync separate type not allowed for HDTV formats

The generator hardware configuration does not support digital separate sync for the specific video type selection in the video format

2079 Number of links not supported

The number of serial digital video data links in the video format exceeds the number of links supported by the generator hardware configuration.

2080 Pixel rate too low

The video format's total (active + blanked) number of pixel clock cycles per horizontal scan line multiplied by the horizontal scan rate is less than the minimum pixel clock frequency supported by the generator hardware configuration for the format video type.

2082 Number of bits not allowed

The generator hardware configuration does not support the number of data bits per color for the serial digital video type selected in the video format.

2083 Invalid quantizing mode

An invalid value has been specified for the digital video quantizing mode (DVQM) parameter.

2084 Invalid Pixel Repetition

In digital mode, double clocking is not supported for this specific hardware. This error may be the result of an older FPGA or hardware.

2085 Invalid Sampling Mode

The value specified for digital video sampling mode (DVSM) is not valid and is inconsistent with the setting of digital video signal type (DVST).

2086 Invalid Video ID Code

The value specified for the CEA-861 Video Identification Code (VIC) with the DVIC parameter is invalid.

2087 Invalid Number of Bits per Audio Sample

The value specified for number of bits per audio sample (NBPA) is invalid.

2088 Invalid Sampling Rate

The value specified for audio sampling rate (ARAT) is invalid.

2089 Invalid Number of Audio Streams

The value specified for number of audio streams (NDAS) is invalid.

2090 Horizontal total not even

The generator hardware configuration does not support interlaced video formats with a total (active + blanked) number of pixel clock cycles per horizontal scan line that is not evenly divisible by 2.

-OR-

The generator hardware configuration does not support a video format with a total (active + blanked) number of pixel clock cycles per horizontal scan line that is not evenly divisible by 2 for the selected analog or digital composite sync type.

2091 Horizontal total not a multiple of 4

The generator hardware configuration does not support a video format with a total (active + blanked) number of pixel clock cycles per horizontal scan line that is not evenly divisible by 4. Mostly applies to video formats using serial digital video.

2092 Horizontal resolution not even

Number of active pixels per line must be evenly divisible by 2 for the given video format type and generator hardware configuration.

2093 Horizontal sync pulse width not even

Number of pixel clock cycles in the horizontal sync pulse width must be evenly divisible by 2 for the given video format type and generator hardware configuration.

2094 Horizontal sync pulse delay not even

The number of pixel clock cycles in the horizontal sync pulse delay must be evenly divisible by 2 for the given video format type and generator hardware configuration.

2096 Horizontal resolution not a multiple of 4

The generator hardware configuration does not support a video format with a number of active pixels per horizontal scan line that is not evenly divisible by 4. Mostly applies to video formats using serial digital video.

2097 Horizontal sync pulse width not a multiple of 4

The generator hardware configuration does not support a video format with the number of pixel clock cycles in the horizontal sync pulse width not evenly divisible by 4. Mostly applies to video formats using serial digital video.

2098 Horizontal sync pulse delay not a multiple of 4

The generator hardware configuration does not support a video format with the number of pixel clock cycles in the horizontal sync pulse delay not evenly divisible by 4. Mostly applies to video formats using serial digital video.

2099 JRAT greater than 200MHz not allowed

The 802BT generator does not support a setting of JRAT greater than 200MHz.

2110 Invalid number of audio channels

The value specified for the number of digital audio channels is out of range.

2111 Invalid digital audio signal type

The value specified for digital audio signal type (DAST) is out of range.

2112 Invalid audio digital signal interface

The value specified for digital audio signal interface (DASI) is out of range.

2113 Invalid number of audio channels available

2114 Invalid audio level shift value

The value specified for digital audio level shift (DALS) is out of range.

2115 Invalid audio sine wave rate

The value specified for digital audio sine wave rate (SRAT) is out of range.

2117 Fs measured is not equal to Fs assigned

The value detected for the sampling frequency is not equal to the value assigned for the audio sampling rate (ARAT). This typically means there is a hardware problem in the generator's digital audio generator.

2118 Invalid audio signal amplitude

The value specified by digital audio sine wave amplitude (SAMP) is out of range.

2119 Send CP info error is not zero

The CP infoframe register on the transmitter is not set to zero and the infoframe is not transmitted. This typically means that there is a hardware problem in the HDMI board.

2120 Send AVI info error is not zero

The AVI infoframe register on the transmitter is not set to zero and the infoframe is not transmitted. This typically means that there is a hardware problem in the HDMI board.

2121 Send SPD info error is not zero

The SPD infoframe register on the transmitter is not set to zero and the infoframe is not transmitted. This typically means that there is a hardware problem in the HDMI board.

2122 Send AUD info error is not zero

The AUD infoframe register on the transmitter is not set to zero and the infoframe is not transmitted. This typically means that there is a hardware problem in the HDMI board.

2123 Send MPEG info error is not zero

The MPEG infoframe register on the transmitter is not set to zero and the infoframe is not transmitted. This typically means that there is a hardware problem in the HDMI board.

2124 Send GEN info error is not zero

The General infoframe register on the transmitter is not set to zero and the infoframe is not transmitted. This typically means that there is a hardware problem in the HDMI board.

2125 Invalid sonic data

The value specified for the digital audio mixer (SDMG) is out of range.

2126 Invalid content aspect ratio

The value specified by the CXAR (content aspect ratio) parameter is invalid.

2128 Invalid audio contents

2129 Invalid signal aspect ratio

The value specified by the SXAR (signal aspect ratio) parameter is invalid.

2130 Horizontal active too small

The number of active pixels per horizontal scan line is less than the minimum supported by the generator hardware configuration.

2140 Horizontal blanking too small

The video format's horizontal blanking period expressed in microseconds and/or number of pixel clock cycles is not supported by the generator hardware configuration.

2141 Horizontal blanking too small

Same as Error number 2140. Found in some firmware releases for different generator hardware configurations.

2150 Horizontal blanking too small

Same as Error number 2140. Found in some firmware releases for different generator hardware configurations.

2151 Horizontal total less than horizontal resolution

The video format's total (active + blanked) number of pixel clock cycles per horizontal scan line can not be less than the number of active pixels per scan line.

2152 Horizontal resolution too large or Horizontal blanking too small

Same as Error number 2140. Found in some firmware releases for different generator hardware configurations.

2155 Horizontal blanking too small

Same as Error number 2140. Found in some firmware releases for different generator hardware configurations.

2180 Horizontal pulse width too small

The generator hardware configuration does not support video formats having horizontal sync pulse widths less than one pixel clock cycle long.

2181 Horizontal sync pulse width not even

Number of pixel clock cycles in the horizontal sync pulse width must be evenly divisible by 2 at the current pixel clock rate for the video format and generator hardware configuration.

2190 HSPW too small for HDTV sync

The generator hardware configuration does not support video formats having horizontal sync pulse widths less than two pixel clock cycles long for the current video and HDTV sync type selections.

2191 HSPW must be even for HDTV sync

The number of pixel clock cycles in the horizontal sync pulse width must be evenly divisible by 2 for the current video and HDTV sync type selections.

2200 Horizontal pulse width too large

The generator hardware configuration does not support a horizontal sync pulse width that is greater than the horizontal blanking period.

2201 Horizontal pulse delay not even.

The number of pixel clock cycles in the horizontal sync pulse delay must be evenly divisible by 2 at the current pixel clock rate for the video format and generator hardware configuration.

2205 Frame sync pulse width too small

The generator hardware configuration does not support a Frame Sync pulse width less than horizontal scan period.

2206 Frame sync pulse width too large

The Frame Sync pulse width can not be greater than the total (active + blanked) number of horizontal scan lines in one frame of video.

2207 Probe sync pulse width too small

The probe sync pulse width is less than minimum supported by the generator hardware configuration.

2208 Probe sync pulse width too large

The probe sync pulse width is greater than maximum supported by the generator hardware configuration.

2230 Horizontal pulse delay extends sync beyond blanking

The generator hardware configuration does not support the video format's combination of horizontal sync pulse delay and pulse width that places any portion of the horizontal sync pulse outside of the horizontal blanking period.

2231 Vertical serration adjustment too big

The video format's HVSA setting beyond the maximum limit for the video type selected and generator hardware configuration.

2240 Vertical total too small

The total (active + Blanked) number of horizontal scan lines per frame a progressive scan (non-interlaced) video format is lees than the minimum supported by the generator hardware configuration.

2250 Vertical total too small for interlaced format

The total (active + blanked) number of horizontal scan lines per frame is less than the minimum number supported by the generator hardware configuration.

2270 Vertical total is even

The generator hardware configuration does not support interlaced scan video formats having an even total (active + blanked) number of horizontal scan lines per frame.

2280 Vertical total too large

The total (active + blanked) number of horizontal scan lines per frame exceeds the maximum limit for the generator hardware configuration.

2300 Vertical active too small

The active number of horizontal scan lines per frame of a progressive scan (non-interlaced) video format is less than the minimum supported by the generator hardware configuration.

2310 Vertical blanking too small

The number of blanked horizontal scan lines per frame for a progressive scan (non-interlaced) video format is less than the minimum supported by the generator hardware configuration.

2320 Vertical active too small for interlaced format

The active number of horizontal scan lines per frame of an interlaced video format is less than the minimum supported by the generator hardware configuration.

2321 Vertical active not even

The generator hardware configuration does not support interlaced scan video formats having an odd active number of horizontal scan lines per frame.

2330 Vertical blanking too small for interlaced format

The number of blanked horizontal scan lines per frame for an -interlaced video format is less than the minimum supported by the generator hardware configuration.

2350 Vertical pulse too small

The vertical sync pulse width is less than the minimum supported by the generator hardware configuration.

2370 Vertical pulse too large

The vertical sync pulse width is greater than the maximum supported by the generator hardware configuration.

2390 Vertical pulse too large for interlaced format

The vertical sync pulse width combined with the number of pre and post-equalization pulses for an interlaced format is greater than the maximum supported by the generator hardware configuration.

2391 Incompatible analog composite sync & digital composite sync types

The generator hardware configuration does not support the video format outputting both analog composite sync and digital composite sync type selections at the same time.

2392 Incompatible analog composite sync & digital separate sync types

The generator hardware configuration does not support the video format outputting both analog composite sync and digital separate sync type selections at the same time.

2393 Analog composite sync type not compatible with analog video type

The generator hardware configuration does not support the video format's analog composite sync type being added to the current analog video type.

2394 ACS available on green only

The generator hardware configuration supports adding analog composite sync to only the green analog video output

2395 Sync type selection incompatible with analog video type selection

The video format's analog video type selection requires the use of analog composite sync.

2396 Invalid analog composite sync type

The current firmware does not support the format's analog composite sync type parameter value (ASCT setting) or the generator hardware configuration does not support a video format's analog composite sync type for non-interlaced operation.

2397 Invalid digital composite sync type

The current firmware does not support the format's digital composite sync type parameter value (DSCT setting) or the generator hardware configuration does not support a video format's digital composite sync type for non-interlaced operation.

2398 Invalid digital separate sync type

The current firmware or generator hardware configuration does not support the format's digital separate sync type parameter value (DSST setting)

2399 Invalid sync type selection

The current firmware does not support the format's active sync type selection (SSST setting).

2400 Analog composite sync type and digital separate sync type incompatible

The generator hardware configuration does not support analog composite sync and digital separate sync being active at he same time for the given analog composite sync type parameter value (ASCT setting) and digital separate sync type parameter value (DSST setting).

2401 Invalid horizontal sync pulse delay

The generator hardware configuration does not support the format's current horizontal sync pulse delay setting

2405 Frame sync pulse delay negative

The video format's frame sync pulse delay setting must be zero or a positive number.

2406 Frame sync pulse delay too large

The video format's frame sync pulse delay setting exceeds the maximum limit supported by the generator hardware configuration.

2407 Negative probe sync pulse vertical delay

The video format's probe pulse vertical delay setting must be zero or a positive number.

2408 Probe sync pulse vertical delay too large

The video format's probe pulse vertical delay setting exceeds the maximum limit supported by the generator hardware configuration.

2409 Negative probe sync pulse horizontal delay

The video format's probe pulse horizontal delay setting must be zero or a positive number.

2410 Probe sync pulse horizontal delay too large

The video format's probe pulse horizontal delay setting exceeds the maximum limit supported by the generator hardware configuration.

2425 Sync type selection not supported

The current firmware does not support the video format's active sync type selection (SSST setting) or the active sync type selection is not supported by the current analog video type selection (AVST setting).

2430 Vertical pulse delay extends sync beyond blanking

The generator hardware configuration does not support non-interlaced video formats having a vertical sync pulse period greater that the vertical blanking period

2450 Vertical pulse delay extends sync beyond blanking

The generator hardware configuration does not support interlaced video formats having a vertical sync pulse period greater that the individual blanking periods between the fields.

2465 Pixel clock pulse gate = 1 and pixel depth = 8

The generator hardware configuration does not support outputting a pixel clock output when the video format's pixel depth is eight bits-per-pixel.

2466 Pixel clock pulse gate = 1 not allowed

The generator hardware configuration does not support a pixel clock output.

2490 EQ before too large

The video format's number of lines of pre-equalization for analog or digital composite sync must not exceed the number of lines of vertical sync pulse delay.

2495 EQ after too large for interlaced format

The interlaced video format's number of lines of post-equalization for analog or digital composite sync must not exceed the number of scan lines from the end of the vertical sync pulse to the start of video for either field.

2496 EQ after too large

The non-interlaced video format's number of lines of post-equalization for analog or digital composite sync must not exceed the number of scan lines from the end of the vertical sync pulse to the start of video.

2550 Not enough video memory

The generator hardware configuration does not have enough video memory to support the video format's combination of active pixels per line (HRES setting) and active lines per frame (VRES setting).

2551 Insufficient memory

Not implemented at the time this document was created.

2553 No PCMCIA card found in drive

When attempting to download a bitmap no PCMCIA card was detected in the generator's PCM slot.

2554 PCMCIA card is write-protected

When attempting to download a bitmap to a PCMCIA card, the PCM card was write-protected.

2555 PCMCIA card is bad

When attempting to download a bitmap to a PCMCIA card, the PCM card was found to be bad.

2704 Invalid horizontal physical size

The video format's horizontal physical size value can not be negative.

2705 Invalid physical size units

The current firmware does not support the type number used for the video format's units of measure for physical size (USIZ setting).

2706 Invalid vertical physical size

The video format's vertical physical size value can not be negative.

2714 Pedestal swing out of range

The video format's blanking pedestal level (AVPS setting) can not be less that 0.0% of the peak video level or more than 100.0% of the peak video level.

2715 Gamma correction out of range

The current firmware does not support a video format's gamma correction factor (GAMA setting) of less than 0.1 or greater than 10.

2716 Analog video swing out of range

The generator hardware configuration does not support the video format's analog video swing value (AVSS setting) for the given analog video type selection.

2717 Sync swing out of range

The generator hardware configuration does not support the video format's analog video composite sync swing value (ASSS setting) for the given analog video type selection.

2719 Video swing calibration out of range

The generator hardware configuration does not support the current user defined analog video swing calibration factors (AVSC settings) for one or more of the red, green or blue channels. The valid factory default setting is 1.00 for all three channels.

2720 Sync swing calibration out of range

The generator hardware configuration does not support the current user defined analog video composite sync swing calibration factors (ASSC settings) for one or more of the red, green or blue channels. The valid factory default setting is 1.00 for all three channels.

2721 NTSC TV signals require blanking pedestal

The generator hardware configuration does not support producing NTSC TV video outputs that do not use a blanking pedestal (AVPG setting of 0) as required by the NTSC specifications.

2722 Blanking pedestal out of range for NTSC TV signal

The generator hardware configuration does not support producing NTSC TV video outputs that do not use a nominal blanking pedestal level (AVPS setting) of 7.5 IRE as required by the NTSC specifications.

2741 Digital video signal type not supported

The generator hardware configuration does not support any type of digital video outputs.

2742 Invalid digital video signal type

The current firmware does not support the format's digital video type selection (DVST setting).

2743 Digital video polarity not positive

The generator hardware configuration and/or the firmware does not support digital video formats having a logic low level for the active (lit) pixels.

2745 Can not have analog AND digital video

The generator hardware configuration does not support the simultaneous generation of analog and digital video signals.

2747 Invalid analog video signal type

The current firmware for a given model generator does not support the video format's analog video type selection.

2748 Analog video signal type not supported

The generator hardware configuration does not support the video format's analog video type selection.

2760 Digital video not supported

The generator hardware configuration does not support the video format's digital video type selection.

2761 Digital video signal swing out of range

The value specified for the digital video signal swing is out of range.

2762 Digital video swing calibration out of range

The value specified for the digital video swing calibration is out of range.

2763 Invalid XVSI

The value specified for the interface selection (XVSI) is invalid.

2800 Pseudo-random noise seed value exceeds limit

The seed value for the pseudo-random noise analysis exceeds its maximum value.

2801 Pseudo-random noise sequence exceeds limit

The length of the pseudo-random noise sequence exeeds maximum value.

2802 Pseudo-random noise type is not supported

The pseudo-random noise type is not supported.

2803 No signal input to analyzer or TMDS error

There is no signal input to the receive interface of the analyzer.

2804 X coordinate for delta patch out-of-range

The value specified for the X coordinate of the delta patch test is out-of-range.

2805 Y coordinate for delta patch out-of-range

The value specified for the Y coordinate of the delta patch test is out-of-range.

2806 Patch height must be greater than one

The patch height specified for a delta error test must be greater than one.

3000-3999 Image errors

3000 Invalid color name

The current firmware does not support a named color used by one or more primitives in the user defined custom image

3001 Invalid pattern name

The current firmware does not support a named fill patterns used by one or more primitives in the user defined custom image

3002 No image memory

There is not enough unused edit buffer memory space available to start a new custom image editing session.

3004 Invalid font name

The current firmware does not support a named font used by one or more primitives in the user defined custom image

3005 Image editor running

The current firmware does not allow a new custom image editing session to be started while the current custom image editing session is still running.

3006 Nothing to save

An attempt was made to save the contents of a custom image editing buffer when there was no open custom image editing session to save.

3007 Overwrite ROM Image

A user defined test image can not be saved using the same name as that of a built-in test image (case insensitive).

3008 Image save failed

Saving the contents of the custom image editing buffer failed for a reason other than those reported by error codes 3005 or 3006.

3010 R, G or B 8-Bit video DAC setting out of range

A combination of system calibration factors, user calibration multiplier settings and video output level settings have resulted in one or more calculated input values to go below zero or above the analog video Digital-to-Analog Converter's maximum limit of 255.

3011 R, G or B 6-Bit video DAC setting out of range

A combination of system calibration factors, user calibration multiplier settings and video output level settings have resulted in one or more calculated input values to go below zero or above the analog video Digital-to-Analog Converter's maximum limit of 63.

3015 R, G or B 10-Bit video DAC setting out of range

A combination of system calibration factors, user calibration multiplier settings and video output level settings have resulted in one or more calculated input values to go below zero or above the analog video Digital-to-Analog Converter's maximum limit of 1023.

3020 Kill EPROM image

Built in test images can not be removed from the firmware.

3025 Image not found

A test image of a given name could not be found as either a built-in test image in the firmware or as a user defined custom image.

3050 Grayscale video DAC setting out of range

One or more internal calculations have resulted in an analog video DAC input grayscale setting below zero or greater than 100% video level.

4000-4999 Test sequence errors

4000 Invalid format name

The test sequence contains one or more steps that have an invalid format name parameter.

4001 Invalid image name

The test sequence contains one or more steps that have an invalid image name parameter.

4002 No sequence memory

There is not enough unused edit buffer memory space available to start a new test sequence editing session.

4003 Sequence memory full

There is not enough free battery backed user storage memory to save the sequence that is in the edit buffer.

4004 Sequence not found

A test sequence of the given name could not be found in the user storage memory area.

4005 Sequence editor running

The current firmware does not allow a new test sequence editing session to be started while the current test sequence editing session is still running.

4006 No sequence to save

An attempt was made to save the contents of a test sequence editing buffer when there was no open test sequence editing session to save.

4007 Sequence buffer full

No more steps can be added to the current sequence being edited because no more edit buffer space is available.

4008 Invalid delay setting in sequence

The test sequence contains one or more steps that have a negative number for the step delay time.

4010 Font index out of range

An attempt was made to use a font at an index location that is less than zero (0) or greater than the highest index number in use.

4020 No font present at given index

Attempt to access a font at a valid index but the specified index is empty because of a previous delete.

4030 Invalid font location

Can not install a font that has not first been transferred to memory.

4040 Sequence is running

A sequence editing session can not be started while a sequence is running.

4045 No sequence buffer

An attempt was made to change a parameter in a sequence step when there were no sequence steps in the current sequence being edited.

4100 Pattern index out of range

The selected index number for a drawing primitive's fill pattern is less than zero or greater than the highest number used by the current firmware.

4576 Can not convert to inches, not valid units

The format's current physical units of measure (inches or millimeters) is unknown and the firmware is unable to convert a dimension to inches.

4579 Can not convert to mm, not valid units

The format's current physical units of measure (inches or millimeters) is unknown and the firmware is unable to convert a dimension to millimeters.

5000-5999 Directory errors

5002 No directory memory

The DIRN or NAMI command failed because there is an insufficient amount of managed memory for the buffer request.

5003 Directory memory full

The DIRA or DIRS command failed because there is insufficient room in the directory memory pool for the requested save.

5006 No directory to save

An attempt was made to save the contents of a directory editing buffer when there was no open directory editing session to save.

5009 Directory list full

This occurs during DIRA and DIRS commands when attempting to save more directories than supported by the current firmware.

5010 Invalid name index

The value of the <index> parameter used for a NAMQ? query is can not be zero(0).

6000-6999 Bitmap errors

6006 No map to save

An attempt was made to save the contents of a bit map editing buffer when there was no open bit map editing session to save.

6020 Map not found

An attempt was made to access a bit map whose name can not be found in the generator's list of currently stored bitmaps

6030 Invalid map dimensions

A bit map can not have a horizontal or vertical dimension of less than one (1) pixel.

6035 Invalid map depth

The current firmware and/or generator hardware configuration does not support pixel depth setting of the selected bit map.

6036 Map data index

An attempt was made to recall a bit map at an index location that is less than zero (0) or greater than the highest index number in use for bit maps.

7000-7999 LUT errors

7006 No LUT to save

An attempt was made to save the contents of a color lookup table editing buffer when there was no open color lookup table editing session to save.

7010 No LUT buffer

An attempt was made to modify the contents of a color lookup table editing buffer when there was no open color lookup table buffer available.

7011 Invalid LUT Index

An attempt was made to recall a color lookup table at an index location that is less than zero (0) or greater than the highest index number in use for color lookup tables.

7020 LUT not found

8000-8999 Font errors

8450 Cannot remove font. Font not found.

Attempt to use FNTK command to delete a nonexistent font by name.

8455 Cannot remove built-in font

Attempt to use FNTK command to delete a built-in font.

8460 Font already exists in memory

Attempt made to transmit a font to the generator which already contained a font with the same name.

9000-9999 System errors

9450 Corrupted format

Checksum error in data for a particular video format

9451 Bad location for format, failed verify

This occurs during FMTV command and FMTV? query when you attempt to verify data integrity at an invalid location.

9452 Bad location for format verify

This occurs during a FMTZ? query when you try to determine if an invalid location has been erased.

9453 Kill EPROM format

Cannot delete factory default formats stored in EPROM

9453 Can not change EPROM contents

This occurs during FMTW or FMTZ commands when you try to overwrite or zero out an EPROM format.

9454 Bad location for format erase

This occurs during FMTE command when you try to access an invalid format memory location.

9456 Bad location for format read/write

This occurs during FMTR or FMTW commands when you try to read or write to an invalid format memory location.

9457 Bad location for format name read

This occurs during FMTR? query when you try to read or write to an invalid format memory location.

9458 Bad location for format copy

This occurs during FMTD command when you try during copying to access an invalid format memory location.

9459 Can not change EPROM contents

This occurs during FMTD command when you try during copying to overwrite an EPROM format.

9460 Bad location for format duplicate

This occurs during FMTD and FMTI commands when you try to use one or more invalid format memory locations as the command arguments.

9467 Bad location for format erase

This occurs during FMTZ command when you try to make one or more invalid format memory locations as the command arguments.

9470 Can not change EPROM contents

An attempt was made to insert a format using the FMTI command into an EPROM format memory location.

9471 Bad location for format yank

This occurs when you try to remove (yank) one or more formats from invalid format memory locations using the FMTY command.

9472 Can not change EPROM contents

This occurs when you try to remove (yank) one or more formats from EPROM format memory locations using the FMTY command.

9475 Can not change EPROM contents

One or more EPROM format locations was given as the destination location for the FMTD command.

9477 Error duplicating formats

The <first> memory location parameter used with the FMTD command is greater than the <last> memory location parameter.

9480 Format not found / Format data missing

The FMTR command tried to read a format from an empty format storage location.

9490 DDC mod not present

The generator hardware configuration does not support DDC communications.

9491 DDC not available

The generator hardware configuration does not support DDC communications.

9492 DDC2B no ACK from receiver

Low level DDC communications failed with Unit Under Test (UUT). No DDC acknowledgment bit was received from the UUT.

9493 DDC2B arbitration lost

Low level DDC communications failed with Unit Under Test (UUT). DDC bus arbitration lost with the UUT.

9494 DDC2B timeout on bus

Low level DDC communications failed with Unit Under Test (UUT). DDC communications timed out with the UUT.

9496 EDID header not found

A valid block of header data could not be found in the EDID data read back from Unit Under Test (UUT).

9497 DDC old monitor

A DDC compliant Unit Under Test (UUT) could not be found connected to the generator.

9498 I2C address missing

There was a communications error within the generator hardware architecture because the device address was missing.

9499 I2C count missing

There was a communications error within the generator hardware architecture because the data count was missing.

9500 I2C stream too big

There was a communications error within the generator hardware architecture because the data stream size exceeded the size supported by the device.

9500 Sequence data not found

An attempt was made to use the SEQR command to read a sequence from an empty sequence storage location.

9501 I2C data missing

There was a communications error within the generator hardware architecture because the device data stream was missing.

9502 I2C register missing

There was a communications error within the generator hardware architecture.

9503 I2C data byte missing

There was a communications error within the generator hardware architecture because the device data stream had missing data.

9504 Serial digital video PLL not locked

There is an internal problem with the generator's serial digital video hardware's Phase Lock Loop circuit.

9505 TV output hardware not ready

The generator's serial digital video generating hardware is not yet ready to output video

9506 Serial digital video hardware not ready

The generator's TV signal generating hardware reports it is not yet ready to output valid video

9507 I2C offset missing

There was a communications error within the generator hardware architecture

9508 Invalid HDCP receiver KSV

The HDCP Key Selection Vector returned from the HDCP receiver in the Unit Under Test (UUT) is not valid.

9520 HDCP key combination not supported

The HDCP key combination between the Tx and the Rx is invalid. The Tx may have production keys and the Rx public keys.

9521 HDCP failed after a while

The HDCP authentication started but failed after a while.

9522 HDCP key combination not supported

The HDCP authentication did not start.

9523 HDCP production keys not supported

HDCP test initiated and specified production keys where are not supported in generator option.

9524 Invalid transmitter KSV

HDCP video transmitter KSV sent by the generator is invalid.

9525 HDCP Ri value not ready

HDCP authentication cannot start because HDCP Ri value (link verification response) at the transmitter is not ready.

9527 HDCP Ri do not match

HDCP authentication cannot start because HDCP Ri (link verification response) values at the transmitter and receiver do not match.

9528 HDCP was interrupted

HDCP authentication was interrupted possibly by disconnecting the cable.

9529 HDCP receiver not detected

HDCP authentication failed to start because the hot plug was not detected.

9530 HDCP invalid for animation

HDCP test will not run when an animated image is loaded.

9531 I2C segment number missing

The segment number of the enhanced DDC bus is missing.

9532 I2C address 1 missing

The first address of the enhanced DDC bus is missing.

9533 I2C address 2 missing

The second address of the enhanced DDC bus is missing.

9538 Memory address out of range

The generator encountered a memory address out of range condition.

9539 Memory count missing

The generator encountered a memory count missing condition.

9540 Memory stream too big

The generator encountered a memory stream too big condition.

9541 Memory data missing

The generator encountered a memory data missing condition.

9542 Memory address missing

The generator encountered a memory address missing condition.

9544 Repeater not ready

The generator encountered a repeater not ready condition.

9545 Repeater mismatch

The generator encountered a repeater mismatch condition.

9546 FIFO not ready

The generator encountered a FIFO not ready condition.

9600 Can not save format to EPROM

An attempt was made to save a format edit buffer's contents to a location in the firmware EPROM.

10000-10999 System errors

10000 Out of memory

There is not enough unused battery backed user memory space to store the contents of the given edit buffer

10010 Invalid file check sum

The data object file that has been recalled from the generator's memory contains an invalid checksum. Data may be corrupted.

10020 Invalid file version

The data object file that has been recalled from memory contains a file version number that does not match the current firmware. Data may not be properly interpreted by the firmware

10025 File type

The data object file that has been recalled from memory contains a file type identification that is not supported by the current firmware.

10026 File size

The size of the data object file that has been recalled from memory does not match the size information stored in the file's header data.

10030 Feature not implemented

The generator hardware configuration does not support one or more settings in the video format.

10031 Feature not available

The generator hardware configuration does not support the selected feature.

10035 Video board not detected

An attempt was made to reprogram the firmware Flash EPROMs in a Model 822 series generator without a video board installed. The video board's memory is used as a buffer for the initial uploading of the firmware data.

10040 Buffer overflow

The generator encountered a buffer overflow condition.

10100 Filename alias not found

An attempt was made to delete a filename alias that does not exist.

10200 Font not overwriteable

An attempt was made to save the contents of a font editing buffer to a location in the firmware EPROM.

10205 Font save failed

There is not enough unused battery backed user memory space to store the contents of the font editing buffer.

10210 Font table range

The recalled font data object contains a reference to a nonexistent table in the data object.

10215 Font table Index range

The recalled font data object contains a reference to a nonexistent location in one of the tables in the data object.

10220 Font not found

An attempt was made to recall a font by name that is not stored in the generator.

10225 Can not delete font in EPROM

Ann attempt was made to delete a font stored in the firmware EPROM.

10230 Invalid font check mode

The current firmware does not support the selected test method on the contents of the font edit buffer.

10235 No font definition

The recalled font does not contain valid font definition data need to determine the size needed by the edit buffer.

10240 Font character high range

The character height setting of the font in the edit buffer is less than one or greater than the maximum supported by the current firmware.

10241 Font ascent descent sum

The character height setting of the font in the edit buffer is does not match the sum of the character ascent and descent settings

10242 Invalid font character range

The first or last character number setting of the font in the edit buffer is greater than the maximum supported by the current firmware or the number of the first character is greater than the number of the first character.

10300 CEC receive bit error

The generator encountered a CEC receive bit error condition.

10301 CEC receive time error

The generator encountered a CEC receive time error condition.

10302 CEC receive FIFO error

The generator encountered a CEC receive FIFO error condition.

10303 CEC receive start error

The generator encountered a CEC receive start error condition.

10304 CEC receive drop error

The generator encountered a CEC receive drop error condition.

10305 CEC receive free error

The generator encountered a CEC receive free error condition.

10310 CEC transmit line error

The generator encountered a CEC transmit line error condition.

10311 CEC transmit arb lost

The generator encountered a CEC transmit arb lost error condition.

10312 No acknowledgement from receiver

Upon sending a CEC message from the command line, the target CEC device does not acknowledge the message.

10313 CEC transmit failed

The generator encountered a CEC transmit failed condition.

10320 CEC message error

The generator encountered a CEC message error condition.

D Format Reference

Topics in this appendix:

- Formats by type

SDTV Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
480i	720 x 480	Interlace	15.734	59.940	13.500
480i#	720 x 480	Interlace	15.734	59.940	12.272727
480i#KA	720 x 480	Interlace	15.734	59.940	12.272727
480i2x_1	720 x 480	Interlace	62.937	239.760	53.999968
480i2x_2	720 x 480	Interlace	63.000	240.000	54.054
480i2x29	720 x 480	Interlace	15.734	59.940	13.500
480i2x30	720 x 480	Interlace	15.750	60.000	13.5135
480i2x59	720 x 480	Interlace	31.469	119.880	27.000
480i2x60	720 x 480	Interlace	31.500	120.000	27.027
480i2xL1	720 x 480	Interlace	15.734	59.940	13.500
480i2xL2	720 x 480	Interlace	15.750	60.000	13.5135
480i2xL3	720 x 480	Interlace	31.469	119.880	26.999984
480i2xL4	720 x 480	Interlace	31.500	120.000	27.027
480i2xL5	720 x 480	Interlace	62.937	239.760	53.999968
480i2xL6	720 x 480	Interlace	63.000	240.000	54.054
480i2xS1	720 x 480	Interlace	15.734	59.940	13.500
480i2xS2	720 x 480	Interlace	15.750	60.000	13.513500
480i2xS3	720 x 480	Interlace	31.469	119.880	26.999984
480i2xS4	720 x 480	Interlace	31.500	120.000	27.027
480i2xS5	720 x 480	Interlace	62.937	239.760	53.999968
480i2xS6	720 x 480	Interlace	63.000	240.000	54.054
480i4x29	2880 x 480	Interlace	15.734	59.940	54.000
480i4x30	2880 x 480	Interlace	15.750	60.000	54.054
480i4xL1	2880 x 480	Interlace	15.734	59.940	54.000
480i4xL2	2880 x 480	Interlace	15.750	60.000	54.054
480i4xS1	2880 x 480	Interlace	15.734	59.940	54.000
480i4xS2	2880 x 480	Interlace	15.750	60.000	54.054
480iLH	720 x 480	Interlace	15.734	59.940	13.500
480iSH	720 x 480	Interlace	15.734	59.940	13.500
480iWH	960 x 480	Interlace	15.734	59.940	18.000

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
480p#	640 x 480	Interlace	31.469	59.940	24.545454
480p#KA	640 x 480	Progressive	31.469	59.940	24.545454
480p119	720 x 480	Progressive	62.937	119.880	54.000
480p119L	720 x 480	Progressive	62.937	119.880	54.000
480p119S	720 x 480	Progressive	62.937	119.880	54.000
480p120	720 x 480	Progressive	63.000	120.000	54.054
480p120L	720 x 480	Progressive	63.000	120.000	54.054
480p120S	720 x 480	Progressive	63.000	120.000	54.054
480p239	720 x 480	Progressive	125.874	239.760	107.999992
480p239L	720 x 480	Progressive	125.874	239.760	107.999992
480p239S	720 x 480	Progressive	125.874	239.760	107.999992
480p240	720 x 480	Progressive	126.000	240.000	108.108
480p240L	720 x 480	Progressive	126.000	240.000	108.108
480p240S	720 x 480	Progressive	126.000	240.000	108.108
480p2x59	1440 x 480	Progressive	31.469	59.940	54.000
480p2x60	1440 x 480	Progressive	31.500	60.000	54.054
480p2xL1	1440 x 480	Progressive	31.469	59.940	54.000
480p2xL2	1440 x 480	Progressive	31.500	60.000	54.054
480p2xS1	1440 x 480	Progressive	31.469	59.940	54.000
480p2xS2	1440 x 480	Progressive	31.500	60.000	54.054
480p4x59	2880 x 480	Progressive	31.469	59.940	108.000
480p4x60	2880 x 480	Progressive	31.500	60.000	108.108
480p4xL1	2880 x 480	Progressive	31.469	59.940	108.000
480p4xL2	2880 x 480	Progressive	31.500	60.000	108.108
480p4xS1	2880 x 480	Progressive	31.469	59.940	108.000
480p4xS2	2880 x 480	Progressive	31.500	60.000	108.108
480p59	720 x 480	Progressive	31.469	59.940	27.000
480p59LH	720 x 480	Progressive	31.469	59.940	27.000
480p59SH	720 x 480	Progressive	31.469	59.940	27.000
480p60	720 x 480	Progressive	31.500	60.000	27.027
480p60LH	720 x 480	Progressive	31.500	60.000	27.027
480p60SH	720 x 480	Progressive	31.500	60.000	27.027
480pWH	960 x 480	Progressive	31.469	59.940	36.000
487i	720 x 487	Interlace	15.734	59.939	13.500
576i	720 x 576	Interlace	15.625	50.000	13.500
576i#	720 x 576	Interlace	15.625	50.000	14.750
576i#KA	720 x 576	Interlace	15.625	50.000	14.750
576i2x_1	720 x 576	Interlace	62.500	200.000	54.000
576i2x25	720 x 576	Interlace	16.625	50.000	13.500
576i2x50	720 x 576	Interlace	31.250	100.000	27.000
576i2xL1	720 x 576	Interlace	31.250	100.000	27.000
576i2xL2	720 x 576	Interlace	62.500	200.000	54.000
576i2xLH	720 x 576	Interlace	16.625	50.000	13.500
576i2xS1	720 x 576	Interlace	31.250	100.000	27.000
576i2xS2	720 x 576	Interlace	62.500	200.000	54.000
576i2xSH	720 x 576	Interlace	15.625	50.000	13.500
576i4x25	2880 x 576	Interlace	15.625	50.000	54.000

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
576i4xLH	2880 x 576	Interlace	15.625	50.000	54.000
576i4xSH	2880 x 576	Interlace	15.625	50.000	54.000
576i50	720 x 576	Interlace	31.250	100.000	27.000
576i50_H	960 x 576	Interlace	31.250	100.000	37.125
576i50_L	960 x 576	Interlace	31.250	100.000	37.125
576i50WH	960 x 576	Interlace	31.250	100.000	36.000
576i50WL	960 x 576	Interlace	31.250	100.000	36.000
576iLH	720 x 576	Interlace	15.625	50.000	13.500
576iSH	720 x 576	Interlace	15.625	50.000	13.500
576iWH	960 x 576	Interlace	15.625	50.000	18.000
576p#	768 x 576	Progressive	31.250	50.000	29.500
576p100	720 x 576	Progressive	62.500	100.000	54.000
576p100L	720 x 576	Progressive	62.500	100.000	54.000
576p100S	720 x 576	Progressive	62.500	100.000	54.000
576p200	720 x 576	Progressive	125.000	200.000	108.000
576p200L	720 x 576	Progressive	125.000	200.000	108.000
576p200S	720 x 576	Progressive	125.000	200.000	108.000
576p2x50	1440 x 576	Progressive	31.250	50.000	54.000
576p2xLH	1440 x 576	Progressive	31.250	50.000	54.000
576p2xSH	1440 x 576	Progressive	31.250	50.000	54.000
576p4x50	2880 x 576	Progressive	31.250	50.000	108.000
576p4xLH	2880 x 576	Progressive	31.250	50.000	108.000
576p4xSH	2880 x 576	Progressive	31.250	50.000	108.000
576p50	720 x 576	Progressive	31.250	50.000	27.000
576p50LH	720 x 576	Progressive	31.250	50.000	27.000
576p50SH	720 x 576	Progressive	31.250	50.000	27.000
576pWH	960 x 576	Progressive	31.250	50.000	36.000
576pWH_	960 x 576	Progressive	31.250	50.000	37.125
576pWL	960 x 576	Progressive	31.250	50.000	36.000
576pWL_	960 x 576	Progressive	31.250	50.000	37.125
Betacam	768 x 480	Interlace	15.734	59.940	14.318
NTSC#KA	640 x 480	Interface	15.734	59.940	12.273
NTSC#	640 x 480	Interface	15.734	59.940	12.273
NTSC	710x 480	Interface	15.734	59.940	13.500
NTSC-LH	720 x 480	Interface	15.734	59.940	13.500
NTSC-SH	720 x 480	Interface	15.734	59.940	13.500
NTSC-J	710 x 480	Interface	15.734	59.940	13.500
NTSC-JLH	720 x 480	Interface	15.734	59.940	13.500
NTSC-JSH	720 x 480	Interface	15.734	59.940	13.500
NTSC44	720 x 480	Interface	15.734	59.940	13.500
PAL-60	710 x 480	Interface	15.734	59.940	13.500
PAL-M	710 x 480	Interface	15.734	59.940	13.500
PAL-N	702 x 574	Interface	15.625	50.000	13.500
PAL#KA	768 x 574	Interface	15.625	50.000	14.750
PAL#	768 x 574	Interface	15.625	50.000	14.750
PAL	702 x 574	Interface	15.625	50.000	13.500
PAL-NC	720 x 574	Interface	15.625	50.000	13.500

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
TEST25	640 x 480	Progressive	31.250	59.524	25.000

HDTV Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
720p23	1280 x 720	Progressive	17.982	23.976	74.176
720p24	1280 x 720	Progressive	18.000	24.000	74.250
720p25	1280 x 720	Progressive	18.750	25.000	74.250
720p29	1280 x 720	Progressive	22.478	29.971	74.177
720p30	1280 x 720	Progressive	22.500	30.000	74.250
720p50	1280 x 720	Progressive	37.500	50.000	74.250
720p59	1280 x 720	Progressive	44.955	59.940	74.175824
720p60	1280 x 720	Progressive	45.000	60.000	74.250
720p100	1280 x 720	Progressive	75.000	100.000	148.500
720p119	1280 x 720	Progressive	89.910	119.880	148.351648
720p120	1280 x 720	Progressive	90.000	120.000	148.500
1035i29	1920 x 1035	Interlace	33.716	59.940	74.175824
1035i30	1920 x 1035	Interlace	33.750	60.000	74.250
1080i25	1920 x 1080	Interlace	28.125	50.000	74.250
1080i29	1920 x 1080	Interlace	33.716	59.940	74.175824
1080i30	1920 x 1080	Interlace	33.750	60.000	74.250
1080i50	1920 x 1080	Interlace	56.250	100.000	148.500
1080i59	1920 x 1080	Interlace	67.433	119.880	148.351648
1080i60	1920 x 1080	Interlace	67.500	120.000	148.500
1080p23	1920 x 1080	Progressive	26.973	23.976	74.175824
1080p24	1920 x 1080	Progressive	28.125	24.000	74.250
1080p25	1920 x 1080	Progressive	28.125	25.000	74.250
1080p29	1920 x 1080	Progressive	33.716	29.970	74.175824
1080p30	1920 x 1080	Progressive	33.750	30.000	74.250
1080p50	1920 x 1080	Progressive	56.250	50.000	148.500
1080p59	1920 x 1080	Progressive	67.433	59.940	148.351648
1080p60	1920 x 1080	Progressive	67.500	60.000	148.500
1080s23	1920 x 1080	Interlace	26.973	47.952	74.175824
1080s24	1920 x 1080	Interlace	27.000	48.000	74.250
108Oi25_	1920 x 1080	Interlace	31.250	50.000	72.000
1152iLA	960 x 1152	Interlace	31.250	50.000	36.000
1152iLA_	960 x 1152	Interlace	31.250	50.000	37.125
1152iLH	1920 x 1152	Interlace	31.250	50.000	72.000
1152iLH_	1920 x 1152	Interlace	31.250	50.000	74.250
1152iSH	1280 x 1152	Interlace	31.250	50.000	48.000
1152iSH_	1280 x 1152	Interlace	31.250	50.000	49.500
TEST81	1024 x 768	Progressive	61.738	77.173	81.000

VESA DMT Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
DMT0659	640 x 480	Progressive	31.469	59.941	25.1752
DMT0660	640 x 480	Progressive	31.500	60.000	25.200
DMT0672	640 x 480	Progressive	37.861	72.809	31.500
DMT0675	640 x 480	Progressive	37.500	75.000	31.500
DMT0685	640 x 480	Progressive	43.269	85.008	36.000
DMT0685D	640 x 400	Progressive	37.861	85.080	31.500
DMT0685F	640 x 350	Progressive	37.861	85.080	31.500
DMT0785H	720 x 400	Progressive	37.927	85.039	35.500
DMT0856	800 x 600	Progressive	35.156	56.250	36.000
DMT0860	800 x 600	Progressive	37.879	60.317	40.000
DMT0872	800 x 600	Progressive	48.077	72.188	50.000
DMT0875	800 x 600	Progressive	46.875	75.000	49.500
DMT0885	800 x 600	Progressive	53.674	85.061	56.250
DMT1043	1024 x 768	Interlace	35.522	86.957	44.899808
DMT1060	1024 x 768	Progressive	48.363	60.004	65.000
DMT1070	1024 x 768	Progressive	56.476	70.069	75.000
DMT1075	1024 x 768	Progressive	60.023	75.029	78.750
DMT1085	1024 x 768	Progressive	68.677	84.997	94.500
DMT1170	1152 x 864	Progressive	63.851	70.013	94.500
DMT1175	1152 x 864	Progressive	67.500	75.000	108.000
DMT1185	1152 x 864	Progressive	77.094	84.999	121.500
DMT1243G	1280 x 1024	Interlace	46.433	86.871	78.750
DMT1260A	1280 x 960	Progressive	60.000	60.000	108.000
DMT1260G	1280 x 1024	Progressive	63.981	60.020	108.000
DMT1275A	1280 x 960	Progressive	75.000	75.000	126.000
DMT1275G	1280 x 1024	Progressive	79.976	75.025	135.000
DMT1285A	1280 x 960	Progressive	85.938	85.002	148.500
DMT1285G	1280 x 1024	Progressive	91.146	85.024	157.500
DMT1648	1600 x 1200	Interlace	62.500	96.080	135.000
DMT1660	1600 x 1200	Progressive	75.000	60.000	162.000
DMT1665	1600 x 1200	Progressive	81.250	65.000	175.500
DMT1670	1600 x 1200	Progressive	87.500	70.000	189.000
DMT1675	1600 x 1200	Progressive	93.750	75.000	202.500
DMT1680	1600 x 1200	Progressive	100.000	80.000	216.000
DMT1685	1600 x 1200	Progressive	106.250	85.000	229.500
DMT1760	1792 x 1344	Progressive	83.640	60.000	204.750
DMT1775	1792 x 1344	Progressive	106.270	74.997	261.000
DMT1860	1856 x 1392	Progressive	86.333	59.995	218.250
DMT1875	1856 x 1392	Progressive	112.500	75.000	288.000
DMT1960	1920 x 1440	Progressive	90.000	60.000	234.000
DMT1975	1920 x 1440	Progressive	112.500	75.000	297.000
DMT2060	2048 x 1536	Progressive	95.820	60.000	239.933008
DMT2075	2048 x 1536	Progressive	120.450	75.000	319.915008

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
SMT0660	640 x 480	Progressive	31.469	59.941	25.1752
SMT0660D	640 x 400	Progressive	31.469	59.941	25.1752
SMT0760H	720 x 400	Progressive	31.469	59.941	28.3221
SMT0760V	720 x 480	Progressive	31.469	59.941	28.3221

VESA CVT Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVR0660	640 x 480	Progressive	29.375	59.464	23.500
CVR0760	768 x 480	Progressive	29.634	59.866	27.500
CVR0860	800 x 600	Progressive	36.979	59.837	35.500
CVR0860H	848 x 480	Progressive	29.514	59.745	29.750
CVR0960D	960 x 600	Progressive	37.054	59.957	41.500
CVR1060	1024 x 768	Progressive	47.297	59.870	56.000
CVR1060H	1064 x 600	Progressive	36.969	59.820	45.250
CVR1160D	1152 x 720	Progressive	44.398	59.916	58.250
CVR1260	1280 x 960	Progressive	59.201	59.920	85.250
CVR1260D	1224 x 768	Progressive	47.327	59.907	65.500
CVR1260E	1280 x 768	Progressive	47.396	59.995	68.250
CVR1260G	1280 x 1024	Progressive	63.194	59.957	91.000
CVR1260H	1280 x 720	Progressive	44.444	59.979	64.000
CVR1360H	1360 x 768	Progressive	47.368	59.960	72.000
CVR1460	1400 x 1050	Progressive	64.744	59.948	101.000
CVR1560D	1536 x 960	Progressive	59.257	59.977	100.500
CVR1660	1600 x 1200	Progressive	74.006	59.924	130.250
CVR1660D	1680 x 1050	Progressive	64.674	59.883	119.000
CVR1760D	1728 x 1080	Progressive	66.605	59.950	125.750
CVR1760H	1704 x 960	Progressive	59.147	59.865	110.250
CVR1860H	1864 x 1050	Progressive	64.723	59.929	131.000
CVR1960	1920 x 1440	Progressive	88.822	59.974	184.750
CVR1960D	1920 x 1200	Progressive	74.038	59.950	154.000
CVR1960H	1920 x 1080	Progressive	66.587	59.934	138.500
CVR2060	2048 x 1536	Progressive	94.769	59.980	209.250
CVR2160H	2128 x 1200	Progressive	74.082	59.986	169.499984
CVR2360D	2304 x 1440	Progressive	88.778	59.945	218.750
CVR2460D	2456 x 1536	Progressive	94.706	59.940	247.750
CVR2560	2560 x 1920	Progressive	118.474	59.987	322.250016
CVR2560E	2560 x 1536	Progressive	94.761	59.975	257.750
CVR2560H	2560 x 1440	Progressive	88.787	59.951	241.500
CVR2760H	2728 x 1536	Progressive	94.789	59.993	273.750016
CVR3060D	3072 x 1920	Progressive	118.425	59.962	382.749984
CVR3260	3200 x 2400	Progressive	148.140	60.000	497.749984
CVR3460H	3408 x 1920	Progressive	118.484	59.992	422.749984

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVR3860	3840 x 2880	Progressive	177.688	59.989	710.750016
CVR3860D	3840 x 2400	Progressive	148.125	59.994	592.499968
CVR4260H	4264 x 2400	Progressive	148.113	59.989	655.249984
CVR4660D	4608 x 2880	Progressive	177.695	59.992	847.249984
CVR5160H	5120 x 2880	Progressive	177.699	59.993	938.249984
CVT0650	640 x 480	Progressive	24.688	49.673	19.750
CVT0660	640 x 480	Progressive	29.688	59.375	23.750
CVT0675	640 x 480	Progressive	37.684	74.769	30.750
CVT0685	640 x 480	Progressive	42.892	84.600	35.000
CVT0750D	640 x 680	Progressive	24.740	49.778	23.749998
CVT0760D	768 x 480	Progressive	29.948	59.896	28.750002
CVT0775D	768 x 480	Progressive	37.654	74.710	36.750
CVT0785D	768 x 480	Progressive	42.843	84.502	42.500
CVT0850	800 x 600	Progressive	30.998	49.916	30.750
CVT0850H	848 x 480	Progressive	24.621	49.540	26.000
CVT0860	800 x 600	Progressive	37.654	59.861	38.250
CVT0860H	848 x 480	Progressive	29.826	59.659	31.500
CVT0875	800 x 600	Progressive	47.115	74.905	49.000004
CVT0875H	848 x 480	Progressive	37.684	74.769	41.000
CVT0885	800 x 600	Progressive	53.741	84.898	56.750
CVT0885H	848 x 480	Progressive	42.969	84.751	46.750
CVT0950D	960 x 600	Progressive	30.833	49.651	37.000
CVT0960D	960 x 600	Progressive	37.212	59.635	45.250
CVT0975D	960 x 600	Progressive	47.075	74.841	58.750
CVT0985D	960 x 600	Progressive	53.600	84.676	67.750
CVT1050	1024 x 768	Progressive	39.634	49.980	51.999996
CVT1050H	1064 x 600	Progressive	30.871	49.712	40.750
CVT1060	1024 x 768	Progressive	47.816	59.920	63.500
CVT1060H	1064 x 600	Progressive	37.352	59.859	50.500
CVT1075	1024 x 768	Progressive	60.294	74.900	82.000
CVT1075H	1064 x 600	Progressive	47.146	79.954	65.250
CVT1085	1024 x 768	Progressive	68.677	84.895	94.500
CVT1085H	1064 x 600	Progressive	53.750	84.913	75.250
CVT1150D	1152 x 720	Progressive	37.025	49.764	54.500
CVT1160D	1152 x 720	Progressive	44.859	59.972	66.750
CVT1175D	1152 x 720	Progressive	56.415	74.721	85.750
CVT1185D	1152 x 720	Progressive	64.453	84.918	99.000
CVT1250	1280 x 960	Progressive	49.405	49.853	83.000
CVT1250D	1224 x 768	Progressive	39.499	49.809	62.250
CVT1250E	1280 x 768	Progressive	39.593	49.929	65.249996
CVT1250G	1280 x 1024	Progressive	52.679	49.838	88.500
CVT1250H	1280 x 720	Progressive	37.071	49.827	60.500
CVT1260	1280 x 960	Progressive	59.699	59.939	101.250
CVT1260D	1224 x 768	Progressive	47.739	59.823	76.000
CVT1260E	1280 x 768	Progressive	47.776	59.870	79.500
CVT1260G	1280 x 1024	Progressive	63.668	59.895	109.000
CVT1260H	1280 x 720	Progressive	44.772	59.855	74.500

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT1275	1280 x 960	Progressive	75.231	74.857	130.000008
CVT1275D	1224 x 768	Progressive	60.191	74.771	97.750
CVT1275E	1280 x 768	Progressive	60.289	74.893	102.250
CVT1275G	1280 x 1024	Progressive	80.295	74.902	138.750
CVT1275H	1280 x 720	Progressive	56.456	74.777	95.750
CVT1285	1280 x 960	Progressive	85.793	84.859	148.250
CVT1285D	1224 x 768	Progressive	68.598	84.793	112.500
CVT1285E	1280 x 768	Progressive	68.633	84.837	117.500
CVT1285G	1280 x 1024	Progressive	91.456	84.839	159.500
CVT1285H	1280 x 720	Progressive	64.398	84.846	110.250
CVT1350H	1360 x 768	Progressive	39.564	49.892	69.000
CVT1360H	1360 x 768	Progressive	47.720	59.799	84.750
CVT1375H	1360 x 768	Progressive	60.288	74.891	109.000
CVT1385H	1360 x 768	Progressive	68.668	84.880	125.250008
CVT1450	1400 x 1050	Progressive	54.113	49.965	100.000
CVT1460	1400 x 1050	Progressive	65.317	59.978	121.750
CVT1475	1400 x 1050	Progressive	82.279	74.867	156.000
CVT1485	1400 x 1050	Progressive	93.881	84.960	179.500
CVT1550D	1536 x 960	Progressive	49.479	49.929	99.750
CVT1560D	1536 x 960	Progressive	59.670	59.910	121.250
CVT1575D	1536 x 960	Progressive	75.218	74.844	155.250
CVT1585D	1536 x 960	Progressive	85.817	84.884	178.500
CVT1650	1600 x 1200	Progressive	61.795	49.915	131.500
CVT1650D	1680 x 1050	Progressive	54.121	59.974	119.500008
CVT1660	1600 x 1200	Progressive	74.537	59.869	161.000
CVT1660D	1680 x 1050	Progressive	65.290	59.954	146.250
CVT1675	1600 x 1200	Progressive	94.095	74.976	204.750
CVT1675D	1680 x 1050	Progressive	82.306	74.892	187.000
CVT1685	1600 x 1200	Progressive	107.208	84.951	235.000
CVT1685D	1680 x 1050	Progressive	93.859	84.941	214.750
CVT1750D	1728 x 1080	Progressive	55.616	49.925	127.250
CVT1750H	1704 x 960	Progressive	49.507	49.957	110.500
CVT1760D	1728 x 1280	Progressive	67.134	59.941	155.749984
CVT1760H	1704 x 960	Progressive	59.739	59.979	135.250
CVT1775D	1728 x 1080	Progressive	84.653	74.914	197.749984
CVT1775H	1704 x 960	Progressive	75.240	74.865	172.750
CVT1785D	1728 x 1080	Progressive	96.514	84.884	226.999984
CVT1785H	1704 x 960	Progressive	85.856	84.922	198.500
CVT1850H	1864 x 1050	Progressive	54.051	49.909	132.750008
CVT1860H	1864 x 1050	Progressive	65.314	59.976	162.500
CVT1875H	1864 x 1050	Progressive	82.341	74.924	207.500016
CVT1885H	1864 x 1050	Progressive	93.849	84.931	238.000
CVT1950	1920 x 1440	Progressive	74.171	49.980	192.250
CVT1950D	1920 x 1200	Progressive	61.816	49.932	158.250
CVT1950H	1920 x 1080	Progressive	55.621	49.929	141.500
CVT1960	1920 x 1440	Progressive	89.532	59.968	233.500
CVT1960D	1920 x 1200	Progressive	74.556	59.885	193.250

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT1960H	1920 x 1080	Progressive	67.158	59.963	173.000
CVT1975	1920 x 1440	Progressive	112.879	74.953	298.000
CVT1975D	1920 x 1200	Progressive	94.038	74.930	245.250
CVT1975H	1920 x 1080	Progressive	84.643	74.906	220.750
CVT1985	1920 x 1440	Progressive	128.599	84.940	339.499968
CVT1985D	1920 x 1200	Progressive	107.184	84.932	281.249984
CVT1985H	1920 x 1080	Progressive	96.513	84.884	253.249984
CVT2050	2048 x 1536	Progressive	79.118	49.980	219.000
CVT2060	2048 x 1536	Progressive	95.446	59.654	267.250
CVT2075	2048 x 1536	Progressive	120.384	74.959	339.000
CVT2085	2048 x 1536	Progressive	137.182	84.943	388.500
CVT2150H	2128 x 1200	Progressive	61.794	49.914	175.000
CVT2160H	2128 x 1200	Progressive	74.633	59.516	213.750016
CVT2175H	2128 x 1200	Progressive	94.095	74.976	272.500
CVT2185H	2128 x 1200	Progressive	107.229	84.967	312.250016
CVT2350D	2304 x 1440	Progressive	74.179	49.986	230.249984
CVT2360D	2304 x 1440	Progressive	89.525	59.963	280.750016
CVT2375D	2304 x 1440	Progressive	112.847	74.932	357.500
CVT2385D	2304 x 1440	Progressive	128.612	84.948	409.500
CVT2450D	2456 x 1536	Progressive	79.066	49.947	262.500
CVT2460D	2456 x 1536	Progressive	95.465	59.966	320.000
CVT2475D	2456 x 1536	Progressive	120.346	74.935	407.249984
CVT2485D	2456 x 1536	Progressive	137.206	84.957	466.499968
CVT2550	2560 x 1920	Progressive	98.816	49.957	346.250016
CVT2550H	2560 x 1440	Progressive	74.146	49.964	256.250
CVT2560	2560 x 1920	Progressive	119.247	59.953	419.749984
CVT2560H	2560 x 1440	Progressive	89.521	59.961	312.250016
CVT2575	2560 x 1920	Progressive	150.408	74.979	534.249984
CVT2575H	2560 x 1440	Progressive	112.855	74.937	397.250016
CVT2585	2560 x 1920	Progressive	171.453	84.962	609.000
CVT2585H	2560 x 1440	Progressive	128.606	84.944	454.750016
CVT2750H	2728 x 1536	Progressive	79.108	49.973	291.750016
CVT2760H	2728 x 1536	Progressive	95.430	59.944	335.000
CVT2775H	2728 x 1536	Progressive	120.336	74.929	451.500
CVT2785H	2728 x 1536	Progressive	137.208	84.959	516.999968
CVT3050D	3072 x 1920	Progressive	98.819	49.959	414.250016
CVT3060D	3072 x 1920	Progressive	119.259	59.959	503.749984
CVT3075D	3072 x 1920	Progressive	150.376	74.963	640.000
CVT3085D	3072 x 1920	Progressive	171.465	84.968	732.500032
CVT3250	3200 x 2400	Progressive	123.528/	49.991	545.499968
CVT3260	3200 x 2400	Progressive	149.086	59.970	660.749952
CVT3275	3200 x 2400	Progressive	187.948	74.969	839.000
CVT3285	3200 x 2400	Progressive	214.230	84.978	959.749952
CVT3450H	3408 x 1920	Progressive	98.851	49.975	460.250016
CVT3460H	3408 x 1920	Progressive	119.294	59.977	559.250048
CVT3475H	3408 x 1920	Progressive	150.424	74.987	710.000
CVT3485H	3408 x 1920	Progressive	171.453	84.962	812.000

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CVT3850	3840 x 2880	Progressive	148.179	49.976	789.499968
CVT3850D	3840 x 2400	Progressive	123.537	49.995	794.250048
CVT3860	3840 x 2880	Progressive	178.845	59.975	955.750016
CVT3860D	3840 x 2400	Progressive	149.071	59.964	794.250048
CVT3875	3840 x 2880	Progressive	225.493	74.964	1212.249984
CVT3875D	3840 x 2400	Progressive	187.966	74.977	1007.500032
CVT3885	3840 x 2880	Progressive	257.048	84.975	1386.000
CVT3885D	3840 x 2400	Progressive	214.239	84.982	1151.750016
CVT4250H	4264 x 2400	Progressive	123.512	49.985	726.249984
CVT4260H	4264 x 2400	Progressive	149.061	59.960	881.250048
CVT4275H	4264 x 2400	Progressive	149.061	59.960	1117.250048
CVT4285H	4264 x 2400	Progressive	214.262	84.991	1277.000064
CVT4650D	4608 x 2880	Progressive	148.222	49.991	946.250048
CVT4660D	4608 x 2880	Progressive	178.850	59.976	1147.500032
CVT4675D	4608 x 2880	Progressive	225.496	74.966	1454.000
CVT4685D	4608 x 2880	Progressive	257.039	84.972	1661.500032
CVT5150H	5120 x 2880	Progressive	148.191	49.980	1052.749952
CVT5160H	5120 x 2880	Progressive	178.882	59.987	1276.499968
CVT5175H	5120 x 2880	Progressive	225.516	74.972	1616.499968
CVT5185H	5120 x 2880	Progressive	257.064	84.980	1846.750080

Game Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
240p2x_1	720 x 240	Progressive	15.734	60.055	13.500
240p2x_2	720 x 240	Progressive	15.750	60.115	13.5135
240p2x_3	720 x 240	Progressive	15.734	59.826	13.500
240p2x_4	720 x 240	Progressive	15.750	59.886	13.5135
240p2xL1	720 x 240	Progressive	15.734	60.055	13.500
240p2xL2	720 x 240	Progressive	15.750	60.155	13.5135
240p2xL3	720 x 240	Progressive	15.731	59.826	13.500
240p2xL4	720 x 240	Progressive	15.750	59.886	13.5135
240p2xS1	720 x 240	Progressive	15.734	60.055	13.500
240p2xS2	720 x 240	Progressive	15.750	60.155	13.5135
240p2xS3	720 x 240	Progressive	15.734	59.826	13.500
240p2xS4	720 x 240	Progressive	15.750	59.886	13.5135
240p4x_1	2880 x 240	Progressive	15.734	60.055	54.000
240p4x_2	2880 x 240	Progressive	15.750	60.115	54.054
240p4x_3	2880 x 240	Progressive	15.734	59.826	54.000
240p4x_4	2880 x 240	Progressive	15.750	59.886	54.054
240p4xL1	2880 x 240	Progressive	15.734	60.055	54.000
240p4xL2	2880 x 240	Progressive	15.750	60.115	54.054
240p4xL3	2880 x 240	Progressive	15.734	59.826	54.000

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
240p4xL4	2880 x 240	Progressive	15.750	59.886	54.054
240p4xS1	2880 x 240	Progressive	15.734	60.055	54.000
240p4xS2	2880 x 240	Progressive	15.750	60.115	54.054
240p4xS3	2880 x 240	Progressive	15.734	59.826	54.000
240p4xS4	2880 x 240	Progressive	15.750	59.886	54.054
288p2x_1	720 x 288	Progressive	15.625	50.080	13.500
288p2x_2	720 x 288	Progressive	15.625	49.920	13.500
288p2x_3	720 x 288	Progressive	15.625	49.761	13.500
288p2xL1	720 x 288	Progressive	15.625	50.080	13.500
288p2xL2	720 x 288	Progressive	15.625	49.920	13.500
288p2xL3	720 x 288	Progressive	15.625	49.761	13.500
288p2xS1	720 x 288	Progressive	15.625	50.080	13.500
288p2xS2	720 x 288	Progressive	15.625	49.920	13.500
288p2xS3	720 x 288	Progressive	15.625	49.761	13.500
288p4x_1	2880 x 288	Progressive	15.625	50.080	54.000
288p4x_2	2880 x 288	Progressive	15.625	49.920	54.000
288p4x_3	2880 x 288	Progressive	15.625	49.761	54.000
288p4xL1	2880 x 288	Progressive	15.625	50.080	54.000
288p4xL2	2880 x 288	Progressive	15.625	49.920	54.000
288p4xL3	2880 x 288	Progressive	15.625	49.761	54.000
288p4xS1	2880 x 288	Progressive	15.625	50.080	54.000
288p4xS2	2880 x 288	Progressive	15.625	49.920	54.000
288p4xS3	2880 x 288	Progressive	15.625	49.761	54.000

Medical Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
DatRay5	2048 x 2560	Progressive	186.010	70.996	499.99488
DatRay6	2456 x 2560	Progressive	186.010	70.996	607.880704
DatRay7	2864 x 2560	Progressive	186.010	70.996	700.885696
DatRay8	3280 x 2560	Progressive	186.010	70.996	800.587008
DOM1266O	1200 x 1600	Progressive	109.752	66.316	186.140
DOM1570O	1536 x 2048	Progressive	147.183	70.423	357.950016
DOM1762O	1728 x 2304	Progressive	146.437	61.866	360.820
DOM1763O	1728 x 2304	Progressive	148.364	62.893	360.820
DOM1769O	1728 x 2304	Progressive	163.415	69.039	360.820
DOM1770X	1712 x 2100	Progressive	149.346	69.528	360.820
DOM2060_	2048 x 2048	Progressive	126.847	60.003	357.200
DOM2060Q	2048 x 2044	Progressive	127.769	60.382	360.820
DOM2065X	2048 x 2560	Progressive	169.891	65.092	500.159968
DOM2071X	2048 x 2560	Progressive	186.079	71.022	500.180032
DOM2076A	2048 x 1536	Progressive	118.691	75.599	360.820
DOM2076X	2048 x 2560	Progressive	199.449	76.009	542.500032

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
DOM2365	2304 x 1728	Progressive	116.244	64.904	360.819968
DOM2569G	2560 x 2048	Progressive	144.722	69.014	500.160
DOM2571G	2560 x 2048	Progressive	150.289	71.703	500.160032
MATROX	1280 x 1024	Progressive	77.000	72.368	133.056
Md2	1200 x 1600	Progressive	124.430	75.504	214.019984
Md2SBX	1600 x 1200	Progressive	91.118	73.011	200.460
Md4SBX	1728 x 2304	Progressive	163.415	69.039	360.820
Md5SBV	2048 x 2560	Progressive	199.449	76.009	542.500032
Md5SBX	2048 x 2560	Progressive	186.012	70.997	500.000

Military Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
HOBO	752 x 482	Interlace	15.734	59.940	14.444056
LMC_1	640 x 480	Interlace	15.734	59.940	12.272727
LMC_2	640 x 480	Interlace	15.734	59.940	12.272727
LMC_3	640 x 480	Interlace	15.734	59.940	12.272727
LMC_4	640 x 480	Interlace	15.734	59.940	12.272727
MAVERIK	740 x 476	Interlace	15.734	59.940	14.318182
STANAGA	1244 x 842	Interlace	26.250	60.000	40.005
STANAGB	1560 x 574	Interlace	15.625	50.000	30.000
STANAGC	1262 x 484	Interlace	15.750	60.000	24.003
XGA2	720 x 400	Progressive	39.444	87.849	35.4996

TTL Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
AT&T_EVC	640 x 350	Progressive	25.862	59.866	24.000
AT&T_IVC	640 x 400	Progressive	25.862	59.866	24.000
AT&T_SVC	640 x 400	Progressive	25.862	59.866	24.000
CGA_m14	640 x 200	Progressive	15.700	59.924	14.3184
EGA_m2	640 x 350	Progressive	21.851	59.702	16.257144
HGC_text	720 x 350	Progressive	18.141	49.030	16.000362
HGCgraph	720 x 348	Progressive	18.519	50.051	16.000416
IBM_3164	640 x 400	Progressive	27.648	64.749	22.1184
IBM_3179	640 x 400	Progressive	25.560	60.000	20.488
MDA_m7	720 x 350	Progressive	18.432	49.816	16.257144

Misc. Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
CEA0659	640 x 480	Progressive	31.469	59.941	25.1752
EIA0629	640 x 480	Interlace	15.734	59.940	12.272727
EIA0629K	512 x 384	Interlace	15.734	59.940	12.272727
EIA0729	752 x 484	Interlace	15.734	59.940	14.318182
EIA0729X	752 x 484	Interlace	15.734	59.940	14.318182
ICS1160	1184 x 884	Progressive	55.200	60.000	83.0208
ICS1176	1184 x 884	Progressive	71.712	76.047	105.560504
ICS1660	1664 x 1248	Progressive	77.940	60.000	164.609296
ICS1676	1664 x 1248	Progressive	100.726	76.020	211.121888
ITU0725	768 x 574	Interlace	15.625	50.000	14.750
ITU0725K	640 x 480	Interlace	15.625	50.000	14.750
ITU0925X	920 x 574	Interlace	15.625	50.000	17.750
LD6Du60	1024 x 768	Progressive	48.364	60.005	65.001216
LD8Du75	1024 x 768	Progressive	60.023	75.029	78.750
NEC0656D	640 x 400	Progressive	24.823	56.416	21.050
NEC1140B	1120 x 750	Interlace	32.857	80.042	47.840004

Test Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
RAMP160	4096 x 480	Progressive	31.469	59.941	161.121280
TEST81	1024 x 768	Progressive	61.738	77.172	81.000
TEST150	2048 x 1024	Progressive	50.403	46.887	150.000
TEST165	1600 x 1200	Progressive	76.389	61.111	165.000
TEST250	2048 x 2048	Interlace	79.719	71.722	250.000016
TEST330	2048 x 1536	Progressive	94.178	59.269	330.000
tst300i	2048 x 1536	Interlace	94.178	118.538	299.86304
tst300p	2048 x 1536	Progressive	94.178	59.269	299.86304
tst360i	2816 x 1024	Interlace	97.000	91.037	360.064
tst360p	2816 x 1024	Progressive	97.000	91.080	360.064
tst400i	2816 x 1024	Interlace	97.000	91.037	399.640
tst400p	2816 x 1024	Progressive	97.000	91.080	399.640

Manufacturer Associated Formats

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
APP0560	512 x 384	Progressive	24.480	60.147	15.667
APP0560B	560 x 384	Progressive	24.480	60.147	17.234
APP0629	640 x 480	Interlace	15.734	59.939	12.273
APP0629K	512 x 384	Interlace	15.734	59.939	12.273
APP0667_	640 x 480	Progressive	34.975	66.619	31.338
APP0667	640 x 480	Progressive	35.000	66.667	30.240
APP0675O	640 x 870	Progressive	68.850	75.000	57.283
APP0875	832 x 624	Progressive	49.107	75.087	55.000
APP1059	1024 x 768	Progressive	48.193	59.278	64.000
APP1075	1024 x 768	Progressive	60.241	74.927	80.000
APP1175	1152 x 870	Progressive	68.681	75.061	100.000
HWP1060	1024 x 768	Progressive	47.700	60.000	64.109
HWP1070	1024 x 768	Progressive	56.476	70.069	75.000
HWP1075	1024 x 768	Progressive	62.937	74.925	84.587
HWP1075_	1024 x 768	Progressive	60.241	75.020	80.000
HWP1260G	1280 x 1024	Progressive	63.338	59.979	108.181
HWP1272G	1280 x 1024	Progressive	78.125	72.005	135.000
HWP1275G	1280 x 1024	Progressive	79.976	75.024	134.999
IBM0660D	640 x 400	Progressive	30.296	59.638	24.964
IBM0660	640 x 480	Progressive	30.296	59.638	25.024
IBM0675	640 x 480	Progressive	39.375	75.000	31.500
IBM0770U	720 x 350	Progressive	31.469	70.087	28.322
IBM0770H	720 x 400	Progressive	31.469	70.087	28.322
IBM1043	1053 x 754	Interlace	35.414	86.906	45.542
IBM1043_	1056 x 768	Interlace	35.602	86.940	45.571
IBM1070	1024 x 768	Progressive	56.287	70.009	77.001
IBM1060Q	1024 x 1024	Progressive	63.360	60.000	89.211
IBM1076	1024 x 768	Progressive	61.080	75.782	86.001
IBM1260G	1280 x 1024	Progressive	63.363	60.003	111.519
IBM1267G	1280 x 1024	Progressive	70.755	67.003	120.000
IBM1267_	1280 x 1024	Progressive	70.755	67.003	120.000
IBM1352	1360 x 1024	Interlace	56.469	102.952	102.999
SNY1072	1024 x 768	Progressive	57.870	71.799	75.000
SNY1274G	1280 x 1024	Progressive	78.855	74.112	135.000
SNY1276G	1280 x 1024	Progressive	81.207	76.179	140.001
SUN1061Q	1024 x 1024	Progressive	65.267	61.399	92.940
SUN1077	1024 x 768	Progressive	62.040	77.068	84.374
SUN1166X	1152 x 900	Progressive	61.796	65.951	92.941
SUN1166_	1152 x 900	Progressive	61.846	66.004	94.501
SUN1176X	1152 x 900	Progressive	71.713	76.048	105.562
SUN1176_	1152 x 900	Progressive	71.809	76.150	108.001
SUN1267G	1280 x 1024	Progressive	71.722	66.718	117.050
SUN1267_	1280 x 1024	Progressive	71.678	66.677	118.125

Format	Active (HxV)	Scan	Horizontal Rate (kHz)	Vertical Rate (Hz)	Pixel Rate (MHz)
SUN1276G	1280 x 1024	Progressive	81.130	76.107	135.000
SUN1667G	1600 x 1280	Progressive	89.286	66.931	200.001
VSC1260G	1280 x 1024	Progressive	63.896	59.996	107.856
VSC1460	1440 x 1080	Progressive	67.080	60.000	129.867
VSC1660V	1680 x 1080	Progressive	67.080	60.000	151.332
VSC1875V	1868 x 1200	Progressive	93.975	75.000	240.576
VSC1960H	1920 x 1080	Progressive	67.080	60.000	172.798
VSC1975H	1920 x 1080	Progressive	84.060	75.000	220.637
VSC1975D	1920 x 1200	Progressive	93.975	75.000	246.590

Index

A

Active Format Description 384
alternate image versions 50
analog component video SDTV (CE) CRTs 61
analog composite video 58
analog computer (IT) CRTs 52
analyze an external HDMI/DVI signal 296
analyze InfoFrame data 305
analyze pseudo-random noise 290
analyze signal timing 279
Analyzer connections 273
audio clips 376, 495
audio content 310
audio data 310
Audio device 391
audio image 376, 495
AuxTest composite test image 74

B

Backing up the current files on the file server 155
Basic mode 16
bitmap images 243
boot a generator that is in a stalled state 120, 121
boot a stalled generator from a different host 123
boot device 15
BootDev 120
Booting a generator from the file server 151
Booting up the generator 15
BootNow 16, 121, 122
Browse mode 16
Browsing other media 17
Bus commands 171
bypass hot plug formats 44, 340, 483

C

cached images 72
calibrate all frequencies 88
calibration factors 88
capture a reference frame 298
capture and read pixel data 301
CEC addressing 395
CEC Controller 405
CEC devices 391
CEC features 392
CEC switch 391
CEC test 74
centering 54, 56, 60, 63, 66, 68, 70
clone a generator using the Generator FTP Browser 126
Cloning a generator using the PC card 125
Cloning generators using the Generator FTP Browser 158
CMD (Command) Terminal 23
color component values 245
command line interface 31, 32
Completion handshake 168
Compliance Controller 608
compliance test 501, 520, 679, 749
Component high definition television formats 47
Component SDTV formats 46
Component television format names 176
component values 245
component video 61, 64, 69
Composite television formats 46
composite test image 74
composite video SDTV 58
computer (IT) CRTs 52
computer (IT) FPDs 55
Computer display format names 177
Computer display formats 47
Configuring a file server 139
Configuring format parameters 181
Configuring special sync for FS, LS, or CS 765
Configuring the generator's serial port 32
Configuring the probe feature 761
Connecting a generator directly to a PC 116
Connecting generators to the network 144
Content list 237
Controlling a generator remotely 154
Controlling the probe 764
Copying files between generators 28
Copying files between the generator's flash memory and PC card 27
Copying files from a generator to a PC 26
Copying files from a PC to a generator 24
Copying files to the PC file server 156
Copying the new files to each generator 157
create a format catalog with both custom formats and default formats 231
create a new format 222
Creating a new format using the Format Editor 222
Creating a test sequence 262
Creating an image catalog 247
Creating custom formats using the command line interface 227

Creating format catalogs 230
custom formats 227
custom formats appear in the Source list 229
custom images 240

D

Deck Control 392
deep color 345
delete a user profile 38
Deleting a test sequence 269
Deleting an image catalog 251
Deleting format catalogs 232
Delta time 565, 575, 578
Device OSD Name Transfer 392
DHCP 145, 147
digital component video HDTV (CE) FPDs 64, 69
digital computer (IT) FPDs 55
display size 42
DisplayPort EDID 645
Dolby audio 376, 495
DTS audio 376, 495
DVD player 391
DVI cables and distribution systems 286

E

EDID compliance 593, 615, 643, 659
EDID Editor Tool 620
EDID Formats 614
EDID saved from the ACA 558
EDID test 74
EDID verification 645
Editing a test sequence 266
Editing images 242
Editor Tool 620
Emulate mode 44, 341, 483, 504
Emulating an HDMI CEC device 395
est the quality of video sources 290
Establishing a Telnet session 34
Establishing a terminal session 31
ETHERNET connector 8
extended-gamut 356
external audio source 377, 497

F

file server 139
file server IP address 148
File server specifications 139
file system 14, 138
focus 54, 59, 62
Format Editor 189
format library 46
format naming conventions 46
format parameters 181
Front panel interface 10
FTP Browser 24
FTP server 139
function keys 20

G

Generator file system 14, 138
Generator FTP Browser 24
Generator media 14
Generator operational modes 15
generator's function keys 20
generator's path 18
geometry 53, 59, 62
GPIB connector 8
GPIB port address 163

H

HDCP 667, 672
HDCP compliance test 679, 749
HDCP test 74
HDMI 1.3 deep color displays 345
HDMI compliance 593, 615, 643
HDMI connector pinouts 274
HDMI displays 343, 485
HDMI InfoFrame contents 305
HDMI or DVI cables and distribution 286
HDMI source compliance 615
HDMI testing 338, 481
HDMI video pixel repetition 363
high voltage regulation 54, 60, 63
HostName 123
hot plug bypass 44, 341, 483
HP Bypass 44, 341, 483

I

Image Cache 72
image component values 245
Image Control Tool 345
image options 237
image rendering 72
Image Shift Utility 69
image versions 50, 237
implement pseudo-random noise 326

increment the color component values 245
indicators 10
InetAddr 124
InfoFrame contents 380
InfoFrame data 305
interface 41
interfaces 4
IP address 145, 148

J

Java Runtime Environment 21, 154, 317, 450, 555

L

Library folder 14
Lipsync
  testing display (sink) device 653
  testing source device 659
luminance 54, 56, 59, 62, 65, 67, 70

M

Maintaining the generator's file system 154
MCCS application 536
measure and analyze signal timing 279
menu items 11
Menu selection keys 11
Modifying EDID 587
modifying existing formats 189
modifying format parameters 185, 186
modifying image options 237
monitor audio content 310
monitor auxiliary channels 554
Monitor Control Command Set (MCCS) 536
monitor the CEC bus 320, 560
monitor the EDID 566
monitor the HDCP 563, 574
Monitoring HDMI analyzer signal input 275
multiple commands 167
Munsell Color System 356

N

network interface 34

O

One Touch Play 392
One Touch Record 392
operate a generator remotely 154
Operating special sync for probe pulse 761
Operating the generator remotely through the command line interface 154
operational modes 15
operational status 10
Options key 12
OSD Display 392

P

path 18
path parameter 19
persistence 56, 66, 68, 70
photometry 53, 56, 59, 62, 65, 67, 70
physical connections 40
pixel anomalies 56, 66, 68, 70
pixel error report 299
Pixel Error test 295
pixel repetition 363
Probe coordinate numbering 761
probe feature 761
probe pulse 761
profiles 37
Programming the generator's function keys 20
pseudo-random noise report 293
Pseudo-Random Noise test 290

R

read pixel data 301
Reading 315
Reading EDID 43, 340, 482, 504
Reading pixel 315
ReadRGB test 301
Reboot the generators 157
Recording device 391
reference frame 295
regulation 54, 60, 63
re-initialize the generator using the command line 129
Remote Control Pass Through 392
Removing current files from the generators 157
render images quickly 72
report for the EDID 307, 382, 585, 605, 661
resolution 54, 56, 59, 62, 66, 68, 70
Routing Control 392
Running a test sequence 259
Running an HDCP self-test 676
Running HDCP test in step mode 501, 672, 679, 749
Running the ACA 317, 555, 557, 558

S

save an EDID 558
select the device type 41
select the interface 41
Selecting a boot device 15
Selecting a user profile 37
Selecting images 47
Selecting menu items 11
selection keys 11
self-calibrate the generator 87
Sending multiple commands and queries per line 167
sequence XML file 266
Serial (RS-232) interface 31
SERIAL connector 8
Set top box 391
Setting image component values 245
Setting the file server IP address in the generator 147
Setting the generator's IP address 145
Setting the generator's path 18
Setting the GPIB port address 163
setting up new users 37
Setting up the generator for HDMI testing 338, 481
Settings key 13
Sharing objects on a file server 152
Sink key 43, 44, 340, 341, 482, 483, 503, 504, 613
soft key 11
Source list 43, 340, 482, 503
Source list of formats 180
special sync 761
Status byte 169
Status indicators 10
Status queries and control 169
System folder 14
System Standby 392

T

television format names 175
Telnet session 34
test HDMI or DVI cables and distribution systems 286
test luminance 54, 56
test sequence list 257
test sequence XML file 266
Testing analog component video SDTV (CE) CRTs 61
Testing analog composite video SDTV (CE) CRTs 58
Testing analog computer (IT) CRTs 52
Testing digital component video HDTV (CE) FPDs 64
Testing digital computer (IT) FPDs 55
Testing DVI displays with HDCP 667, 672
Testing EDID for HDMI compliance in HDMI 593, 620, 640, 643
testing focus 54, 59, 62
testing for centering 54, 56, 60, 63, 66, 68, 70
testing for high voltage regulation 54, 60, 63
testing for persistence 56, 66, 68, 70
testing for pixel anomalies 56, 66, 68, 70
testing geometry 53, 59, 62
Testing HDMI displays 343, 485
Testing HDMI displays with HDCP 669
Testing HDMI video pixel repetition 355
testing luminance 59, 62, 65, 67, 70
testing photometry 53, 56, 59, 62, 65, 67, 70
testing resolution 54, 56, 59, 62, 66, 68, 70
Testing with Active Format Description 384
timing information 279
Tuner Control 392
TV 391

U

upgrade a generator 110
Upgrade options and procedures 155
upgrade procedures 155
Upgrading generators over a network 155
user profiles 37

V

video formats 43, 339, 482
Video interfaces 2
video signal quality 290
view analog calibration factors 88
view current HDMI InfoFrame contents 305
View Data 301, 303
view the pixel error report 299
Viewing and modifying format parameters 181, 185, 186
Viewing EDID from a display 593, 643
Viewing image versions 237
Viewing InfoFrame contents 380
Viewing the Content list of images 237
Viewing the test sequence list 257
Virtual Front Panel 21, 154
voltage regulation 54, 60, 63

W

Web interface 21
Web server 21

X

xvYCC 356