

Optical, bactericidal and water repellent properties of electrospun nano-composite membranes of cellulose acetate and ZnO

S. Anitha^a, B. Brabu^b, D. John Thiruvadigal^a, C. Gopalakrishnan^b, T.S. Natarajan^{c,*}

^a Centre for Materials Sciences and Nanodevices, Department of Physics, SRM University, Chennai 603203, India

^b Nanotechnology Research Center, SRM University, Chennai 603203, India

^c Department of Physics, Indian Institute of Technology-Madras, Chennai 600036, India

ARTICLE INFO

Article history:

Available online 1 July 2013

Keywords:

Nanocomposites

Nanoparticles

Fibers

Defects

Hydrophobic

Bactericidal

ABSTRACT

In this report, ZnO nanoparticles embedded cellulose acetate (CA) fibrous membrane with multifunctional properties have been prepared through electrospinning method. The morphology of the electrospun composite membrane was analyzed by scanning electron microscope (SEM). It was found that the polymer concentration in the solution has a significant effect on the morphology of the fibers. The optical property of the sample was tested using photo luminescence (PL) spectra. There is no significant change in the emission features of cellulose acetate with the addition of ZnO. The anti-bacterial property of the sample was studied using disk diffusion method. The wettability of the pure and composite fibrous membrane was also studied by measuring the contact angle of water on the membrane. It was observed that the embedded ZnO in the CA was responsible for the hydrophobic nature of the surface.

© 2013 Elsevier Ltd. All rights reserved.

1. Introduction

Over the past few years, there has been a tremendous growth of research activities to explore electrospinning to develop fibers in the micro and nanometer range using various types of materials or polymers. The nanofibers produced by electrospinning have several remarkable advantages like high aspect ratio, flexibility and high tensile strength. It has attracted the attention of researchers as it is cost effective and simple technique (Greiner & Wendorff, 2007; Li & Xia, 2004; Sundaray et al., 2004). Different types of nanomaterials were successfully incorporated into various polymer matrices owing to their unusual combination of optical, mechanical and bactericidal properties (Joshi et al., 2010; Li, Mahendra, et al., 2008; Li, Shao, et al., 2008; Nah et al., 2008; Seoudi, Abd, & Shabaka, 2008; Yang, Shao, Guan, Li, & Gong, 2004; Zhang et al., 2009; Zhuanga, Cheng, Kang, & Xu, 2010). The properties of these nanocomposites are strongly dependent on the size, dispersion efficiency and morphology of the sample. The in situ growth of nanoparticles in polymer matrixes is attracting increasing interest in terms of practical applications and synthetic challenges. A major obstacle in these processes is the presence

of aggregates and inhomogeneous distribution of nanoparticles (Mackay et al., 2006; Oberdisse, 2006; Smith & Bedrov, 2009).

Electrospun bionanocomposites has been a recent focus of researchers and has a huge impact in diverse areas such as tissue engineering, bone replacement/repair, dental applications, wound healing and controlled drug delivery (Cui et al., 2010; Rujitanaroj, Pimpfa, & Supaphol, 2008; Schneider, Wang, Kaplan, Garlick, & Egles, 2009; Shafei & Abou-Okeil, 2011; Zeng et al., 2003). Cellulose and its derivatives are widely used as versatile materials because of its low cost and its processability into different forms. Unlike starch, it has low water solubility; therefore it allows better control over scaffold design, textile, filtering, etc. However, their applications are still limited due to the lack of antimicrobial activity. Recently, it has been found that these limitations can be overcome by the incorporation of antimicrobial nanoparticles into it (Son, Youk, Lee, & Park, 2004; Son, Youk, & Park, 2006). ZnO is a direct wide band gap semiconductor ($E_g = 3.4$ eV). The high exciton binding energy (~ 60 meV) of this material ensures that it is a promising candidate for stable room temperature luminescent and lasing devices. Moreover, ZnO is a bactericide and inhibits both Gram positive and Gram negative bacteria (Dai, Chen, Wang, Zhou, & Hu, 2003; Tam et al., 2008).

Microbial contamination is a life-threatening issue in food industry, synthetic textiles, packaging, and healthcare care products (Li, Mahendra, et al., 2008; Li, Shao, et al., 2008). Among the various kinds of pathogenic microorganisms, *Staphylococcus* and *Escherichia coli* are closely related species that commonly cause a wide variety of infections and diseases (Bae et al., 2010; Panacek

DOIs of original articles: <http://dx.doi.org/10.1016/j.carbpol.2012.12.020>, <http://dx.doi.org/10.1016/j.carbpol.2011.08.030>

* Corresponding author. Tel.: +91 044 22574860; fax: +91 044 2257 4852.

E-mail address: tsn@physics.iitm.ac.in (T.S. Natarajan).




Fig. 1. SEM image of the ZnO embedded CA membrane with varied polymer concentrations: (a) 6 wt%, (b) 8 wt%, (c) 10 wt%, (d) 12 wt%, (e) 14 wt%, and (f) energy dispersive X-ray spectra analysis (EDAX).

et al., 2009). Therefore, the development of antimicrobial surface coating has attracted increased attention to prevent the microbial contamination (Perelshtein et al., 2009). The use of inorganic antimicrobial agents has gained importance because of their ability to withstand adverse processing condition as compared to organic antimicrobial agents (Wu et al., 2009; Yuvaraj, Kaushik, & Narasimha, 2010). The ability to prepare nanobiocomposites of cellulose acetate and ZnO, paves a way to develop new biocidal agents.

The self-cleaning effect caused by superhydrophobicity is needed for many applications such as self cleaning and anti-fouling coatings. Till date, various methods have been adopted by researchers to produce superhydrophobic surfaces (Tarwal & Patil, 2010). Therefore, developing a simple approach to fabricate the superhydrophobic surface without further coating of low surface energy material is important and scientifically challenging.

In this study, we report the successful preparation and optimization of ZnO embedded CA membrane and also characterization of this biocomposite membrane based on the optical, bactericidal and water repellent properties.

2. Experimental details

2.1. Materials

Cellulose acetate (CA, $M_w = 25,000$) was purchased from Aldrich. Zinc acetate dehydrate, dimethyl formamide (DMF) and acetone were purchased from Sisco Research Laboratories – India.

2.2. Experimental procedure

Initially 0.2 mol of zinc acetate dihydrate was dissolved in mixture of DMF/acetone in the ratio of 4:1. Then the cellulose acetate (14 wt%) was added in to the sol solution and stirred for 5 h to achieve the homogeneous solution which is finally considered as a precursor solution for electrospinning. The concentration of the CA solution was varied between 6 and 14 wt%. The electrospinning process was performed in a similar way as reported in our previous work (Anitha, John Thiruvadigal, & Natarajan, 2011). The flow rate was kept constant at 0.4 ml/h. The distance between the electrodes was about 12 cm. The collected composite membrane was dried initially at 80 °C for 6 h.




Fig. 2. TEM image of the composite fiber and SAED patterns (inset in the left top of the figure). The ZnO nanoparticles are clearly seen in surface of the fibers.

2.3. Measurements and characterization

The scanning electron microscopy (SEM) (Quanta 200 FEG) was used to analyze the sample morphology and energy dispersive X-ray spectroscopy (EDS) analysis gave the chemical composition of the sample. The functional groups present in the sample were analyzed using Fourier transform infrared (FTIR) spectroscopy (Bruker Tensor Instrument). Photo Luminescence study was performed using SPECTRAQ Fluorolog spectrophotometer. Measurement of contact angle of water was performed using axisymmetric drop shape analysis (ADSA)-easy drop goniometer (KRUSS, DSA II GmbH, Germany).

2.4. Antibacterial activity studies

Antibacterial tests were carried out on Gram positive bacteria methicillin-resistant *Staphylococcus aureus* (MRSA) and Gram negative bacteria *E. coli*, *Klebsiella pneumoniae*, *Citrobacter freundii* using Kirby-Bauer disk diffusion method. The bacterial cultures were maintained in Nutrient agar slopes at 4 °C and sub cultured on Nutrient agar plates. The isolated colonies of the respective bacterial strains adjusted to $1-2 \times 10^7$ cfu/ml by 0.5 Mcfarland standards. The culture was inoculated on Muller-Hinton agar plates. CA membrane disks were placed aseptically on the Muller-Hinton agar medium which was already swabbed with the test organism. The experiment was carried out for both CA membranes, with and without ZnO nanoparticles. The plates were incubated at 37 °C for 24 h to observe the inhibition zone.

3. Results and discussion

3.1. Morphological investigation

3.1.1. SEM analysis

It is well known that the morphology of the electrospun fibers is strongly dependent on the number of processing parameters such as polymer concentration, voltage, and distance between the electrodes. The influence of the various polymer concentrations (6, 8, 10, 12 and 14 wt%) in the solution on the morphology of fibers was examined by SEM as shown in Fig. 1a–e, respectively. At lower concentrations, beads are formed along the fiber which is generally considered as defects. These beads may decrease the effective surface area of the fibers. The number of beads formed is reduced as we go from 6 wt% to 12 wt% and the beads completely disappeared in the case of 14 wt% of the solution. However there




Fig. 3. XRD pattern of (a) cellulose acetate fibrous membrane and (b) ZnO embedded cellulose acetate fibrous membrane.

is a considerable increase in the fiber diameter. The average diameter of the optimized fiber was found to be 170 ± 40 nm. The increased polymer concentration in the solution helps to prepare the uniform defect free fiber because at higher polymer concentrations, sufficient chain entanglements serve to stabilize the jet by inhibiting its breakup (Anitha et al., 2011).

EDS analysis was used to identify the composition of the fibers as shown in Fig. 1f. The elemental analysis reveals the presence of ZnO in the fibers. The Al peak in the spectrum comes from the aluminum foil which served as substrate. The carbon peak originates from the polymer part of the fibers.




Fig. 4. FTIR spectra of (a) pure CA fibrous membrane and (b) ZnO embedded CA fibrous membrane.




Fig. 5. PL spectra of (a) pure CA fibrous membrane and (b) ZnO embedded CA fibrous membrane.

3.1.2. TEM analysis

TEM analysis was used to analysis the dispersion efficiency of nanoparticles in polymer matrix directly as shown in Fig. 2. The corresponding SAED patterns of fiber are shown inset in the same figure. From the image, it is clearly revealed that the ZnO particles are well dispersed throughout the cellulose acetate fibers without the presence of agglomeration.

3.2. XRD analysis

The XRD pattern of CA and ZnO embedded cellulose acetate are shown in Fig. 3. The CA fibers exhibit the diffuse characteristics pattern of an amorphous phase with the typical peak around 23° . The observed peaks in the range $30\text{--}50^\circ$ could be indexed as the wurtzite structure of ZnO which is well matched with standard




Fig. 6. Images of bactericidal effect of (a) pure fibrous CA membrane and (b) ZnO embedded CA fibrous membrane against Gram-positive methicillin-resistant *Staphylococcus aureus* (MRSA) and Gram-negative *E. coli*, *Citrobacter freundii*, *Klebsiella pneumoniae*.

diffraction data (JCPDS: 36-145). No additional peaks are detected and which indicates the formation of ZnO in the CA fibers (Hong, Li, Zheng, & Zou, 2006).

3.3. FTIR analysis

The results of the FTIR analysis was used to analysis the interaction between ZnO and cellulose acetate. Fig. 4a and b shows the FTIR spectra of pure CA and CA/ZnO composite fibrous membrane, respectively. The main characteristics bands of CA were assigned as follows: the characteristic absorption peak at 3500 cm^{-1} can be attributed the presence of hydroxyl group and the peaks at 1743, 1270 and 1050 cm^{-1} corresponding to the stretching of C–O group, ether group and C–O– bond of the $-\text{CH}_2-\text{OH}$ group, respectively (Saowakon, Manashuen, Jochen, Pitt, & Tipaporn, 2010).

In Fig. 4b, in addition to the characteristics peak of CA, a new peak around 477 cm^{-1} is assigned to the Zn–O vibration which further confirms the formation of ZnO. By comparing the IR spectra of ZnO/CA composite fibrous membrane with that of pure CA fibrous membrane, the characteristics peak of –OH group was shifted to 3471 cm^{-1} from 3450 cm^{-1} as shown in figure. Similar shift are observed for the peaks located at 1743, 1370 and 1050 cm^{-1} . The observed shifts in the peaks may be described due to the formation of hydrogen bonding between ZnO and CA (Sui, Shao, & Liu, 2007).

3.4. PL studies

In order to investigate the quality and purity of the sample, PL spectrum was recorded for both CA and CA/ZnO composite fibrous membrane shown in Fig. 5a and b, respectively. It is well known that a typical spectrum of ZnO has two major characteristic peaks: a UV near-band-edge (NBE) whose peak emission is around 380 nm and deep-level (DL) emission in the visible region (Guo, Ji, Xu, Simon, & Wu, 2002; Li et al., 2004; Viswanathamurthi, Bhattacharai, Kim, & Lee, 2004). In the PL spectrum of CA/ZnO composites membrane exhibits both characteristics bands of CA and ZnO and the characteristics peaks remained the same as observed in their single component. However, there is no significant change in the observed emission spectra. It clearly indicates that the emission features of cellulose acetate are not significantly affected by the embedded ZnO nanoparticles. In addition to this, yet another interesting observation is that visible emission was quenched in

the observed spectra which may be the result of the surface passivation of ZnO with CA (Richters, Voss, Wischmeier, Ruckmann, & Gutowski, 2008).

3.5. Bactericidal properties

The antimicrobial properties of the fibrous CA (Fig. 6a) and ZnO impregnated CA (Fig. 6b) were evaluated against both Gram positive and Gram negative bacteria under normal lighting condition. Here, Kirby Bauer technique was adopted to evaluate the antimicrobial activity. The bare CA fibrous membrane was used as a control. According to the results obtained, no detectable inhibition Zones were seen for the bare CA. Conversely, the significant Zones were observed for ZnO embedded CA. The diameters of the zone of inhibition around the membranes after one day were measured to be 27 mm, 22 mm, 14 mm for Methicillin-resistant *S. aureus* (MRSA), *E. coli* and *C. freundii*, respectively. However, no antibacterial activity was shown against *K. pneumoniae*. It is seen that the composite membrane had a stronger influence on MRSA than *E. coli*. Such results are in a good agreement with the previously reported literature (Dastjerdi & Montazer, 2010; Wang et al., 2008). The nature of cell wall structure is one of the possible reasons for observed difference in sensitivity.

The *S. aureus* is composed of multi layers of peptidoglycan which has plenty of pores that could render them more susceptible to the intracellular transduction by the nanoparticles leading to cell disruption (Inphonlek, Pimpha, & Sunintaboon, 2010; Li, Guo, et al., 2010; Li, Feng, et al., 2010). In contrast, the cell wall of *E. coli* is relatively thin mainly consisting of peptidoglycan and an outer layer of lipopolysaccharide, lipoprotein, and phospholipids, which would be less prone to the attack of the nanoparticles. Therefore, the nanoparticles had higher antibacterial activity against *S. aureus* than *E. coli* (Mosnier et al., 2009; Zhongbing et al., 2008). To date, several mechanisms have been postulated for the antimicrobial property of ZnO nanoparticles (Applerot et al., 2009; Nadanathangam, Kumar, Kathe, Varadarajan, & Prasad, 2006; Wahab, Mishra, Yun, Kim, & Shin, 2010; Zhang, Jiang, Ding, Povey, & York, 2007). However, much remains unknown mechanism will be the subject of future research. The reason for such an observation in composite fibrous membrane under normal lighting condition is not totally clear yet. A thorough survey of literature till date, have made us assume that the antimicrobial effects of composite

Time(sec)	CA fibrous membrane	ZnO embedded CA membrane
0	 47.4°	 124.2°
5	 43.2°	 124.1°
10	 41.4°	 123.9°
15	 38.7°	 123.2°
20	 37.3°	 123.1°
25	 37.2°	 122.7°
30	 31.2°	 122.4°

Fig. 7. The optical photograph of water droplet on (a) pure and (b) ZnO embedded CA fibrous membrane.

membrane might be associated with the presence of an electrostatic attraction between the positively charged nanoparticles and the negatively charged bacteria (Harris & Richards, 2004; Li, Guo, et al., 2010; Li, Feng, et al., 2010; Sivakumar et al., 2010; Stoimenov, Klinger, Marchin, & Klabunde, 2002).

It is a well known fact that, both Gram positive and Gram negative bacteria have negative charge. The peptidoglycan layer of Gram positive bacterium is rich in teichoic acids, which are negatively charged due to presence of phosphate in their structure. On the other hand, the highly charged lipopolysaccharides, which are the major constituents of the outer membrane of Gram negative

bacterium, impart a strong negative charge to surface of the bacterial cells (Brayner et al., 2006; Koga, Kitaoka, & Wariishi, 2009).

The work of Vimala et al. (2010) which is related to our report, is considered for a comparative account. They demonstrated that the presence of pores in fiber structure is one of the reasons for superior antibacterial activity. The fact that the porous structure absorbs large quantity of water, enormous amount of silver nanoparticles, as a result, is released in to the media. These results cannot be applied to the current work, since the result of WCA measurements confirmed the hydrophobic nature of the prepared sample.

The surface area in contact with the microorganisms determines the antibacterial activity. As the electrospun fibers have large surface area, broad range of probable reaction with surface of the cell wall is possible, when compared to one-dimensional nanostructures prepared using any other physical/chemical methods. Moreover, this method produces nanoparticles which are homogenous and monodispersed. The absence of aggregation of the particles is one of the most distinguishing features of this method. Other chemical methods used for synthesis of nanoparticles in polymers lead to aggregation of particles resulting in decreased antibacterial activity. Yet another factor which is responsible for high antibacterial activity is the enhanced dispersion stability of ZnO nanoparticles in the CA fibers.

3.6. Wettability studies

Contact angle measurement was carried out to evaluate the wetting properties of the fibrous membrane. Most of the previous studies focused on the preparation of hydrophobic and super hydrophobic surface by appropriate surface modification of the sample (Ding, Ogawa, Kim, Fujimoto, & Shiratori, 2008; Patra, Sarkar, Bera, Ghosh, & Paul, 2009; Tarwal & Patil, 2010). Still, it is difficult to achieve the super hydrophobic surface without chemical modification of the sample. Fig. 7a and b shows the contact angle of a water droplet on the fibrous membrane for duration of 30 s.

In the case of pure CA fibrous membrane, the measured contact angle was found to be 47° initially and the contact angle decreases rapidly from 47° to 31° . The observed hydrophobicity of ZnO embedded CA is about 124° , which is much higher than that of the pure CA fibers. The value of the WCA does not change significantly from that observed initial value. From the observed result, it was concluded that the wetting property of the CA has changed from hydrophilic to hydrophobic when ZnO was impregnated into it.

Trapping of more air under water droplets falling on the fibers could be a result of the surface roughness of the fibers caused by electrospinning as well as the presence of nano ZnO. On comparison with the work by Bin Ding, where fabrication of superhydrophobic cellulose acetate (WCA of 132°) was done using simple sol–gel coating of decyltrimethoxysilane and tetraethylorthosilicate (Ding et al., 2006), ZnO impregnated cellulose acetate fibrous showed not only the superhydrophobic nature (WCA 124°) but also a good bactericidal property.

4. Conclusion

ZnO embedded cellulose acetate fibrous membrane has been prepared by electrospinning method. From the analysis of FTIR spectra, it could be concluded that the formation of hydrogen bond between ZnO and CA. The ZnO embedded fibrous membrane showed a better water repellent property than pure CA membrane. The sample exhibited strong antibacterial activity against the *S. aureus*, *E. coli* and *Citrobacter*. Moreover, the wettability of the surface can be changed from hydrophilic to hydrophobic. Our simple method provides a new approach to fabricate the hydrophobic surface without need for further surface treatment. Therefore, the electrospinning technique could be considered as the best suited method for synthesis of composite fibrous membrane, since agglomeration of nanoparticles is prevented and the contact area between the surface and the microorganisms is increased.

References

Anitha, S., John Thiruvadigal, D., & Natarajan, T. S. (2011). A study of defect controlled morphology of organic/inorganic composite nanofibers with different heat flow rates. *Materials Letters*, 65, 167–170.

- Applero, G., Lipovsky, A., Dror, R., Perkash, N., Nitzan, Y., Lubart, R., et al. (2009). Enhanced antibacterial activity of nanocrystalline ZnO due to increased ROS-mediated cell injury. *Advanced Functional Materials*, 19, 842–852.
- Bae, E., Park, H. J., Lee, J., Kim, Y., Yoon, J., Park, K., et al. (2010). Bacterial cytotoxicity of the silver nanoparticle related to physicochemical metrics and agglomeration properties. *Environmental Toxicology & Chemistry*, 29(10), 2154–2160.
- Brayner, R., Ferrari-Iliou, R., Brivois, N., Djedati, S., Benedetti, M. F., & Fievet, F. (2006). Toxicological impact studies based on *Escherichia coli* bacteria in ultrafine ZnO nanoparticles colloidal medium. *Nano Letters*, 6(4), 866–870.
- Cui, W., Li, X., Xie, C., Chen, J., Zou, J., Zhou, S., et al. (2010). Controllable growth of hydroxyapatite on electrospun poly(DL-lactide) fibers grafted with chitosan as potential tissue engineering scaffolds. *Polymer*, 51, 2320–2328.
- Dai, L., Chen, X. L., Wang, W. J., Zhou, T., & Hu, B. H. (2003). Growth and luminescence characterization of large-scale zinc oxide nanowires. *Journal of Physics: Condensed Matter*, 15, 2221–2226.
- Dastjerdi, R., & Montazer, M. (2010). A review on the application of inorganic nanostructured materials in the modification of textiles: Focus on anti-microbial properties. *Colloids and Surfaces B: Biointerfaces*, 79, 5–18.
- Ding, B., Li, C., Hotta, Y., Kim, J., Kuwaki, O., & Shiratori, S. (2006). Conversion of an electrospun nanofibrous cellulose acetate mat from a super-hydrophilic to super-hydrophobic surface. *Nanotechnology*, 17, 4332–4339.
- Ding, B., Ogawa, T., Kim, J., Fujimoto, K., & Shiratori, S. (2008). Fabrication of a super-hydrophobic nanofibrous zinc oxide film surface by electrospinning. *Thin Solid Films*, 516(9), 2495–2501.
- Greiner, A., & Wendorff, J. H. (2007). Electrospinning: A fascinating method for the preparation of ultra fibers. *Angewandte Chemie International Edition*, 46, 5670–5703.
- Guo, L., Ji, Y. L., Xu, H., Simon, P., & Wu, Z. (2002). Regularly shaped, single-crystalline ZnO nanorods with wurtzite structure. *Journal of the American Chemical Society*, 124, 14864–14865.
- Harris, L. G., & Richards, R. G. (2004). *Staphylococcus aureus* adhesion to different treated titanium surfaces. *Journal of Materials Science: Materials in Medicine*, 15, 311–314.
- Hong, Y., Li, D., Zheng, J., & Zou, G. (2006). In situ growth of ZnO nanocrystals from solid electrospun nanofiber matrices. *Langmuir*, 22, 7331–7334.
- Inphonlek, S., Pimpha, N., & Sunintaboon, P. (2010). Synthesis of poly(methyl methacrylate) core/chitosan-mixed-polyethyleneimine shell nanoparticles and their antibacterial property. *Colloids and Surfaces B: Biointerfaces*, 77, 219–226.
- Joshi, P., Zhang, L., Davoux, D., Zhu, Z., Galipeau, D., Fong, H., et al. (2010). Composite of TiO₂ nanofibers and nanoparticles for dye-sensitized solar cells with significantly improved efficiency. *Energy & Environmental Science*, 3, 1507–1510.
- Koga, H., Kitaoka, T., & Wariishi, H. (2009). In situ synthesis of silver nanoparticles on zinc oxide whiskers incorporated in a paper matrix for antibacterial applications. *Journal of Materials Chemistry*, 19, 2135–2140.
- Li, D., Leung, Y. H., Djurisic, A. B., Liu, Z. T., Xie, M. H., Shi, S. L., et al. (2004). Different origins of visible luminescence in ZnO nanostructures fabricated by the chemical and evaporation methods. *Applied Physics Letters*, 85, 1601–1603.
- Li, D., & Xia, Y. (2004). Electrospinning of nanofibers: Reinventing the wheel? *Advanced Materials*, 16, 1151–1170.
- Li, J., Guo, D., Wang, X., Wang, H., Jiang, H., & Chen, B. (2010). The photodynamic effect of different size ZnO nanoparticles on cancer cell proliferation in vitro. *Nanoscale Research Letters*, 5, 1063–1071.
- Li, Q., Mahendra, S., Lyon, D. Y., Brunet, L., Liga, M. V., Li, D., et al. (2008). Antimicrobial nanomaterials for water disinfection and microbial control: Potential applications and implications. *Water Research*, 42, 4591–4602.
- Li, X., Feng, X., Yang, S., Fu, G., Wang, T., & Su, Z. (2010). Chitosan kills *Escherichia coli* through damage to be of cell membrane mechanism. *Carbohydrate Polymers*, 79, 493–499.
- Li, X. H., Shao, C. L., Liu, Y. C., Chu, X. Y., Wang, C. H., & Zhang, B. X. (2008). Photoluminescence properties of highly dispersed ZnO quantum dots in polyvinylpyrrolidone nanotubes prepared by a single capillary electrospinning. *Journal of Chemical Physics*, 129, 114708–114715.
- Mackay, M. E., Tuteja, A., Duxbury, P. M., Hawker, C. J., Van Horn, B., Guan, Z., et al. (2006). General strategies for nanoparticle dispersion. *Science*, 311(5768), 1740–1743.
- Mosnier, J. P., O'Haire, R. J., McGlynn, E., Henry, M. O., McDonnell, S. J., Boyle, M. A., et al. (2009). ZnO films grown by pulsed-laser deposition on soda lime glass substrates for ultraviolet inactivation of *Staphylococcus epidermidis* biofilms. *Science and Technology of Advanced Materials*, 10, 045003.
- Nadanathangam, V., Kumar, S., Kathe, A. A., Varadarajan, P. V., & Prasad, V. (2006). Functional finishing of cotton fabrics using zinc oxide soluble starch nanocomposites. *Nanotechnology*, 17, 5087–5095.
- Nah, C., Lee, Y. S., Cho, B. H., Yu, H. C., Akle, B., & Leo, D. J. (2008). Preparation and properties of nanofibrous nafen mats for ionic polymer metal composites. *Composite Science and Technology*, 68, 2960–2964.
- Oberdisse, J. (2006). Aggregation of colloidal nanoparticles in polymer matrices. *Soft Matter*, 2, 29–36.
- Panacek, A., Kolar, M., Vecerova, R., Pucek, R., Soukupova, J., Krystof, V., et al. (2009). Antifungal activity of silver nanoparticles against *Candida* spp. *Biomaterials*, 30, 6333–6340.
- Patra, S., Sarkar, S., Bera, S. K., Ghosh, R., & Paul, G. K. (2009). Hydrophobic self-cleaning surfaces of ZnO thin films synthesized by sol–gel technique. *Journal of Physics D: Applied Physics*, 42, 075301.
- Perelshtein, I., Applero, G., Perkash, N., Wehrschetz-Sigl, E., Hasmann, A., Guebitz, G. M., et al. (2009). Antibacterial properties of an in situ generated and

- simultaneously deposited nanocrystalline ZnO on fabrics. *Applied Materials & Interfaces*, 2(1), 363–366.
- Richters, J. P., Voss, T., Wischmeier, L., Ruckmann, I., & Gutowski, J. (2008). Influence of polymer coating on the low-temperature photoluminescence properties of ZnO nanowires. *Applied Physics Letters*, 92, 011103.
- Rujitanaroj, P., Pimpha, N., & Supaphol, P. (2008). Wound-dressing materials with antibacterial activity from electrospun gelatin fiber mats containing silver nanoparticles. *Polymer*, 49, 4723–4732.
- Saowakon, W., Manashuen, P., Jochen, W., Pitt, S., & Tipaporn, Y. (2010). Electrospinning of food-grade nanofibers from cellulose acetate and egg albumen blends. *Journal of Food Engineering*, 98, 370–376.
- Schneider, A., Wang, X. Y., Kaplan, D. L., Garlick, J. A., & Egles, C. (2009). Biofunctionalized electrospun silk mats as a topical bioactive dressing for accelerated wound healing. *Acta Biomaterialia*, 5, 2570–2578.
- Seoudi, R., Abd, E. M. S., & Shabaka, A. A. (2008). Effect of polyvinyl alcohol matrices on the structural and spectroscopic studies of CdSe nanoparticle. *Physica B*, 403, 1781–1786.
- Shafei, A. E., & Abou-Okeil, A. (2011). ZnO/carboxymethyl chitosan bionanocomposite to impart antibacterial and UV protection for cotton fabric. *Carbohydrate Polymers*, 83, 920–925.
- Sivakumar, P. M., Balaji, S., Prabhawathi, V., Neelakandan, R., Manoharan, P. T., & Doble, M. (2010). Effective antibacterial adhesive coating on cotton fabric using ZnO nanorods and chalcone. *Carbohydrate Polymers*, 73, 717–723.
- Smith, G. D., & Bedrov, D. (2009). Dispersing nanoparticles in a polymer matrix: Are long, dense polymer tethers really necessary? *Langmuir*, 25(19), 11239–11243.
- Son, W. K., Youk, J. H., Lee, T. S., & Park, W. H. (2004). Preparation of antimicrobial ultrafine cellulose acetate fibers with silver nanoparticles. *Macromolecular Rapid Communication*, 25, 1632–1637.
- Son, W. K., Youk, J. H., & Park, W. H. (2006). Antimicrobial cellulose acetate nanofibers containing silver nanoparticles. *Carbohydrate Polymers*, 65, 430–434.
- Stoimenov, P. K., Klinger, R. L., Marchin, G. L., & Klabunde, K. J. (2002). Metal oxide nanoparticles as bactericidal agents. *Langmuir*, 18, 6679–6686.
- Sui, X., Shao, C., & Liu, Y. (2007). Photoluminescence of polyethylene oxide–ZnO composite electrospun fibers. *Polymer*, 48, 1459–1463.
- Sundaray, B., Subramanian, V., Natarajan, T. S., Xiang, R. Z., Chang, C. C., & Fann, W. S. (2004). Electrospinning of continuous aligned polymer fibers. *Applied Physics Letters*, 84, 1222.
- Tam, K. H., Djuricic, A. B., Chan, C. M. N., Xi, Y. Y., Tse, C. W., Leung, Y. H., et al. (2008). Antibacterial activity of ZnO nanorods prepared by a hydrothermal method. *Thin Solid Films*, 516, 6167–6174.
- Tarwal, N. L., & Patil, P. S. (2010). Superhydrophobic and transparent ZnO thin films synthesized by spray pyrolysis technique. *Applied Surface Science*, 256, 7451–7456.
- Vimala, K., Murali, M. Y., Samba, S. K., Varaprasad, K., Ravindra, S., Narayana, R. N., et al. (2010). Fabrication of porous chitosan films impregnated with silver nanoparticles: A facile approach for superior antibacterial application. *Colloids and Surfaces B: Biointerfaces*, 76, 248–258.
- Viswanathamurthi, P., Bhattarai, N., Kim, H. Y., & Lee, D. R. (2004). The photoluminescence properties of zinc oxide nanofibers prepared by electrospinning. *Nanotechnology*, 15, 320–323.
- Wahab, R., Mishra, A., Yun, S. I., Kim, Y. S., & Shin, H. S. (2010). Antibacterial activity of ZnO nanoparticles prepared via non-hydrolytic solution route. *Applied Microbiology and Biotechnology*, 87, 1917–1925.
- Wang, Y., Du, G., Liu, H., Liu, D., Qin, S., Wang, N., et al. (2008). Nanostructured sheets of Ti–O nanobelts for gas sensing and antibacterial applications. *Advanced Functional Materials*, 18, 1–7.
- Wu, Y., Jia, W., An, Q., Liu, Y., Chen, J., & Li, G. (2009). Multi-action antibacterial nanofibrous membranes fabricated by electrospinning: An excellent system for antibacterial applications. *Nanotechnology*, 20, 245101.
- Yang, X., Shao, C., Guan, H., Li, X., & Gong, J. (2004). Preparation and characterization of ZnO nanofibers by using electrospun PVA/zinc acetate composite fiber as precursor. *Inorganic Chemistry Communications*, 7, 176–178.
- Yuvaraj, D., Kaushik, R., & Narasimha, R. K. (2010). Optical, field-emission, and antimicrobial properties of ZnO nanostructured films deposited at room temperature by activated evaporation. *Applied Materials and Interfaces*, 2(4), 1019–1024.
- Zeng, J., Xu, X., Chen, X., Liang, Q., Bian, X., Yang, L., et al. (2003). Biodegradable electrospun fibers for drug delivery. *Journal of Controlled Release*, 92, 227–231.
- Zhang, D., Karki, A. B., Rutman, D., Young, D. P., Wang, A., Cock, D., et al. (2009). Electrospun polyacrylonitrile nanocomposite fibers reinforced with Fe₃O₄ nanoparticles: Fabrication and property analysis. *Polymer*, 50, 4189–4198.
- Zhang, L., Jiang, Y., Ding, Y., Povey, M., & York, D. (2007). Investigation into the antibacterial behaviour of suspensions of ZnO nanoparticles (ZnO nanofluids). *Journal of Nanoparticle Research*, 9, 479–489.
- Zhongbing, H., Xu, Z., Danhong, Y., Guangfu, Y., Xiaoming, L., Yunqing, K., et al. (2008). Toxicological effect of ZnO nanoparticles based on bacteria. *Langmuir*, 24(8), 4140–4144.
- Zhuanga, X., Cheng, B., Kang, W., & Xu, X. (2010). Electrospun chitosan/gelatin nanofibers containing silver nanoparticles. *Carbohydrate Polymers*, 82, 524–527.