


THE PW "BADGER" Build this 144MHz Receiver

PW READER QUESTIONNAIRE

Your chance to tell us what you think of Practical Wireless



Yaesu's FT-736R. Because you never know who's listening.

Why just dream of talking beyond earth?

With Yaesu's new FT-736R VHF/UHF base station, you can discover some of the best DX happening in ham radio. Via moonbounce. Tropo. Aurora. Meteor scatter. Or satellites.

You see, the FT-736R is the most complete, feature-packed rig ever designed for the serious VHF/UHF operator. But you'd expect this of the successor to our legendary FT-726R.

For starters, the FT-736R comes factory-equipped for SSB, CW and FM operation on 2 meters and 70 cm, with two additional slots for optional 50-MHZ or 1.2-GHz modules (220-MHz North America only).

Crossband full duplex capability is built into every FT-736R for satellite work. And the satel-



lite tracking function (normal and reverse modes) keeps you on target through a transponder.

The FT-736R delivers 25 watts RF output on 2 meters, 220-MHz, and 70 cm. And 10 watts on 6 meters and 1.2-GHz. Store frequency, mode and repeater shift in each of the 100 memories.

For serious VHF/UHF work, use the RF speech processor. IF shift. IF notch filter. *CW Narrow Optional and FM wide/ narrow IF filters. VOX. Noise blanker. Three-position AGC selection. Preamp switch for activating

your tower-mount preamplifier. Even an offset display for measuring observed Doppler shift on DX links.

And to custom design your FT-736R station, choose from these popular optional accessories: Iambic keyer module. FTS-8 CTCSS encode/decode unit. FVS-1 voice synthesizer. FMP-1 AQS digital message display unit. 1.2-GHz ATV module. MD-1B8 desk microphone. E-736 DC cable. And CAT (Computer Aided Transceiver) system software.

Discover the FT-736R at your Yaesu dealer today. But first make plenty of room for exotic QSL cards. Because you *never* know who's listening.







OCTOBER 1988 (ON SALE 8 SEPTEMBER 1988)

VOL. 64 NO. 10 ISSUE 979

Yesterday's World of Technology (new series)

A Practical Antenna Electrometer

"Valved Comms Receivers" The DST100

The Yaesu FT-747GX HF Transceiver Reviewed and All the usual features

Don't miss it—place your order with your newsagent now!

> On sale October 13

PW Review

Kenwood TM-721E Dual Band FM Transceiver Ken Michaelson G3RDG

Practically Yours

Glen Ross G8MWR

24 A Constructor's Shack Test Gear E. P. Esserv GW3KFE

26 Doppler Shift on Satellites—2 Dave Tyler GIPEF

★PW Questionnaire★ Your chance to have your say

32 Understanding Circuit Diagrams—8 R. F. Fautley G3ASG

Kitchen Konstruktion-No. 7 Richard Q. Marris G2BZQ.

PW "Badger" 144MHz Receiver Mike Rowe G8JVE

PW Review Garex 50MHz Pre-amplifier Mike Richards G4WNC

Valved Communications Receivers The BC-348-2 Chas E. Miller

50 Crops and Coils-3 George Pickworth

We are sorry that, due to pressure on editorial space, this month's session of Computing Corner has had to be held over

Regular Features

71 Advert Index

52 On the Air 25 Bookshelf **68 PCB Service** 28 Subscriptions

42 Book Service

13 PW Services

33, 34,44 Swap Spot

12 Comment 14 Newsdesk 25 Short Wave Magazine

12 Write On

Geoff Arnold T.Eng FSERT G3GSR **Assistant Editor**

Dick Ganderton C.Eng MIERE G8VFH Art Editor Steve Hunt

Technical Features Editor Elaine Richards G4LFM

Technical Projects Sub-Editor Richard Ayley G6AKG

Editorial Assistant Sharon George

Technical Artist Rob Mackie

Administration Manager

Kathy Moore

Accounts

Alan Burgess

Editorial and **Advertisement Offices:**

Practical Wireless Enefco House

The Quay Poole, Dorset BH15 1PP

☎ Poole (0202) 678558

(Out-of-hours service by answering machine)

FAX Poole (0202) 666244

Prestel 202671191

Advertisement Manager Roger Hall G4TNT

PO Box 948 London SW6 2DS

☎ 01-731 6222 Cellphone 0860 511382

Advert Copy and Make-up Poole (0202) 676033


COPYRIGHT © PW Publishing Limited 1988. Copyright in all drawings, photographs, and articles published in *Practical Wireless* is fully protected and reproduction or imitation in whole or in part is expressly forbidden. All reasonable precautions are taken by *Practical Wireless* to ensure that the advice and data given to our readers are reliable. We cannot however guarantee it and we cannot accept legal responsibility for it. Prices are those current as we go to press.

COMMUNICATIONS



Kenwood TS440S HF Transceiver

Now available once again from ARE Communications the excellent Kenwood TS440S. General Coverage Receiver 100W output between Top band and 10m. FM fitted as standard. Auto Tuning Unit optional Offered at a discounted price of £1,039.00 or, with ATU £1,199.00.



Kenwood TS680S HF and SIX metre



Yaesu FT23R 2M HANDIE

Due to A.R.E.'s continued policy of direct importing from Japan, we continue to offer Yaesu's best seller at a discounted price to full U.K. spec with FBA9 empty battery case, helical antenna and strap. Price: \$195.00 or complete with FNB10 and NC28C charger



Standard C500 Dual Band Handie

You must have read our adverts by now, we've sold hundreds! 2m & 70cm full duplex 138-170 MHz + 420-469 MHz. Many additional features. Price: £369.00



Icom IC32E Full Duplex dual-band handy

Available Ex-stock, the new Icom IC32E full



Yaesu FT767GX HF + 2m + 6m + 70cm.

Our latest batch direct from Japan guarantees you will not be investing in earlier production models. A complete ham station in one package. All band, all mode, built-in Automatic Tuning Unit, Power Supply Unit, General Coverage Receiver, Digital Power/SWR Meter 100W out, optional 2m/6/70cm modules which just plug in. £1,369.00 including MH1B8 microphone. Also available with one or all VHF modules fitted. Phone for unbeatable price or part-exchange



Yaesu FT736R quad band multimode

The KING of VHF/UHF Base stations, the FT736R has all the facilities any discerning user may need, plus the two most important features: Uncompromised receive performance and a clean transmitted signal. A.R.E.'s continued policy of direct importing guarantees you an unbeatable price of £1,289.00 including MH1B8 microphone; £1,475.00 including 6m card and microphone.

STOP PRESS:

DISCOUNTED PRICES ON KENWOOD 135. ONLY \$1195.00.

DISCOUNTED AVAILABLE, THE NEW IST 135. Saturday by appointment.

Opening Hours Monteri 9.30 to 5.30 Saturday by appointment.

Opening Hours Monteri 9.30 to 5.30 Saturday by appointment. Although infrequently mentioned in our advertising. A.R.E. Complete range of ICOM PRODUCTS. The fabulous ICR7000 and ICR71E receivers, IC735/275/475/575 transceivers, together with the new range of hand-held and mobile transceivers (including the IC32E Dual-bander), all available from stock. Remember, our "MAILBOX" system is still in use and enables us to mail any enquiries quickly and efficiently, plus the added advantage of selling all used equipment at realistic prices. Why wait to place an AD in a magazine? 73 Martin G4HKS







Unit 5 Parsons Green Estate **Boulton Road** Stevenage Herts SG1 4QG



THE FILTER SPECIALISTS



MAIL ORDER DEPT.

Stock Items Normally Despatched within 48 hours.

TEL. 0438 351710

NOW AVAILABLE FOR THE DISCERNING HF OPERATOR



AKD HAVE INTRODUCED TWO COMPLETELY NEW WAVEMETERS

BOTH MODELS COVER THE RANGE 1.5 MHz TO 110 MHz AND ALLOW
TRANSMISSION FREQUENCIES UP TO THE
3rd HARMONIC TO BE MONITORED AND
ASSESSED, THUS ENSURING COMPLIANCE
WITH LICENSING REGULATIONS.



£54.95

WA3-S FEATURES:-

- ★ ALL PUSH BUTTON OPERATION
 ★ AUTO OR MANUAL FREQUENCY SCAN
 ★ 10 SECTION L.E.D. SCALE INDICATION
 ★ 5 L.E.D. BAND INDICATORS

£79.95

- PUSH BUTTON BAND SELECTION
 BATTERY LOW INDICATOR
 INTEGRAL BATTERY COMPARTMENT ★ INTEGRAL BATTER
 ★ EXTERNAL AERIAL

strength meter within its range. Requires PP3 type battery

L.E.D. SCALE INDICATION

★ INTEGRAL BATTER ★ EXTERNAL AERIAL

£49 00

BOTH MODELS REQUIRE PP3 TYPE BATTERY (NOT SUPPLIED) AND COME COMPLETE WITH FULL OPERATING INSTRUCTIONS. APPROX SIZE $150\times50\times65$ mm (NOT INC AERIAL)

WA1 WAVEMETER (CITTED - 0

Our Waveabsorption meter for 2 Mtre transmitters meets licensing requirements range 120Mhz to 450Mhz, very sensitive, can also be used as field

HFC1



9600. Tune from 100, 1Mhz to 160Mhz, gives tuning range of 100Khz to 60Mhz, uses double balanced mixer, with low pass filter on input.

★ Can be supplied with BNC termination for other scanners ★

WA3 FEATURES:-

- ★ 5 BAND SCALES ★ ROTARY BAND SELECTION ★ ROTARY TUNING
- METERED SIGNAL STRENGTH DISPLAY
- INTEGRAL BATTERY COMPARTMENT

WA2

CONVERTER £25.95

WAVEMETER

£25 95



Our Wave absorption meter for the 50 & 70 MHz Bands. Meets licensing requirements. Can also be used as field strength meter within its range. Requires PP3 battery (not supplied).

TV INTERFERENCE PROBLEMS??!!

Are you having trouble receiving a watchable picture on your TV? If so, the cause may be aerialborne interference. For many years AKD has manufactured a low cost range of in-line interference suppression filters that are easily inserted into the aerial system to help reduce the effects of interference from local taxi radio, CB, amateur radio, airport radar, etc. Each filter is terminated in standard aerial co-ax plug and socket and requires no external power. Filting could not be more simple. No technical knowledge is needed. There are 13 standard stocked filters in our range, but individual filters can be tuned to reject interference at specific frequencies if required. If you are not sure which filter type to order or have any questions regarding interference phone our helpline on 0438 351710 and ask for John who will be pleased to assist you in making the best choice of filter.

THE FILTER RANGE IS AS FOLLOWS:

FILTER TYPE RBF1

A range of filters designed to eliminate Radar Blip, especially noticeable on video recorders. Stocked on channel 36 and 846MHz (RAF Boulmer interference) can be tuned at our factory from 420MHz to 890MHz

FILTER TYPE TNF2 (Suitable for UHF TV only)
A range of Tuned Notch filters stocked on generally useful frequencies used by Amateur Radio operators, CB users, Private Taxi companies. Can also be factory tuned to reject any spot frequency up to 300MHz. Now stocked at 50 & 70 MHz. £7.95 each

FILTER TYPE HPF1

Used in weaker reception areas for general interference problems. Use with UHF TV, Video & Pre-Amps

FILTER TYPE HPFS

Used in strong signal area for severe interference on UHF only

Yet another filter is added to the already comprehensive range of AKD filters. The HPF6 is a 6 section UHF high pass filter particularly useful for the rejection of any aerialborne interference below 450 MHz yet having minimal insertion loss on Bands 4 & 5 (UHF TV). It can be

£7.50 each

FILTER TYPE BB1

A general purpose filter that can be used on its own or together with other filters in our range for severe interference problems. Ideal at the input of VCR and Pre-Amps. £6.95 each

FILTER TYPE HPF6



used with UHF TV, video recorders and should be sited before any aerial pre-amp. In common with all the other filters in the AKD range the HPF6 requires no external power and

is simply fitted in line with the aerial co-ax with its standard terminations. Technical Details:—

Pass Band:— Frequency range 470-895MHz Stop Band:— (inner only) DC-450MHz typical >75db @ 300MHz >30db @ 435MHz Input & Output Impedance:— 75 ohms nominal

Case Material: — Aluminium

Case Size: - 122×40×25mm (excl socket, flylead & plug)

Terminations:— Standard Belling Lee type aerial co-ax plug and socket

£17.00 each

Unifilter 'CLAMP-ON' RADIO-FREQUENCY CHOKE

PHONE OR SAE FOR PRODUCT SPECIFICATION & APPLICATION NOTES





Allows leads to be torroidially protected without the need to cut or remove plugs or connectors. Ideally suited for moulded plugs, leads, ribbon, and large diameter cables. Can easily be fitted and stacked in multiples to increase rejection. 'UNIFILITER' works by suppressing the interference currents that flow along the *outside* of cables without affecting the signals or power flowing inside. This means that you don't need to worry about upsetting normal operation or invalidating guarantees. Suitable for both reducing the emission of, or rejecting the effect of, common mode interference as experienced on computer, hi-fi & speaker leads, as well as the normal mans & aerial cables.

UF 4 KIT (SUITABLE FOR SMALLER INSTALLATIONS) £9.89

UF 8 KIT (FOR MULTI INSTALLATIONS) £19.55




ALL PRODUCTS ARE AVAILABLE FROM US DIRECT MAIL ORDER OR WHY NOT MAKE USE OF OUR ACCESS & VISA FACILITIES TO ENSURE MINIMUM DELAY

ALL AKD PRODUCTS CARRY THE USUAL AKD 2 YEAR GUARANTEE. PRICES QUOTED ARE CORRECT AT TIME OF GOING TO PRESS AND INCLUDE VAT, POSTAGE & PACKING

TRADE ENQUIRIES WELCOME TRADE ORDERS CAN NOW BE PLACED BY FAX ON 0438 357591

Props: RT & VEL Wagstaffe. Technical Adviser: John Armstrong

COM



IC-32E Dual Band VHF/UHF FM handportable

Features:

(COM

DUAL BAND TRANSCEIVER IC-32E

- Full cross band duplex operation.
- 20 Dual band memories. Small size.
- - Scanning. Power saver circuit.
- Compatible with ICOM accessories.

When are ICOM going to produce a dual band handportable? This has been the most asked question about new ICOM products for a long time. The IC-32E is the answer.

This exciting new handportable offers full cross-band duplex operation, and with a built-in duplexer allows single antenna operation. 3 Watt output is standard but with the BP7 high power nicad pack or external 13.8v, 5 Watts can be achieved on both bands. The IC-32E comes packed with features, such as the 20 memory channels which can store both a VHF and UHF frequency in one memory and also simplex duplex condition, offset direction and frequency.

There is a choice of five scanning functions, full programmed memory, memory band and priority. The die-cast frame gives a solid construction featuring rubber gaskets for splashproof operation. The IC-32E is supplied with VHF/UHF a dual band antenna, BP3 battery pack and wall charger.


Jcom (UK) Ltd.

Dept PW, Sea Street, Herne Bay, Kent CT6 8LD. Tel: 0227 363859. 24 Hour.

5 Watt output with IC-BP7 nicad.

Count on us!

NEW! IC-3210E Dual Band FM Mobile



If you are newly licensed or just undecided about which band to operate first, then the new ICOM IC-3210 is just the answer. This dual band FM transceiver is ideally suited for the mobile operator. Transmit on one frequency and receive on the other and you're operating full duplex. It's just like talking on the telephone.

The simple and well laid-out front panel ensures quick and easy operation of all its many functions. A great convenience when driving. Optional accessories available are the UT40 tone squelch board. HS15 + SB mobile microphone and switch box SP8 external speaker and PS45 AC power supply.

Features:

- Full crossband duplex.
- 20 double-spaced memory channels.
- Built-in duplexer.
- 2 call channels.
- 4 priority watch functions.
- Programmed, memory and selected band memory scan.
- Variable LCD backlight intensity.
- Tone squelch and pocket beep functions (optional).
- 25 watts output.

Helpline: Telephone us free-of-charge on 0800 521145, Mon-Fri 09.00-13.00 and 14.00-17.30. This service is strictly for obtaining information about or ordering Icom equipment. We regret this cannot be used by dealers or for repair enquiries and parts orders, thank you.

Datapost: Despatch on same day whenever possible.

Access & Barclaycard: Telephone orders taken by our mail order dept, instant credit & interest-free H.P.





South Midland

SCHOOL CLOSE, CHANDLERS FORD IND. EST., EAST

The Communicators **BRANCHES WITH SERVICE FACILITIES**

BIRMINGHAM (021 327) 1497/6313

LEEDS (0532) 350606

FANTASTIC PERFORMANCE, FANTASTIC PRICE



The FT-747GX is a compact SSB/CW/Am and (optionally) FM transceiver providing 100 watts of PEP output on all hf amateur bands, and general coverage reception continuously from 100kHz to 30MHz. A front panel mounted loudspeaker and clear, unobstructed display and control layout make this set a real joy to use. Convenient features include operator selectable coarse and fine tuning steps optimized for each mode, dual (A/B) vfos, along with twenty memory channels which store mode and skip-scan status for auto resume scanning of selectable memories. Eighteen of the memories can also store independent transmit and receive frequencies for easy recall of split-frequency operations. Wideband (6kHz) AM and narrowband (500Hz) CW IF filters are included as standard, along with a clarifier, switchable 20dB receiver attenuator and noise blanker. User programming for more advanced control by an external computer is possible through the CAT (Computer Aided Transceiver) System. The transmitter power amplifier is enclosed in its own diecast aluminum heat-sink chamber inside the transceiver, with forced-air cooling by an internal fan allowing full power FM and packet, RTTY, SSTV and AMTOR operation when used with a heavy duty power supply.

MD-1B8 Base Mic	279.00
MMB38 Mobile Mount	£22.00
D3000568 FM unit	£39.99
FP700 Standard P.S.U	£195.50

MH-1B8 Hand Mic	£21.00
FIF232C Interface	£75.00
FC757AT Automatic ATU	£349.00
FAS14R Remote Ant. SW	280.00
D2000E60 TYCO Unit	C28 05

★ 160-10M HF TRANSCEIVER

★ GENERAL COVERAGE RECEIVER

★ ALL MODE (FM OPTIONAL)

★ 0-100W OUTPUT (25W AM CARR.)

★ CW NARROW (500Hz) STANDARD

★ LARGE CLEAR LCD DISPLAY

★ SIMPLE OPERATION (see pic below)



All major controls are grouped together for convenience and ease of operation.

FRB757 Relay Box	£10.50
FP757HD Heavy Duty P.	S.U.£239.00
FL7000 500W P.E.P. Lin	
SP767 Ext. Spkr	£69.95

FT747GX TRANSCEIVER RRP £659.00 inc VAT

Serious about VHF/UHF? Then the FT736R is for YOU!



- ★ Up to four band capability
 ★ LSB/USB, CW & FM
- ★ Full Duplex crossband operation
- ★ Memory storage of up to 230 frequencies
- Keypad frequency entry
- ★ Fourteen VFO's
- Global call channel
- ★ Programmable channel steps
- Electronic keyer option
- Remote preamplifier switching
- TXCO high stability reference oscillator

OPTIONAL ACCESSORIES

FEX 736/50 FEX 736/1.2 FMP-1 FTS-8 FVS-1 D3000535 D3000534

50MHz module 1.2GHz module AQS Message Processor c/w display CTCSS Tone Squelch Unit Voice Synthesiser Unit Internal lambic Keyer Unit Fast Scan TV (ATV) Mod/Demod Unit

£239.00 £425.00 SP767 MD-188 £189.00 MH-1B8 £45.00 £33.00 FIF232Cvan £15.95 FIF232C

600Hz Filter External Spkr c/w Audio Filters £69.95 Desktop Microphone 679 NO Hand Scanning Microphone CAT/INC Interface for Packet & CAT £21.00 £68.95 CAT Interface for RS232 O/P £75.00 CAT Interface for Apple II series

FT736R R.R.P. £1450.00 C/W 2M & 70cms.

LEEDS SMC (Northern) Nowell Lane Industrial Estate Leeds LS9 6JE Leeds (0532) 350606 9-5.30 Mon-Sat CHESTERFIELD SMC (Midlands) 102 High Street New Whittingtor Chesterfield Chest (0246) 453340

SMC (TMP) Unit 27, Pinfold Lane Buckley, Clwyd Buckley (0244) 549563 10-5 Tues, Weds, Fri 10-4 Sat

SMC (Jersey) 1 Belmont Gardens St. Helier, Jersey Jersey (0534) 77067 9-5 pm Mon-Sat Closed Wed

IRELAND SMC N. Ireland 10 Ward Avenue County Down 0247 271875

BIRMINGHAM SMC (Birmingham) 504 Alum Rock Road Alum Rock Birmingham B8 3HX (021-327) 1497/6313 AXMINSTER Reg Ward & Co Ltd 1 Western Parade West Street, Axminster Axminster Devon EX13 5NY Axminster (0297) 34918 9-5.30 Tues-Sat



Southampton Showroom open 9.00-5.00 Monday to Friday, 9.00-1.00 Saturday, Service Dept open Mon-Fri 9.00-5.00.

AGENTS: JOHN DOYLE, TRANSWORLD COMMS, NEATH (0639) 52374 DAY (0639) 2942 EVE

DAVID STENNING, G4JA, LOUTH 0507 604967, (024024) 4378 EVE.

munications Ltd. YAESU

EIGH, HANTS, SO5 3BY TEL: 0703 255111 FAX: 0703 263507 TLX: 477351

CHESTERFIELD (0246) 453340

AXMINSTER (0297) 34918



from COMET & HOKUSHIN

SMC are proud to present 1 new mobile and three new base station antennas incorporating the very latest in aerial technology to give outstanding durability whilst maintaining excellent performance characteristics.

WX1
VHF/UHF Base
144/432 MHz
4.5/7.2dB Gain
200W Max
£49.95

727VM

70N2DX

CA2X4 MAX VHF/UHF Base 144/432 MHz 8.5/11.9db Gain 200W Max £99.95

£30 88

£37.75

CA2X4 KG VHF/UHF Mobile 144/432 MHz 6.0/8.4db 120W Max £39.95

Also still available the two best selling amateur antennas, the ubiquitous 78F 2m 7/8 wave £21.15 and the GP144W 2m base £42.00

CURRENT STOCKS ALSO INCLUDE THE FOLLOWING: 2m/70cms fold over

2m/70cms fold over

2m/70cms fold over

		BAS	SE /	ANT	E
	de .	ABC	223		
		GP2	23		
		GP\	/14	4DX	(
	и.	GP\	155		
		GP4			
		GP7			
and the		358			
100	_	HS9		17	
	ă.	поз	100	٧	
		_	_	_	

ANTENNAS 2m 3 × 5/8 2m 3 × 5/8 2m 2 × 5/8 S/Steel 2m 2 × 5/8 H/Duty 70cms 3 × 5/8 70cms 70cms 3 × 5/8 G/F 60-905MHz

£63.97 £45.00 £53.13 £45.50 €47.50 £88.20 £57.75 £57 75

MOBILE ANTENNAS

2QW 2NF 2m 5/8 wave fold over £13.25 2SE 2m 5/8 wave fixed £13.25 2VF 2m 1/2 wave fold over £16.13 2m $\frac{7}{8}$ wave ball mount £15.00 2m $\frac{8}{8}$ wave £24.10 70cms 2 \times 5% fold over £29.37 78R 88F 268F 632 80 70cms 70cms 3 × 5/8 fold over £33.73



POLARPHASER



Have you ever wanted to control the polarisation of your xy crossed Yagi from RH-LH, CIRCULAR, VERTICAL or HORIZONTAL, even whilst transmitting? Then this revolutionary product is what you thave been waiting too! this revolutionary product is what you have been waiting for!
The SMC POLARPHASER enables you to alter the

The SMC POLARPHASER enables you to after the polarisation of your aerals continuously through the full 360°. For satellite users the benefits to be obtained from instantaneous shack control of polarisation are obvious, enabling effective utilization of receive capabilities and power resources along with the ability to reduce or even totally eliminate co-channel interference for terrestial use.

VSWR Frequency Power Connectors 2 metre less than 1-5:1. 144-146MHz. 150 Watts SO239 or 'N' (please specify).

70cms less than 1.3:1 430-440 MHz 100 watts 'N' type

£49.00 inc VAT (SO239) £69.00 inc VAT £54.00 inc VAT ('N') P&P £2.25

UK Patent No. 2157894A. Manufactured by S.M.C. Design by G2HCG

P.S.U.'s

DUAL BAND MOBILE

NEW FROM



The Communicators



A range of 12VDC power supplies to suit all needs. Specially manufactured to the highest quality using only the best in components and materials. With a choice of either 4, 8 or 2SA continuous output (6, 10 & 35A surge handling) these P.S.U.'s are built to the stand the rigours of everyday operation. Both the 8 and 25A units are fitted with overvoltage protection.

All the above power supplies are keenly priced and are available from all leading retail outlets. Carriage

3A £19.95 inc VAT only £2.50 84 £59.95 inc VAT only £3.50 only £175.00 inc VAT 25A

ROTATORS



engineering standards combined with pin sharp setting means accuracy technology from the rotator company

SMC

£38.50 £78.00 £155.00 £169.00 £219.00 £327.00 £449.00 £325.00 £325.00 £345.00 £445.00

£149.95

AR200XL G-250 AR40 AR40 G-400RC CD45 G-600RC HAM IV T2X HDR300 G-800SDX G-1000SDX G-2000 KR500 KR5400 KR5400A

ROTATORS
Offset type Twist/Switch control
Bell type, Twist/Switch control
Bell type, Twist/Switch control
Bell type, 360 deg, meter
Bell type, meter readout
Bell type, 360 deg, meter
Bell type, meter readout
Bell type, meter readout
Bell type, meter readout
Bell type, poigtal readout
Bell type, 450 deg, var. spd
Bell type, 450 deg, var. spd
Bell type Meter ± 90 deg,
Azimuth/Elev. Dual control Azimuth/Elev. Dual control Azimuth/Elev. Computer cont

ROTATOR HARDWARE

Support bearing Chan. Master Support bearing FU200 etc. Rotary bearing Guy type Rotary bearing 1.5%" mast Rotary bearing 2" mast Lower mast clamp G-400/600 9523 9523/FU200 9525 KS050

£19.95 £21.95 £19.95 £19.95

£0.72

ROTARY CONTROL CABEL

RC5W RC6W

DNTROL CABEL
Sway for G-400RC etc. perimtr
6 way for G-250/400 etc. perimtr
8 way for CD45 etc perimtr
Free carriage on all rotators.
Prices are inclusive of VAT.
Carriage on Rotator Hardware
Carriage on Rotator Cable

GUARANTEE

Importer warranty on Yaesu Musen products Ably staffed and equipped Service Department Daily contact with the Yaesu Musen factory. Tens of thousands of spares and test equipment.
Twenty-five years of professional experience.

Free Interlink delivery on major equipment.

Small items, Plugs, Sockets, etc. by post £1.75. Antennas, Cables, Wire & larger items. Lynx up to £5.00. Interlink delivery available, upon request, for items other than radios, from £7.30 depending on weight. Same day despatch whenever possible

PRICES & AVAILABILITY SUBJECT TO CHANGE WITHOUT PRIOR NOTICE

FREE FINANCE .

On many regular priced items SMC offers.
Free finance (on invoice balances over \$120) 20% down and the balance over a months or 50% down and the balance over a year.
Details of eligible items available on request.

You pay no more than the RRP price!



ALL MAKES OF EQUIPMENT STOCKED **BEST PRICES — FRIENDLY SERVICE**

SONY AIR-7 HAND-HELD AM/FM 108-176MHz + LW/MW/FM UNBEATABLE VALUE

The best VHF monitor there is. That's a fact! 108-176MHz plus LW/MWFM broadcast. Covers air, marine, PMR etc. LCD display, memories, scanning, lockout priority etc. Supplies are short but we are the UK's largest stockist, so check with us!



PRICE

SONY ICE7600DS PORTABLE COMMUNICATIONS

Not a toy, but a serious communications receiver. 150kHz-30MHz AM/SSB plus FM76-108MHz. Digital readout, memories, clock and provision for external antenna. Listen to the DX at work! Mains or battery.





£157 FREE SECURICOR

VHF/UHF AIRBAND MONITOR



SIGNAL R535 £249 Carr. Free

This latest receiver covers both civil and military bands. Coverage is 108-143MHz & 220-380MHz AM. Featuring a 60 channel memory, the receiver will enable you to monitor virtually any air traffic. The 12 volt requirement makes it ideal for base, mobile or portable work.

SONY ICF2001D RECEIVER SUPER PORTABLE AM/SSB/CW + AIR BAND COVERAGE

Described as "the best portable on Described as "the best portable on the market" by a recent reviewer, it covers 150kHz-300MHz AM:SSC/CW plus AM VHF air band and FM broadcast. Memories scanning, etc. are all included. The SSB performance is superb and can match many base station receivers. 230/110v AC power supply included.



£299 FREE SECURICOR


OTHER SONY PRODUCTS

	T-070 T-0
ICF7600DA Analogue SW receiver	£129.00
ICF-SW1S Micro short-wave receiver	£249.00
ICF-PRO80 SW/VHF receiver	£299.00
AN1 Active SW antenna	£49.00
AN3 Vertical for Air-7 receiver	£45.00
BP23 Ni-cad battery pack	£15.95
ACD4 Mains PSU/charger	£15.95
DCC127A 12v car PSU	£19.95

All our Sony stocks carry UK cards and do not have serial numbers etc. removed from boxes!

GLOBAL AT1000 AERIAL TUNER

The AT100 is a receiver aerial tuner designed to give you maximum performance from your receiver. Covering



the frequency range 150kHz to 30MHz it matches all the modern receivers produced in recent years. Ideal for matching long wire, dipoles or balanced leeder.

£69.00 POST FREE

R537S AIR-**BAND MONITOR** 118-136MHz

This well known receiver is ideal for the senious air-band enthusiast, superb sensitivity and selectivity, this pocket size monitor is unrivaled in value for money. 2 fixed channels are possible and the squelch control ensures silent background. Complete with battery and whip.



£69.50 CARR FREE

THIS MONTH'S OFFER A Complete HF Station



OFFER ENDS 8th OCTOBER

£759

This month we are offering a complete HF station comprising FT747 and 30 amp AC PSU for a bargain price. With most rigs costing over £1.000 its nice to offer something a bit more realistic in price! Features include 100 watts output on all bands, Rx from 100kHz to 30MHz. 20 memories, dual vto swide and narrow cw filters, digital display, LSB/USB/CW/AM with squelch plus FM option. We have found it to be excellent and can thoroughly recommend it. The matching power supply is generously rated and fitted with thermal fan and full protection.

SCANNING AERIALS

Better than any pre-amp



15dB Gain

CLP 5130 Beam

Illustrated above, this beam antenna covers 105-1300MHz. A forward gain of up to 13dB and a front to back ratio of 15dB provides the means of dramatically improving reception. With a VSWR better than 2.1 it can also be used for transmission up to 500 watts. Boom 6', longest EL,6'.

£89.00 plus post £3.00 CLP 5130 50MHz-1300MHz version in stock £179.00 + £7.00 carriage

D130N Discone

The D130 antenna is the leader in discones and used by military and research establishments. What better recommendation! Covering 25-1300MHz with low VSWR, it is supplied complete with 50 ft of ultra low loss cable and N plugs. £82.50 plus post £3.00

NEW MINI-DIPOLE KIT LF-8040 £29.95

A new low priced hf antenna that will fit into most gardens. The kit is complete with wire and provides a coaxial fed dipole that needs no atu. It covers 80 & 40 metres and has a total length of 70ft. Just follow the instructions and plug your coax feeder into the SO239 socket, and you are ready to go. £29.95 plus £1.50 post.

The new X500 from Diamond gives almost 9dB & 12dB gain on 2m/70cm, Height is 5.2m in white fibre glass with "N" socket. Cheaper than

a linear! Just think, 25w on 2m = 200w erp and 400w on 70cm! Now you can really make

X500 "DOMINATOR" 2M/70cm

nurself heard!

П

BOOKS SPECIALLY FOR YOU!

NEW 1988 EDITION

COMPLETE VHF/UHF FREQUENCY GUIDE 26-2250MHz £5.95 + £1.00 p&p

AIRBAND FREQUENCY GUIDE

The new edition of this famous guide will be available at end of August. Now running to 100 pages, it is crammed with gen that is essential reading for the airband enthusiast. Lots of editorial and pictures plus new cross reference of frequencies in alphabetical and supposed pages. Order Order verse server server today. numerical order. Order your copy today.

Price £5.95 +£1 P&P

NEW 1988 EDITION

UK LISTENERS CONFIDENTIAL FREQUENCY LIST 1.6-30MHz £6.95 + £1.00 p&p FIFTH EDITION



£129 + £3 carr.

RECEIVERS (Free delivery)

R5000 Short Wave 150kHz-30MHz	£875.00
R2000 Short Wave 150kHz-30MHz	£595.00
VC20 VHF conv. for R5000	£167.00
VC10 VHF conv. for R2000	£161.95
FRG8800 150kHz-30MHz	£639.00
FRV8800 VHF converter	£100.00
IC-R71 Short wave 150kHz-30MHz	£825.00
Sony 7600DS Short wave	£159.00
Sony ICF2001D band Short wave + air band	£299.00
Lowe HF125 Short wave	£375.00
FRG9600 Scanner 60-950MHz	£509.00
IC-R7000 Scanner 25-2000MHz	£957.00
AOR 2002 Scanner 25-1300MHz	£475.00
Sony Air-7 VHF scanner	£227.00
Sony Pro-80 VHF + SW scanner	£299.00
R537S Air band monitor	£69.50
R535 Air band scanner	£249.00
R528 Air band xtal scanner	£125.00
WIN 008 Air band scanner	£175.00

Completely revised and updated, this publication is one that should be on every enthusiast's bookshelf. The previous edition sold 6000 copies in 18 months. This latest issue is 25% larger and has been completely re-written with a new easy-to-read layout. No other publication offers you so much information for such low cost. It provides complete details of all the services in the UK that make use of the VHF/UHF spectrum with listings from 26 to 2250MHz without gaps, and additional listings to 56GHz. Each section begins with full details of the services that use each segment of the spectrum followed by details of individual services in frequency order. Users covered include the emergency services, marine, aeronautical, land mobile etc. Many of these services use duplex frequencies and full details of the splits are included for base and mobiles. Although many of the frequencies listed cannot be monitored without a licence, all listenders should find this book a mine of information. Tremendous value!

This famous listing is now in its fifth edition. Completely updated for 1988 and a lot thicker. Many additional frequencies have been added and of course some have been defled where the service is known to no longer exist. Packed full of information on all that happens between 1.6 and 30MHz, you will find this fascinating reading. Covering all aspects of the shortwave service, here is just a selection of the listings included: AVIATION, BROADCAST, MARINE, EMBASSY. MILITARY, RTTY, FAX, PRESS, and much more. Not only frequencies and stations, but in many cases times of transmissions as well. This is not an American import, but a UK printed manual specially for UK listeners. If you are one of the lew people that haven't purchased one of these yet, then you really don't know what you have been missing. If on the other hand you have our previous editions, we know that you will want to get the latest edition. Available end of March, Order your copy today.

HF Transceivers

£1995.00 £1695.00 Kenwood TS940S Kenwood TS930S £1129.00 Kenwood TS140S Yaesu FT757GX11 Yaesu FT767GX Yaesu FT747GX £859.00 £959.00 £1550.00 £659.00 Icom IC735 Icom IC751A £939.00

2M Transceivers Kenwood TH21E Kenwood TR751E

£189.00 £599.00

Kenwood TS711E Kenwood TS711E Kenwood TH205E Kenwood TH215E Kenwood TH25E Yaesu FT290 MK11 Yaesu FT290 MK11 Yaesu FT29R + Par Icom IC2E Icom IC2E Icom IC2E Icom IC275E Icom IC270E Icom IC3200E Icom IC Micro 70cm Transceivers £898.00 £215.26 £252.00 £258.00 £429.00 £255.00 £225.00 £269.00 £359.00 £1039.00 £556.00 £239.00

£218.00

Kenwood TS811E Kenwood TH405E Kenwood TH415E Icom IC4E

Station Accessories Station Accesson Adonis AM 303G Mic Adonis AM 303G Mic Adonis FX8 Dash mic Sagant superod 2m Sagant subby 2m ant P300 30amp PSU Revex MS1 Monitor Airband Mag antenna

£273.00 £298.00

€49.95 £49.95 £65.95 £96.00 £69.00 £12.95 £9.95 £149.00 £249.00 £29.00


HP4A TVI Braid Breaker HP4A TVI Braid Breaker
HK708 Morse key
G5RV Ant. complete
New Diamond VSWR Meters:
SX200 18-8200MHz
SX400 140-825MHz
SX600 1.8-525MHz
Carriage: Free on orders over £100.
Under £100 add £2.50 for larger parcels & £1.00 for small packages

POCKET GUIDE TO FAX & RTTY STATION FREQUENCIES £2.95 + 90p Available now.

ALINCO SAVES YOU MONEY & SERVES YOU WELL

- * 144-146MHz (Rx. option 140-170MHz)
- * 25 watts output. ("HE" model 45 watts)
- * 21 memories & 2 "call" channels.
- * Programmable Scanning & Priority channel
- * 12.5kHz & 25kHz steps.
- * Includes microphone & mobile mount.
- ★ Bright LCD display
- * Reverse repeater etc.

Designed for optimum performance combined with small size, the ALINCO ALR-22E reaches new heights in both technical performance and value for money. We've managed to keep the price down to a level that cannot be matched by any other manufacturer



- * 2M FM 144-146MHz
- * RX 140-170MHz!
- * 3 Watts output
- * Battery Saver
- ★ 10 memories
- * LCD Readout
- * S-meter
- * Tone Burst
- * Priority
- * 12.5KHz steps
- * 12v DC operation!

Another winner from ALINCO. A true handy transceiver with no extras to buy! Unlike its competitors, you get the nicad pack (500mAH) AC charger, and provisions for direct 12v DC charge. Measuring $168 \times 61 \times 30$ mm it's a beauty! Optional accessories include speakermic, mobile bracket and high power packs. Get the facts today!





2m FM Mobile ALR-22E

- ★ 2m/70cm. Full duplex operation.
- * 25 watts FM on both bands.
- ★ Single antenna socket output.
- * 21 memories & 2 "call channels".
- ★ Programmable scanning and priority.
- * 12.5KHz & 25KHz steps.
- * Includes all hardware & microphone.
- * Bright LCD readout.
- * Reverse repeater operation.
- * 12 months warranty parts & labour.

OTHER ALINCO ITEMS

ALR22HE 50 watt	299.00
ALR72E 70cm mobile	299.00
MM1 mobile mounts	10.9
ALX2E 2m h'held	189.00
EBP3N Batt pack	28.9
EBP2N Batt pack	
EDH10 DC to DC	
ESC5 Case and clip	15.50
EDC2 Cigar charge cable	
ELH230D11 30w Amp	75.00
ELH260D 50w Amp	119.00
DC1 DC leads for mobiles	5.9
DC2 DC lead for amps	4.50

NEW DUAL BAND HANDHELD!

The new ALINCO DJ-500E will shortly be available covering 2m & 70cm with full duplex. Features include 10 memories on each band and programmable offsets. Receive frequency can be extended from 130-169 & 420-469MHz approx. Measuring 58 × 176 × 30 mm it is pretty compact. As usual all the standard accessories are supplied at the basic price. Watch for our super opening price!

ALINCO DJ-500E 2M/70 cm

- ★ 2m/70cm Coverage
- * Full duplex
- * Extended Rx ranges
- * Programmable Memo
- * Scanning
- * Keyboard Entry
- **★** Compact size
- * No extras
- * Price? T.B.A.





RETAIL & MAIL ORDER: - 18-20, Main Road, Hockley, Essex SS5.4QS.

Tel: (0702) 206835, 204965

RETAIL ONLY:- 12, North Street, Hornchurch, Essex RM11 1QX.

Tel: (04024) 44765

Visa and Access by telephone. 24hr. Answerphone.



SONY



KENWOOD

Kenwood RZ1 150kHz, 950MHz	£399
Kenwood TS140	0083
Kenwood TR721	€649
Kenwood R5000	£799
Black Jaguar	£199
CTE 1600 2 Meter	£169

191 FRANCIS ROAD LEYTON · E10 6NQ · LONDON

TELEX 8953609 LEXTON G PHONE 01-558 0854 01-556 1415 FAX 01-558 1298

DRESSLER ACTIVE ANTENNAS



ARA 30 ACTIVE ANTENNA

50 kHz . . . 40 MHz WITH LIMITED PERFORMANCE UP TO 100MHz

Professional electronic circuitry with very wide dynamic range. Meets professional demands both in electronics and mechanical ruggedness. 1.2m long glass fiber rod. Circuit is built into waterproof 2.5 mm thick aluminium tube. Ideal for commercial and swh-receiving systems. \$129. See Review in August 1985 Issue p.35

Both antennas come complete with 7 metres of cable, interface, power supply and brackets.

OPEN MON - SAT 9AM - 5.30PM INTEREST FREE HP FACILITIES AVAILABLE PROMPT MAIL ORDER ON MANY ITEMS







ICOM





FIRST CLASS SHORT WAVE RE-CEIVER. BUY THIS FOR £825 AND RECEIVE AN ARA 30 FREE. WORTH

Also R7000 complete with ARA900

PHONE FOR BEST PRICE

ICOM IC32G ICOM IC2GE ICOM IC228

All ICOM models available. + YAESU Accessories.

YAESU

FRG 8800 £575 FRV 8800 £95 FR767 + 2MTR £1550 FT23 + FNB108 Charger £259



ELECTRONICS LIMITED

Clayton Wood Close West Park Leeds LS16 60E Tel: 0532 744822

For products you can rely upon to give amazing results

For information on **Active Antennas**, **RF Amplifiers**, **Converters**. Audio Filters, the Morse Tutor and Speech Processors

send or telephone for a free catalogue and selective data sheets as required.

All our products are designed and made in Britain. Orders can be despatched within 48 hours subject to availability.





REALISTIC®

PROGRAMMABLE SCANNING RECEIVERS



THE BEST CHOICE FOR YOUR HOME OR CAR

A Realistic PRO-2004. The ultimate in today's solid-state high-technology scanners! Delivers a wide range of frequencies not found on most scanners. Search mode finds new channels, selectable scan and search speeds, two-second scan delay. Lock-out key for temporarily bypassing channels. Squelch control and priority function. Continues tuning from 25-520 MHz and 760-1300 MHz. 300 channels for storing frequencies. Large LCD channel/frequency display with electroluminescent back lighting, built-in speaker, telescoping aerial. Jacks for external aerial, headphone, external speaker, tape record and DC power supply. Measures: 23/16 x 10¹¹/16 x 8¹¹/16". Mains operation (or 13.8 VDC neg. gnd. power cord, extra). Memory back-up requires 9v battery. 20-9119

B Realistic PRO-2021. Features direct keyboard entry, search and scan in two speeds and two-second scan delay. Priority function will automatically switch to the priority channel when a call is received on it and individual lock-outs for temporarily bypassing channels. Scan up to 200 channels in these bands: VHF Lo 68-88 MHz, VHF AIR 108-136 Mhz, VHF Hi 138-174 MHz, UHF Lo 380-470 MHz and UHF Hi 470-512 MHz. Easy-to-read LCD channel/frequency display electroluminescent back-lighting, squelch control and built-in speaker, telescoping aerial. Jacks for external speaker, external aerial, tape recorder and DC power supply. Size: 31/8 x 101/4 x 8". Includes mounting bracket for mobile use and DC power cord. Mains operation (or 13.8 VDC neg. gnd.). Memory back-up requires 9v battery. 20-9113 £199.95



Over 400 Stores And Dealers Nationwide

Prices may vary at Dealers. Offers subject to availability.

Tandy, Tandy Centre, Leamore Lane, Bloxwich, Walsall, West Midlands. WS2 7PS

RAE Confusion

Heads very swollen at this end, in fact we shall probably have to alter all our doors to the Moorish style to allow my free passage through them. Reason—I am through the RAE!

The certificate arrived last week; two credits are mentioned all of which is in part due to the PW publication Passport to Amateur Radio. I think this is "A1", and as far as I am concerned is "essential reading" for any future candidate.

There seems to be a bit of confusion this year. Pink Pass Slips are definitely no longer issued. Instead two certificates are issued, one being a "you are through" certificate and the other tells just "how well you have done". As I had no Pink



Pass Slip my application for an Amateur Licence was returned by the Radio Amateur Licensing Unit at Chetwynd House, Chesterfield. However, after a few phone calls I found out that the City and Guilds had not told Chetwynd House of the change of the art. Just how daft can you get? Chetwynd House need your "how well you have done" certificate in place of the hitherto Pink Pass Slip.

I feel that some mention of this fact in *PW* would not only help the next batch of would-be amateurs (Christmas is not that far off), but would also earn the appreciation of Chetwynd House who are, at the moment, doing their best to cope with a situation which is not of their doing.

N. S. Hemingway, Rochdale, Lancs.

We have had reports from several quarters on this problem, which was apparently due to some sort of brainstorm in the corridors of power at CGLI. We understand that the DTI, RSGB and RALU knew nothing of the change until the new paperwork began to arrive with licence applications at Chetwynd House.—Ed.

No Waiting in Nottingham!

In the penultimate paragraph of his letter ''Waiting'' in August *PW*, Mr Hawkings has a good point, though not quite accurate! As the college in the Nottingham conurbation which is the major supplier of Amateur Radio Courses, we have to plead guilty to failing to provide non-examination courses for the s.w.l. If Mr Hawkings could tell us where the bodies are we will be only too pleased to provide the facilities for him to run a course for us, as it is evident that he is no beginner. Indeed, his experience from the 1950s would be invaluable. He is not quite accurate in that there are no non-vocational courses, as we run a Constructors' course and have also attempted to run

PW COMMENT

Good Law-Bad Law

IN MY LEADER IN THE MAY ISSUE OF PWI talked about the problems being experienced in magazine publishing because of the way that readers use today's advanced photocopying technology, to make unauthorised copies of interesting articles for friends and workmates.

One American hobby magazine, not in the radio field but in model engineering, closed recently with an announcement in its final issue that this was largely due to the loss in sales which had resulted from readers photocopying articles for other hobbyists to use rather than buying their own copy of the magazine.

Similar problems exist in video recordings, where viewers make copies of hired videos to keep for themselves, or tape TV films either for "time-shifting"—to view at a more convenient time than the original broadcast—or to keep for their own collection.

Legislation currently under discussion in the UK, to improve protection for the rights of copyright holders, contained a proposal that video copies made by individuals must be wiped after 28 days. The idea—attractive on the face of it—was that "time-shifting" is alright, but making your own copies of commercial films or videos was to be stopped.

In fact the idea is laughable. Unless, of course, rented videos and TV films could be coded in some magical way, so as to cause the copy video to self-destruct in 28 days. Say! Wouldn't that be a great theme for a TV series!

I am glad to say that common sense won through, and our legislators decided that since there was no possible way that such a 28-day law could be enforced, they may as well drop the idea.

As I've remarked before, no matter how good the idea behind it, law that cannot be enforced is bad law. It invites defiance, and that defiance will soon spread. The present UK law on listening to the radio, as enshrined in the Wireless Telegraphy Acts, is bad law. It says that you may listen to authorised broadcasting stations and to licensed amateur stations, but not to any other sort of station unless you have a particular licence or permit for the radio service concerned.

Now unless you do something really stupid, it is very, very unlikely that you will get found out even if you do listen to other sorts of stations. It would need something of the organisation

of a police state, with informers and roving inspectors, in order to enforce such a law.

One way of getting found out is, of course, to make use of information which you gain by listening to those "naughty" stations. Breakdown trucks which are first on the scene of a road accident because they've been monitoring the police, fire or ambulance channels, for example.

Surely it would make more sense to scrap the present listening provisions of the Wireless Telegraphy Acts and replace them by a law which prohibits you from making use of what you might hear. Such law already exists in some other countries, and it could be coming here, too. There have been several broad hints recently from the Radio Regulatory Department of the Department of Trade and Industry, that we may see just such a change announced this year. We'll keep you posted

I doubt, though, that there will be any change to the provisions of the Interception of Communications Act 1985, which make it an offence to intentionally intercept communications on a public telecommunication system, which for the radio listener means the radio links of any public telephone or telegraph system (e.g. cellular, cordless or radio telephones). The penalty can be up to two years in prison and/or a £2000 fine.

* * *

I'm afraid we've once again come round to the time of year when we must increase our cover price—it's risen to £1.30 this month, as no doubt you've noticed. You've probably also noticed that some of our competitors have recently applied much larger price rises, which must make PW even better value for money by comparison—more pages for less money!

To try to cushion the blow, we're holding our present subscription rates for a further month. If you wish to take advantage of this offer, you have until 8 October 1988 to send in your subscription application or renewal if you are in the UK, or until 31 October 1988 if you are overseas. See page 28.

We're also having to revise some of the charges for our mail order services, to keep up with rising costs. For details see "Our Services" and our individual mail order service advertisements.

Geoff Arnold

an "After the RAE" course-without any success over the last three years.

For your information I enclose a listing of the amateur radio courses being offered by the College in the session 1988/89. See 'News Desk'' pages.-

On the subject of Novice/Student licences, where are all the rumours coming from? RSGB deny all knowledge of any proposals! Yet there are documents circulating with suggestions for band allocations and even specimen questions. If these are serious specimen questions then I have the suspicion that with VERY little extra effort the third class recipient of a free-for in effect that is what it will be-handout from the licensing authorities, could obtain a proper licence.

As an RAE tutor over a number of years I know that an individual willing to put some work into their studies is in with an excellent chance. The problem nowadays is not the radio part of the RAE but that

many students do not have sufficient command of the English language to decipher the questions; C & G please notel


This vociferous minuscule minority who are prepared to give anybody anything are, in my opinion, on a hiding to nothing for, as a professional educator, I find that youngsters nowadays are not interested in anything, cannot communicate their thoughts. and are positively turned off by the thought of that good old Anglo-Saxon four-letter word WORK. I shall await with interest the flood of youngsters into our hobby

R. G. Wilson G4NZU Senior Lecturer i/c Radio Courses. Arnold & Carlton College of Further Education, Nottingham

There certainly seems to be continued confusion as to just what stage the Novice/ Student Licence proposal has reached, with denials, leaks and rumours abounding. If there is no official announcement soon, the whole idea is in danger of descending into farce.—Ed.

Send your letter to the Editorial Offices in Poole, the address is on our Contents page. Writer of the Star Letter each month will receive a voucher worth £10, to spend on items from our PCB or Book Services, or on PW back numbers, binders, reprints or computer program cassettes. And there's a £5 voucher for every other letter published.

Letters must be original, and not duplicated to other magazines. We reserve the right to edit or shorten any letter. Brief letters may be filed via our Prestel Mailbox number 2026/1191. The views expressed in letters are not necessarily those of Practical Wireless.



Broadcast Quality

I live about twenty miles as the wave wiggles from Droitwich. This means that there is a strong BBC signal on long and medium wave averaging about 750mV peak-to-peak from the antenna

At this level, it is possible to get loudspeaker reception off a crystal set, in fact my 1926 Brownie No. 2 will provide enough urge for comfortable listening on a 2000Ω horn loudspeaker. and splendid results on headphones.

I have been surprised to find that the occasional heavy bass distortion I had noticed on pop and disco music on Radios 1 and 2 through a 1929 KB, and on other ancient and modern mains sets, was also present on the crystal set, so what are the BBC doing? Are they adding too much bass boost to suit ghettoblasters and plastic squawk boxes, or is it something to do with compressing the wideband stereo signals into mono for the a.m. bands?

At its worst, the distortion sounds like intermodulation. with the bass chopping up the higher registers to give a raw sound like a portable set with failing batteries.

I had to put it down to distortion caused by the strong signal until I tried the crystal set. Perhaps it's a BBC plot to drive us on to f.m.! Has anyone else noticed?

Anthony Hopwood Upton-on-Severn, Worcs.

OUR SERVICES

QUERIES

We will always try to help readers having difficulties with a Practical Wireless project, but please observe the following simple rules:

1. We cannot give advice on modifications to our designs, nor on commercial radio, TV or electronic equipment.

We cannot deal with technical gueries over the telephone.

3. All letters asking for advice must be accompanied by a stamped, self-addressed envelope (or envelope plus International Reply Coupons for overseas readers).

4. Write to the Editor, "Practical Wireless", Enefco House, The Quay, Poole, Dorset BH15 1PP, giving a clear description of your problem.

5. Only one project per letter, please.

BACK NUMBERS AND BINDERS

Limited stocks of most issues of PW for the past 18 years (plus a few from earlier years) are available at £1.40 each, including post and packing to addresses at home and overseas (by surface mail).

Binders, each taking one volume of PW are available Price £3.50 plus £1 post and packing for one binder, £2 post and packing for two or more, UK or overseas. Prices include VAT where appropriate.

CONSTRUCTION RATING

Each constructional project is given a rating, to guide readers as to its complexity:

Beginner

A project that can be tackled by a beginner who is able to identify components and handle a soldering iron fairly competently. Intermediate

A fair degree of experience in building electronic or radio projects is assumed, but only basic test equipment is needed to complete any tests and adjustments.

A project likely to appeal to an experienced constructor, and often requiring access to workshop facilities and test equipment for construction, testing and alignment. Definitely not recommended for a beginner to tackle on his own.

COMPONENTS, KITS AND PCBS

Components for our projects are usually available from advertisers. For more difficult items, a source will be suggested in the article. Kits for our more recent projects are available from CPL Electronics, and from FJP Kits (see advertisements). The printed circuit boards are available from our PCB SERVICE (see page 68 of this issue).

CLUB NEWS

If you want news of radio club activities, please send a stamped, self-addressed envelope to Club News, "Practical Wireless", Enefco House, The Quay, Poole, Dorset BH15 1PP, stating the county or counties you're interested in.

ORDERING

Orders for p.c.b.s, back numbers and binders, PW computer program cassettes and items from our Book Service, should be sent to PW Publishing Ltd., FREE-POST, Post Sales Department, Enefco House, The Quay, Poole, Dorset BH15 1PP, with details of your credit card or a cheque or postal order payable to PW Publishing Ltd. Cheques with overseas orders must be drawn on a London Clear-

Credit card orders (Access, Mastercard, Eurocard or Visa) are also welcome by telephone to Poole (0202) 678558. An answering machine will accept your order out of office hours.

SUBSCRIPTIONS

Subscriptions are available at £14 per annum to UK addresses and £18.50 overseas. For further details, see the announcement on page 28 of this issue. Airmail rates for overseas subscriptions can be quoted on request.

New 2m Rig

Navico have launched a new type of 144MHz band f.m. transceiver. There are two models, the AMR1000 and the AMR1000S.

The AMR1000 is a simple to operate fully channelised set, capable of both 12.5kHz and 25kHz spacing.

The AMR1000S has all the features of the 1000, but has full scanning and priority channel, memories, etc.

Both sets display either the frequency or channel selected, the power (5W/25W) and S-meter strength. The speaker is front facing for mobile use and the 600kHz duplex offset is automatically added for repeater channels.

There are a number of accessories available for



these two rigs, extension loudspeakers (one's waterproof), a telephone style handset, a mains p.s.u. and antennas.

The AMR1000 with fistmic costs £215, with telephone handset £240. The AMR1000S with fist

mic costs £260 and with telephone handset £279 (all exclusive of VAT).

Navico Ltd., Star Lane, Margate, Kent CT9 4NP. Tel: 0843 290290.

SILVAR Update

In the August issue we mentioned SILVAR (Student International Links Via Amateur Radio). Well, it was due to take place between July 20 and 22. Unfortunately, the schools involved have not achieved the high degree of co-ordination necessary in time. So it has been postponed until a later date, probably the third week in November.

If that gives you more time to organise yourself so you can help, contact: P. Daly GOGTE, 48 Lincoln Road,

Stevenage, Herts SG1 4PJ.

Data Service to Schools

The DTI and BT are jointly offering over £500 000 to help all secondary schools install telephone lines to access data services.

The offer means that every secondary school should now be able to install a telephone line to help teachers and pupils gain experience of the sort of data services that are already used extensively in industry.

In recent years, schools have made increasing use of the information services offered by Prestel, NERIS and the Times Network
Systems. The DTI have
supplied the micros and
modems which enable
schools to connect to data
services, but many schools
only make intermittent use
of the equipment because
there is no suitably locate'd
telephone line. The DTI/BT
offer aims to correct this.

Local education authorities will be offered £100 towards the cost of installing a new line in every secondary school. The current total cost of installation is £115. Apparently, to qualify these lines must be ordered by the end of September 1988.

Moves to Ban Illegal CB

A reply to a Written Parliamentary Question recently made interesting reading.

'I have tabled an Order under Section 7 of the Wireless Telegraphy Act 1967 banning the import. sale, manufacture or possession of 27MHz Citizens' Band Apparatus which cannot be legally used, and also updated Regulations requiring that 934MHz CB equipment conforms to the appropriate specifications. The widespread sale of unapproved apparatus has led to interference to authorised radio services including, most seriously, to emergency services. The introduction of these measures will ensure that unapproved equipment is removed from the market and that the range of approved equipment covers the new CEPT CB radio service, in harmony with the rest of Europe.

Better late than never, I suppose!

RNARS Awards

If you would normally send your application for RNARS awards to Don Walmsley G3HZL, you should note the new address.

Don Walmsley G3HZL. 15 Carter Croft, Upper Tean, Stoke-on-Trent, Staffs ST10 4JB.

Snap-in Switches

ITW Switches have added another version to their Series 18 line voltage selector switches. The snapin mount eliminates the need for associated mounting hardware. The panel cut-out needed measures 17.2 x 31.5mm.

The switches have an approved rating of 5A,

250V a.c./10A, 125V a.c. They also have a saddle slider arrangement which is lubricated for life, totally retained and enclosed.

For more information on the Series 18 switches, contact:

ITW Switches, Norway Road, Portsmouth, Hants PO3 5HT. Tel: 0705 694971.



HF Convention

The lecture programme for the HF Convention on September 25 at the Belfrey Hotel, Milton Common, Oxford has been finalised. 1030-1130—"EMC—The Politics and the European Community Directive" by Dan Bernard G4RLE (EMC Committee Chairman) and Alan Dearlove G1WZZ (EMC Committee Member). 1145-1245-"HF Equipment-New or Secondhand?" by Angus MacKenzie G30SS. 1330-1415-Trophy Presentation by the

President, Sir Richard Davies

G2XM.

1430-1530-"QRP Forum" by Peter Linsley G3PDL and members of the G-QRP Club. 1545-1800—DX Slide Presentations: "Building a US Contest Super-station" by Paul Bittner WOAIH. "The 1988 DXpedition to Kingman Reef, Palmyra and Kiritimati Is" by Paul Granger F6EXV.

Doors open to the Convention at 9.30am and the admission is £3. Other attractions are a car boot sale, WAB stand, Southern 10m FM Group, RNARS QRQ c.w. tests, Doctor DX Computerised Contesting, Pile-up Copying Competition and there will be refreshments available and the bar will be open.

25 Years in Boxes

West Hyde Developments has been supplying the electronics industry with enclosures and accessories for 25 years now.


They are introducing a new range of plastics cases called Elegant. These are manufactured in West Germany by Bopla. The enclosures are moulded from high impact polystyrene with a two-tone light grey finish. There are seven different sizes

available and the cases can be used free-standing, wallmounted or for hand-held equipment.

There are various options available for each size of case, including ventilation slots; flat, aluminium or plastics end panels or clip-in trim pieces.

For more details on the enclosures, contact:

West Hyde Developments
Ltd.,
9–10 Park Street Ind Est.,
Aylesbury, Bucks.
HP20 1ET.
Tel: 0296 20441.



The Ex-G Radio Club

The Ex-G Radio Club was founded in 1959 by Reg Cherrill W3HQO. He was a native of Kidderminster and had a love of, and respect for, Great Britain and its citizens. He was obviously not alone and so the Ex-G Radio Club was formed.

Full membership is open to amateurs born in Britain and now domiciled abroad, although present citizenship is not important. Associate membership is open to amateurs living abroad, not British born but whose spouse or parents were.

Ken Haswell GM2CWL has recently taken over the job of the UK secretary/treasurer from Frank Fletcher G2FUX. Ken is handling the distribution of the Ex-G Bulletin in the UK now. He is happy to supply details, application forms, etc., upon receipt of an s.a.e. at 6 Cameron Avenue, Balloch by Inverness,

Scotland IV1 2JT.

The licence for the callsign G4EXG is being transferred to George Reid G4OIS. George is a regular participant in many of the club nets and he will be responsible for the proper use of the G4EXG callsign.

The club nets of interest to UK/European amateurs and s.w.l.s are as follows: Saturdays 1830Z, CW Net, 14.065MHz; Sundays 1730Z, Canadian Net, 14.150MHz; Sundays 1900Z, Worldwide Net, 14.346MHz; Daily 1230Z, Family Net, 14.333, 21.410, 28.850MHz depending on conditions.

The editor of the Ex-G Bulletin is George Nixon GI3ION/W6, 1140 Sherman Avenue, Menlo Park, CA 94025, USA. George produces some 20 pages of articles and news every quarter and is looking for items of interest—preferably with a UK or Commonwealth flavour! If you can help, please drop him a line.



28/50MHz Capability

The Icom IC-575A transceiver covers two rather under-used bands, 28 and 50MHz. With the sunspot cycle approaching its peak over the next year or so, these bands are improving and many operators are thinking seriously about using them.

The transceiver is an all-mode set with the receiver covering 25 to 56MHz continuously. The transmit section covers 28–29.7 and 50–54MHz. It is also capable of dual band working.

As with many rigs of this

type, the various functions are far too numerous to mention in the small space here, interested readers should send for the appropriate brochure for more information. A few of the facilities that caught the eve are that it has full and semi-break in capability on c.w. There are 99 memory channels and multiple scan functions available. The power output is a maximum of 50W for s.s.b., c.w. and f.m. modes and 25W on a.m.

Icom (UK) Ltd., Sea Street, Herne Bay, Kent CT6 8LD. Tel: 0227 363859.

College Courses

Birmingham: The Wythall Radio Club will be holding its popular RAE tuition classes again this year. They start on September 8 so you might be just in time. The classes start at 8.30pm in the Club Room, Wythall Park Community Centre, Silver Street, Wythall. Morse classes are available on Tuesday evenings. More details from: Chris Pettitt GOEYO. Tel: 021-430 7267.

Nottingham: A full course for the May exam will run on Wednesday evenings from 6.30pm. The course starts on September 21. A short course aimed at the December exam is on Thursdays starting at 6.30pm. Another short course preparing for the May exam will start on January 12. Other courses available at the Arnold & Carlton College of Further Education, Digby Avenue, Mapperley, Nottingham are: a constructors class on Tuesdays at 7pm, starting September 20: a Morse class on Wednesdays at 7pm starting September 21 as well as a summer term programme with preparing for the RAE and after the RAE. These courses start after Easter 1989. Tel: 0602

876503 for further details.

Reach: Both RAE and Morse classes started in September at Reach Village Centre. That's about 9km west of Newmarket. Further details from: John. Tel: Newmarket 742039. Bristol: The RAE course meets Wednesdays, 7-9pm at the West Bristol Adult Education Areas, Stoke Lodge, Shirehampton Road, Stoke Bishop, Bristol. The Morse course meets on Mondays, 7-9pm at the same venue. The tutor for both courses will be B. E. Carr G4UHO and the fee for each course is £36.60. Tel: 0272 683112 for further details, if required. Coventry: The Henley College, Henley Road, Bell Green, Coventry, are again running the RAE course. The classes are Thursday evenings from 7-9pm. Apparently after finishing this course, the college have two suggestions for students. You can either bite your nails waiting for the results or use your fingers on a Morse key and join the Morse course they run. More details from: T. Farmer, Tel: 0203 611021 ext 290. Solihull: An RAE course will

be held at Light Hall School, Shakespeare Drive, Solihull, for the May exam. Enrolment is September 19. The tutor is R. A. Copsey G4TDF.

NEWS DESK ... compiled by G4LFM and G8VFH


VHF/UHF & SHF Transceivers

South Midlands
Communications have sent
only details of the FT-?11
series of transceivers. I say
?11 because the type
number depends on the
band.

The FT-211RH is the 144MHz band version, the FT-711RH is the 430MHz band one and the FT-2311R is the 1296MHz band version. The range are f.m. mobile/base transceivers.

The reversible sloped front panel allows overhead mounting and has soft green back-lighting of all the controls. Operating features include both push-button and knob memory selection, tuning in selectable steps, ten memory channels storing repeater splits, reverse repeater, call channel recall, various scanning modes and priority channel monitoring.

The FT-211RH has an output of 5/45 watts, the FT-711RH is 4/35 watts



and the FT-2311R is 1 or 5/10 watts. The price of the 1296MHz version is £475 including VAT and all are available from stock.

If you would like more details on any of these transceivers, contact:

South Midlands
Communications Ltd.,
SM House,
School Close,
Chandler's Ford Ind. Est.,
Eastleigh,
Hants SO5 3BY.
Tel: 0703 255111

More Laminates

Avel have announced three additions to their range of laminated transformers. They are six 50VA clamp mounting types, six 100VA frame mounting types and five 20VA clamp mounting types with only single 240V primary winding.

All the transformers will conform to BS3535 and to BS415 and CEE15 where appropriate. They will also have options like p.c.b. tags plated for flow soldering, fine winding wires skeined to the tags for extra mechanical strength and insulated terminal covers.

The range has fully

shrouded, double-section split bobbins made from 30 per cent glass filled nylon. The transformers are designed to operate at full rating at 25°C and with a maximum temperature rise of 55°C.

Each transformer is subjected to a 4kV r.m.s. flash test and to electrical, mechanical and insulation tests according to the requirements of the particular standards involved in the spec.

More details from: Avel-Lindbeg Ltd., South Ockendon, Essex RM15 5TD.

Hampshire County Award

To promote activity between stations in the county of Hampshire and other amateurs, the Royal Naval Amateur Radio Society have created this award.

It is made on a points basis, gained for each station contacted within the county boundary. Two points can be gained by working G3BZU or any other RNARS sponsored special event station (such as

GB3RN) provided it is operating within the county boundary.

The award is issued in three classes:

Class 1 UK—50 points, EU—20 points, DX—15 points. Class 2 UK—30 points, EU—15 points, DX—10 points. Class 3 UK—20 points, EU—10 points, DX-5 points.

All contacts must have been made after 1 October 1960. Log extracts and 50p (UK) or £1 (overseas) to Hampshire County Award Manager, G2GM. QTHR.

More Scope with LCD

An instrument for recording, processing and displaying electrical signals on a liquid crystal digital and dot matrix display is now available from Universal Instruments.

Combining the functions of a digital oscilloscope, transient recorder, signal averager and digital multimeter, the Iskrascope uses microprocessor control, a membrane keyboard and adjustable viewing angle screens to

display a variety of signals. The digital oscilloscope mode has a dot matrix display of 100 × 80mm, timer interval measurement from 5µs to 3.5h with the ability to output the register to a recorder for a permanent record. The Y sensitivity is from 5mV/cm to 20V/cm in 12 ranges with the time base going from 10µs/cm to 500s/cm

in 24 ranges. Extensive trigger modes are available as well as an analogue output.

Voltage and resistance measurements are indicated on a separate $3\frac{1}{2}$ digit display with volts from 20mV to 650V and ohms from 200 Ω to 20M Ω , both in six ranges.

When closed for transit, the instrument measures 83 × 331 × 294mm and weighs 5.1kg (including the rechargeable cells). The price, at £1185 plus VAT for the ODU0401, isn't quite in the hobbyist market, but it sounds like an interesting instrument. For more details, contact:

Universal Instrument Services Ltd., Unit 62, GEC Site, Cambridge Road, Whetstone, Leicester LE8 3LH. Tel: 0533 750123.

Master Class

Kevin Fox G4MDQ plans to start a c.w. master class in the all-mode section of the 144MHz band. From the press release it seems aimed at those in the South Yorkshire/North Nottinghamshire area. The purpose is to encourage people who've mastered the code and acquired a Class A licence to use the code on air.

He hopes this will achieve the following objectives: Improve key technique by regular sending practice. Improve copying and sending speed. Familiarise the budding h.f. operator with c.w. procedures and abbreviations by on-air simulation of an h.f. QSO. Provide "expert" tuition from local h.f. operators.

Members of the net will hopefully acquire the confidence and skills to become multi-talented h.f. operators, able to use both phone and c.w. as they choose. The speed of the net will be governed by the participants, and/or the slowest member(s).

Anyone interested in the appropriate area can contact Kevin on-air between 1730-1900 Monday to Friday.



Practical Wireless, October 1988

Mercury Award

This was created to promote activity between Royal Naval Amateur Radio Society members and other amateurs. The basic certificate is issued in three classes: Class 1 UK, 20 points required. Class 2 EU, 10 points required. Class 3 DX, 5 points required.

The certificate allows for increases in increments of 10 points. Band/Mode endorsements need an IRC

or s.a.s.e. when applying.
One point is awarded for
each contact with a member
per band. Contacts with
G3BZU or RNARS
sponsored special event

stations (GB3RN, GB3RM, GB3RNR, GB3HMS, etc.) are worth double points. So are contacts in the v.h.f. bands.

All contacts must be after 1 October 1960. Log extracts and 50p (UK) or £1 (overseas) to Mercury Awards Manager, G3HZL, QTHR.

The latest Hioki digital The latest Hioki digital

multimeter from Universal Instruments is a 19999 count $4\frac{1}{2}$ digit instrument with a basic d.c. voltage accuracy of 0.04%.
Resolution for both a.c. and d.c. is $10\mu V$ and a wideband frequency response with true r.m.s. reading gives accuracy even with distorted waveforms.

The Model 3230 uses a large 12mm character size l.c.d. with function annunciators for easy reading. Measurements of d.c. voltages are from 10µV to 1000V and a.c. voltage measurements are from 10µV to 750V with specification accuracy provided to a bandwidth of 100kHz. Resistance is from $10m\Omega$ to $20m\Omega$, both d.c. and a.c. from 1µA to 20A plus and audio/visual continuity and diode check.

The unit can be run for about 70 hours from a single 9V battery or continuous

use from a standard a.c. adaptor. The input impedance is greater than $10m\Omega$ on all ranges, with the lowest range being better than 100mΩ. The multimeter comes complete with battery, test leads, spare fuses and instructions for £318.05 excluding VAT. More details from: Universal Instrument Services Ltd., Unit 62, GEC Site. Cambridge Road, Whetstone.



Digital Capacitance Meter

Levell Electronics has introduced a new, widerange, hand-held digital capacitance meter. This instrument has a $3\frac{1}{2}$ digit, 12mm high liquid crystal display and will measure capacitors from 0.1pF to 20 000µF.

The accuracy on most ranges is $\pm 0.5\%$ reading ± 1 digit. The meter is powered by a PP2 type battery with low battery and over-range readings indicated on the display. It weighs only 350g and measures $180 \times 87 \times 42$ mm. The case is made of



high impact ABS and is provided with a tilt stand for bench use.

For more details on the 7705 capacitance meter, contact:

Levell Electronics Ltd., Moxon Street, Barnet, Herts. EN5 5SD. Tel: 01-440 8686.

MK From STC

MK Products are now available from STC Electronic Services. On the leaflet they sent recently five different products were detailed.

There were filtered mains sockets, designed to combat the effects of voltage spikes and transients on the mains wiring. These can be very useful if you run computers and the like. The sockets provide "two-way filtering" so preventing a noisy piece of equipment from creating

local transients.

Another product range are the residual current circuit breakers. MK produce both the type that plugs into any standard 13A socket outlet and the type which replace 13A sockets. In each case the trip current is 30mA.

For more details of these and the other MK products that STC now stock, contact:

STC Electronic Services, Edinburgh Way, Harlow, Essex CM20 2DF. Tel: 0279 26777.

Modular Enclosures

SRS have introduced two new versions of the Varicon

19in enclosure system. The 300 series is available in three different depth and nine height measurements. Doors and/or insert panels are provided with locking handles to allow the cabinets to be serviced from all angles.

The 500 series enables the components to be mounted onto a 180° swing frame allowing the entire contents of the cabinet to be reached easily.

Both series features include vent slots in blank doors and insert panels; cable entry plates for the bottom panel; earthing points in doors, side panels bottom panel, top plate and corner joints plus a decorative strip for name insertion. For further details, contact:

SRS Products Ltd., 19 Mead Industrial Park, Harlow, Essex CM20 2SE. Tel: 0279 418401.

Memory Problems Eliminated

One problem with NiCad cells is their gradual loss of capacity, brought about by recharging before the cells have first been totally discharged. This loss occurs because cells tend only to remember the level of charge put back rather than the original capacity.

Cirkit Distribution have manufactured the NC 101 discharge/charge cycler to combat this problem. It is completely automatic from start cycle through to fully charged condition. Four current selectable ranges are available for a variety of battery packs.

Once the batteries have discharged to one volt per cell, charging commences under the control of a precision crystal oscillator at charging currents determined by electronic constant current control circuitry. When full charge is reached, charging stops and an indicator shows that the batteries may be removed.

The discharge period varies with the initial discharge state of the batteries. The maximum cycle time is 8 hours 33 minutes, but will normally be around 6 hours says Cirkit. The unit has two outputs, the first with fixed settings for an eight-cell NiCad battery pack of either 500 or 600mAh and the second for a four-cell NiCad battery with selectable capacity of

225, 500, 600 or 1200mAh.

For safety, outputs are short circuit protected, there is an audible warning of reverse battery polarity, open circuit protection and a split bobbin transformer and internally fused mains.

The NC101 is available ready built at £49.95 including VAT, or in kit form (comprising board level kit at £27.10 and hardware kit at £12.50, both including VAT).

For more details on the NC101, contact:
Cirkit Distribution Ltd.,
Park Lane,
Broxbourne,
Herts. EN10 7NQ.
Tel: 0992 444111.


Multimeter Plus

The new multimeter from Alpha Electronics does more than the usual d.m.m. functions. It has the additional benefits of capacitance and frequency measurement too. The basic d.c. accuracy is 0.5%.

The 3650 has a large 3 1/2 digit liquid crystal display and is capable of measuring a.c. and d.c. voltages to 750 and 1000V respectively. Alternating and direct current can be measured to 20A and resistance is measured to $20M\Omega$. Capacitance, frequency and both audible and visual continuity tests, as well as diode and hFE tests are also possible.

The unit is powered by a single 9V battery and uses c.m.o.s. technology with a dual slope integrated a/d measuring system. It has an input impedance greater than 10MΩ.

The unit comes complete with battery, test leads,



spare fuse, solid carrying case and full operating instructions for £59.95 plus

For more details on the 3650 d.m.m., contact: Alpha Electronics Ltd. Unit 5. Linstock Trading Estate, Wigan Road, Atherton Manchester M29 0QA. Tel: 0942 873434.

Rally Calendar

*September 11: The Lincoln Hamfest will be held at the Exhibition Centre on the Lincolnshire Show Ground site. Admission is by lucky programme. All the usual attractions will be

September 20: The annual Amateur Radio Auction and Barbecue will again take place at the Cricket Pavilion "B" Building Entrance, BTI Radio Station, A5 Trunk Road, Hillmorton Rugby. It's organised by the Rugby ATS. The admission charge is only 20p per person and the large car park is free. Anyone may place an item in the auction, with or without a reserve price, free of charge. However, the Rugby ATS will retain 10% (£10 maximum) on all items sold. September 24/25: The first El Hamfest will take place at the Grand Hotel, Malahide. Co. Dublin. There will be a dinner on the 24th, with a grand draw at 5.15pm sharp on the 25th. The weekend will consist of sessions on all aspects of amateur radio together with lectures by Louis Varney G5RV and it is rumoured that Hugh Turnbull, the Director Atlantic Division of the ARRL will be giving a lecture too. Talk-in will be on S22. More details on all the events and available accommodation at the hotel can be obtained from: Christopher Yeates EI7AAB. Tel: Dublin 215145.

Centre. Doors open at 10am and the admission has been held at £1 for adults, accompanied children free. There is ample free parking adjacent to the sports hall and there will be reserved parking for the disabled. Morse tests will be available and can be booked through

held in the Harlow Sports

*PW/SWM in attendance

the RSGB. Catering will be available in the new Time Out cafeteria and lounge bar. Details from: G4MIS. Tel: 0279 722622 (evenings and weekends).

September 30-October 9: The BBC Radio Show will take place at Earls Court, London. Doors are open from 10am to 10pm except Saturdays and Sundays when it's 11am to 7pm. It's a "one-off" event, timed to celebrate 21 years of broadcasting by Radios 1, 2, 3 and 4 and local radio. The Show will have a central feature of a stage set complete with broadcasting studio. On this stage, almost continuous shows will be presented.

*October 2: The Welsh Amateur Radio Convention is at the usual venue. Oakdale Community College, Blackwood, Gwent. More details from: B. Davies GW3KYA. Tel: 0495 225825.

October 9: The Armagh Radio Rally is to be held in the Drumsill House Hotel. Doors are open from 12 noon to 6pm. For more details of this successful rally, contact: J. A. Murphy.

Tel: Armagh 522153.

Intelligent LCD Modules

Crotech is now stocking reflective, transflective and transmissive l.c.d. modules that display up to 160 alphanumeric characters. The modules are available with a choice of formats from 16 to 40 characters per line and up to four lines. Power requirement for all types is a single +5V line.

Crotech provides installation kits with each module that simplify

mounting in standard rectangular panel cutouts. The kit includes a protective window and adjustment pots for contrast and back light level.

For more information on these l.c.d. modules, contact

Crotech Instruments Ltd, 2 Stephenson Road, St Ives, Huntingdon, Cambs. PE17 4WJ. Tel: 0480 301818.

Special Event Stations

GB2WVR: This station will be on the air for the World Veteran Rowing Championships in Strathclyde Country Park, Motherwell. The dates for this event are September 5 to 11. For more details contact: Brian GM0EGI. QTHR, or Paddy GM3MTH. OTHR

GB1RLD: Two members of Radio Link—Derby Hospital Broadcasting will be operating the special event station from the outside broadcast caravan at the City Hospital, Derby. They

will be using 144MHz v.h.f. on September 17 and 18 from 1000 to 1600. John Huddlestone G1UJX. Tel: Derby 676822.

GB2LNM: The Loch Ness Monster special event station will be on the air over the weekend September 24 to 26. Operation will be on 3.5 to 28MHz using mainly 3.7MHz ± , 7.065MHz, 14.140-14.240 and other bands as conditions permit. The long awaited Nessie Appreciation Society Certificate should now be available, for more details, contact: Paddy GM3MTH. QTHR or Danny GM4LDU. QATHR.

TV Antenna Amplifier

September 25: The 1988

Harlow Mobile Rally will be

An increasing number of households now possess two (or more) TV sets, most usually working off the one antenna. Maplin Electronics have introduced an antenna amplifier which serves to boost the signal to one TV set or overcomes the losses which occur when two TV sets are operated from one antenna


The white amplifier box $(151 \times 79 \times 52$ mm) can be fixed to the wall or left freestanding. It features an on/off switch and red "on" indicator light. The unit can be left on continuously, if

wanted.

The amplifier has three coaxial sockets. The antenna lead plugs into one and the TV set/sets plug into the other two sockets. The 1.8m mains cable should be connected to a plug fitted with a 3A fuse. Bandwidth: 470-860MHz Typical Gain: 7dB Maximum Output: 96dBuV Input/Output Impedance: 75Ω Cost: £11.95 For more details on the antenna amplifier, contact: Maplin Electronics, PO Box 3, Rayleigh,

Essex SS6 8LR.

SOLDERLESS WIRING EASIWIRE



way, WITHOUT solder: with Circuigraph Easiwire from BICC-VERO

With Easiwire all you do is wind the circuit wire tightly around the component pins. No soldering, no chemicals, no extras, simplicity itself. Circuits can be changed easily, and components re-used.

Easiwire comes in kit form. It contains all you need to construct circuits: a high-quality wiring pen with integral wire cutter, 2 reels of wire, a tool for component positioning and removal, a flexible injection moulded wiring board, double-sided adhesive sheets, spring-loaded terminals and jacks for power connections and an instruction book. Of course, all these components are available separately too.

To take advantage of the special introductory offer, complete the coupon on the right and send it to:

BICC-VERO ELECTRONICS LIMITED, Flanders Road, Hedge End, Southampton, SO3 3LG



Please rush me	Easiwire ki	ts, retail	price £18;	
special introductory of	fer £15 (i	includes	p & p and VAT)	

I enclose cheque/postal order for....., made payable to **BICC-VERO Electronics Limited**

Please debit my credit card as follows:

Card Number


Expiry Date

Signature

or phone 04892 88774 now with your credit card number (24-hour answering service).

Kenwood TM-721E 144/430MHz Transceiver

Following on from his recent user review of the Alinco ALD-24E dual-band mobile transceiver, Ken Michaelson G3RDG turns his attention this month to the new dual-bander from Kenwood.



We recommend you don't wind the mic cable round the steering wheel like this!

The TM-721E is really two complete units in one box, with the facility of being able to tune in a station on each band and feed both signals to a common loudspeaker. Their relative levels can be manipulated by a balance control so that you can actually listen to two stations at the same time! It has two readouts of frequency on the display, the main band being used shown on the left-hand side in large numerals and the other band, termed the "subband", being in smaller numerals with the world SUB shown above it.

On first impressions I thought it was going to be a very complicated rig to operate, but after a few minutes of thought and careful reading of the instruction manual, everything fell into place.

Installation

The frontal area of the rig is the same size as a normal car radio, but the depth is greater, being 219mm with the substantial cooling fins on the back, so it might not be possible to mount it in the normal radio opening. I hung the review rig from the underside of the car fascia using the mounting bracket supplied, with the antenna and power leads coming in from under the carpet.

The antenna used for the mobile

tests was a Diamond DP-EL770H dual-band whip, which was secured to the car roof by an SAGMS magnetic mount. Since the TM-721E has separate inputs for the two bands (SO-239 for 2m and "N" for 70cm), I had to use a diplexer which, in this case, was a Maldol type HS-780 unit.

Controls

The main tuning is done by a 20mm diameter knob on the far left of the panel. This control operates in steps, which are factory-set at 12.5kHz for the 144MHz band and 25kHz for the 430MHz band. Both these figures can be altered should the need arise, and can be set to 5, 10, 15, 25 or 12.5kHz. First the F (function) button is pressed and then the REV/STEP button. The current stepping rate will then be shown on the display. A different rate can then be selected by turning the tuning knob (or pressing the UP/ DOWN buttons on the microphone). That's all there is to it. The actions to do this have to be completed within five seconds of pressing the F button, otherwise the unit reverts to normal operation. This gave me quite a surprise the first time it happened.

I should point out that the F button is coloured orange and the three func-

tions which can be carried out after pressing it—L OUT, STEP and DIM —are also lettered in orange.

To the right of the main tuning control are three push-button switches arranged vertically. These are TONE, VFO and MR/M. The description of the operation of the TONE button is not quite clear from the instruction manual as it suggests that in the European version when the button is depressed "the repeater control signal of 1750Hz is activated", and in the UK version "the key is used to activate the 1750Hz tone burst". In fact, when the button is depressed the letter T appears in the display area, and when the p.t.t. switch on the microphone is pressed, a tone is automatically transmitted. The sending of the tone is cancelled by a further pressure on the button, at which time the letter T disappears from the display area.

The next button down, VFO, is used to return to the VFO mode after operating in the MR (memory recall) mode. The last button is MR/M, which is used to access the memory channels and also to store frequency and shift in the memories, of which there are 14, numbered 0-9 and A-d.

It is a simple matter to enter any desired frequency into the memory area. The frequency and shift should be selected using the VFO button. The F button is pressed next, and the memory channel indicator in the display area lights. The desired channel is now selected using either the main tuning knob or the UP or DOWN buttons on the microphone. Pressing the MR/M button again writes the information into the particular memory channel selected, the Findicator and the memory channel number illuminations go out and the unit returns to the VFO mode. All perfectly straightforward, the only thing being that all this has to be completed within five seconds, otherwise the TM-721E reverts to the VFO mode! However, after a little practice I found no difficulty in completing the operation within the required time.

Under the main tuning control are two buttons, one marked with an arrow pointing upwards and the other an arrow pointing downwards. These move the operating frequency in steps of 1 MHz up or down. To their right is a small knob which is complementary to the main tuning control but acts on the "sub-band", moving it at the same rate as the main band. I found this very useful.

Beneath the display area are nine push-buttons, commencing with the previously mentioned F key. The others are as follows: SCAN—self-explan-

Practical Wireless, October 1988

★ MAKER'S SPECIFICATIONS

GENERAL

Frequency range:

Emission mode: Antenna impedance: Supply requirements:

Dimensions: Weight:

144-146MHz 430-440MHz F3E (f.m.) 50Ω unbalanced 13.5V d.c. ± 15% Transmit: 9.5A (max)

1.8kg (3.97lb) approx.

Receive: 600mA (squelched) 150W x 50H x 219D mm (overall)

Circuit type:

Sensitivity Selectivity Double superhet IF1 16.9MHz (v.h.f.) 30.825MHz (u.h.f.) (for 12dB SINAD): <0.16µV

Spurious responses: Squelch sensitivity: -60dB >2W (8Q. 5% t.h.d.) Audio output:

RECEIVER

TRANSMITTER

RF output power:

Maximum deviation: Spurious emissions: Audio distortion:

Mic impedance:

5W/45W (v.h.f.) 5W/35W (u.h.f.) ±5kHz

60dB below carrier <3% at 60% mod. (300–3000Hz) 500-600Ω

atory; SHIFT-selects the desired repeater offset; AL-switches the 'priority alert" system on or off; REV -reverses the transmit and receive frequencies when on; MUTE-used, if required, to reduce the volume of the "sub-band" receiver output by approximately 20dB; ABC-allows you to exchange the contents of the "subband" and main band automatically whenever a signal is strong enough to open the "sub-band" squelch; DUAL -turns the "sub-band" display off and allows single-band reception; and BAND—used to change the contents of the main band, "sub" to "main" and back again.

In a horizontal row under these nine switches are three slide controls and one more push-button. From left to right they are: LOCK-which deactivates all functions except the p.t.t. switch; BALANCE-which controls the proportion of the total audio output volume from each of the two bands; SUB SQUELCH-adjusts the squelch threshold of the "sub-band"; and LOW-which selects the transmitter output power level.

In the normal course of operation, the rig emits a "beep" tone when any function is activated, but if the user prefers this can be cancelled by switching the unit off, then holding down the MUTE button whilst switching on again. Repeating this procedure will bring back the "beep" which, incidentally, has a rather unusual feature. It is programmed to sound a series of definite musical tones for various functions, as listed in the manual, and commencing with "A", followed by

"A#", and then "B" right up the scale to "A", with high "F" being a key operation without effect. So anyone blessed with perfect pitch will know what button they have pressed without looking.

Operating

It is interesting to note that the TM-721E will perform perfectly in the packet mode, both on 144 and 430MHz, with no modifications, I connected it up to run through my AEA PK-232 modem, feeding the outgoing audio signal through the normal microphone socket, and taking the incoming signal from the external loudspeaker socket at the rear. Everything functioned as it should, and there was no difficulty in accessing several of the mailboxes on both bands. The antenna in use in this case was an Icom AH-7 discone, erected about 10 metres above ground.

I used the rig in the car for some time, completing several long journeys with everything working as it should have done, thought I must confess to having taken the manual with me as a memory-jogger. I used the fist microphone supplied with the rig, which was a dynamic type having UP and DOWN buttons on it to alter the frequency. This was most helpful as I could shift frequency without looking down at the

There was much less activity outside the London area, and I found it difficult sometimes to get a contact. The users of both bands appeared to be regulars having daily chats and it was

quite hard to break in. Having managed it, the best I got most times was a report. However, all the signal reports were complimentary and, since the power output was quite considerable, I was able to get into repeaters which were situated at some distance from

I considered it inadvisable to transmit for any length of time while stationary, because of the substantial battery drain of around 9.5A at full power, so the majority of operating was done motoring along quiet a country roads. I experienced no problems with electrical interference, which must be partly due to the fact that the rig has been designed to suppress ignition noise.

Conclusions

Although the TM-721E is obviously intended as a mobile rig, I used it as a base station at the commencement of the review, and I must say that it performed very well. In my opinion, using it in this manner enabled far more use to be made of the very many facilities available. I know that this view might be challenged by mobile users, but the wealth of information given in the display area can only be appreciated, I think, when the set is stationary.

The price of the TM-721E is £699.00, and the Maldol 144/430MHz diplexer costs £23.29, both prices including VAT. Thanks are due to Lowe Electronics Limited, Chesterfield Road, Matlock, Derbyshire DE4 5LE, telephone 0629 580800, for the loan of the equipment for this review. PW

Then place a regular order with your newsagent



Dear Newsagent. please reserve/deliver my monthly copy of

PRACTICAL WIRELESS

Name Address

Signed

Distributed

Practically Yours

By Glen Ross G8MWR

Let me start with some abject grovelling. In the June issue I gave a computer listing for calculating distances from Maidenhead locators. In line 320 you will find:

(T\$(4))=(ASC(T\$(6)) etc.

The equals sign should be replaced with a plus sign and all will be well.

Diplexing

There are now several good dualband (144/430MHz) antennas available. Unfortunately, many of the dualband rigs which are available have separate antenna input sockets for each band. How do you cope with the problem of getting one plug into two sockets? The answer is a simple bit of circuitry called a diplexer. This is a device which sorts out the various frequencies and routes them to the appropriate rig. They are available commercially at a rather nasty price but those that I have measured, whilst safe to use, do not show up any too well on separation and also tend to have an unacceptable loss when placed in circuit.

The Circuit

The circuit of a home-made diplexer which is well within the construction capabilities of the newcomer to home-brewing is shown in Fig. 1. It consists of three coaxial sockets and four series-resonant circuits. Hopefully you will remember that a series-resonant circuit has a very low impedance at resonance and a high impedance off resonance. How does the circuit work?

Consider a 144MHz (2m) signal coming in on the antenna socket SK2. The tuned circuit L2/C2 is resonant at 144MHz and, having a low impedance, passes the signal to the 2m output SK1. The tuned circuit L3/C3, being resonant at 433MHz, exhibits a high impedance at 2m and so stops the 144MHz signal from reaching the 70cm output socket SK3. On 433MHz the opposite action takes place.

More Protection

The action already described will do a fair job but it can be improved upon. The tuned circuit L1/C1 which is connected from the 2m output to earth is

Capacitors Trimmers (see text) C1, 3 5pF 2 15pF 2 C2, 4 Inductors Air-spaced, self-supporting L1, 3 3 turns 22s.w.g., 6mm dia., 12.6mm long L2, 4 5 turns 22s.w.g., 6mm dia., 20mm long Miscellaneous Sockets, BNC, N, etc., as required (3 off); die-cast box; nuts. bolts, washers and solder tags.




Fig. 1: Circuit diagram of the 144MHz/430MHz diplexer




Fig. 2: A layout suitable for operation at fairly low powers

series resonant at 433MHz and so any signal at that frequency which manages to find its way through L2/C2 is shorted to earth. As it has a high impedance off resonance, L1/C1 has no effect on the 144MHz signals. The tuned circuit L4/C4 is series resonant at 144MHz and removes any leakage at that frequency which reaches the 70cm output socket.

Specification

How well does the circuit do its job? Looking first of all at the insertion or through loss, this was measured at less than 0.1dB on 144MHz, and was slightly higher at 0.17dB on 433MHz. When you consider that you need a loss of 3dB to lose one S-point of signal strength, these losses can be disregarded. The blocking of 144MHz at the 70cm output, and of 433MHz at the 2m output was greater than 60dB. This means an unwanted output of 1 microwatt for every 1 watt of power applied, which is more than satisfactory.

Construction

The unit can be built in a small diecast box, and a suitable layout is shown in Fig. 2. Trimmer capacitor types required will depend on the transmitter powers to be used. Ceramic piston and compression types are suitable for low powers, for higher powers airspaced trimmers (e.g. Jackson C804 series) will be necessary.—Ed.

Tuning the unit is simple. First connect the rigs to the correct output sockets. Until all the following steps are completed DO NOT TRANSMIT.

Tune the 144MHz rig to a strong signal and adjust C2 for the highest Smeter reading. Tune the 433MHz rig to a strong signal and adjust C3 for the best S-meter reading.

Now connect the 144MHz rig to the 70cm output on the diplexer and the 433MHz rig to the 2m output. Tune to a strong 144MHz signal and adjust C4 for minimum S-meter reading. Tune to a strong 433MHz signal and adjust C1 for minimum S-meter reading. For safety, run through all the above steps a second time then reconnect the rigs to the correct outputs and the job is completed.

REALISTIC®

Portable All-Band World Receiver



Realistic DX-440. Tune into international news, views and entertainment from all over the world! This exciting "Voice Of The World" receiver features PLL synthesized circuitry which locks onto exact frequency so you can enjoy drift-free reception from around the globe. Receives FM stereo and full AM (150-29,999 KHz) including longwave, mediumwave and SW bands. Simply punch in any frequency with the direct-entry keys or use the 9-station memory for even faster access! Features automatic and manual scanning modes to locate any station on the air. With built-in monaural speaker, LCD quartz clock with timer, telescoping aerial and headphone socket. Requires 2 "AA" and 6 "C" batteries or AC/DC adapter.



20-221 £149.95

Tunes You Into A World Of Better Listening

Over 400 Tandy Stores And Dealers Nationwide.

Prices may vary at Dealers. Offers subject to availability.

Tandy, Tandy Centre, Leamore Lane, Bloxwich, Walsall, West Midlands, WS2 7PS.

A Constructor's Shack Test Gear

What kind of test equipment do amateurs have in their shack? P. Newton believes it depends on the kind of amateur.

Amateur Radio these days is very definitely a grouping of three distinct and separate activities: those who operate, those who construct things, and those who only natter over repeaters or on simplex f.m. Thus, the test equipment requirement for any station will vary somewhat. Let us take the chap who constructs (me!), and see what is in his shack, and what each box does.

Oscilloscopes If one were to be restricted to just one item, a decent 'scope with a 15MHz bandwidth, calibrated sweep speeds and calibrated Y amplifier would undoubtedly come first—for the very simple reason that it can be persuaded to do so many things. It can be a d.c. voltmeter, a.c. voltmeter, a.f. signal generator, distortion analyser and so forth.

General Coverage Receiver Any old receiver will do, provided it has a b.f.o. and has reasonable calibration. Here, I use a Heath GC1U. To measure frequency accurately on it, I have to inject a signal and use a counter. However, it serves well enough to find "where I am" when grid-dipping a tuned circuit for instance; as the detector element in the antenna noise bridge, for a general hunt-round for spurious transceiver outputs—and as a merry noise in the shack when a circuit won't perform as intended!

Multi-range Testmeter This should be of $10\ 000\Omega/V$ sensitivity on d.c. ranges and $1000\Omega/V$ a.c., or better. There are four here; one was homemade back in the "forties", one was bought in the early fifties and I have a

couple of modern Japanese ones. One is endowed with a 2500 volts range, which is handy for checking one's valved linear h.t. supplies.

RF Signal Generator I have two here. One is a pre-WWII vintage American "standard" or laboratory generator, covering l.f. up to 30MHz. The other will go up to 144MHz on harmonics, but is by no means r.f.-tight and so is not a lot of good as a measuring tool, though it is still extremely useful.

AF Signal Generator An old, but very good generator giving an output up to around 25kHz and down to below 50Hz; it has a "self-check" system in that it has an inbuilt beat circuit against the mains frequency.

Frequency Counter This little box was picked up at a club junk sale; runs off 12 volts from an external p.s.u. and has a liquid crystal display.

GDO This home-brew item is a set comprising a p.s.u. and separately an h.f. grid dip oscillator going from m.w. up to about 85MHz, plus another one covering 144MHz and 432MHz.

Antenna Noise Bridge Invaluable for antenna measurements, particularly when used with the general-coverage receiver. This caters for Murphy's Law, which in this context states that an antenna designed to resonate in the band won't!

Coaxial Attenuators These were of Belling-Lee origin, back in the dawn of history and were calibrated by me against a laboratory attenuator of known accuracy.

BC221 Wavemeter Invaluable old box, rigged out with a mains p.s.u.

Serves mostly as a precision signal generator in frequency terms.

Valve Voltmeter (with r.f. head) This is an old commercial unit, long since sold out of service as beyond economical repair; time, patience and some constructional work have restored it to adequate operation.

RF Field Strength Meter Just a tuned circuit, diode and meter, but so useful!

That summarises what I already have in the shack, over and above the station itself and its s.w.r. indicator, a.t.u. and so on.


With this lot, I can do antenna measurements with some hope of success (items 2, 3, 4, 6, 7, 8, 9, 12). Receivers can be built, evaluated and transmitters likewise. I can construct equipment for special modes such as data communications, or SSTV, and I can have a lot of fun too. Above all, I have all that is required to service the station equipment.

Calibration

No test equipment is worth using unless you have a clear idea of its limitations. For example, that is the reason for the sometimes ridiculously inflated gain figures claimed in the pages of this and other magazines for antennas; people just don't know the limitations of their test facilities. Again, it's not a lot of use measuring the voltages around a stage if the testmeter is of unknown accuracy since it fell off the bench last week!

In the amateur radio scene, calibration is a matter of applied gumption. For instance, if you have a 144MHz handy-talky, you can measure the voltage of the battery at the end of a full charge and keep a note of the reading; next time the voltmeter needs calibrating on that range, repeat the exercise and compare the results. The oscilloscope with a built-in calibrator is a great help, but it doesn't take much to build a little box using, say, a 10MHz crystal oscillator and a squarer which can be checked for frequency on the station receiver or counter, and in voltage by checking the d.c. supplies; it can then be used on the 'scope input as a more severe check-and of course you will never put a 'scope probe on any circuit without adjusting the probe capacitor on the calibrator waveform.


Calibration of this simple nature is enough to keep reasonable hold of the



Some of the sort of test gear used in a constructor's shack

results you obtain from any experiment; but of course, it won't stop you making a Charlie of yourself in the way you interpret valid results, nor for that matter will it stop you making "measurements" that your test gear could never validate! The latter two forms of error are as inevitable as night follows day, and all you can do is to hope you will spot the fallacy before you open your mouth.

As examples of the latter, consider how many times people have said in the past ten years that the absence of a balun accounts for the "skewed" polar diagram of an antenna. It is interesting to notice that (a) the problem was never blamed on the balun when no one bothered to use a balun(!!) and (b) that if you do adequately controlled measurements in an r.f. anechoic



An oscilloscope from the secondhand market

chamber, then you find the balun has no skewing effect whatever, certainly up to 1GHz. Of course, the skewing effect is in fact caused by disturbing objects around the test site. For example, an apple tree flowering 200 yards to one side of the site, at 200MHz caused a 5 degree skew as compared with December; and a train coming round the hill at a half-mile behind the reception area of the test site would guarantee gain variations of \pm 1dB or

The moral is simple: having made your test equipment, and checked it regularly, you must treat all results with caution. If they defy the law of common sense, odds-on either they are inherently wrong, or the interpretation is wrong. If they defy Ohm's Law, look out!

BOOKSHELF


W1FB'S ANTENNA NOTEBOOK by Doug DeMaw W1FB

Published by the American Radio Relay League Available from the Practical Wireless Book Service 208 x 276mm, 123 pages. Price £4.95 plus 75p P&P

The book was written for enthusiasts rather than engineers, so readers don't have to have lots of previous knowledge before the book is useful.

It's mainly simple wire and tubing antennas that have been detailed as these can provide very satisfactory performance for a host of operating objectives. There is no high level mathematics in the book, only simple equations are used to either explain something or to calculate the length on an antenna element. Detailed drawings are used to help clarify constructional methods.

There are chapters on such types of antennas as dipoles, single-wire antennas, simple verticals, high performance wire antennas, limited space and "invisible" antennas and



special receiving antennas. Other topics covered are matching techniques and simple antenna measurements.


One thing you notice about the book is the size of the print, much larger than usual and very easy to read. All the drawings are also well laid-out and very clear.

BEAM ANTENNA HANDBOOK

by William I. Orr W6SAI & Stuart D. Cowan W2LX
Published by Radio Publications Inc
Available from Practical Wireless Book Service
137 x 207mm, 268 pages. Price £6.75 plus 75p P&P
ISBN 0 933616 04 X

The authors of this book have followed the development of the Yagi antenna over the years and are ardent enthusiasts of this compact and efficient array. The information gained in their experiments, plus the work done by other enthusiasts have been gathered together in this handbook.

It covers all aspects of h.f. and v.h.f. Yagi antenna design, construction, installation, testing and operation. New information is provided on the effects of element taper, mounting hardware and matching systems. Dimensions are provided in both English and



Metric measurements.

To help those who like to build antennas for bands they were not designed for, scaling information is provided too.

For more books on all aspects of the radio hobby, see our Book Service on pages 42–44

Short Wave Short Wave Magazine Magazine

RESTORING AN EDDYSTONE 940

Tim Wright continues his series on this popular valved receiver from the past.

REGULARS

Airband, Scanning, Seen & Heard, Grassroots, What Receiver?

REVIEW

The Sony ICF-2001D receiver is the subject of this month's review

..SEPTEMBER ISSUE OUT NOW.....SEPTEMBER ISSUE OUT NOW.....

Doppler Shift on Satellites Part 2

In Part 1, Dave Tyler G1PEF, AMSAT UK3742, started to explain the effects of Doppler shift on the signals to and from the satellite. Now, in Part 2, we continue with the explanation and go through some worked examples.

Because we have an inkling that the Sat. TX frequency is going to be higher than the Gnd. RX frequency, we can transpose the formula that we used previously to show this:

Sat. TX f =

Gnd. RX f+

(Relative Velocity Speed of Light × Gnd. RX f)

where:

Relative Velocity is in metres per second. Speed of light is in metres per second and TX and RX frequencies are in Hz.

When used with our values talked about in Part 1.

145 911 123 =

145 910 000 +

$$\left(\frac{2.31 \times 1000}{300\,000\,000} \times 145\,910\,000\right)$$

This is just some 3 hertz out of our estimate that we calculated in Part 1. Not bad!

So, the satellite is required to transmit on 145.911 123MHz. Now, we can translate this for the uplink by:

581.0047-145.911 123=435.093 577

Already this is some 1123Hz different from our first uplink figure, not taking Doppler effect into account.

This 435.093 577MHz is the frequency the satellite must receive for correct operation. This time the station is transmitting to the satellite. So, as the satellite is moving away from the station, a greater frequency is required at the ground due to the Doppler effect, to arrive at the satellite at 435.093 577MHz.

The formula this time is:

Gnd. TX f =

Sat. RX f+

$$\frac{\text{Relative Velocity}}{\text{Speed of light}} \times \text{Sat. RX f}$$

where:

Relative Velocity and Speed of light are in metres/second and f is in hertz

With values inserted,

435 096 927 =

435 093 577 +

$$\left(\frac{2.31 \times 1000}{300\ 000\ 000} \times 435\ 093\ 577\right)$$

The ground station uplink frequency for Station 1 is 435.096 927MHz, some 2227Hz difference from the non-adjusted figure.

The Cornish station (1) transmits on 435.096 927MHz and hears his own signal on 145.910MHz, during which the Portuguese station (2) is tuning across the band and hears the Cornish one.

We can calculate the Portuguese Gnd. RX frequency as we already know that the Sat. TX frequency is 145.911 123MHz.

145 909 951 =

145 911 123 -

$$\left(\frac{2.41 \times 1000}{300\ 000\ 000} \times 145\ 911\ 123\right)$$

This leaves a difference of -1172Hz, which is what we would expect from the beacon calculations.

The Portuguese station receives the Cornish station on 145.909 951MHz. To enable this station to talkback, the uplink frequency must reach the satellite at 435.093 577MHz.

Again the formula, using the calculated relative velocity factor for the Portuguese station (2):

435 097 072 =

435 093 577 +

$$\left(\frac{2.41 \times 1000}{300\ 000\ 000} \times 435\ 093\ 577\right)$$

The Portuguese uplink frequency is therefore 435.097 072MHz.

Finally, the Uruguay station (3) hears Station 1 and Station 2 in QSO and wishes to join in. We can calculate the Uruguay Gnd. RX frequency, as the satellite is still transmitting at 145.911 123MHz.

Formulas again:

145 909 319 =

145 911 123 -

$$\left(\frac{3.71 \times 1000}{300\ 000\ 000} \times 145\ 911\ 123\right)$$

Again some 1804Hz difference, as expected from the beacon frequency calculations.

The Uruguay station (3) has a Gnd. RX frequency of 145.909 319MHz, but to enable talkback we still require the satellite to receive a frequency of 435.093 577MHz.

So, allowing for the velocity:


435 098 957 =

435 093 577 +

$$\left(\frac{3.71 \times 1000}{300\ 000\ 000} \times 435\ 093\ 577\right)$$

Station (3) at Uruguay therefore needs an uplink at 435.098 957MHz.

As you can see from this example, although 6 different up/down link frequencies are shown on the ground, only 1 corresponding pair are used on the satellite.



Helpful Data

Sat. Translation		Beacon Frequency
OSCAR-10	581.0047	145.809
OSCAR-12	581.8	435.797 Mode JA 435.910 Mode JD
RS 5 RS 7	-116.5	29.451
RS 7	-116.5	29.501

Chart for 581.0047 translation frequency (OSCAR-10)

Beacon (MHz)	Rel. Vel.	Uplink (MHz)	Downlink	(MHz)	
145.8078 145.8079	2.46 2.26	435.1070 435.1068	145.900		
145.8080 145.8081 145.8082 145.8083 145.8084	2.05 1.85 1.64 1.44 1.23	435.1066 435.1064 435.1062 435.1060 435.1058			
145.8085 145.8086 145.8087 145.8088 145.8089	1.02 0.82 0.61 0.41 0.2	435.1056 435.1054 435.1052 435.1050 435.1048			
145.8090	0	435.1047	1		
145.8091 145.8092 145.8093 145.8094 145.8095	-0.2 -0.41 -0.61 -0.82 -1.02	435.1045 435.1043 435.1041 435.1039 435.1037		435.0945 435.0943 435.0941	145.910
145.8096 145.8097 145.8098 145.8099 145.8100	-1.23 -1.44 -1.64 -1.85 -2.05	435.1035 435.1033 435.1031 435.1029 435.1027			
145.8101 145.8102	-2.26 -2.46	435.1025 435.1023			

Chart for -116.5 translation frequency (RS-series)

Beacon (MHz)	Rel. Vel.	Uplink (MHz)	Downlink	(MHz)	
29.4503 29.4504	7.13 6.11	145.9341 145.9335	29.430		
29.4505 29.4506 29.4507 29.4508 29.4509	5.09 4.07 3.05 2.03 1.01	145.9329 145.9323 145.9317 145.9311 145.9305		145.9229	29.420
29.4510	0	145.9300	1		
29.4511 29.4512 29.4513 29.4514 29.4515	-1.01 -2.03 -3.05 -4.07 -5.09	145.9294 145.9288 145.9282 145.9276 145.9270			
29.4516 29.4517	-6.11 -7.13	145.9264 145.9258			

All this, of course, is instantaneous at 0600GMT, the satellite distance (slant range) is continually changing.

The next calculated relative velocities at 0615GMT for Stations 1, 2 and

3 are: 2.28, 2.37 and 3.31km/sec respectively. See Fig. 2.1 and 2.2 for the differences, while keeping Station 1 Gnd. RX frequency the same.

Our example took account of the





Chart for 581.8 translation frequency (OSCAR-12)

Beacon (MHz)	Rel. Vel.	Uplink (MHz)	Downlink (MHz)	
435.8080 435.8079 435.8078 435.8077 435.8076	-7.57 -7.50 -7.43 -7.36 -7.29	145.9373 145.9372 145.9371 145.9371 145.9370	435.8700	145.9270	435.8800
435.8075 435.8074 435.8073 435.8072 435.8071	-7.22 -7.15 -7.08 -7.01 -6.95	145.9369 145.9369 145.9368 145.9367 145.9367		145.9269	
435.8070 435.8060 435.8050 435.8040 435.8030	-6.88 -6.19 -5.50 -4.81 -4.12	145.9366 145.9359 145.9353 145.9346 145.9339			
435.8020 435.8010 435.8000 435.7990 435.7980	-3.44 -2.75 -2.06 -1.37 -0.68	145.9333 145.9326 145.9319 145.9313 145.9306			
435.7970	0	145.9300	1		
435.7960 435.7950 435.7940 435.7930 435.7920	0.68 1.37 2.06 2.75 3.44	145.9293 145.9286 145.9280 145.9273 145.9266			
435.7910 435.7900 435.7890 435.7880 435.7870 435.7860	4.12 4.81 5.50 6.19 6.88 7.57	145.9260 145.9253 145.9246 145.9240 145.9233 145.9226			



near maximum Doppler shift which could occur during a pass, due to high relative velocities. However, this effect is reduced considerably on OSCAR-10, to such an extent that the shift is negligible and at a later stage the shift reverses direction as the satellite travels towards the stations. The principle can be used with any orbiting satellite.

For those who possess a computer, here is a BASIC program which has been kept simple to enable its use on most machines.

Charts are also shown for those who do not wish to use a computer. The principles are the same.

If they are used during a pass, we can achieve a QSO spot on frequency, first time more times than not, instead of all that hunting around for our own signals.

We saw earlier that we need to take into account the Doppler shift or, if you prefer, the relative velocity of the satellite with the frequency in use to the station. I also said that we have to calculate the relative velocity of the satellite. The method we used was to

subtract two successive slant ranges and divide by the time to give us km/sec. Then I showed you the formula:

Gnd. RX f =

Sat. TX f ±

 $\left(\frac{\text{Relative Velocity}}{\text{Speed of light}} \times \text{Sat. TX f}\right)$

where:

Relative Velocity and Speed of Light are in metres per second and f is in hertz

If you look carefully, we can find all these factors except the relative velocity in m/s. Gnd. RX f = the beacon frequency received at the station in Hz.

Sat. TX f = the beacon frequency in Hz, listed in the satellite's technical notes.

Speed of light in metres per second = 300 000 000

Transposing the formula:

Relative Velocity =

 $\left(\frac{\text{Sat. TX f-Gnd. RX F}}{\text{Sat. TX f}}\right)$

 \times 300 000 000

This is the basis of the program.

Line 80 means a station on the transponder band calling for a clear frequency. You can check the program works by using the values in Figs. 2.1 and 2.2 on the inputs.

Line 120 checks for a minus value at SATFRX which indicates a non-inverting transponder i.e. RS series, all it does is reverse the polarity of the frequency values on printout, if your computer does not have this statement, leave it out but remember the frequency will be in negative form, just ignore the minus sign.

If you are using the charts, check the beacon frequency at your station and look up the same (or close to it) value on the right chart for the satellite in use, then shown for a constant downlink are the varying uplinks.

If you change the downlink value by

any amount (within the passband of the transponder) you must change the value of the given uplink by the same amount.

That is, using the translation frequency of OSCAR-12, 581.8 and its beacon frequency of 435.8075MHz, for a downlink of 435.870MHz the uplink is 145.9369MHz. If the downlink frequency is changed to 435.880MHz then the corresponding uplink will be 145.9269MHz and pro rata. As this has an inverting transponder any increase in the downlink frequency will decrease the uplink frequency.

Before operating on any satellite please find out its operational status, this information can be obtained by sending your request along with an s.a.e. to: AMSAT UK, London E12 5EQ.

For up-to-the-minute information on satellites, read "Amateur Satellites" in On the Air, every month in PW

SUBSCRIPTION OFFER

One Year — £14.00 Two Years — £26.00 Three Years — £36.00

ACT NOW!... ACT NOW!... ACT NOW!... TO AVOID PRICE INCREASES EFFECTIVE FROM 8 OCTOBER 1988 TO UK ADDRESSES, 31 OCTOBER OVERSEAS (SEE PAGE 12)

Wherever you live, a Postal Subscription will ensure that you receive your copies of PRACTICAL WIRELESS and/or SHORT WAVE MAGAZINE regularly, through your own letterbox, before it gets onto your newsagent's shelf. Order a Joint Subscription and you will qualify for the Special Discount.

Fill in the Order Form below and post it to: PW Publishing Ltd., FREEPOST, Subscriptions Dept., Enefco House, The Quay, Poole, Dorset BH15 1PP (no stamp required). Credit Card Orders taken on (0202) 678558.

Overseas subscriptions outside Europe are now despatched by Accelerated Surface Post for faster delivery.

ease malcale me ry	pe of subscription red	quired: Special Joint Subscription	To: PW Publishing Ind., IREEPOST, Subscriptions Dept., Enefca House, The Qua Profe, Darver BH1.5. TPP (no stamp required).
Parked	Short Wave	Special John Subscriptor	Name
Vireless	Mary and a second	STOTEWE	Address
	Transaction over		1
1. 4	The state of the s		4
A ST			\square Lenciose cheque/PO (Pavable to PW Publishing Ltd) $\mathfrak L$
	M		☐ Charge to my Access/Visa Card the amount of €
	H-E-10		
See above (UK)	☐ See SWM (July)	□ £27.00 (UK)	Card No.
See above (UK) £18.50 (Overseas)	☐ See SWM (July) for offer details	☐ £27.00 (UK) ☐ £30.00 (Overseas)	Card No Valid from to

1988 PW READER SURVEY

It's over three years since we last asked our readers about their involvement in the radio hobby, their interests, and their likes and dislikes. There have been a lot of changes during that time, the "CB boom" has come and gone, and new modes such as AMTOR and packet radio have arrived on the scene.

So, we thought it was about time we let you have your say again, about the hobby and about Practical Wireless too. What you tell us will help to shape the magazine as we gallop towards the 1990s!

1. Do you hold a	current UK amateur transmi	tting licence?	12. Have you submitted a planning application in connection
Yes	□ 01 No	□ 02	with your radio hobby during the past 5 years?
	ntinue with the following question	ns, if "NO" skip to	Yes
Q4.			If "YES" was it successful? Yes
2. Which class of	licence do you have?		73/97 April 900 V 65/975 VARC 30 T
"A"	□ o1 "B"	□ 02	13. Have you experienced any TVI problems due to your transmissions during the past 5 years?
	e you held an Amateur licen	:e?	Yes
Up to 1 year	☐ 01 11-20 years	☐ 04	If "YES" have you managed to cure them:
2–5 years	O2 21 years or more	□ 05	Totally 🔲 03
6–10 years	□ 03		Partially Q4
4. Do you hold a	UK Citizens' Band licence?		Not really U os
Yes	□ 01 No	□ 02	14. How much money have you spent on the radio hobby within the past year? (Include QSL expenses, books and magazines,
5. How old are y	ou?		club or society dues, and other incidental expenses)
15 and under	□ o1 40–59	□ 04	Up to £50
16-21	02 60 and over	□ 05	£51-£250
22-39	□ 03		£251-£500 🗆 03 Over £2500 🗆 06
6. How old were hobby?	you when you became intere	sted in the radio	15. Is your radio equipment separately insured?
15 and under	□ o1	□ o4	(i.e. Not under a household contents policy) Yes
16-21	02 60 and over	05	10-10 Table 10 10-
22-39	□ 03		16. Is your interest in radio connected with your job?
7. About how me	any hours a week do you de	vote to the radio	It influenced my choice of job
hobby?			It resulted from my job No connection with my job 02
Up to 1 hour	□ 01 11–20 hours	□ 04	
2-5 hours	O2 21 hours or more	□ 05	17. Do you own a home computer?
6-10 hours	⊔ оз ∣		Yes 01 No 02
8. How much do	you use the h.f. amateur ba	nds?	If "YES" please state which model
	Often Sometimes	Never	18. Do you use a home computer in conjunction with your radio hobby?
1.8MHz 3.5MHz		□ o3	Yes O1 No O2
7MHz	☐ 04 ☐ 05 ☐ 08	□ 06 □ 09	
10MHz		☐ 12	19. Do you consider that a Novice or Student Licence would be good for amateur radio in the UK?
14MHz	□ 13 □ 14	□ 15	Yes O1 No O2
18MHz	□ 16 □ 17	□ 18	
21MHz	☐ 19 ☐ 20	□ 21	20. Should UK Amateur Licences retain a minimum age requirement?
24MHz	□ 22 □ 23	☐ 24	Yes 01 No 02
28MHz	□ 25 □ 26	□ 27	21. Do you consider that the ability to send and receive Morse
9. How much do	you use the v.h.f./u.h.f. amo	ateur bands?	code signals manually is still relevant?
******	Often Sometimes	Never	Yes □ 01 No □ 02
50MHz		☐ 03 ☐ 04	MANAGE AND COMPANY OF THE PROPERTY OF THE PROP
70MHz 144MHz	☐ 04 ☐ 05 ☐ 08	□ 06 □ 09	22. Do you construct any of the following items of radio equipment?
430MHz		12	Transmitters 01 Test equipment 06
1.2GHz	D 13 D 14	15	Receivers 02 Power supplies 07
2.4GHz-5.6GH		□ 18	Converters/transverters 03 Antennas 08
10GHz	□ 19 □ 20	□ 21	Amplifiers 04 Digital equipment 09
Above 24GHz	□ 22 □ 23	□ 24	Antenna tuning units
10. Which mode	s do you use?		23. How often do you indulge in the following?
cw	□ 01 FAX	□ 06	Often Sometimes Never
Phone	O2 SSTV	□ 07	Contests 01 02 03
RTTY	□ o3 FSTV	□ 08	Nets 04 05 06
AMTOR	Other	09	DXing
Packet	□ 05		QSLing
11. Do you use:			Fox-hunts
Repeaters?	□ 01		Short-wave listening 16 17 18
Satellites? Moonbounce?	02		TV-DXing
Moonbounce?	□ 03		

- CUT ALONG DOTTED LINE -

NEW BEARCAT

IT'S HERE AT LAST!

Bearcat's latest high technology scanner is now available in this country. It covers 10 mtrs, 6 mtrs, Airband, High Band, UHF and 950MHz.

The UBC 200XLT is the hand held scanner with the latest facilities - 850-950MHz in 12.5KHz steps, 200 memories in 10 Banks.

Super LCD Backlight for discreet listening in the dark, detachable Nicad pack, C.W. charger @ £249.00 (£5.00 P&P)

ONLY LIMITED STOCKS AVAILABLE **OUR NEXT DELIVERY IS IN** TWO MONTHS

RAYCOM

COMMUNICATIONS SYSTEMS LTD

TEL: 021-544 6767

SUMMER SPECIAL OFFERS WHILE STOCKS LAST

Icom ICR7000 + Royal 1300	£899.00
Icom IC3200E 25W Dual Band Mobile	£399.00
BJ200 Mk2 Handheld AWFM Scanner	£199.50
Sony ICF2001 D SW Receiver plus Airband	£289.00
Sony ICF7600DS Super SW Receiver	£199.00

SCANNERS

YAESU FRG9600 from the company who specialises in fitting extra options as supplied to Government departments and professional bodies. We also upgrade existing models, please call for more details, prices, delivery and

information	
Yaesu FRG9600 Basic Model Improved 'S' Meter + Sens	£465.00
Yaesu FRG9600/RWC Mk2 60-950MHz 'N' Connector Fitted	£495.00
Yoesu FRG9600/RWC MkS HF 100KHz-950MHz Active Mixer	£625.00
Yoesu PAL Video Unit for above	£27.50
Icom ICR7000 25M-2GHZ superb quality professional Rx	£859.00
Icom ICR7000/AH7000 Receiver plus Matching Discone	£937.50
Kenwood RZ 1 New 500kHz-950MHz Wide and Narrow AM/FM	
Fox VHF-UHF Multi Function Mobile Scanner FM only	£139.00
Uniden-Bearcat UBC 50XL VHF-UHF 10ch, H/held Scanner	£95.00
Uniden-Bearcat UBC 70XL VHF-UHF 20ch, Miniature H/held	£179.00
Uniden-Bearcat UBC 100XL VHF-UHF-Airband H/held Scanner	£189.00
Uniden-Bearcat UBC 175XL VHF-UHF-Airband Desk-Top	£175.00
BJ200 Mk2 VHF-UHF-Airband-Military Airband H/held	£199.50
AOR 2002 25-550, 800-1300MHz Desk-Top/Mobile AM/FM	£469.00
Sony Air 7 Top Quality VHF-Airband Handheld Scanner	£245.00
Package deal on above Mk3/5 FRG9600 c/w AH7000 discone, C	
AC PSU, complete receiving station HF-UHF including delivery UK mainla	nd.
Add C100 00 to above more	

PACKAGE DEAL AVAILABLE ON ALL MAKES. IF IT'S GOOD, WE STOCK IT!

A new concept in Amateur Radio uniden 2830

It's here at last! A beautifully-made processor-controlled full feature 10w (20w PEP) multimode transceiver with LCD readout and all functions necessary to work DX multimode transceiver with LCD readout and all functions necessary to work DA with Sporadic E and in the forthcoming sunspot maxima and also for transverting to the VHF and UHF bands. Work out the facts ... how much is a Two Metre Multimode? How much is the Uniden 2830 Ten Metre Multimode and a 2 metre transverter? With the Uniden 2830 you can have two bands for the price of one, with 10 watts on each band and all modes including CW. * S.A.E. for copy of Review Features

- ★ All modes, AM/FM/USB/LSB/CW ★ LCD readout of frequency/functions ★ CW with Sidetone


- All modes, AM/FM/USB/LSB/CW
 LCD readout of frequency/functions
 CW with Sidetone
 FM bandwidth compatible with VHF/UHF
 10Watts continuously variable o/p AM and FM

 * Scanning feature, up and down steps on mi
 * Selectable frequency steps, 10kHz, 1kHz, 100Hz
 * Ten metre band selectable in 500kHz steps
 * Build-in VSWR meter and protection circuit
 * Superb receiver sensitivity 3uV FM

Just TEN of the many reasons for choosing the UNIDEN 2830

THIS PRODUCT IS EXCLUSIVE TO RAYCOM, WE ARE THE U.K. DISTRIBUTOR. WHOLESALE ENQUIRIES WELCOME

10 metre band amateur transceiver



2M transverter £169.00 6M transverter £189.00 Package Deal: 2M + 2830

£399.00 Post £10

HANDHELDS

* = Extended Receiver coverage availa	ble, call for details
YAESU FT727R/FNB4A 2.5W (5W) DI	UAL BANDER C/W CHRGR £395.00
*YAESU FT23R/FBA10 2.5W (5W) 2N	
*YAESU FT73R/FNB10 2 5W (5W) 70	CMS C/W CHARGER £299.95
ICOM MICRO 2E 2 5W 2MTR HAND	HELD WITH CHARGER £209.00
ICOM 32E DUAL BANDER	£399.00

Many other types of handheld stocked, please enquire

SHORT WAVE RECEIVERS

Yaesu FRG8800 Short Wave 100KHz-30MHz all Mode	Mem £589.00
Yaesu FRG8800/FRV8800 as above with VHF Conv. fit	ted £679.00
Icom ICR-71 Top Grade Communications Receiver	£799.00
Sony PRO80 HF/VHF Handheld Scanner c/w accessor	es £345.00
Sony 2001D Short Wave/Airband Receiver	at £349.00
Sony SW1 Micro Short Wave Receiver	£249.00
Many more makes and models in stock, PLEASE (CALL FOR PRICES
DELIVERY COSTS and any advise or information, or send	large SAE (Insured

MOBILES

YAESU FIZITRH 45W ZMTR MOBILE WITH FREE	
1/4 WAVE ANT	£339.00
YAESU FT212RH NEW 45W 2MTR MOBILE DVS FEATURE O	PT £349.00
*ICOM IC28E 2MTR 25W MOBILE WITH FREE 5/8 ANTENNA	£359.00
ICOM IC48E 70cm 25W	£428.00
ICOM IC3200 Dual Band 25W	SPECIAL E399
Compare out propel	

Many other types and makes stocked, please enquire

PORT ABLES

FT290RMK2	2.5W MULTIMODE STANDARD ACCESSORIES	£399.00
FT290RMK2	2.5 WATT M/M AS ABOVE C/W NICADS CHRGR	£425.00
FT290RMK2	FL2025 (STD) WITH 25W LINEAR AMPLIFIER	£489.00
FT690RMK2	6MTR 2 5W MULTIMODE STANDARD ACCES	£399.00
FT690RMK2	6MTR 2 5W M/M AS ABOVE C/W NICADS CH	£425.00
FT790RMK2	NEW 70CM 2 5W MULTIMODE DUE OUT SOON	£499.00

ANTENNAS & ACCESSORIES

ANTENNAS & ACCESSORIES

NOW AVAILABLE AT RAYCOM: CUSHCRAFT, BUTTERNUT, HY-GAIN ANTENNAS, JAYBEAM, TONNA, MET, HAM-M ROTATORS, Call for full details, prices, availability and delivery costs.

ICOM AH7000 SUPER 250-1300MHz DISCONE £79.50

G5RV HALF SIZE HF ANTENNA ready to use ... £16.50

G5RV HALF SIZE HF ANTENNA ready to use ... £16.50

G8KW-TYPE 7.1MHz TRAP DIPOLE KIT SO239 £24.50

G8KW-TYPE 3X 7.1 TRAPS ONLY. LESS CABLE .£9.95

RAYCOM AIRBAND-VHF SIX ELEMENT DISCONE £12.50

SUN KG209 SE2M 5/8 MOBILE TILT-OVER 259 £14.50

SUN KG209 SE2M 5/8 MOBILE TILT-OVER 259 £14.50

GAMMA TWIN 2 METRE SLIM JIM KIT INC. INST. £14.50

RAYCOM CAST GUTTERMOUNT CW SO239/COAX £8.50

GAMMA TWIN 2 METRE SLIM JIM KIT INC. INST. £14.50

RAYCOM/RWC HB9CV 2 METRE 22 EMINI BEAM £12.50

TAYCOM/RWC HB9CV 2 METRE 22 EMINI BEAM £12.50

The above popular products POST FREE.

(UK mainland only)

YAESU FT 747GX

£649.00 including our FREE fitted MOD Board!

We improve the reciprocal mixing perfor-We improve the reciprocal mixing perior-mance by up to 15dB which gives you receive performance of higher priced rigs! Only available from Raycom, buy it elsewhere if you want SECOND BEST! YAESU IS STILL BEST VALUE FOR MONEY!

LL CURRENT YAESU AND ICOM HF RIGS STOCKED, CALL FOR A DEAL!


ROYAL 1300 WIDEBAND DISCONE

Following the huge success and popularity of the 25-1300MHz, wideband discone antenna Icom AH 7000 & Welz - Diamond D109 with transmit facilities on VHF-UHF amateur bands, Raycom decided to persuade a UK manufacturer to make a "BRITISH COPY!" at a very competitive price!

COMPLETE WITH PROFESSIONAL CABLE & CONNECTORS AT ONLY £65.00



CALL IN, EASY TO GET TO, EASY PARKING



RAYCOM COMMUNICATIONS SYSTEMS LTD INTERNATIONAL HOUSE, 963 WOLVERHAMPTON ROAD OLDBURY WEST MIDLANDS B69 4RJ

Telephone 021 544 6767. Fax 544 7124. Telex 336483 Identi-G



RAYCOM gives you MORE PURCHASING POWER!



FOR FAST SERVICE PHONE IN YOUR ORDER WITH ANY MAJOR CREDIT CARD OR IN MOST CASES WE CAN OFFER YOU INSTANT CREDIT OF UP TO £1,000,00 (SUBJECT TO STATUS. RAYCOM ARE LICENSED CREDIT BROKERS. APR 29.8%, SUBJECT TO VARIATION. FREE CREDIT ON CERTAIN PRODUCTS AT M.R.P. PRICES, 50% DEPOSIT AND SIX MONTHLY PAYMENTS. PLEASE TELEPHONE FOR MORE DETAILS AND APPLICATION FORMS.



NEW INFOLINE 0836 282228 available 5-9pm (weekdays only)



FOR THE BEST IN AMATEUR RADIO

Opening hours 9am-5.30pm 6 days, late nights Thursday & Friday till 7pm. We stay open later!

ORDERING INFORMATION

ALL PRODUCTS WE ADVERTISE ARE NORMAL STOCK ITEMS. OUR NEW MAIL ORDER DEPARTMENT CAN NOW DESPATCH MANY ITEMS SAME DAY, BUT PLEASE ALLOW UP TO 14 DAYS. DELIVERY TIME IS SUBJECT TO CARRIAGE METHOD. IF ORDERING BY MAIL PLEASE INCLUDE CARRIAGE AND STATE YOUR DAYTIME TELEPHONE NUMBER. ALL PRODUCTS OVER 1750.00 CARRIAGE FREE. PLEASE ALLOW TIME FOR PERSONAL CHEQUES TO CLEAR. PLEASE CALL BEFORE ORDERING AND FOR MORE INFORMATION

PLEASE TEL: 021 544 6767

THROUGH YOUR CONTINUOUS AND VALUED CUSTOM, RAY WITHERS COMMUNICATIONS LTD. HAS MOVED AND EXPANDED TO ENABLE US TO OFFER YOU EVEN BETTER SERVICE AND PRICES - STILL WITH THE RAYCOM GUARANTEE, BEST EQUIPMENT, BEST SERVICE, BEST PRICES, BEST BACK-UP, AND PLENTY OF PARKING FACILITIES AND EASIER TO GET TO! WE NOW BOAST THE BEST CENTRAL FACILITIES IN THE COUNTRY, WHY NOT POP ALONG AND SEE THE LATEST TRANSCEIVERS, SHORTWAVE/SCANNING RECEIVERS AND ACCESSORIES? MOST OTHER PRODUCTS ADVERTISED IN THIS MAGAZINE ARE AVAILABLE AT RAYCOM, AND DON'T FORGET OUR EXCLUSIVE PRODUCTS AND MODIFICATIONS!

Reading & Understanding Circuit Diagrams

(with a bit of theory thrown in)

The H.F. Oscillator

The h.f. (high frequency), or r.f. (radio frequency), oscillator can take many forms. Some are designed especially for a very high degree of frequency stability and others to have very low noise, just to give you two examples. Some oscillators are used at a single frequency and others need to be variable over a wide band. In all types, a most desirable feature is that the frequency stays just where it has been set, usually within about 100Hz after allowing a short "warm-up" time.

A change of temperature is the most common cause of the frequency of an oscillator changing. This follows changes in the inductance and capacitance values due to temperature variations. Most components tend to increase their value as they get hotter and, of course, get smaller as they cool. Now, if both the inductor and the capacitor in an oscillator (or any other tuned circuit) are subject to an increase in temperature, unless special components are used, the effect will be that the frequency to which the oscillator is turned will drift downwards.

One method of reducing this effect is to use capacitors which have a negative temperature coefficient. This simply means that instead of increasing capacitance with a temperature rise, the capacitance is actually reduced. Obviously, if the inductance goes up and the capacitance goes down the net effect will be a reduced frequency change. As air-spaced variable capacitors have a normal positive temperature coefficient, C1 in Fig. 8.1, the other two fixed capacitors, C2 and C3, could be negative temperature coefficient types as they are both in parallel with the variable tuning capacitor and so will have an effect on the oscillator frequency.

Last month, we started to look at the pieces that go to make a superheterodyne receiver. Now, in Part 8, R. F. Fautley G3ASG continues that process further into the receiver.

Before confusion sets in, C2 and C3 are in series with one another, but theoretically they can be replaced by a single capacitor which would be in parallel with C1. Capacitor C1 is used as the front panel control to vary the oscillator frequency and tune the receiver to the required signal.

The connection to the transistor emitter from the junction of C2 and C3 has the same effect as the tap on the inductor L1 in Fig. 6.3. In this case it's a capacitive tap on the tuned circuit, having the same effect of providing input to the transistor gate from some of its own output, except that in this case the output is from the emitter. This is because it is a common collector circuit with the collector "earthed" to high frequency signals as the circuit in Fig. 3.9.

Why is it the same if the tap is on the inductor or the capacitor? Think of the tuned circuit at **resonance** when the whole lot (L1, C1, C2, C3 and the transistor base input capacitance as well as any "stray" capacitance) looks like a pure high value of resistance. If you've forgotten about that, look up in Part 6 about regenerative detectors. The tap is then a tap on a resistor, just like a fixed potentiometer. So, as long as the tap is on either the capacitor or the inductor it's the same thing.


Resistors R1, R2 and R3 provide the d.c. conditions for correct operation. Resistor R3 also develops the oscillator output voltage, which is taken from the emitter because it provides a low impedance output which is, to some extent, more isolated from the base input. This isolation is necessary to prevent any external stage to which it is connected (for example, a mixer) from influencing the frequency sensitive components in the gate circuit. Capacitor C5 passes the oscillator signal to a following stage whilst isolating d.c. voltages, and C6 bypasses the 12V d.c. supply and also provides a near short circuit to earth for the collector at signal frequencies.

The I.F. Amplifier

The i.f. amplifier in Fig. 8.2, shows a typical circuit using a m.o.s.f.e.t., bipolar transistors (the ordinary sort) can also be used. The f.e.t. is shown here because the application of a.g.c. (automatic gain control) to the stage can be seen more clearly. With the ordinary sort of transistors, the a.g.c. voltage has to be applied at the base input together with the biasing resistors making the circuit look a bit cluttered.

What is this a.g.c. all about? Automatic gain control is simply a means of altering the gain of a stage or stages dependent on the strength of the signal being received. If the signal is very weak, maximum gain will be required to make it readable, but for a very strong local station, the gain would need to be reduced to prevent the receiver **overloading**. Let's get overloading out of the way first.

The maximum voltage input to any stage obviously must be limited, it can't be expected to handle hundreds of volts without breaking! In fact, signals received by the antenna do not



R1 Tr1 Gate 2 Tr2 C8 12V

Gate 1 Source

R2 C5 R3 C6 C7 Earthy

Fig. 8.2

often exceed about 100mV even if you live near to a broadcasting station. However, these signals are amplified by the r.f. and i.f. stages to produce up to a few volts from quite small signals of only a few microvolts. So, if a strong local station of about 1mV is tuned in it is likely that, after amplification, one of the receiver stages will have a signal at its input which is high enough to exceed the dynamic range of its active device (transistor or valve).

The dynamic range of a device refers to the highest input signal which can be applied to it without the introduction of distortion into its output. If the output waveform is not the same shape as that at the input, then it is distorted. The most usual form of this distortion is a flattening of one or both of the waveform peaks. This is due either to the collector current reaching its saturation level (maximum current of which the device is capable), or the peaks of the input signal exceeding the bias applied to the input to the device. The waveforms in Fig. 8.3 show the effect of overdriving a stage with a sinewave, the input is in (a) and the excessively distorted output at (b).

When listening to a signal, the introduction of distortion is usually easily discernible, especially to the hi-fi enthusiast! So that's the reason for a.g.c., it automatically reduces the gain when receiving strong signals and increases it for weak signals. Correctly designed, an a.g.c. circuit will prevent overloading and also maintain a nearly constant output level for a very considerable change of input.

The a.g.c. signals can be derived either from some point in the i.f. amplifier or from the a.f. stages, the principle being the same. For the reception of a.m. signals it is convenient to utilise the i.f. signals as the carrier is available, when rectified, to provide the d.c. signal even when no modulation is present. With s.s.b. and c.w. signals, there is no continuous carrier available but, even so, a.g.c. is still useable providing that means can be found to maintain the a.g.c. voltage during the very short breaks in signal between words or Morse characters. This is possible by using a long decay time constant on the a.g.c. system.



Fig. 8.3

The time constant of a circuit is a measure of the time taken either to charge or discharge it. A short time constant is obtained by using small values of R and C, and a long time constant by higher values. In Fig. 8.2. the values of R5, R2 and C5 will affect the time constant of the a.g.c. circuit.

The components C1, L1, C2 and L2 in the i.f. amplifier are both tuned circuits resonating at the intermediate frequency (i.f.). The broken line surrounding these components indicates that they are inside a screening can, usually made of aluminium. The reason for mounting the inductors and capacitors inside a can is to attempt to contain the "fields" around the components within the confines of the can and so prevent them from interacting with other fields. This is particularly important where other tuned circuits are operating at the same frequency (as in our case where C3, L3, C4 and L4 are also tuned to the i.f.).

Why is this screening so important? Before getting into the screening problem, let us take a look at the circuit surrounded by the broken line. All four components inside the can, together with the can itself, constitute an i.f. transformer. It is called a transformer because in this case the two inductors are mounted close to each other so that the magnetic fields surrounding each of them interact. Depending on the shape of the coil windings and their spacing from each other, the bandwidth or frequency response can, within limits, be controlled. Now, if the field surrounding other inductors were to impinge on the fields of the coils making up one transformer, at the very least they would change its selectivity characteristic and so alter its bandwidth. The worst that can happen would be that the stage would start oscillating around the frequency of the i.f. Why could it cause oscillation? That's because energy from T2 in Fig. 8.2, impinging on T1 is the same as feeding some output from an amplifier back to its own input, the very condition we discussed previously to make an oscillator oscillate. The feedback must, of course, be positive or add to the input (be in phase with the input) to cause actual oscillation, but even if negative it could be undesirable as then the stage gain would be reduced.

By surrounding each pair of tuned circuits (i.f. transformer) by a metal can, the fields external to the i.f. transformer caused by its tuned circuits can be very considerably attenuated. So, if each transformer is so "screened" the chance of oscillation or distorted bandwidth is almost eliminated. Nothing is 100 per cent, however, so the transformers are kept physically as far apart as practically possible to further minimise the risk of interaction

Resistors R1 and R2 provide the bias necessary on Gate 2 and with R3, set the d.c. condition necessary for maximum stage gain. Other components, C7, C8 and R4 perform similar functions to those described in similar positions for other circuits, so you should be able to work those out for yourself?

The a.g.c. input needs some explanation. The idea of a.g.c. has already been covered, so just the application to the amplifier is required. A negative-going (with respect to earth) d.c. signal from a later stage is connected via R5 to Gate 2. A very strong received signal will apply a voltage from the a.g.c. part of the demodulator to Gate 2 which will oppose the quiescent bias on the gate, thus making its potential less positive. This will reduce the gain of the stage and so prevent overloading to some extent, but such a simple approach could not be expected to provide the best solution as it would probably introduce some distortion of its own. This is because the f.e.t. would be handling larger signals just when the a.g.c. had reduced the current through the device so also reducing the available current swing. However, the idea behind these articles is to enable the various circuits to be recognised, not designed for optimum performance.

Next, in Part 9, we'll finish looking at the superheterodyne receiver.

SWAP SPOT

Have FT-708R 432MHz hand-held transceiver, complete with mobile mounting bracket, mobile mic and ext. speaker. equipment has full 432MHz band coverage plus scanning. Would exchange for h.f. c.w. rig, single-bander, anything considered. Tel: 0664 60773.

Have 3½ inch Myford lathe, BG. SC. and accessories, all in good working order. Would exchange for Trio TS-530SE h.f. transceiver or

similar, must be working. Geoff. Tel: Norwich 406331 evenings. E708

Have Sommerkamp FT-250/FP-250 240W p.e.p. h.f. s.s.b./c.w.

Have Bell and Howell 2146XL 8mm cine camera with shoulder case, plus Hanimex 808D projector both in mint condition. Would exchange for 144MHz transceiver. Alan. Tel: 0840 212177.

Got a camera, want a receiver? Got a v.h.f. rig, want some h.f. gear to go with your new G-zero? In fact, have you got anything to trade radio-wise?

If so, why not advertise it FREE here. Send details, including what equipment you're looking for, to "SWAP SPOT". Practical Wireless. Enetco House, The Quay, Poole, Dorset 8H15 1PP, for inclusion in the first available issues of the magazine.

A FEW SIMPLE RULES. Your ad. should follow the format of those appearing below, it must be typed or written in block letters; it must be not more than 40 words long including name and address/telephone number. Swaps only—no items for sale—and one of the items MUST be radio related. Adverts for ILLEGAL CB equipment will not be screened.

The appropriate licence must be held by anyone installing or operating a radio transmitter.

Have Collins 51J-4 with 3 mechanical filters and Siemens E-310a allwave receivers. Would exchange for German WW2 ex-service equipment, W.S. No 1 or W.S. No 11. R. Otterstad OZ8RO, Vejdammen 5, DK-2840 Holte, Denmark. Tel: 010 452 801875.E724

transceiver with mic and manual, v.g.c. Would exchange for Sony CRF synthesised receiver, will also consider Panasonic RF-6300 or similar receiver. Tel: 061 7431570.

Kitchen Konstruktion

So far in this series, a number of very simple, low-cost ideas have been submitted, all of which can be made on the kitchen table. These were aimed at those who haven't the luxury of a workshop or bench.

It doesn't bear contemplation, the possible reaction of your nearest-and-dearest to you soldering or metal working on his or her delicate kitchen table or fitted worktop. (Our illustrious editor had the misfortune to drill through his Formica kitchen worktop many years ago, and has not been entirely forgiven since!)

So in the interest of preserving domestic harmony, you might like to construct yourself a simple working surface, on which you can do these rather unsocial activities.

Christened the "Table Hook" it is a derivation of the once popular and massive "Bench Hook", used by carpenters to hold pieces of wood steady whilst they were being sawn.

The "Table Hook" consists of a flat surface board, with a "back stop" and a "front stop" attached (Fig. 1).

Construction

The surface board should be as large as is convenient, for individual circumstances, and made of thick, goodquality plywood. No doubt the local timber supplier will have an off-cut from which a piece can be sawn.

Chipboard should be avoided as the edges crumble and powder, and wood screws and nails have a nasty habit of pulling out when put under stress.

Along the underside of the front edge of the board, a stout piece of wooden battening should be glued and screwed into place, using countersunk screws and woodworking adhesive. This "front stop", when the "Table Hook" is in use, is pushed up against the front edge of the kitchen table to hold the work surface in position. A "back

In No.7 of his occasional series, Richard Q. Marris G2BZQ shows us how to make a "Table Hook". A device that will surely save your kitchen table from the rigours of electronic construction.

stop" is fitted in a similar manner along the rear edge of the working surface. This performs two functions, the first is, it stops bits and pieces dropping off the work surface on to the table, and the second is, it acts as a firm edge to place chassis or panels against while they are being drilled or cut. While performing either of the last two functions you must lean against the "front stop" to hold the working surface of the "Table Hook" secure.


Refinements

The following refinements can be optionally added to the "Table Hook":

- 1. A longish steel rule can be screwed near the front edge for easy measurement of wire, etc., preferably marked in inches and metric measure.
- 2. A soldering iron stand can be made using a piece of wire coat hanger formed into an "M" shape, and then pushed into a couple of appropriate size holes made part-way through the working surface towards the rear right-hand side.

3. The underside of the "Table Hook" can be covered with cork tiles (easily cut with a sharp craft knife), glued into place. This will stop the whole assembly scratching the surface of the table.

bly scratching the surface of the table. When the "Table Hook" gets grubby, just wipe it down with a damp cloth and allow it to dry. It's not worth painting or varnishing its surface because in no time at all it will look tatty and scratched. Due to the "Table Hook's" low profile, it can easily be stored when not in use. There's no end to the refinements one could make to this device (see "Table-Top Workbench", PW August 1983); with a little ingenuity all sorts of jigs and clamps could be added for drilling and bending light-gauge sheet metal.



SWAP SPOT

Have Handbook of Wireless Telegraphy 1938 volume two. Would exchange for 144MHz v.s.w.r. meter or anything RX. Tel: 0993 811747 after 6.30 pm. E618

Have FDK-700 144MHz f.m., 144MHz and 432MHz Microwave Modules converters (28MHz i.f.). Would exchange for either Datong D-70, RTTY/c.w./FAX for Commodore VIC20 or transverters with 28MHz i.f. Write to, R. Jones, 37 Maes-Y-Bedol, Garnant, Ammanford, Dyfed SA18 2ER.

Have DST-100 MKII wartime receiver "Collectors item" 50kHz to 30MHz continuous tuning, in very good condition with workshop manual. Would exchange for smaller receiver, i.e. Realistic, Trio, Eddystone, etc. or w.h.y? Durham 0388 527700

Have Yaesu FRG-8800 receiver with v.h.f. converter. Would exchange for a PRO-2004 scanner with AH-7000 antenna. Tel: 0443 755876.

Have Realistic PRO-2004 scanner as new. Would exchange for any 100kHz to 30MHz receiver with s.s.b. (l.s.b./u.s.b.)/c.w./a.m./f.m. modes. Mr J. T. Stephens. Tel: 0256 53896.

Have Sony CRF-320 32-band all-mode receiver, cost £780, original owner. Set has intermittent fault on short wave. Would exchange for American general coverage valved receiver, e.g. HRO-60, NC-400, HQ180. Tel: 0533 896391.

Have Racal RA17L general coverage receiver in good working order. Would exchange for good SLR camera or w.h.y? John Carver GM0IZC. Tel: 0224 780545 daytime.

Have Polaroid "Polavision" movie outfit complete with zoom lens, camera and replay monitor. As new in original box. Would exchange for v.h.f. scanner or h.f. receiver or w.h.y? Tel: 01-906 4206. E668

Quality

MORSE KEY KITS

from
R.A. KENT ENGINEERS

Leading British manufacturers of top quality morse keys in kit form, renowned throughout the world for their outstanding performance and reliability.

SOLID BRASS MORSE KEY KIT

Our well known Standard Morse Key Kit is machined from solid brass, using ball race bearings, silver contacts and fine pitched screw threads to provide a key of outstanding quality. Available as a complete kit or machine parts only requiring a base to complete.

TWIN PADDLE MORSE KEY KIT

Our Twin Paddle Morse Key Kit is also machined from solid brass and uses ball race bearings with fine pitched screw threads and the solid steel base gives outstanding stability in use.

ELECTRONIC KEYER KIT

The Electronic Key Kit is supplied with an assembled and tested printed circuit board, together with a steel case and hardware. It provides iambic operation for squeeze keying at speeds of 5-40 w.p.m. with fully adjustable side tone. Alternatively, the assembled PCB, together with the three control potentiometers, is available to enable the constructor to finish.

Please send large SAE for further details to -





R. A. KENT (ENGINEERS)

243 Carr Lane, Tarleton, Preston, Lancs. PR4 6YB Telephone: Hesketh Bank (0772) 814998

TX - 3 RTTY/CW/ASCII TRANSCEIVE

Split-screen, type-ahead operation, 24 memories, clock, review store, callsign capture, RTTY auto CR/LF, CW software filtering and much more. Needs interface or TU. BBC-B/Master and CBM64 tape £20, disc £22. SPECTRUM tape £35, +3 disc £37 inc. adapter board (needs interface/TU also).

Also VIC20 RTTY/CW transceive program, tape £20.

RTTY/CW/AMTOR/SSTV RECEIVE

This is still a best-selling program and it's easy to see why. Superb performance on all 4 modes, switch modes at a keypress to catch all the action. Text and picture store with dump to screen, printer or tape/disc. The essential software for the SWL. Needs interface. BBC-B/Master, CBM64 tape £25, disc £27. VIC20 tape £25. SPECTRUM tape £40, +3 disc £42 inc. adapter board (needs interface also). The SPECTRUM software-only version is still available £25, +3 disc £27.

TIF1 INTERFACE for TX-3 and RX-4. RTTY and CW filters, computer noise isolation for excellent reception. Transmit outputs for MIC, PTT and KEY. Kit £20 (assembled PCB + cables, connectors), ready-made £40 state rig. Available only with TX-3 or RX-4 software.

Also MORSE TUTOR £6, LOGBOOK £8, RAE MATHS £9 for BBC and CBM64 (disc £2 extra), SPECTRUM, ELECTRON, VIC20.

Prices include VAT and p&p, 1st Class inland, airmail overseas, normally by return. Eire, C.I., BFPO deduct 13%.

technical software (P.W.)

Fron, Upper Llandwrog, Caernarfon LL54 7RF. Tel. 0286 881886








The PW "Badger"

This tuneable f.m. receiver designed by Mike Rowe G8JVE is capable of covering the all-mode and f.m. sections of the 144MHz amateur band.

Unlike many other amateur v.h.f. receivers that have appeared over the years this one does not plump for the easy option; crystal frequency control. The receiver section which sets the "Badger" apart from most others, is the v.f.o. (Fig. 1). This is designed around a Vackar oscillator, running between 14.81MHz and 15.03MHz, tuned by a Varicap diode D2. To reduce oscillator drift the voltage supplied to the diode tuning network is stabilised by a 78L05 voltage regulator chip IC3. The output of the v.f.o. is buffered by Tr9 and Tr8, these help to minimise the effect of loading presented by following stages and thus further ensure good oscillator stability. The buffer is followed by two tripler stages. Tr7 and Tr6 (see Fig. 2), giving a final local oscillator injection frequency of 133.3 to 135.3MHz. This gives a receiver coverage of 144MHz to 146MHz using a first i.f. of 10.7MHz.

The receiver's signal frequency amplifier stage uses a dual gate m.o.s.f.e.t. (Tr1), which is inductively coupled by a band-pass filter arrangement, L3 and L4, to a single-gate f.e.t. mixer (Tr2). The 10.7MHz i.f. output from Tr2 is transformer coupled to Tr3 which together with Tr4 offers matching and roofing to a 10.7MHz crystal filter



(FL1). Transistors Tr3 and Tr4 also offer some extra i.f. amplification.

The MC3357 integrated circuit (IC1) performs the following tasks; 2nd local oscillator 10.245MHz, mixer, i.f. amplifier/limiter, discriminator and squelch. The second i.f. selectivity is provided by a 455kHz ceramic filter, type CFM 455F, with a bandwidth of 12kHz.

The squelch circuit in IC1 provides a d.c. level, which when a signal is present, drives Tr11 into conduction and lights the "Busy" indicator l.e.d. (D3). The collector voltage of Tr11 is also used to drive Tr12, which in turn disables the little known mute facility of the LM380 (IC2). If pin 1 of IC2 is taken low the audio output of the chip





Fig. 2: Circuit diagram of receiver



SHOPPING Resistors 0.25W 2% Metal film 47Q 2 R4.5 180Ω **R25** 220Ω R3 270₽ 2 R23,27 330Ω 1 **R26** 390Ω R41 2 470Ω R36,39 3 R15,30,31 1kQ 1.5kΩ 3 R9,22,35 3 1.8kΩ R7,11,12 2.2kΩ 1 **R18** 2.7kΩ 3 R8,28,42 3.9kΩ 3 R6, 10, 24 6.8kΩ 1 R34 10kQ 4 R17,20,21, 33 22kQ 2 R16,37 39kΩ 1 R14 47kΩ 3 R13,29,32 68kΩ 2 R1,2 100kΩ R40 220kΩ **R19** 470kΩ **R38** Potentiometer, vertical preset 220kΩ R46 Potentiometer, Lin. 3W 10-turn type (Electromail code 173-445) 100kΩ 1 R45

Potentiometer, Log.

Potentiometer,

1

R43

R44

with on/off

Log,

4.7kΩ

switch 10kΩ

1	Capacit		
			ramic plate
1	10pF	1	C16
1	12pF	4	C3,4,7,35
	22pF	1	C25
1	33pF	2	C25 C28,39
1	68pF	2 2	C27,38
	470pF	2	C20,21
	Disc cera	mic	
1	10nF	4	C36,41,43,
-			44
	Monolithi	c cerami	
1	1nF	2	C2,5
I	10nF	12	C6,8-
1			12,33,34,
1			37,40
1			46,50
	Miniature	polyeste	r
1	10nF	1	C30 C22
1	68nF	1	C22
-	0.1µF	8	C1,13,14,15, 24,26,29,42
1	0.22µF	1	C23
1	Polystyre		
1	33pF	1	C49
1	47pF	1	C47
1	150pF	1	C48
1	330pF	1	C45
	Electroly	tic, 16	V single-ended,
1	p.c.b. typ	e	
I	22µF	1	C17
ı	100µF	1	C32
	470µF		C19
	Tantalum	bead 35	5V
1	1µF	2	C31,51
-	4.7µF	1	C18

-20	alummu
	254mm

washers etc.

ductors(1) (see Table 1); Self-adhesive cabinet feet (4); p.c.b.; Knobs (2); 46mm precision multi-turn counter mechanism (Electromail code 509-428); A120 two-part aluminium case 76 x 102 x (5); SK1 single hole SO239 socket; SK2 mono 3.5mm jack socket; 20mm chassis mount fuse holder; 1A 20mm fuse; Hook-up wire; Miniature 2 core screened cable; Miniature 50Q coaxial cable; Small grommet; 6BA Mounting pil-

FL1 10M15A(1); FL2 CFM455F Cirkit stock number 1645522; XL1

HC18U 10.245MHz crystal(1); In-

Semiconductors

D3

D4 D2(3)

D₆

D1

D₅

Tr5,11,12

Tr3,4,10(4)

Tr6-9

Tr2(1)

Tr1(1)

IC2 IC1(1)

IC3

1

Diodes Green I.e.d.

Red I.e.d.

BZY88C8V2

BB609A

1N4148

1N5401

Transistors

2N2369A 4

Integrated circuits

Miscellaneous

3

3

BC237

BF244A

2SK55

3SK81

LM380N

78L05

MC3357P 1

(1) Cirkit Holdings plc, Park Lane, Brox-bourne, Herts EN10 7NQ. Tel: 0992 444111.

lars x 12mm long, nuts, bolts,

(2) Electromail, PO Box 33, Corby, Northants NN17 9EL. Tel: 0536 204555.

(3) Electrovalue Ltd, 28 St Judes Road, Englefield Green, Egham, Surrey TW20 0HB. Tel: 0784 33603.

(4) Maplin Electronic Supplies Ltd, PO Box 3. Rayleigh, Essex SS6 8LR. Tel: 0702 554161.

(5) Minffordd Engineering, Sun Street, Ffestiniog, Gwynedd. Tel: 076 676 2572.



Table 1: Coil Data


Coil No.	Turns	Wire s.w.g.	Coil Former	Remarks
L1	1	_		1/0.6mm insulated hook-up wire wound over L2
L2			Toko S18	Orange with aluminium core
L2 L3 L4 L5				Orange with aluminium core
L4				Orange with aluminium core
L5	1			1/0.6mm insulated hook-up wire wound over L6
L6 L7			Toko S18	Orange with aluminium core
L7				Violet with Ferrite core
L8	21	24	T50-6	enamelled copper wire wound evenly around toroid (Cirkit 55-00506)
L9			Toko 7E	LMC4200A 455kHz a.m./i.f.
T1			Toko 10k	KACS1506A 10.7MHz f.m./i.f. (Cirkit 35-15060)

is muted and its operating current falls accordingly. The LM380 gives final audio amplification to loudspeaker level. Diode D5 provides protection against damage from supply polarity reversal.

L3/L4 share double screening can(1)

Construction

It is suggested that construction commences by soldering in all the resistors. It should be noted that many components are soldered on both sides of the p.c.b. These are to provide both r.f. and 0V returns for track-side earthing networks. All through-board connections are shown on component placement diagram Fig. 3. Next fit all the capacitors taking care over the polarity of the electrolytic and tantalum types. Be careful not to overheat



Internal view of prototype receiver

the polystyrene capacitors in the v.f.o. circuit as these are easily damaged.

Now fit IC1 and IC2 (note IC2 has pins 3-5, 7 and 10-12 soldered to both sides of the p.c.b. to provide earthing and heat sinking). Fit all the transistors, IC3, XL1, FL1, FL2 and all the diodes (take care over polarity). Next wind L8 oscillator coil (see Table. 1), tin the ends and gently push them into their holes in the p.c.b. The finished coil assembly is secured to the p.c.b. with silicone rubber compound, as any movement of the coil will give rise to frequency instability in the v.f.o. Now fit L2-4, L6, L7, L9 and T1, wind L2 and L6 as per Table 1. Then fit suitable screening cans over L1/2 and L3/4. Where off-board connections are to be made fit Veropins (see Fig. 3).

As for the mechanical construction of the receiver, this is up to the individual. The size of the case will depend to some extent on the type of tuning system to be used. The author's prototype used a 10 turn potentiometer and multi-turn dial assembly, purchased at a rally. This arrangement is catered for in the component listing, but a cheaper though more complex design could use two epicyclic drives in series and a normal cermet pot. Details for such a system appeared in July 1985 issue of PW, Part 4 of the PW "Colne". Once the case has been drilled to take the p.c.b. and all off-board controls, the completed p.c.b. may be installed. Next wire up and connect, "Busy" light (D3), the power indicator (D4), the volume, squelch and tuning potentiometers.

Finally check for any short circuits or dry joints especially on the regulated lines. A short on the line to IC1 will almost certainly destroy Tr5.

Alignment

Connect 12V to the receiver preferably via a current-limited p.s.u., and check the current which should be less than 250mA. Should the current be any higher than the specified figure switch the receiver off immediately and investigate. Check the voltage on the regulated supply rails, the one feeding the v.f.o. should be 5V and that for IC1 approximately 7.5V.

Preset the cores of the following inductors; L2-4 set cores to approximately 0.5mm into formers, L6 and L7 set cores to approximately 1mm out of formers. Leave the adjustment of T1 and L9 for the moment.

Connect a frequency counter across R30 or listen on a general coverage receiver. With R45 at maximum frequency position carefully separate the turns on L8 for a reading of 15.03MHz. Next turn R45 to its minimum frequency position and adjust R46 to give a reading of 14.81MHz. Repeat the oscillator alignment procedure several times until the coverage of the v.f.o. is correct.

Following on, connect a voltmeter from TP1 to ground and adjust L7 for a maximum reading. Then with the aid of a diode probe (Fig. 4) on the multimeter, connected to TP2 adjust L6 for a maximum reading. If a frequency counter is available connect it from TP2 to ground and check the local oscillator swings between 133.3MHz and 135.3MHz.

Lastly using a signal generator (or local transmission) tune L2-4, L6 and T1 for best signal-to-noise ratio. Then finally tune L9 for best audio quality and signal-to-noise ratio.




Fig. 4: Details of diode probe

Trouble Shooting

No problems have arisen with the prototype receiver, but in the event of trouble the following d.c. voltages in Tables 2,3 and 4 were obtained on the prototype using a high impedance meter. Receiver supply voltage set at 12V.

Table 2

Device number	Drain	Gate 2	Gate	1 Source					
Tr1	7.7	6.0	0	0					
Tr2	11.9	***	0	0.8					
Tr3	4.8	***	0	1.2					
Tr4	5.7	***	0	0.7					
Tr10	2.2	•••	0	0.8					

Table 3


Device Number	Emitter	Base	Collector
Tr5 Tr6 Tr7 Tr8	7.5 0.3 0.3 7.7	8.2 r.f. 0.6 8.4	12 11.6 11.6 12
Tr9 Tr11	0	0.7 0.7	8.4 0.1 Squelch
Tr11	О	0	open 10.3 Squelch closed
Tr12	0	0.1	6.2 Squelch
Tr12	0	0.7	0 Squelch closed


Table 4


Pin ∲ Number	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
IC1	7.5	6.8	7.1	7.5	1.0	1.0	1.0	7.5	3.0	2.0	2.0	0.5	2.6 0	0	0	2.0
IC2	6.2	0	0	0	0	0	0	6.0 1.8	1777/JN 13	0	0	0	0	12		

^{*=}Squelch closed


Fig. 3: Full-size double-sided track pattern and component location diagram of receiver. Screen made of single sided p.c.b. material suspended below main p.c.b., copper side away from track, with 4 short lengths of wire soldered through holes in main p.c.b.







Garex 50MHz Pre-amplifier



Garex intended it to be.

The pre-amp design actually started life with Timestep Electronics, but the design and manufacturing rights are now held by Garex Electronics. I'm sure there are many of you who will be pleased to hear that this popular design is now readily available again. In fact the pre-amp is available for a whole range of spot frequencies from 40MHz to 200MHz with the amateur bands and 137MHz (WX Satellites) being stock items.

The review sample was supplied ready-wired with 25mm tinned leads for the input, output and ground connections. The red and blue power leads were somewhat longer at 150mm. Also included with the pre-amp was a single-sided A4 instruction sheet which gave a very brief circuit description and details of the connections. A circuit diagram was also included, along with a p.c.b. layout. If you are interested in using the pre-amp at the masthead then you can power feed the preamp via the coaxial cable by implementing a couple of simple mods which are also described in the instruction sheet.

Getting Started

The first thing to do is to find a suitable enclosure, as it is very important to provide adequate screening when dealing with such a high gain circuit. Fortunately I had a 50mm square die-cast box available which was ideal, though I must admit that the pre-amp looked quite lost when finally mounted inside. If you would rather "home-brew" a case then a very effective screened enclosure can be built using double-sided p.c.b.

In order to obtain maximum performance it is also essential to ensure that good quality connectors are used for the r.f. input and output, though if you are hard wiring the pre-amp into a rig, the leads should be kept as short as possible.

The final connection is the power



supply which should be between 8 and 17 volts and well smoothed.

pre-amplifier

50MHz

through its paces.

One final and essential point to remember is that the pre-amp does not have any transmit/receive switching so make sure that you either provide your own switching or, if fitting inside a rig, fit it on the receive side of the TX/RX relay.

Circuit Description

The Garex 50MHz pre-amp uses a well established design which has been used successfully on 144MHz for some time. The active device is a Philips BF981 dual-gate m.o.s.f.e.t. which is biased for optimum performance at 50MHz. There are two tuned circuits, one on the input and one on the output, with the 50Ω matching provided by capacitive taps. The power supply is fed through an RC filter to reduce the risk of instability and to attenuate power supply noise.

Performance

As mentioned earlier, the pre-amp was mounted in a small die-cast box and used at the shack end of the feeder for all the review tests.

The first test was to evaluate the gain of the review sample, which was achieved by using a signal generator with an accurate attenuator. First the generator was connected directly to the 50MHz receiver and tuned to the desired frequency. The attenuator was then adjusted to give a reading of S9 on the receiver. The attenuator reading was noted and the pre-amp was then connected between the generator and the receiver. The attenuator was then re-adjusted to give the same S9 reading on the receiver's S-meter. The difference between the two attenuator readings represents the gain of the pre-amp. These tests revealed that there was a 7dB gain spread over the range 50 to 52MHz. The actual figures were 22dB

at 50MHz, 19dB at 51MHz and 26dB at 52MHz. This is actually a very high gain and probably more than required for most applications.

The current consumption was dependent on the supply voltage and ranged from 9mA at 7 volts to 10.5mA at 14 volts. Despite the apparent supply tolerance, the biasing values were optimised for 12 volts so this should be used if possible. The review sample showed a tendency to self oscillation if the input and output were left open circuit. I managed to trace this problem to long power leads, the cure being to provide some additional power supply decoupling. This emphasises the point that great care must be taken when installing any high gain v.h.f. device. The main thing is to ensure that all the connections to the unit are kept as short as possible.


I had a few problems with the on-air performance as the extremely high gain caused overloading of the frontend of my 50MHz rig when there were strong signals about (yes, there are strong signals on 50MHz!). I can't really blame Garex for this, as the preamp was actually performing as designed. I'm sure Garex are only responding to the market demands in producing a such a high gain pre-amp. It seems to be a fact of life that some people gauge the performance of a preamp by the amount of gain it provides, whereas the important point is the noise factor. In practice a gain of around 10 to 15dB is more than adequate for most 50MHz rigs.

Conclusion

The pre-amp design is well tried and has survived the test of time quite well. I still have reservations concerning the high gain, but you can of course pad down the output to reduce it to a more manageable 10 to 15dB. The mechanical construction was sound and the alignment was good, so if you're looking for a small pre-amp either to mount inside your rig or, with a bit more effort, to masthead mount then the Garex 50MHz pre-amp would make a very cost effective choice.

The Garex 50MHz pre-amp costs £11.45 inc. VAT and is available from Garex Electronics, 7 Norvic Road, Marsworth, Tring, Herts. PH23 4LS. My thanks to Garex for the loan of the review sample.

MERLIN WAY, BOWERHILL, MELKSHAM, WILTSHIRE SN12 6TJ. Tel: 0225 706886.



Look out for Merlin Systems at the following rallies and exhibitions, RAFARS, at RAF Halton, Aylesbury, Bucks on June 18, the Longleat Rally on June 26, the NEC Exhibition on the 15, 16, 17 July and the Scarborough Amateur Radio Society Rally on 31 July. You may also call at the Warehouse but please ring first.

NEW SYSTEM

MERLIN SYSTEMS PC Turbo 256K Ram, 8088 CPU, 1 Diskdrive, Hires Mono Monitor, 84 Keyboard, Par printer port, Radio and MSDos software and Merlin Systems backup. £450.00 + £15.00 P&P.

Up Market desk L 102cm \times W 74cm \times H 74cm with keyboard recess and cableing trunking. New only £50.00 + £16.00 P&P.

POWER SUPPLIES AND TRANSFORMERS

Bench mains input PSU in a blue case with switched input and HT output 6.3vac lamp for valve heaters 250vdc HT stabilised. H 115m W 185mm D 125mm \$8.00.

2nd USER SYSTEMS

2nd USER SYSTEMS
BBC B with DFS one 40 track SS drive. £250.00. BBC+ 128K 1770 DFS, S way rom, one 40 track DS drive. £350.00. IOTEC IONA 64K CPM 2.2.2 40 track DS drives.. £160.00. Apple II+ with one disk drive and software. £150.00. FRANKLIN ACE 1000 with disk drive and software this is a Apple compatible. £150.00. P&P £10.00.

COMPUTER PARTS
APPLE cards, \$100 cards, PSUs, NEW 12 inch green screen composit input Hires open frame monitor, only needs 12 volts DC. £30.00. P&P £5.00.

NEW Made by well known Japanese manufacturer, twin cassette mechanism, complete with stereo heads, counter doors and leads only 26.00 P&P £1.00. Complete working LW, MW, FM, stereo music center PCB (the cassette plugs in) only 25.00 P&P £1.50.

PANIAL ELECTROLYTCIS | 5 × 3300ut 25v | 1.30

RADIAL ELECTROLYTCIS		5 × 3300uf 25v	1.30
10 × 4.7uf 25v	30p	2 × 3400uf 40v	75p
10 × 22uf 10v	30p	MISCELLANEOUS	
10 × 22uf 25v	35p	1 × I.E.C. 1amp mains filter socket	1.25
10 × 47u1 25v	35p	1 × I E.C. 3amp mains filter socket	1.50
10 × 47uf 35v	40p	1 × 1 E.C. 6amp mains filter socket	1.75
5 × 47uf 250v	60p	5 × push latching pcb switches	70p
10 × 100uf 10v	35p	5 × slide pcb switches	70p
10 × 220uf 10v	35p	10 × phono plugs	50p
10 × 220uf 16v	35p	5 × 240v panel neons	70p
10 × 220ut 25v	40p	5 × 24v panel lamps	70p
10 × 220uf 40v	45p	5 × MES lamp holders	50p
10 × 220uf 50v	45	5 × 2way 3pole switches with knobs	1.20
10 × 470ut 25v	35p	4 × 4way dill switches	30p
10 × 470ut 50v	E0-	5 x 1.7amp 200v bridge rectifiers	1.20
10 × 1000ut 25v	35p	3 × 1amp 50v bridge rectifiers	50p
POWER ELECTROLYTICS	- 03150	10 × 5mm × 2mm red leds.	1.00
5 × 50ut × 50 ut 200v	60p	3 × 5mm × 2mm green leds	1.00
2 × 220uf 315v	1.75	MERLINS KIT PACKS	
2 × 220uf 400v	2.00	1 × mixed power capacitors	1.75
2 × 470ut 200v	1.50	1 × mixed pf capacitors	1.50
2 × 15000u125v	1.75	1 × mixed axial electrolytics	1.50
2 × 22000ut 25v	2.00	1 × mixed wire wound resistors	2.20
		Post and Packing, up to £10.00 a	
			uu £1.50,
£10.00 to £20.00 add £1.00. F	nease add VAI	to total.	

BONEX

12 Elder Way, Langley Business Park, Slough, Berkshire SL3 6EP Telephone: 0753 49502 Fax: 0753 43812

Telex: 848132

DISTRIBUTORS OF ELECTRONIC COMPONENTS

CHANGE OF ADDRESS FROM LONDON OFFICES

We wish to advise you that BONEX LTD have moved to new and larger premises, and are now situated at the above address.

The following products are available from BONEX:

- * I.F. Transformers
- ★ Fixed Inductors
- ★ Axial Inductors
- ★ Chip Inductors
- ★ High-power Inductors
- ★ Moulded Coils
- ★ Variable Coils
- ★ Quadrature Coils
- ★ Ceramic Filters
- ★ Crystal Filters ★ Helical Filters
- ★ Linear Filters
- ★ Pilot Tone Filters
- ★ U.H.F. Filters
- ★ Toroidal Rings
- ★ Ferrite Cores/Beads
- ★ Quartz Crystals
- ★ Signal Diodes
- * Varicap Diodes ★ Zener Diodes
- ★ Double Balanced Mixers

- * Ni-Cads, Cables
- ★ Silver/Enamelled Wires
- ★ Full Range of Capacitors
- * Variable R.F. Trimmers
- ★ Full Range of Connectors
- * BNC/PL259TNC/F/Adapters
- * Hardware, Boxes, Heatsinks
- ★ CMOS, TTL, Linear I.C.s
- ★ Voltage Regulators
- * Small Signal Transistors ★ Audio/Power Transistors
- * R.F. L. Power Transistors
- * R.F. H. Power Transistors
- * Field Effect Transistors
- * Gas F.E.T.s
- ★ VMOS, Mosfets, Darlingtons
- ★ Switches, Test Equipment
- * Expo Drills, Antex Irons
- ★ Tools, Cutters, Reamers
- ★ Drake Transformers
- ★ Vero Board, Bread Boards

Please ring for more details, catalogue available

GAREX ELECTRON

WEATHER SATELLITE SYSTEMS

This is the genuine MICROWAVE METEOSAT system, 24 hour geostationary (prediction charts not required)

Not to be confused with cheaper, computer add-on devices that normally utilise the VHF Satellites which are only usable for a few minutes at a time.

Our complete plug in and go package requires no computer, no software, and can be up and running, including dish alignment within 10 minutes.

Nothing more to buy: Dish, Microwave Receiver, Frame Store, 12" B/W Monitor AND ALL PLUGS & CABLES £995.95 Expandable to include VHF Satellites and colour. Designed by Timestep Electronics, now supplied by Garex.

* * NEW * * The spectacular NIMBUS system

For stunning animated views of weather events as they move across the globe, this is the COMPLETE GROUND STATION: dish, microwave receiver, RM Nimbus Microcomputer, colour (or B/W) monitor and ALL SOFTWARE, PLUGS AND CABLES. Yes, everything!

More wonders than we can describe in this space!! Call or write for further details.

VHF SYSTEMS

£74.75

£155.25

£454.25

Anniversary

£42.50

£49.95

VHF Active Antenna + 35mm cable VHF 10 Channel Receiver Colour Frame Store (suits VHF & Microwave) SAE for full details and prices of other 'separates'

GAREX VHF RECEIVERS

The celebrated Timothy Edwards designs now owned & manufactured by GAREX.

- * A simple but versatile design capable of covering spot frequencies in the range 25-200MHz.
- * Excellent sensitivity (typically better than 0.4μV for 12dB SINAD).
- ★ Double superhet (10.7MHz and 455kHz IFs).
- Choice of IF bandwidths from weather satellite to '12.5kHz' PMR standards.
- The basic receiver is single channel crystal controlled. Multichannel options.
- ★ 2 watt audio output stage having a low quiescent current. ★ Size: 153 × 33mm. Requires 10-14V DC supply.

PRICES:

Stock Versions: (fully assembled, aligned & tested boards) 6m, 4m, 2m & Weather Sat.

Complete cased versions & special options: details & prices on request. Crystals can be supplied if required; most popular 2 metre frequencies and the currently active Weather satellites are readily available. Crystal prices on request. £15.50

Mains power supply module

GAREX VHF PREAMPLIFIERS

- ★ Compact size: 34 × 9 × 15mm
- ★ Up to 26dB gain

25th

*

1963-1988

Year

Anniversary

25th

*

*

*

Year

*

886

Anniversary

- ★ Can be made for any frequency in the range 40-200MHz
- ★ 3dB bandwidth ±3MHz (at 145MHz)
- ★ Uses BF981 (0.7dB NF at 200MHz)
- ★ Input & output impedance 50 ohms
- ★ 1dB compression: +10dBm
 ★ Saturated output: +15dBm

* Supply voltage 8-17V DC at 5-10mA
Stock Versions: (fully assembled, aligned & tested boards)
6m, 4m, 2m, & Weather Sat.
£11.45

Other versions: prices & details on request.

- * NEW * HIGH PERFORMANCE * 2 METER PRE-AMPLIFIER
- ★ 3 band-pass stages for improved selectivity.
- * 16dB gain with 1dB NF.
- * RF switched (failsafe action): gas-filled relays. Assembled, tested

Main Distributors for REVCO ELECTRONICS LTD.

Ask for details of the latest REVCO "Whippet" and "Kwikfit" antennas and solderless co-axial adaptors (see PW June 87).

> Prices include UK P&P and 15% VAT Ask for details of our Interest Free Credit

GAREX ELECTRONICS

HARROW HOUSE, AKEMAN STREET, TRING HP23 6AA TEL: TRING (044282) 8580 and CHEDDINGTON (0296) 668684

Callers by appointment only

* * * * 25th Anniversary Year 1963-1988 * * *

BOOK SERVICE

The books listed have been selected as being of special interest to our readers. They are supplied from our editorial address direct to your door. Some titles are overseas in origin.

HOW TO ORDER

Add 75p per order postage (overseas readers add £1.50 for surface mail postage) and send a postal order, cheque or international money order with your order (quoting book titles and quantities) to PW Publishing Limited, FREEPOST, Enefco House, The Quay, Poole, Dorset BH15 1PP. Payment by Access, Mastercard, Eurocard or Visa also accepted on telephone orders to Poole (0202) 678558. Books normally despatched by return of post but please allow 28 days for delivery.

★ A recent addition to our Book Service.

O/P = Out of print, O/S = Out of stock.

RADIO

★ AIR & METEO CODE MANUAL
Joerg Klingenfuss 10th edition
Contains detailed description of the World Meteorological Organisation Global Telecommunication System operating FAX and RTTY meteo stations, and of its message format with decoding examples. Also contains detailed description of the Aeronautical Fixed Telecommunication Network amongst others. 293 pages £14.00

BETTER RADIO/TV RECEPTION A. Nallawalla, A. T. Cushen and B. D. Clark

An Australian publication giving guidance and advice both to listeners seeking reliable reception of some distant radio station, and to DX listening hobbyists. 134 pages £9.95

BETTER SHORTWAVE RECEPTION (USA) W. S. Orr W6SAI & S. D. Cowan W2LX
Receivers, antennas, propagation, DX listening techniques for the short waves and v.h.f. 158 pages €5.50

★ PASSPORT TO WORLD BAND RADIO
This book gives you the information you need to explore
and enjoy the world of broadcast band listening. It
includes features on different international radio stations, receiver reviews and advice as well as the hours and language of broadcast stations by frequency. 398 pages £11.95

SCANNERS (updated)
Peter Rouse GU1DKD
A guide for users of scanning receivers, covering hardware, antennas, accessories, frequency allocations and operating procedure. 177 pages £7.95

SCANNERS 2
Peter Rouse GU1DKD
The companion to Scanners, this provides even more information on the use of v.h.f. and u.h.f. communications band and gives constructional details for accessories to improve the performance of scanning equipment.

* SHORT WAVE RADIO LISTENERS' HANDBOOK Arthur Miller

In easy-to-read and non-technical language, the author guides the reader through the mysteries of amateur, broadcast and CB transmissions. 207 pages £6.99

RADIOTELETYPE CODE MANUAL

★ RADIOTELETYPE CODE MANUAL

10th Edition

Joerg Klingenfuss

This book provides detailed descriptions of the characteristics of telegraph transmission on short waves, with all commercial modulation types including voice frequency telegraphy. It provides comprehensive information on all RTTY systems and c.w. alphabets. 96 pages £8.00

THE SATELLITE EXPERIMENTER'S HANDBOOK (USA)
A guide to understanding and using amateur radio, weather and TV broadcast satellites. 207 pages. £9.25

BEGINNERS

AN INTRODUCTION TO RADIO DXING (BP91)

R. A. Penfold

How to find a particular station, country or type of broadcast and to receive it as clearly as possible. 112 pages £1.95

BEGINNER'S GUIDE TO RADIO (9th Edition)
Gordon J. King
Radio signals, transmitters, receivers, antennas, components, valves and semiconductors, CB and amateur radio are all dealt with here. 266 pages £6.95

BEGINNER'S GUIDE TO ELECTRONICS
Owen Bishop
For youngsters thinking of a career in electronics; theory and applications in computers, radio, TV, recording, medical and industrial electronics. 240 pages £5.95

ELECTRONICS SIMPLIFIED—CRYSTAL SET CONSTRUCTION (BP92)
F. A. Wilson
This is a book especially written for those who wish to

take part in basic radio building. All the crystal sets in the book are from old designs but updated to take account of modern components. 72 pages, £1.75

QUESTIONS & ANSWERS

Basics of electrical theory, radio and semiconductors, receivers, amateur and CB radio, and test equipment. 110 pages £3.95

THE SIMPLE ELECTRONIC CIRCUIT AND COMPONENTS Book 1 (BP62)
The aim of this book is to provide an in expensive but comprehensive introduction to modern electronics. 209 pages £3.50

TELEVISION

AN INTRODUCTION TO SATELLITE TELEVISION (BP195) F. A. Wilson

Answers all kinds of questions about satellite television. Answers all kinds of questions about satellite television. For the beginner thinking about hiring or purchasing a satellite TV system there are details to help you along. For the engineer there are technical details including calculations, formulae and tables. Plenty of advice for the d.i.y. enthusiast. 104 pages. £5.95

A TV-DXERS HANDBOOK (BP176)
R. Bunney
Information on transmission standards, propagation, receivers including multi-standard, colour, satellites, antennas, photography, station identification, interference, etc. Revised and updated 1986. 87 pages £5.95

SATELLITE TELEVISION

Peter S. Pearson
How satellite TV works, setting up your own TVRO terminal, the costs, the programmes available. 72 pages

GUIDE TO WORLD-WIDE TELEVISION TEST CARDS

Edition 2
Keith Hamer and Garry Smith
The main purpose of this book is to assist long distance
television enthusiasts (TV DXers) around the world with
signal identification. There are 240 test cards, identification slides and clock captions pictured. It is in "semialphabetical" order, that is the stations are in alphabetical
order in their geographical sections. 52 pages O/P

THEORY

AMATEUR RADIO & ELECTRONICS STUDY GUIDE

3rd Edition

In Ridpath ZL18CG

This book aims to fill the gap between high level amateur radio handbooks and over-simplified beginners manuals. It is written in a "students own notes" format that hopes to put the reader more at ease than formally written text books do. 216 pages £7.00

COMMUNICATION (BP89)
(Elements of Electronics—Book 5)
F. A. Wilson
Fundamentals of line, microwave, submarine, satellite, digital multiplex, radio and telegraphy systems are covered, without the more complicated theory or mathematics. 256 pages £2.95

FOUNDATIONS OF WIRELESS
AND ELECTRONICS (10th Edition)
M. G. Scroggie and S. W. Amos
Covering d.c. and a.c. circuits, L. C, tuned circuits and
selectivity, valves, semiconductors, transmission lines,
antennas, radiation, oscillation, modulation, detection,
amplification, superhet receivers, c.r.t.s, waveform generators and switches, computers and power supplies. erators and swind 551 pages £8.95

LEVEL II RADIO & ELECTRONICS THEORY Ian Ridpath ZL18CG
A sequel to Amateur Radio & Electronics Study Course, this book covers advanced theory up to a level needed on most technician courses. The handwritten format is designed to make the student feel as though the pages are his own notes. 169 pages £6.70

PRACTICAL ELECTRONICS CALCULATIONS AND FORMULAE (BP53) F. A. Wilson This has been written as a workshop manual for the

LISTENING GUIDES

AIR BAND RADIO HANDBOOK
David J. Smith
With air band radio you can eavesdrop on the conversations between aircraft and those on the ground who
control them. The author, an air traffic controller, explains more about this listening hobby. 174 pages
F5 90

electronics enthusiast. There is a strong practical bias and higher mathematics have been avoided where possible. 249 pages £3.95

FLIGHT ROUTINGS 1988
T. T. Williams
Identifies the flights of 168 airlines, schedule, charter, cargo and mail, to and from the UK and Eire and overflights between Europe and America. 104 pages £4.00

DIAL SEARCH (5tir Edition 1988/89) George Wilcox The listener's check list and guide to European broadcasting. Covers medium wave, long wave, v.h.f. and short wave, including two special maps, making the most of your portable and many more. 46 pages £3.25

AIR TRAFFIC CONTROL
David Adair
A guide to air traffic control with maps, drawings and photographs explaining how aircraft are guided through crowded airspace. 176 pages £6.99

GUIDE TO BROADCASTING STATIONS
19th Edition (1987/88)
Philip Darrington
Frequency and station data, receivers, antennas, Latin
American DXing, reporting, computers in radio, etc. 240 American DX pages £6.95

* GUIDE TO FACSIMILE STATIONS

★ GUIDE TO FACSIMILE STATIONS
8th Edition
Joerg Klingenfuss
This manual is the basic reference book for everyone interested in FAX. Frequency, callsign, name of the station, ITU country/geographical symbol, technical parameters of the emission are all listed. All frequencies have been measured to the nearest 100Hz. 262 pages £12.00

GUIDE TO FORMER UTILITY TRANSMISSIONS 3rd Edition

Joerg Klingenfuss

This manual is built on continuous monitoring of the radio spectrum from the sixties until the recent past. It is a useful summary of former activities of utility stations and provides information to the active radio monitor in the classification and identification of radio signals. 126 pages £8.00

GUIDE TO UTILITY STATIONS

GUIDE TO UTILITY STATIONS
6th Edition
Joerg Klingenfuss
This book covers the complete short wave range from 3 to 30MHz plus the adjacent frequency bands from 0 to 150kHz and from 1.6 to 3MHz. It includes details on all types of utility stations including FAX and RTTY. There are 15802 entries in the frequency list and 3123 in the alphabetical callsign list plus press services and meteorological stations. 494 pages £19.00

HF OCEANIC AIRBAND COMMUNICATIONS (3rd Edn.)
Bill Laver
Aircraft channels by frequency and band, main ground radio stations, European R/T networks, North Atlantic control frequencies. 29 pages £3.50

★ INTERNATIONAL RADIO STATIONS GUIDE (BP255) Updated and completely re-written in June 1988. It provides the casual listener and DXer with an essential reference work designed to guide them around the ever more complex radio bands. 312 pages £4.95

THE COMPLETE VHF/UHF FREQUENCY GUIDE

THE COMPLETE VHF/UHF FREQUENCY GUIDE Updated 1988

This book gives details of frequencies from 26–2250MHz with no gaps and who uses what. Recently updated, there are chapters on equipment requirements as well as antennas, etc. 88 pages. £5.95

THE INTERNATIONAL VHF FM GUIDE

Julian Baldwin G3UHK & Kris Partridge G8AUU
The latest edition of this useful book gives concise
details of repeaters and beacons worldwide plus coverage maps and further information on UK repeaters. 70 pages £2.85

UK LISTENERS CONFIDENTIAL FREQUENCY LIST (5th Edition) Bill Laver

Covering the services and transmission modes that can be heard on the bands between 1.635 and 29.7MHz. 147 pages £6.95

VHF/UHF AIRBAND FREQUENCY GUIDE

(Updated)
A complete guide to the airband frequencies including how to receive the signals, the frequencies and services, VOLMET and much more about the interesting subject of airband radio. 74 pages. £5.95

WORLD RADIO TV

WORLD RADIO TV
HANDBOOK 1988
Country-by-country listings of long, medium and short wave broadcasters and TV stations. Receiver test reports. English language broadcasts. The s.w.l.'s "bible". 576 pages £17.95

INTERFERENCE

INTERFERENCE HANDBOOK (USA) William R. Nelson WA6FQG

How to locate and cure r.f.i. for radio amateurs, CBers and TV and stereo owners. 253 pages £6.75

RADIO FREQUENCY INTERFERENCE (USA)

What causes r.f.i? Are all r.f.i. problems difficult, expensive and time-consuming to cure? These questions and many more are answered in this book. 84 pages £4.30

TELEVISION INTERFERENCE MANUAL (RSGB)

B. Priestley
TV channels and systems, spurious-radiation TVI,
strong-signal TVI, audio breakthrough, transmitter design. 78 pages £2.94

AMATEUR RADIO

AMATEUR RADIO CALL BOOK (RSGB)
Winter 87/88 Edition
This useful work now incorporates a 48-page reference
section of useful information for amateur radio enthusiasts. 310 pages £7.25

AMATEUR RADIO LOGBOOK Standard logbook for the Standard logbook for the transmitting amateur in horizontal A4 format. 25 lines per page. 96 pages £2.30

AMATEUR RADIO
OPERATING MANUAL (RSGB)
A mine of information on just about every aspect of amateur operating, including international callsign series holders, prefix lists, DXCC countries list, etc. 204 pages

AMATEUR RADIO SATELLITES the first 25 years Arthur C. Gee G2UK
The material in this souvenir publication is drawn from the author's archives. It is mainly a pictorial account on the pattern of developments which have occurred over the last 25 years. 34 pages £2.25

CARE AND FEEDING OF POWER GRID TUBES

(USA)
This handbook analyses the operation of EIMAC power grid valves and provides design and application informa-tion to assist the user of these valves 156 pages £6.75

HOW TO PASS THE RADIO AMATEURS' EXAMINATION (RSGB) G. L. Benbow G3HB The background to multiple choice exams and how to study for them with nine sample RAE papers for practice, plus maths revision. 91 pages £3.00

PASSPORT TO AMATEUR RADIO
Reprinted from PW 1981-1982
The famous series by GWJGA, used by thousands of successful RAE candidates as an aid to their studies. Plus other useful articles for students of amateur radio. 96 pages £1.50

QUESTIONS & ANSWERS
AMATEUR RADIO
F. C. Judd G2BCX
What is amateur radio? The Radio Amateurs' Exam and
Licence. The technology, equipment, antennas, operating procedure and codes used by amateurs. 122 pages

RADIO AMATEUR'S GUIDE RADIO WAVE PROPAGATION (HF Bands) F. C. Judd G2BCX

The how and why of the mechanism and variations of propagation in the h.f. bands. 144 pages £8.95

RADIO AMATEUR'S MAP OF NORTH AMERICA (USA) Shows radio amateurs prefix boundaries, continental boundaries and zone boundaries. 760 x 636mm £2.25

RADIO AMATEUR'S PREFIX MAP OF THE WORLD (USA) Showing prefixes and countries, plus listings by order of country and of prefix. 1014 × 711mm £2.50

RADIO AMATEUR'S WORLD ATLAS (USA)

17 pages of maps, including the world-polar projection. Also includes the table of allocation of international callsign series. £2.95

THE RADIO AMATEUR'S DX GUIDE (USA)

15th Edition
The guide contains information not easily obtained

elsewhere and is intended as an aid and quick reference for all radio amateurs interested in DX. 38 pages. £2.95

THE RADIO AMATEUR'S QUESTIONS & ANSWER REFERENCE MANUAL 3rd Edition

ANSWER REFERENCE MANUAL 3rd Edition R.E.G. Petri G8CCJ
This book has been compiled especially for students of the City and Guilds of London Institute RAE. It is structured, with carefully selected multiple choice questions, to progress with any recognised course of instruction, although it is not intended as a text book. 258 pages F8 95.

THE 1988 ARRL HANDBOOK FOR THE RADIO AMATEUR

THE RADIO AMATEUR
This, the sixty-fifth edition is available only in hardback, the first time the ARRL have done this. New construction projects are the theme of this edition, there is a deluxe memory keyer, receiver projects, a linear QSK converter, a low-powered balanced Transmatch and a d.t.m.f. decoder. Updated every year, this provides useful reference material for the radio amateur. It also includes 18 pages of p.c.b. track pattern for you to build your own boards. 1157 pages £19.25 (hardback)

VHF HANDBOOK FOR RADIO AMATEURS (USA) H. S. Brier W9EGQ & W. I. Orr W6SAI

nd satel-VHF/UHF propagation, including moonbounce an lites, equipment and antennas. 335 pages £7.95

VHF/UHF MANUAL (RSGB)
G. R. Jessop G6JP
Theory and practice of amateur radio reception and transmission, between 30MHz and 24GHz. 520 pages

DATA & REFERENCE

DIGITAL IC EQUIVALENTS AND PIN CONNECTIONS (BP140)

AND PIN CONTROL

A. Michaels
Equivalents and pin connections of a popular selection of
European, American and Japanese digital i.c.s. 256

INTERNATIONAL DIODE **EQUIVALENTS GUIDE (BP108)**

A. Michaels

Possible substitutes for a large selection of many different types of semiconductor diodes. 144 pages £2.25

INTERNATIONAL TRANSISTOR EQUIVALENTS GUIDE (BP85)

Possible substitutes for a popular selection of Europear American and Japanese transistors. 320 pages £3.50

LINEAR IC EQUIVALENTS AND PIN CONNECTIONS (BP141) A. Michaels

Equivalents and pin connections of a popular selection of European, American and Japanese linear i.c.s. 320 pages

NEWNES AUDIO & HIFI ENGINEER'S POCKET

Vivian Capel
The is a concise collection of practical and relevant data for anyone working on sound systems. The topics covered include microphones, gramophones, CDs to name a few. 190 pages Hardback £9.95

NEWNES COMPUTER ENGINEER'S POCKET BOOK

POCKET BOOK
This is an invaluable compendium of facts, figures, circuits and data and is indispensable to the designer, student, service engineer and all those interested in computer and microprocessor systems. 203 pages Hardback £8.95

NEWNES ELECTRONICS POCKET BOOK

5th Edition
Presenting all aspects of electronics in a readable and largely non-mathematical form for both the enthusiast and the professional engineer. 315 pages Hardback

NEWNES RADIO AMATEUR AND LISTENER'S POCKET BOOK Steve Money G3FZX
This book is a collection of useful and intriguing data for the traditional and modern radio amateur as well as the short wave listener. Topics such as AMTOR, packet radio, SSTV, computer communications, airband and maritime communications are all covered. 160 pages Hardback £8.95 Hardback £8.95

NEWNES RADIO AND ELECTRONICS ENGINEER'S POCKET BOOK (17th Edition) Keith Brindley

Useful data covering maths, abbreviations, codes, symbols, frequency bands/allocations, UK broadcasting stations, semiconductors, components, etc. 201 pages Hardback £6.95

★NEWNES TELEVISION AND VIDEOENGINEER'S POCKET BOOK

Eugene Trundle

This is a valuable reference source for practitioners in
'entertainment' electronic equipment. It covers TV
reception from v.h.f. to s.h.f., display tubes, colour
camera technology, video recorder and video disc equipment, video text and hi-fi sound. 323 pages Hardback
£9.95

POWER SELECTOR GUIDE (BP235)

J. C. J. Van de Ven

This guide has the information on all kinds of power devices in useful categories (other than the usual alpha numeric sort) such as voltage and power properties making selection of replacements easier. 160 pages £4.95

RSGB RADIO DATA REFERENCE BOOK

G. R. Jessop G6JP
The 5th Edition of an essential book for the radio amateur's or experimenter's workbench. 244 pages Hardback £8.56

SEMICONDUCTOR DATA BOOK

A. M. Ball
Characteristics of about 10 000 transistors, f.e.t.
u.j.t.s, diodes, rectifiers, triacs and s.c.r.s. 175 pag
£9.95

TRANSISTOR SELECTOR GUIDE (BP234)
J. C. J. Van de Ven
This guide has the information on all kinds of transistors in useful categories (other than the usual alpha numeric sort) such as voltage and power properties making selection of replacements easier. 192 pages £4.95

FAULT-FINDING

ARE THE VOLTAGES CORRECT?
Reprinted from PW 1982-1983
How to use a multimeter to fault-find on electronic and radio equipment, from simple resistive dividers through circuits using diodes, transistors, i.c.s and valves. 44 pages £1.50

GETTING THE MOST FRC /I YOUR MULTIMETER (BP239) R. A. Penfold

n. A. Pentold This book is primarily aimed at beginners. It covers both analogue and digital multimeters and their respective limitations. All kinds of testing is explained too. No previous knowledge is required or assumed. 102 pages £2.95

* MODERN ELECTRONIC TEST EQUIPMENT

Keith Brindley
This book describes in a down-to-earth manner how the main categories of test equipment work. The subjects covered include analogue and digital meters, oscilloscopes, signal sources, frequency, time and event counters, spectrum and logic analysers, displays and automatic test equipment. 134 pages £6.95

OSCILLOSCOPES, HOW TO USE THEM, HOW

THEY WORK (Revised 2nd Edition)

lan Hickman

This book describes oscilloscopes ranging from basic to advanced models and the accessories to go with them 133 pages £6.95

PRACTICAL HANDBOOK OF VALVE RADIO REPAIR

VALVE RADIO REPAIR
Chas E Miller
The definitive work on repairing and restoring valved broadcast receivers dating from the 1930s to the 60s Appendices giving intermediate frequencies, valve characteristic data and base connections. 230 pages Hardback £17.50

QUESTIONS & ANSWERS
RADIO REPAIR
Les Lawry-Johns
How to fault-find and repair valved and transistorised receivers, car radios and unit audio equipment. Suggested lists of tools and spare parts. 106 pages £3.95

SERVICING RADIO

HI-FI AND TV EQUIPMENT
Gordon J King
A very practical book looking at semiconductor characteristics, d.c. and signal tests, fault-finding techniques for audio, video, r.f. and oscillator stages and their application to transistor radios and hi-fi 205 pages £9.95

TRANSISTOR RADIO FAULT FINDING CHART (BP70) C. E. Miller

Used properly, should enable most common faults to be traced reasonably quickly. Selecting the appropriate fault description at the head of the chart, the reader is led through a sequence of suggested checks until the fault is cleared. 635 × 455mm (approx) £0.95

PROJECT CONSTRUCTION

HOW TO BUILD ADVANCED SHORT WAVE RECEIVERS (BP226) R. A. Penfold

Greater satisfaction can be gained from the hobby of shortwave listening when using home constructed equipment. This book gives full practical constructional details of a number of receivers as well as some add-on circuits like S-meters and noise limiters. 118 pages

HOW TO DESIGN AND MAKE YOUR OWN P.C.B.s (BP121) R. A. Penfold

Designing or copying printed circuit board designs from magazines, including photographic methods 80 pages

INTRODUCING ORP
Collected Articles from PW 1983-1985
An introduction to low-power transmission, including constructional details of designs by Rev. George Dobbs G3RJV for transmitters and transceivers from Top Band to 14MHz, and test equipment by Tony Smith G4FAI. 64 pages £1.50

MORE ADVANCED POWER SUPPLY PROJECTS

MORE ADVISOR (BP192)
R. A. Penfold
The practical and theoretical aspects of the circuits are covered in some detail. Topics include switched mode power supplies, precision regulators, dual tracking regulators and computer controlled power supplies, etc. 92

POWER SUPPLY PROJECTS BP76 R. A. Penfold

This book gives a number of power supply designs including simple unstabilised types, fixed voltage regulated types and variable voltage stabilised designs. 91

PRACTICAL POWER SUPPLIES
Collected Articles from PW 1978-1985
Characteristics of batteries, transformers, rectifiers, fuses and heatsinks, plus designs for a variety of mainsdriven power supplies, including the PW "Marchwood" giving a fully stabilised and protected 12V 30A d.c. 48 pages £1.25

ROJECTS IN AMATEUR RADIO AND SHORT VAVE LISTENING

WAVE LISTENING
F. G. Rayer G30GR
Full constructional details are given for all projects, including housing the units in a suitable case. All the projects are either on p.c.b. or matrix board. 90 pages £4.95

★ QRP NOTEBOOK
Doug DeMaw W1FB
This book deals with the building and operating of a successful QRP station. Lots of advice is given by the author who has spent years as an ardent QRPer. All the text is easy to read and the drawings are large and clear. 77 pages £3.95

SOLID STATE SHORT WAVE RECEIVERS FOR BEGINNERS (BP222)

BEGINNERS (BP222)
R. A. Penfold
There is a strange fascination in listening to a broadcast which has been transmitted over many thousands of kilometres. This is even more the case when you've built the receiver yourself. This book contains several designs will give a fairly high level of performance. 93 pages £2.95

AUDIO FREQUENCIES

AUDIO (BP111)
(Elements of Electronics—Book 6)
F. A. Wilson
This book studies sound and hearing, and the operation of microphones, loudspeakers, amplifiers, oscillators, and both disc and magnetic recording. 320 pages £3.50

ANTENNAS (AERIALS)

AERIAL PROJECTS (BP105)

R. A. Penfold Practical designs including active, loop and ferrite aerials plus accessory units. 96 pages £1.95

ALL ABOUT CUBICAL QUAD ANTENNAS (USA) W. I. Orr W6SAI & S. D. Cowan W2LX

Theory, design, construction, adjustment and operation of quads. Quads vs. Yagis. Gain figures. 109 pages O/S

ALL ABOUT VERTICAL ANTENNAS (USA) W. I. Orr W6SAI and S. D. Cowan W2LX Theory, design, construction, operation, the secrets of making vertical work. 191 pages £7.50

AN INTRODUCTION TO ANTENNA THEORY (BP198)

H. C. Wright

This book deals with the basic concepts relevant to receiving and transmitting antennas. Lots of diagrams

reduce the amount of mathematics involved. 86 pages £2.95

BEAM ANTENNA HANDBOOK (USA)
W. I. Orr W6SAI & S. D. Cowan W2LX
Design, construction, adjustment and installation of h.f.
beam antennas. 198 pages €6.75

OUT OF THIN AIR

Collected Antenna Articles from PW 1977-1980 Including such favourites as the ZL Special and "2BCX 16-element beams for 2m, and the famous "Slim Jim", designed by Fred Judd GZBCX. Also features systems for Top Band, medium wave/long wave loop designs and a v.h.f. direction finding loop. Plus items on propagation, accessories and antenna design. 80 pages £1.80

SIMPLE, LOW-COST WIRE ANTENNAS FOR RADIO AMATEURS (USA)
W. I. Orr W6SAI and S. D. Cowan W2LX
Efficient antennas for Top Band to 2m, including "invisible" antennas for difficult station locations. 191 pages £6.75

THE ARRL ANTENNA BOOK

14th Edition (USA)
A station is only as effective as its antenna system. This book covers propagation, practical constructional details of almost every type of antenna, test equipment and formulas and programs for beam heading calculations. 327 pages £9.10

THE ARRL ANTENNA COMPENDIUM Volume 1

(USA)
This book makes fascinating reading of hitherto unpublished material. Among topics discussed are quads and loops, log periodic arrays, beam and multi-band antennas, verticals and reduced size antennas. 175 pages £9.25

THE RADIO AMATEUR ANTENNA HANDBOOK William I. Orr W6SAI & Stuart D. Cowen W2LX Yagi, quad, quagi, I-p, vertical, horizontal and "sloper" antennas are all covered. Also towers, grounds and rotators. 190 pages £6.75

TWO-METRE ANTENNA HANDBOOK F. C. Judd wrote this book for and

F. C. Judd wrote this book for radio amateurs new to the 144-146MHz band. The range of antennas described will cater for most situations, particularly those where space is a problem. 157 pages £6.95

WIRES & WAVES Collected Antenna Articles from PW 1980 Antenna and propagation theory, including NBS Yagi design data. Practical designs for antennas from medium waves to microwaves, plus accessories such as a t.u.s, s.w.r. and power meters, and a noise bridge. Dealing with TVI. 160 pages £3.00

★ W1FB'S ANTENNA NOTEBOOK

Doug DeMaw W1FB

This book provides lots of designs, in simple and easyto-read terms, for simple wire and tubing antennas. All
drawings are large and clear making construction much
easier. 124 pages £4.95

25 SIMPLE AMATEUR BAND AERIALS (BP125)

How to build 25 simple and inexpensive aerials, from a simple dipole through beam and triangle designs to a mini-rhombic. Dimensions for specific spot frequencies, including the WARC bands. 80 pages £1.95

25 SIMPLE INDOOR WINDOW AERIALS (BP136)

AND WINDOW ARRIALS (BF 130)
E. M. Noll
Designs for people who live in flats or have no gardens, etc., giving surprisingly good results considering their limited dimensions. 64 pages £1.75

25 SIMPLE SHORT WAVE **BROADCAST BAND AERIALS (BP132)**

E. M. Noll
Designs for 25 different aerials, from a simple dipole through helical designs to a multi-band umbrella. 80 pages £1.95

25 SIMPLE TROPICAL AND MW BAND AERIALS (BP145)

Simple and inexpensive aerials for the broadcast bands from medium wave to 49m. 64 pages £1.75

COMPUTING

AMATEUR RADIO SOFTWARE (RSGB) John Morris GM4ANB

Using a computer for c.w., RTTY, data, plus calculations for antennas, distance, bearing, locators, satellites, sun, moon and circuit design. 328 pages Hardback £9.41

AN INTRODUCTION TO COMPUTER COMMUNICATIONS (BP177) R. A. Penfold

Details of various types of modern and their applications, plus how to interconnect computers, moderns, and the telephone system. Also networking systems and RTTY. 96 pages £2.95

AN INTRODUCTION TO COMPUTER PERIPHERALS (BP170)
J. W. Penfold
Covers monitors, printers, disk drives, cassette recorders, moderns, etc., explaining what they are, how to use them and the various types of standards. 80 pages £2.50

MICROPROCESSING SYSTEMS AND CIRCUITS (BP77) (Elements of Electronics—Book 4) F. A. Wilson

A comprehensive guide to the elements of micropro-cessing systems, which are becoming ever more in-volved in radio systems and equipment. 256 pages

MORSE

INTRODUCING MORSE
Collected Articles from PW 1982-1985
Ways of learning the Morse Code, followed by constructional details of a variety of keys including lambic,
Triambic, and an Electronic Bug with a 528-bit memory. 1 riambic, and an 48 pages £1.25

THE SECRET OF LEARNING MORSE CODE

Mark Francis
Designed to make you proficient in Morse code in the shortest possible time, this book points out many of the pitfalls that beset the student. 87 pages £4.95

SWAP SPOT

Have Practica BC1 SLR camera, zoom, telephoto, flash plus lots of accessories cost over £250. Would exchange for good v.h.f. receiver or scanner, any make, but must cover 70MHz to 90MHz range amongst others. Mr. Small, 8 Cherry Tree Road, Chinnor, Oxon OX9 E554

Have JWR/M2 CB rig converted 40-channel 29.310MHz to 29.700MHz with mic and lead. Would exchange for similar unconverted CB or 20 volt 15 amp transformer or 430MHz linear amp or 430MHz switched pre-amp, w.h.y? Walshe. Tel: 0609 71636. E562

Have Codar CR-70A short wave radio, works well. Would exchange for capacitance meter with good range. Tom Benfield, 47b Warneford Street, Hackney, London E9 7NG.

Have Hondo II acoustic guitar in leather case as new plus electronic guitar tuner and pick-up. Would exchange for h.f. receiver, please write. 59 Camborne Road, Hattersley, Via Hyde, Cheshire SK14 E579

Have Boat outfit 8ft 3in dinghy, 2 h.p. Yamaha, trailer, life jackets, oars, lighting board, cost £700+. As new, Would exchange for AR2002 scanner in mint condition, G1JNV QTHR Bolton (0204) 852786.

Have SX-200 scanner with manual plus Eddystone EC10 h.f. RX. Would exchange for good h.f. RX, BBC or Spectrum computer, camera outfit or w.h.y? G1OJS QTHR or Tel: Chesterfield 0246 569217. E586

Have home-built 1kV a.c. p.s.u. (mains input), must be collected by arrangement. Would exchange for a useful technical item. Zebreh, 69 Talgarth Road, London W14.

Got a camera, want a receiver? Got a v.h.l. rig, want some h.f. gear to go with your new G-zero? In fact, have you got anything to trade radio-wise?
If so, why not advertise it FREE here. Send details, including what equipment you're looking for, to "SWAP SPOT", Practical Wireless. Enelco House, The Quay, Poole, Dorset BH15 1PP, for inclusion in the first available

issues of the magazine.

A FEW SIMPLE RULES. Your ad. should follow the format of those appearing below, it must be typed or written in block letters, it must be not more than 40 words long including name and address/telephone number. Swaps only—no items for sale—and one of the items MUST be radio related. Adverts for ILLEGAL CB equipment will not

be accepted.

The appropriate licence must be held by anyone installing or operating a radio transmitter.

Have DNT 40 channel f.m. CB with built in mains p.s.u., odds or cash. Would exchange for Yaesu FV-707DM (v.f.o.) with leads and manual. Syd. Tel: Bursledon (042 121) 4333. 1900-0000 hrs. E595

Have crystal set, 1920's Gecophone style, working with original cats whisker, basket wound coil and period Brown's "A" headphones. Would exchange for good SLR camera. Mann. Tel: Cambridge 860150.

Have Yaesu 211RH 144MHz f.m. rig with mobile speaker, Revco magmount antenna all mint. Would exchange for station scope for FT-901DM or FT707 or w.h.y? 10 Apple Tree Road, Stanfree, Bolsover, Chesterfield, Derbyshire. E598

Have Hewlett Packard 7475A six-pen graphics plotter, brand new never been unpacked. Would exchange for 430MHz or 144MHz hand-held transceiver or base station. Tel: 0235 816947.

Have Philips Portable Office P5010 with built in screen, tape recorder and keyboard, brand new never been unpacked. Would exchange for 144MHz or 430MHz hand-held transceiver. Tel: 0235 816947.

Have Trio R-2000 plus VC-10 fitted for Icom IC-R70/71, Trio fitted with Kokusai mechanical filters for s.s.b. and c.w. Would exchange for w.h.y? Tel: 0272 828586 pm except Thursdays or Saturdays. E614

Reg Ward & Co. Ltd. 1 Western Parade, West Street, Axminster, Devon, EX13 5NY. Telephone: Axminster (0297) 34918

Yaesu		о Ісом		KENWOOD			
NCCL	188 00 (3 00) 188 00 (3 00) 188 00 (3 00) 188 00 (3 00) 188 00 (3 00) 188 00 (2 50) 188 00 (2 50) 19 50 (2 00) 10 50 (2 00) 10 50 (2 00) 10 50 (2 00) 12 50 (2 00) 12 50 (2 00) 12 50 (2 00) 12 50 (2 00) 12 50 (2 00) 13 14 50 (2 00) 13 14 50 (2 00) 14 15 10 (2 00) 15 10 (3 00) 16 10 (3 00) 17 10 (3 00) 18 45 (2 00) 18 45 (2 00) 18 45 (2 00) 19 10 (2 00)	AT100 100W ATU (75)1745) AT150 150W ATU (75)1745) 150W ATU (75)5 1	P.O. A. — TSS40S 448.00 — ATS440 949.00 — SP\$40 355.00 13.50 AT\$30S 318.00 AT\$30S 318.00 AT\$30S 318.00 AT\$30S 318.00 AT\$30S 318.00 AT\$40S 478.00 AT\$440 478.00 AT\$440 478.00 AT\$440 478.00 AT\$440 478.00 AT\$440 478.00 AT\$450 478.00 AT\$450	9 Band TX General Cov RX Auto/ATU Ext Speaker 9 Band TX General Cov RX 9 Band TX General Cov RX 9 Band TX General Cov RX Auto/ATU HX Speaker Ext Speaker 10 Band ATUPower Meter External Speaker Unit HX Band ATUPower Meter External Speaker Unit HX Band ATUPower Meter External Speaker 10 Band ATUPower Meter External Speaker 10 Band Soop Unit (830940) 10/160 ZWW Linear 12 M Min H4H 10cm Min H6H 10cm H6	1995 00		
— Datong Products —		VIRROPLEX	SP425	140-525MHz PWR/SWR/PEP 1.8-200-430-800-1240MHz	99.95 (3.00) 59.95 (3.00) 119.95 (3.00) 169.95 (3.00)		
VLF Very low frequency conv. FL2 Multi-mode audio filter FL3 Audio filter for receivers ASP/B r.f. speech clipper for Trio ASP/A r.f. speech clipper for Yaesu	89.70 (2.50) 129.00 (2.50) 82.80 (2.50) 82.80 (2.50)	lambic Standard lambic Deluze Vibrokeyer Standard Vibrokeyer Deluxe The Original Standard The Original Deluxe	63.33 (3.00) 578.09 (3.00) 63.98 (3.00) HANSEN 78.09 (3.00) W720S 73.54 (3.00) FSSE	130/440 MHz 20/200W 3.5-150MHz 20/200W	52.75 (2.50) 42.75 (2.50)		
ASP As above with 8 pin conn D75 Manual RF speech clipper D70 Morse Tutor RFA AD270-MPU Active dipole with mains p.s.u. AD370-MPU DC144/28 ANF ANF Automatic notch filter	36.00 (2.50) 51.75 (2.50) 69.00 (2.50) 39.67 (2.50) 67.85 (2.50)	BENCHER BY1 Squeeze Key, Black base Squeeze Key, Chrome base STARMASTER Kenpro Electronic Keyer Unit (No Paddie)	67.42 (3.00) SMCS 2U 76.97 (3.00) SMCS 2N Kenpro KP21N T30 T100 T200 54.70 (3.00) WAI	Miscellaneous 2 Way 50239 Switch 2 way 'n Sts Switch 1 way Switch 'n' Socket Deluxe 30W Dummy Load 100W Dummy load 200W Dummy load Wavemeter 120-450MLP Packet/RTY Terminal	18.95 (2.50) 23.50 (2.50) 27.00 (2.50) 10.29 (2.50) 45.00 (3.00) 65.00 (3.00) 24.95 (2.00) 269.95 (3.00)		
SRB2 Auto Woodpecker blanker RFA RF switched pre-amp	86.25 (2.50) 36.00 (2.50)	Kenpro Electronic Keyer Unit (No Paddle) Kenpro Electronic Memory Keyer (No Paddle)	54.70 (3.00) WAI 96.00 (3.00) PK232	Packet/RTTY Terminal	269.95 (3.00)		
Instant credit available. Mail/Telephone order by cheque credit card. Cheques cleared before a cods despatched. (F&)	ore -	OPEN TUES - SAT. 9.00-5.30 (CLOSED MONDAYS)	STOCK ITEMS USUALLY DESPATCHED WITHIN 48 HRS.	DELIVERY/INSURANCE I IN BRACKETS	PRICES		



npact and lightweight, an ideal QRP rig for 3.5MHz CW. Great for /P and holiday operation! A COMPLETE kit! - Includes ALL Hardware, VFO, Audio Filter, RIT, Sidetone etc. and fully detailed building instructions £76.25 including postage. (Ready built and air tested £126.50)

Also included in our Kit Range:

	FULL KIT	PART KIT
"CARLTON" 3 Band RX for 80/40/20m	£63.00	
TU1 Mk2 : Antenna Tuning Unit	£36.80	£24.50
TU2 Mk2 : TU with SWR Bridge	£45.00	£32.70
TUA1 : SWR Bridge	£14.50	€ 9.20
AF2 AUDIO FILTER	£11.50	€ 8.50
AF3 BASIC AUDIO FILTER BOARD	2 6.90	
CM1 CAPACITANCE METER	£22.60	£14.00
DEMENDED! The "EIIII" Vite are COMPLETE	in event detail and com-	with EIII I

REMEMBER! The "FULL" Kits are COMPLETE in every detail and come with FULL Instructions. The "PART" Kits consist of the PCB's and all board mounted components plus, of course, the detailed instruction Manual.

All prices include postage

For full details of these and the rest of our range, send a SAE to: LAKE ELECTRONICS, 7 MIDDLETON CLOSE, NUTHALL, NOTTINGHAM NG16 1BX.

or ring Alan, G4DVW on (0602) 382509 (callers by appointment only p

TENNAMAST SCOTLAND MOBILE, PORTABLE, WALL MOUNTED OR TENNAMAST BASE MOUNTED 24 HOUR ANSWER SERVICE TENNAMAST ARE FAST BECOMING THE NAME FOR WIND-UP TILT-OVER MASTS. THEY ARE: EASY TO OPERATE — SAFE TO USE — SLIM AND ELEGANT — SUITABLE FOR HE & WHF. DESIGNED AND BUILT PROFESSIONALLY BY BENTHUSIASTS FOR ENTHUSIASTS. WRITE OR TELEPHONE FOR MORE DETAILS. DESPATCHED NORMALLY WITHIN 7 DAYS. WE CAN ALSO SUPPLY VK2ABO BEAM KITS. ALSO CENTRES AND SPREADERS FOR QUADS AND MANY OTHER ITEMS TOO NUMEROUS TO LIST. It to be a lett by 81 MAINS ROAD BEITH AYRSHIRE KA15 2HT. TEL: (05055) 3824 GM60AL. GM4VHZ.

TEL

QUARTZ CRYSTALS

QuartSLab MARKETING LTD

P.O. Box 19 Erith Kent DA8 1LH Telephone: 01-318 4419 24 hr Ansafone:

Dartford (0322) 330830 Telex: 8813271 GECOMS-G (Attention QUARTSLAB)

An SAE with all enquiries please PRICES NOW INCLUDE VAT

STOCK CRYSTALS

CRYSTALS FOR 2 METRES

HC25 52.70 FOR ONE CRYSTAL 52.50 EACH FOR 2 OR MORE

RX CRYSTALS 44MHz Series Res 14 15MHz 20 & 30pF TX CRYSTALS 12MHz 30 & 40pF 18MHz 25 & 20pF R0-R7, S8-S23, & S32 Scanner Crystals SR9 crystals £3.45

HC6 12.80 FOR ONE CRYSTAL 22.60 EACH FOR 2 OR MORE TX CRYSTALS

4MHz 30pf

AMHz 30pf

AMHz Series res

R0-R7, S R0-R7, S11, S20-23

4 METRE CRYSTALS FOR 70.26 IN HC6/U at £2.80 each TX 8.78250 RX 29.7800

IA 8.7829 RX 29 7800

TOP (GRYSTALS 65.50pr or £3.25 each

TOP (GRYSTALS 65.50pr or £3.25 each

TOP (F1 F1 F2 F7 F7 Series Wood & Douglas and FDK MULTI U11

SUB (433 2) SU20 RB0 RB1 RB2 RB3 RB4 RB5 RB6 RB6 RB10 RB11 RB13 RB14

RB15.

A013, Also for MULTI U11 ONLY SU16 SU18 CONVERTER CRYSTALS IN HC18U AT C3.30 each. 22 000. 38 666, 42 000, 98 000, 101 000, 101 500, 105 666, 116 000 FREQUENCY STANDARDS C3.20 each. HC3U 1000MHz 10 0000MHz.

HCBU 1000Hrz 10.000MHz HCIBU 1000Hz 7 00MHz 10 70MHz 48 00MHz 100 00MHz TONEBURST, I.F. & MPU CRYSTALS IN HCIB 22.60 each. 7 168MHz (FC 1750 HZ 10ne). 10.245 (pt 10.7 I F) 1 3.2768 4.000 5.0688 10.2400 14.3180 15.00000 YAESU CRYSTALS FOR F1101's F7901 & et Ct 60 each. Many available ex stock (A list is available on request please send S.A.E.)

Full list available on request, please send SAE

PRICES NOW INCLUDE VAT

MADE TO ORDER CRYSTALS

FUNDAMENTAL	S	OVERTONES	
FREQUENCY RANGE	PRICE	FREQUENCY RANGE	PRICE
1 TO 1.5MHz	£12.40	3rd OVT 21 00 TO 65 00MHz	€5.25
1.5 TO 2 0MHz	€5.90	5th OVT 60.00 TO 110.0MHz	€5.90
2.0 TO 6.0MHz	€5.50	5th OVT 110 00 TO 125 0MHz	68.83
6 TO 21MHz	£5.25	7th OVT 125.00 TO 175.0MHz	£11.60
21 TO 25MHz	€7.50		

2.0 to 175.0MHz 2 weeks approx. 1 TO 1.499MHz 3 to 4 weeks

Unless otherwise requested fundamentals will be supplied for 30 pt Inati d overtones for series resonate operation.
PLEASE SPECIFY WHEN ORDERING - else HC25*1 capacities and PLEASE SPECIFICATION OF THE MINISTREE OF T

DISCOUNTS Price on application for 10 + units to same frequency specific bulk purchases of mixed frequencies.

COMMRICIAL CRYSTALS, available on last delivery and at competitive prices.

EMERICIAL SERVICE: FOR XTALS 1 to 175MHz. Add the surcharge the such XTAL. Days refer to working days. 4 days. + £12, 6 days. + £7, 8 days. + £5, 13 days. + £8, 13 days. + £8, 13 days. days + Σ 3. CRYSTALS SOCKETS HC25 Ω 0 25 ea. HC6 Ω 0 30 ea. MINIMUM ORDER CHARGE

£1.50 unless ordered with crystals.

TERMS Cash with order post inc. to UK & Ireland. Cheques & PO's to QSI., T.

PRICES NOW INCLUDE VAT

Valved Communications Receivers The BC-348 (Part 2)

This month, Chas E. Miller continues his indepth description of the US Air Force BC-348 series of receivers, covering various modifications to augment their performance and versatility for civilian use, plus notes on servicing and realignment.

It is unlikely that many of these receivers still exist in unmodified form, but as is unfortunately the case with all too many such exercises, the quality of the workmanship and the performance obtained may leave something to be desired. The following notes will assist the owner of a BC-348 to realise the maximum performance. They are based entirely on practical experience with sets spanning a period of some three years.

Power Considerations

The provision of a mains-derived power supply has always been the prime object in the modification of the BC-348, as few domestic locations could tolerate the whine of the dynamotor, quite apart from the difficultty of providing the necessary 24V d.c.! Some informed opinion leans toward having the mains power pack external to the receiver itself, probably in the same cabinet as the loudspeaker, to avoid heat within the set, and this is certainly a point worth consideration. However, if one is prepared to provide a ventilation louvre in the cabinet top, it is perfectly possible to fit a power pack in the space vacated by the redundant dynamotor.

The standard policy for the heaters of the valves was to rewire them for 6.3V parallel operation, in which case they will consume some 2.5A, to which must be added the current drawn by any dial lamps, etc. To be on the safe side the transformer rating must be at least 3A, and preferably somewhat more. An unmodified set could have its heaters supplied by a 24V-28V transformer rated at 0.75A or a little more. The h.t. line being around 225V, a transformer giving at least 250-0-250V is required to allow a drop through the smoothing arrangements. A point that must be noted is that negative bias is employed for the output valve, derived from resistors in



the h.t. negative line. Therefore, the normal practice of earthing the h.t. negative supply rail cannot be followed, and the connection must be made to the terminal formerly used for the dynamotor. It may be more convenient to use standard earthed-can electrolytics rather than the type with an insulated negative, in which case they may be wired as normal (Fig. 2.1), but with the centre-tap of the h.t. winding disconnected from earth and taken to the h.t. negative terminal. A 50µF, 50V electrolytic wired across from h.t. negative to chassis will eliminate any hum that might occur.

Loudspeaker Matching

As with many military receivers, the BC-348 was designed for use with headphones, the output transformer catering for alternative load impedances of 500 or 4500Ω . It is possible to use another transformer to match


one of these outputs to a standard loudspeaker, or to replace the original transformer by a conventional type. The 41 or 6K6GT requires a load of approximately 8000 ohms under its conditions of use in the BC-348; the transformer ratio must, of course, be chosen to suit the impedance of the loudspeaker to be used. If the original transformer is to be retained the additional transformer must be suitable for matching 4500Ω to the loudspeaker impedance The ratio of the windings is found from the well-known formula

$$\sqrt{\frac{Ra}{LS \text{ Impedance}}}$$

For example, a 40Ω loudspeaker requires a transformer of 45:1 turns ratio to match it to the 6K6GT.

Extra A.F. Sensitivity

The above-mentioned use of headphones made it possible for the BC-348 to deliver ample output without the



need for an a.f. voltage amplifier prior to the output stage. It will be found, however, that a.f. sensitivity is just a little too low for really satisfactory loudspeaker work, and improvements in this respect are most desirable. The time-honoured method used was the construction of a small amplifier stage using, say, a 6J5 triode, and built on the ex-dynamotor mounting plate.

There are other options available which may be more attractive, especially if the room on the plate has already been taken up by the a.c. mains power pack. One possibility is to replace the 6K6GT with a high-slope output valve such as the 6AG6. This has a mutual conductance of 10mA/V as compared with the 2.3mA/V of the 6K6GT (or 41) and would greatly increase the a.f. sensitivity. Note though that the bulb size may cause problems in some marks of the receiver, and that the comparatively heavy heater current (1.5A) may require the services of a larger mains transformer.

The Mullard EL33 has a slope of 9mA/V for a heater current of 0.9A and is also worth consideration. Replacement of the 41 by either type just mentioned will, of course, necessitate a change of valve-holder.

If the power pack has been mounted externally to the receiver there will be no shortage of space for another valve stage in the set, but rather than having to carve holes in the dynamotor plate the owner could consider relocating the output valve to a position on the power pack, leaving its vacated holder to accommodate an amplifier triode, such as the 6J5.

In the later marks where a 6SR7 is used as detector/a.g.c./b.f.o. valve an interesting and highly effective modification is possible. This is to replace the final i.f. amplifier (6SR7) with a 6B8 double-diode-pentode as used in the earlier sets; it is fitted into the 6SR7 holder in order that the wiring to the detector and a.g.c. diodes shall remain undisturbed. The alterations to the holder for the pentode section of the 6B8 are minor and easily carried out.

Since the new valve has a top cap for its control grid, the i.f. transformer must be slightly modified to provide a lead from the top of its can instead of the bottom. The construction of the transformer makes this a very simple process which may be achieved with only the removal of the two cansecuring nuts; the stout wires to which the windings are soldered travel the full length of the can and the grid connection is available immediately. All that is required is a small extension to the existing trimmer access holes to accommodate the top cap lead. The valve base vacated by the 6SJ7 may now be used to accommodate a 6SN7 double-triode; one section takes up the duty of b.f.o., the other becomes the extra a.f. amplifier. The writer can vouch for the excellent performance obtainable from this modification. (See Fig. 2.2).

Increased I.F. Sensitivity

The gain of the i.f. stages of the -J and later marks may be increased dramatically by replacing the existing coupling/neutralising coil by a tightlytuned alternative, and dispensing with the crystal filter, if, indeed it has not already been removed by a previous modifier! The coil will be found mounted on a small paxolin panel just above the b.f.o. coil assembly, and may be removed from the front panel. The coil should be put to one side for possible future use, as it makes an excellent b.f.o. coil itself should the existing one fail. The replacement should be wound on a former of similar diameter, into which a portion of an old ferrite antenna rod may be slipped to increase the inductance. About 125 turns of 36 s.w.g. wire will be found to be suitable; it should be shunted by a fixed trimmer of about 270pF, and a variable of 0-100pF. It must be stressed that these values depend a lot on the exact way in which the coil has been wound (pile winding is simple and effective) and may have to be varied to suit the individual. No difficulty should be experienced, however, in producing a coil which will tune to the 915kHz i.f. with a sharpness that will bring a very considerable increase in the gain of the stage.

Separate Gain Controls

The original method of having the r.f. and a.f. gain controls mounted on the same shaft and operating them alternatively is not altogether satisfactory for normal s.w.l. use. When the mode switch is set to "AVC" the r.f. gain control is by-passed to earth via a 100Ω resistor, and is rendered ineffective. Likewise, selecting "Manual"

shorts out the a.f. gain control to give maximum gain, the output of the receiver being controlled only by the r.f. gain control. A better system may be achieved by installing a separate r.f. gain potentiometer ($10k\Omega$) on the front panel, and transferring to it the leads from the original, so that it may be operated independently of the a.f. gain. At the same time the fixed 100Ω resistor should be removed and discarded, whilst the lead from the top end of the a.f. gain potentiometer to the mode switch should also be disconnected. Both gain controls will then work normally whichever mode is selected.

Fitting an S-Meter

The method described in previous articles in this series, and in "Versatile Valve Monitor and S-Meter" (PW, May 1986) may again be successfully employed. Alternatively, a system that was much in vogue with BC-348 owners many years ago may be revived. This depends on the change of screen grid current in the 2nd i.f. amplifier when the a.g.c. comes into operation. (See Fig. 2.3). It is fairly easy to disconnect the relevant electrode from the common G2 supply line and to take it to point B on the diagram. It will be seen that a simple bridge circuit is formed, one arm being the current path through the valve. The meter should have an f.s.d. of around 500μA-1mA, the exact value not being critical, as the value of R2 may be altered to provide the desired degree of sensitivity to suit the instrument. The zero-set potentiometer VR1 may be replaced (if a $1k\Omega$ type is not available) with a $5k\Omega$ type shunted by a $1.8k\Omega$ resistor. Do not omit the decoupling capacitor for the valve G2, which should be connected directly between the relevant pin and the nearby earth point.




Fig. 2.2: Modifications to the last i.f./b.f.o. stages (-J and later marks) to include an extra a.f. amplifier, plus a continuously variable-tuned b.f.o. for s.s.b. reception. New components have values shown; existing components do not. The b.f.o. coil is the redundant i.f./xtal coupler removed from set (see text)

Adding Mediumwave Coverage


This is a much more ambitious project and should not be attempted unless the owner/modifier has ample experience in the construction and adjustment of tuned circuits. For this reason, the following notes will be of a general nature as it is felt that the degree of skill required will make highly detailed data superfluous.

The conversions of the near-useless 200kHz-500kHz band to m.w. coverage would be much simpler were it not for the 915kHz i.f. which, of course, is bang in the middle of the m.w. broadcast band! Even with a fairly narrow i.f. bandwidth it is all too plain that strong stations from about 890-940kHz (337-319m) are likely to prove to be an acute embarrassment unless the most stringent precautions are employed to exclude them from the i.f. section of the receiver. Unfortunately the main contender will be the BBC Radio 2 network on 909kHz, with transmitters of up to 140kW power.

To ensure sharp tuning, all r.f. tuning coils should be double-wound and fitted with iron-dust cores for accurate alignment at the l.f. end of the band. The existing trimmers, for the high end, should prove to be adaptable for the new coils. A very necessary adjunct is a series antenna filter or rejector. This may be made up in a similar manner to the i.f. tuning coil described above, and is adjusted for minimum response with an input at i.f. from a signal generator, and perhaps subsequently with an antenna input from a very strong transmitter which is posing interference problems. In practice, excellent coverage throughout the greater part of the m.w. band may be achieved, making this admittedly lengthy conversion job very rewarding in the long

General Servicing Note

These receivers were made to very high mechanical and electrical standards and are likely to give little trouble in either respect. It is the writer's experience that the most probable source of faults will be previous unsatisfactory modification work. For this reason it is desirable that all existing "mods" should be closely examused when a receiver is first acquired. The connection of the h.t. negative lead mentioned earlier is one item that may easily be overlooked by a modifier unused to the negative-bias arrangement. Another common fault is the use of too thin a gauge of wire for the valve heater supply, particularly when an external power pack is used. There can be a significant voltage drop along thin cables which may reduce the actual heater voltage to well below 6V, and thus impair the efficiency of the valves. Similarly, when the original power supply socket of the receiver is used for the new p.s.u., even a very



*Adjust value to suit meter sensitivity

Fig. 2.3: "Traditional" BC-348 S-meter circuit. Voltage across C-D for values shown is 0.7V approx. The SET ZERO preset is adjusted for the same voltage across A-B

small degree of poor contact between plug and socket can affect the l.t. voltage markedly.

The bane of so many old receivers -leaky h.t. decoupling capacitors -does not appear to affect the BC-348 to any great degree, making it one of the most reliable of sets in this respect. Consequently the risk of burned-out or changed-value decoupling resistors is also small. The only major component which is likely to be a little troublesome is the band-switch. It has been found that in some cases good contacts cannot be established with certainty when the knob is rotated clockwise, but much better results may be obtained when a counter-clockwise movement is used. This is worth bearing in mind if the sensitivity on one or more bands seems far below par.

Alignment

The BC-348 must be one of the very easiest receivers to line up. There are no complicated damping operations to be carried out on the i.f. transformers, only the last needing a certain amount of extra care. The r.f. alignment is particularly straightforward.

I.F. Alignment: Connect the signal generator output to the grid of the mixer/ frequency-changer valve. This is more easily done by clipping the live lead to the appropriate section of the tuning gang. Connect an output meter across the loudspeaker terminals and adjust the first three i.f.t.s for maximum at 915kHz. The fourth transformer requires slightly different treatment. For this operation the signal generator is connected to the grid of the last i.f. amplifier via a 0.1µF capacitor, and is set initially to 910kHz. The primary winding and then the secondary winding are tuned for maximum with the cores turned in a clockwise direction, i.e., towards the centre of the coils. The generator should then be tuned through 915kHz to 920kHz, where another peak of the same amplitude as at 910kHz should be obtained. This will indicate that the correct "doublehump" response has been achieved. Some slight re-adjustment of the cores may be required to obtain equality between the two "humps". If a wobbulator and oscilloscope are available the job will, of course, be greatly facilitated.

R.F. Alignment: The exceptionally easy adjustment mentioned previously is due to there being but one trimming frequency for all bands other than the lowest. All trimmers are available through holes in the r.f. coil cans, and are clearly marked to correspond with the Band numbers. For example, the trimmers marked 1 on the antenna, r.f., and oscillator cans all apply to Band 1. There is one extra trimmer for Band 1 which is mounted away from the others and is unmistakable. Commence with this trimmer with the receiver and generator tuned to 200kHz. Adjust for maximum, then proceed to the other Band 1 trimmers at 500kHz. Repeat these operations until no further improvement is possible. The high bands are all adjusted at their maximum frequency, e.g., Band 2 is adjusted at 3.5MHz, Band 3 at 6MHz, and so on. Since the padders are of fixed value there is no adjustment possible at the lower ends of these bands, and only if there should happen to be severe discrepancies in the dial readings will it be advisable or necessary to investigate further.

B.F.O. Problems

Normally the permeability-tuned b.f.o. assembly gives no trouble, but cases are known of a sudden and complete failure to oscillate which is almost impossible to "pin down". Where time is of the essence it may well be easier to scrap the existing coil and either wind another or use the redundant crystal coupling coil mentioned earlier. When this is done (see Fig. 2.2) a small variable capacitor will take the place of the coil assembly on the front panel; in practice this will be found to be rather more convenient than the former b.f.o. control. The control knob can be marked to indicate upper or lower side-band for s.s.b. reception. When the r.f. gain control modification has been carried out as well, it will be found that the BC-348 can acquit itself very well indeed on s.s.b. as well as for general listening purposes.

C.M.HOWES COMMUNICATIONS





Eydon, Daventry, Northants NN11 6PT (mail order only)

Phone: 0327 60178

EASY TO BUILD KITS

The HOWES SWB30 kit enables you to build an essential piece of station test equipment

easily and at reasonable cost. The SWB30 not only indicates SWR and RF power, but also



features a power attenuator that reduces the level of radiated tuning signal and provides an excellent match to your transmitter at all times whilst the antenna or ATU is being adjusted. A resistive bridge circuit is used to give accurate, repeatable results over a wide frequency range.

- * Nominally flat resp;onse in SWR and power modes from 1 to 200MHz
- * Smart, custom made moving coil meter unit.
- * Power handling suits radios of 1 to 100W RF output, provided a tuning signal of less than 30W is used.
- ★ Unit can double as a 50 Ohm "dummy load" at 15W continuous.
- ★ Ideal companion for the HOWES CTU30 all HF bands ATU kit.

SWB30 kit: £12.50 Assembled PCB module: £17.30

ASL5 - DUAL BANDWIDTH RECEIVE FILTER

On todays crowded bands, high quality filtering makes all the difference. You can upgrade the performance of almost any radio by the addition of the ASL5 filter kit. It simply connects in line with the external 'speaker or phones output of the set, giving a CW bandwidth of 300Hz (-6dB) and sharp roll-off for speech modes typically 50dB down at 3.3kHz - a big improvement to the performance offered by a normal crystal I.F. filter as fitted to most receivers and transceivers. This kit offers a very cost effective and worthwhile improvement. Suits all the popular rigs, Yaesu, ICOM, Kenwood etc. 12 to 14V DC operation.

ASL5 kit: £14.90

Assembled PCB module £22.50

DCRx DIRECT CONVERSION COMMUNICATIONS RECEIVERS

The HOWES DcRx receivers have become the popular choice of both the beginner looking for a low cost start into the hobby, and the experienced operator building a low power (QRP) station. These little sets offer amazing performance for simple equipment. Versions are available for each of the following bands:- 160, 80, 40, and 20/30 Meters. They can also be combined with some of our other kits to form transceivers. Tuning capacitors to suit all but the 160M version are available at £1.50 each, you need two per receiver. Modes: SSB and CW

DcRx kit: £15.60 Assembled PCB module: £21.50

Other	HOWES KITS include:	KIT	Assembled PCB
CTX40	and CTX80 QRP Transmitters for 40 and 80M	£13.80	£19.90
MTX20	10W 20M CW Transmitter	£22.90	\$29.90
CVF20,	CVF40, CVF80 VFOs to suit above TXs	£10.40	£16.90
CSL4	CW/SSB Filter for DcRx	29.90	£15.90
DCS2	Signal Indicator Meter/Driver for DcRx	26.60	£10.60
CV220	and CV620 2 and 6M to 20M RX converters	£17.50	\$23.90
XM1	Crystal Controlled Frequency Marker	£16.80	£21.90
ST2	Side-tone/Practice Oscillator	28.80	£13.50
AP3	Automatic Speech Processor	£15.90	£22.80
CM2	Quality mic with VOGAD	£11.90	£15.90
CTU30	All HF bands ATU for RX or 30W TX	£27.90	£33.90
TRF3	Shortwave Broadcast TRF receiver	£14.80	\$20.20
HC220	and HC280 20 and 80M Transverters from 2M	£52.50	\$83.50

All kits include PCB and all board mounted components, plus full clear instructions. Help, advice and sales are only a 'phone call away, but please send an SAE for a copy of our free catalogue.

UK P&P is £1.00 per order. Delivery normally within 7 days.

73 from Dave G4KQH, Technical Manager

BCD ELECTRONIC SERVICES

//BCD

SOMERSET HOUSE, SOMERSET STREET, **HULL HU3 3QH** TEL: 0482 225437

TELEX: 592592 KHMAIL G (ATTN BCD146)


BF256	0.40	BFS23A	1.50	MC1496	1.20	SL6270	2.25	2N2905A	0.45
BF480	0.85	BFW92A	1.35	MC3340P	1.85	SL6440	3.65	2N2369A	0.45
BF981	0.85	BFX89	1.15	MC3357	3.05	SL6601	2.95	2N3866	1.35
BFQ23	2.25	BFY90	1.20	MPF102	0.40	SL6700	4.45	2N4427	1.75
BFQ51	2.10	BLX65	2.50	MPS918	0.30	TDA7000	2.55	2N4921	0.70
BFR34A	1.65	BLY33	1.85	NE564	3.10	UA733	1.00	2SC1947	6.75
BFR90	1.30	J304	0.60	NE565	1.25	VN66AF	1.60	2SC2053	1.50
BFR91	1.50	J309	0.60	NE592	1.20	ZTX327	1.50	3N201	1.25
BFR94	8.75	J310	0.60	SL560	2.25	ZN414Z	1.10	3SK51	2.60
BFR96	1.75	1 M3089	3.50	SI 1612	4.85	ZN416F	1.65	3SK87	0.40


808 SERIES FILM TRIMMERS 1.4-5.5PF, 2-10PF, 2-22PF 25p: 5.5-65PF 40p.

UNITED KINGDOM TABLE OF RADIO FREQUENCY ALLOCATIONS The comprehensive guide to frequency allocations 9KHz-400GHz
An invaluable publication for all radio users. 308 pages £12.00 (ZERO VAT)

PLEASE ADD 60P POSTAGE & PACKING + VAT (# 15% TO TOTAL

PLEASE MENTION PRACTICAL WIRELESS WHEN REPLYING TO ADVERTISEMENTS





Crops and Coils part 3

Measurements, Mains Eliminators and Battery Chargers

A scientist was once described as a person who measured things. Having said that, measuring the length or frequency of a radio wave required ingenuity and practical skills in addition to sound technical knowledge. So, there were few better ways for budding scientists to develop their talents than to become a radio experimenter, says George Pickworth.

The early radio pioneers used their skills to develop a means of generating signals of known frequencies. Probably the best approach was to use a high frequency alternator but such machines were expensive and extremely difficult to make. Moreover, the upper frequency limit of the very best was only about 100kHz. A less costly approach was to use a high speed "interrupter" in a d.c. source, but this was a failure.

Nonetheless, before the First World War, high frequency alternators, or "wave mills" as they were called, were used both for transmitting and as local oscillators in receivers where the beat note was produced mechanically in specially designed headphones. It was the most sensitive design at that time, but further development was abandoned as experimenters moved to higher frequencies.

However, high frequency alternators were used until recent years to superimpose a "tone" on a.c. power lines. This was used to switch street lights on or off or to change domestic meters from the cheap to normal rates during the peak period. They operated at a few kHz and could be heard on a low cost loudspeaker connected to the mains through an isolation transformer.

Calibration

Meanwhile, spark transmitters using tuned systems and operating between 0.5 and 1MHz continued to be developed, but frequency measurement was beyond the capability of mechanical devices. So operators had to either precisely measure the physical features of the coils and condensers, and by using already well established formulae, calculate the resonant frequency, or, measure the actual length of the wave by observing when an antenna of known length was in resonance.

As the latter required little more than a tape measure and a hot wire ammeter it is no wonder that it was favoured by experimenters and commercial operators. Even experimenters first exploring the ultra short waves (those between 1 and 10 metres) had little option but to use basically the same technique. Indeed, with refine-

ments, it was used almost to the beginning of the Second World War.

Because the length of a wave can be visualised far better than its frequency, specific parts of the radio frequency spectrum are still referred to by wave length

While it is still perfectly satisfactory to measure the length of long waves, a point is ultimately reached where the unit of length is too small to be meaningful, the alternative is to measure the frequency, but this technique had to await the development of crystal

Unfortunately, the cost of standard crystals was beyond the resources of young experimenters wishing to accurately calibrate their receivers in 1938. Instead, they used broadcast stations which periodically announced their frequency. The usual method was to make a graph by plotting the frequency of as many stations as possible against the dial readings.


I preferred the Raymart Logging Dial because it had a 100 to 1 reduction drive with a dual pointer system which gave extremely high resolution. This enabled "spot" frequencies to be accurately recorded and special high definition graphs covering sectors of particular interest to be prepared in


addition to an overall graph for each plug-in coil. But unfortunately with even the best equipment it was impossible to reinsert a tuning coil into its holder in exactly the same position each time it was changed and this slightly affected the calibration of a receiver. Incidentally, graphs were used with the famous HRO receivers, which also used plug-in coil units, until about 1946.

Calibration was laborious, extending over a considerable time and if a receiver was modified, as was usually the case with experimenters, calibration was upset and the graphs were useless. To overcome this problem, serious experimenters made their own "wave meters".

They were usually simple single valve tunable oscillators, constructed with high quality components and a rigid "hard wired" tuning coil, covering typically 6 to 12MHz on fundamentals and up to 24MHz on harmonics. They were calibrated by tuning to zero-beat with stations of known frequency so that a graph could be prepared and used to calibrate other receivers.

My wave meter was solidly constructed on an extremely rigid aluminium panel. The tuning condenser





(capacitor), of instrument quality, was mated to an Eddystone vernier dial. The complete instrument was protected in an old crystal set cabinet with a hinged lid which held the graph. To eliminate loading effects which could upset calibration, a low power battery output valve was used as the oscillator which generated sufficient r.f. energy to make physical contact with the receiver unnecessary. As it became operational almost immediately, it only needed to be switched on for the time required for a zero-beat.

Eliminators

A large proportion of the population still used battery operated receivers in 1938 and many continued to do so throughout the war years, no doubt because they cost less than all-mains sets. So there was a large demand for batteries which in turn reduced their cost which was much to the advantage of experimenters.

The numerous taps on the 120 volt high tension (h.t.) batteries allowed individual valve elements to be supplied with the correct voltage without recourse to resistance networks, but the penalty was five or more h.t. leads, and three or four grid bias leads (g.b.), all having their own identification tags.

After using batteries, I was more than pleased to be given a "battery eliminator" when its owner decided to graduate to an all-mains receiver. It was simply a power supply unit delivering about 150 volts smooth d.c. from the 250 volt a.c. mains and after installing additional filtering condensers, was used to power my short wave receivers. I could now use larger output valves and by using resistor networks, use just a single pair of h.t. leads. "Automatic" grid bias was possible and could be adjusted for optimum sound quality now that it was no longer necessary to over-bias to economise on battery drain. Moreover, noise, caused by electrolytic action in 'dry" batteries was absent.

Much of my listening had been with a pair of high impedance S. G. Brown Headphones connected as the anode load of the output valve, but it was dangerous to continue this practice when using the "eliminator". But as I had advanced from a high impedance balanced armature loudspeaker to a low impedance moving coil type which required a matching transformer, it was logical to use its primary winding as an audio frequency choke to divert signals through an isolation condenser to the phones. To revert to loudspeaker listening, the headphone jack plug was removed and the transformer's secondary winding reconnected to the loudspeaker.

Accumulators

While the "eliminator" provided smooth h.t., there was no comparable device to give smooth low tension (l.t.) for the filaments. Large capacity condensers were unavailable so it was virtually impossible to obtain smoothed d.c. current directly from rectified a.c. A commercial device did claim to do this, and while suitable for medium wave reception it was not satisfactory for the short waves. So there was really no option other than to continue with 2 volt accumulators.

As the current demand by a typical domestic receiver was only about 0.5A, the accumulators used a pair of thick self supporting plates instead of multiplates typical of car batteries. Some had hydrometers, featuring a pointer or coloured balls, to indicate the state of charge.

A drawback was corroded terminals and the fear that acid might escape and damage furniture, although this could be reduced by using a jelly electrolyte developed for use in early transportable receivers. The biggest drawback was having to take them 4km to the radio shop to be charged. So, disenchanted with transporting accumulators in my cycle pannier bag, I decided to construct my own charger.

But I could not obtain a suitable rectifier although they were advertised by the Westinghouse Company. Charging accumulators was a significant part of the radio business and may well have been the reason for them not selling rectifiers. So I decided to make one myself.

Rectifiers

My first effort used a piece of clock spring tuned to the 50Hz mains as a crude vibrator type rectifier. Although it worked, it was noisy and the contact points, salvaged from old telephone switches, quickly burnt out. Contact breaker points from a motor car would have been better.

Then I tried an electrolytic rectifier. This consisted of four one-gallon earthenware jars filled with a solution of ammonium phosphate. The electrodes were large sheets of lead connected to form a bridge circuit. Although cumbersome and messy, it actually worked, albeit inefficiently.

It was not operated from a transformer, but directly from the mains using the houselights as a ballast. The fuse box in the pantry facilitated breaking into a suitable circuit. Shades of the days when the mains were d.c. and it was quite common to charge accumulators in this way. The advantage of this method was that it maintained a constant current (depending upon the number of lights switched on), irrespective of the state of charge of the accumulator. It avoided the problem with transformer systems in that a flat accumulator is equivalent to a short across the charger.

Even when all the lights in the circuit were switched on, the total load was only about 250 watts, well within the limits of the rectifier. Most of the time it was much less.

I made a great mistake by not anticipating that grandmother would revert to plugging her old electric iron into the sitting room light socket now she had a 15 amp socket installed in the kitchen especially for her new iron. It was a very early lesson on not to assume anything.

The result was disastrous. The rectifiers boiled over making a terrible mess and smell. It was the smell that alerted grandmother, otherwise there may well have been a serious fire.

Grandmother had got over the much earlier traumatic experience of uncle shorting the accumulator leads of her first radio and setting the curtains on fire. She had come to terms with me cluttering the box room with wires and all sorts of things which she did not understand. She had reluctantly tolerated the rectifier in her pantry, but this latest episode was too much for her. Moreover, it alarmed me and I never used it again. But more important, it stimulated my desire to advance to allmains receivers.

In Part 4— LEARNING FROM THE PIONEERS

On The Air On The HF Bands

Reports to Paul Essery GW3KFE PO Box 4, Newtown, Powys SY16 1AR

What a month! Wind, rain, thunder, lightning, poor conditions for much of the time, two rigs to be mended and a keyer in need of repair—ugh!

Seriously, the month of July is hardly a time when one expects much compared with, say, mid-September through October and early November. This period was definitely below expectations but, as always, there are flashes of light in the gloom.

First, the Malyj Vysotskij Island DXpedition. This station, signing 4J1FS, was a joint Russo-Finnish expedition to an island owned by Russia but leased to Finland: operators OH2BH, OH5NZ, UZ3AU, UR2AR and UW3AX. The 4J1FS callsign was jointly agreed upon and it seems that the DXCC ruling that this could be a new country goes as far back as 1970. However, the DXCC it seems are now wanting to renege on that decision to the extent that they want to run everything through the mangle again against the current country criteria which have been amended since then to legislate out some anomalies. The 4J prefix was chosen as it is not used in mainland Russia but only in Antarctic areas where the presence of a Russian contingent does not imply a sovereignty claim; by the same token the suffix was chosen to imply Finland and Soviet. Regardless, everyone is talking about M-V island, of course!

Talking of DXpeditions, that 4W0EA effort seems, at the time of writing, to have turned into a "Busted Flush". Their visas have not been received and word had it that if they were not to hand by July 21... finito. The latest news has it that the passports had been "mislaid" by the Yemeni authorities.

South Orkneys: VP8BRT is on S. Signy Is and I understand he will be there until June 1989.

The activity from 7Q7 is now apparently nil. 7Q7LW is back in UK as G3JSU, while 7Q7AE is still licensed but QRT. On the other hand, Pitcairn Is activity is at an all-time high now. VR6HJ is the fifth YL active, so that the YLs now outnumber the OM operators! Check for them around 0630Z, with a scan of the region around 14.140-14.150MHz.

Svalbard hunters could do worse than look for SP5DRH/JW on 7 or 14MHz, c.w. and s.s.b. QSLs go to Jacek's home QTH.

9L1GG has been dishing them out, especially on c.w. for a long while now, but is now preparing for a retirement to Paraguay.

Phoney!

That C31IU on Top Band back in February was Andorra Slim; the real licensee hasn't been there in years says QSL Manager W8JAQ.

That GB75DXN from DXNS Editor G4DYO was only valid for March 11-April 7. However, Bren has been getting some cards for c.w. on July 8. Don't waste pasteboard!

Contests

Turning to the Contest scene, we find the first two weekends of October set aside for the s.s.b. and c.w. legs respectively of the VK/ZL/Oceania Contest. 1000Z Saturday to the same on Sunday: operate to a maximum of twelve one-hour blocks (1000-1100Z, 1400-1500Z for example). All Bands 1.8-30MHz except WARC bands. They work the world, we work VK/ZL/Oceania stations. Same station can be worked on each band for QSO and multiplier credit. Exchange RS (T) plus serial from 001 upwards. Two points per QSO; multiplier is each VK/ZL/Oceania prefix worked. Final score is total QSO points times multiplier on each band. SWL entries combine c.w. and s.s.b. leg scoring for final total. Entries to NZART Contest Manager ZL1AAS, 146 Sandspit Road, Howick, New Zealand to be received no later than 15 February 1989.

October 29-30 is down for the CQ WW DX SSB Contest, while the October 9 date is for the RSGB 21/28MHz SSB Contest. October 16 is Jamboree-on-the-Air, and the RSGB 21MHz CW Contest.

WAB

From G8XTJ, I have a note of the WAB doings. Look for them around 3.76 and 7.06MHz at almost any time of day. ZS6BBY was the first to claim the Overseas Introductory Award by working 25 areas in ten different counties. For the UK mobiles on h.f. the new ACCLAIM Award (Activating Counties Large Area Island Mobile) seems to have given a boost to the number of applicants. All the details on the WAB programme can be obtained from Brian Morris G4KSQ, 22 Burdell Avenue, Sandhills Estate, Headington, Oxford OX3 8ED. Don't forget the uses to which the funds so raised are put.

The 3.5MHz Band

The only reporter this time is GOHGA (Stevenage) who has 80 watts out on this band. Angie mainly uses this band between 2000 and around 0200. She found many G stations out to around 160km, DJ70M, DF2YK, Y22FK, PA3CWG, PA3DCW. G3MCK, SP9EQS/1, HG60HQ, DF5XN, DK2OY/TF for a new one on the band, ON4CW, GW4YYY, Y24EA, PA0WKI, GM3TMK for a natter, SMOLPC, SP6BFK, HA5PD, HA6OJ, OK1DUX, DJ3WM, DJ4N GODRT (QRP both ways) and DL6ZBA. DJ4NT.

The 7MHz Band

It must say something about conditions this period that 7MHz seems to have been so popular! G3NOF (Yeovil) found El1000 for the thousandth anniversary of the foundation of Dublin and added EJ4GRC on Inishbofin. Don noted my comments on 'insurance contacts" and says that on quite a few occasions he has received QSLs from stations when he himself hadn't bothered to send a card as he doubted he'd made the contact; and a rather similar proportion of his QSLs outgoing have come back marked "not in log". G3NOF says that nowadays he always notes the contacts in front of and after his own, so that he has some extra detail in case of a query.

Ted **G2HKU** (Sheppey) made it, using c.w., to W1PL, CM5ON, ZL2UW and ZL2AGY. He says he found both the conditions and the static variable this month!

G4KKI (Swinton) has been off the air for a rebuild. The main rig now is an HW7 acquired last year cheaply as a non-runner. Since then it has been first brought back to life in the original form and since redesigned. It now has a stepped attenuator, switched band-pass filter, double balanced mixer, r.i.t., a four-pole audio filter and an S-meter. On the transmit side the rig now has a pair of 2N3866s with a watt on 21MHz, two on 14MHz and a little more on 7MHz. This lot runs attached to a T-Match a.t.u. via a Monimatch to a halfsized G5RV. On 7MHz the results included c.w. contacts with G3KVA, G3GXI/P, FD1NRY, PA3CLX, SM7FHJ, G3XAP, GM3VTH who was using the OXO transmitter design of the QRP Club, an R2000 and an indoor trap dipole, G3MBN (QRP), G3IJV (QRP), GM3HBT (QRP), GOCHC (QRP), F6IFH (QRP) and DJ0PJ (QRP).

GOISN (Ruislip) is ex-G1MOG and runs a Yaesu 767 into either a trap vertical or a G5RV. This set-up accounted for s.s.b. contacts with IK2LFF, SP9KAG, YU3JI, YO9FAF, RA4OR, UB4WZA, DL7UR/M, GI0BFO, GM4XYF, EI5M, GD4XWH and UZ9WXA.

GOHGA now runs 70 watts of c.w. to a 29m wire. On 7MHz, Angie managed lots of DLs, PAs, ONs, Fs, GM and GW when there was a path, a few OZs, many USSR stations there for the picking, many Ys, a few EAs and Is, GB75CCC in the IARU contest with G3JKS at the helm and EA6ZY, who will be recalled by OTs as G6ZY.

The 14MHz Band

GOHGA has antenna problems on this band, so she has to be a bit wary. Many contacts were made, but after midnight when she can get on, usually the Yanks she is after are snapped up by Russians. However, a couple of interesting ones included U19PK for a Moscow special-event station of some sort and DK2OY/TF for a new one on the band.

Turning to GOISN we find that he made it on s.s.b. to UC1WWO, N3FIB/MM, UQ1GWC, 4X4JU, TF5BW, W3GIS, 8P6OV, WB3KBZ/VP9, CP6XH, 5T5NU, CO6CD, UZ9FZZ, VP5HM and XE1GGO on Packet.

G2HKU managed contacts with OHO/K8MFO, VK2QL, WB5BIR, WM5G, KL7Y, W3LPL, W1RM, AX4XA, K2QZ, 5NOELT, VE3PR, KH6IJ, VI88WIA, VK3KS, WB8E, VE1CIL, K6DC, NN7U, 7X4VUK, K4FU, N4LS, K3MGR, TA2D, 9H3IJ, UA6HSD/UAOQ and W6WQX, all on c.w., plus an s.s.b. QSO with 4J1FS on M-V Island.

Next we have G3NOF's letter. Don says he noticed s.i.d.s disturbing the band and also noted that after 0730Z conditions were changing very rapidly. 0530–0730Z saw long path openings to VK and short path openings to W6/7. Some Pacific stations came in between 0730–1000Z, Africans around 0730 and again in the early evening. Asians appeared

DEWSBURY



ELECTRONICS

From the makers of the world renowned STAR MASTERKEY a new MORSE KEYBOARD.

Send perfect morse as easily as typing a letter. It has never been as easy to send morse.

Variable transmission. Speed 1-99 wpm or 100-200-300 -400 wpm for Meteor Scat operation.

4 Message Memories each of 255 characters. 26 scratch pad memories each of 127 characters. All memories stored on non volatile. Ram-Messages stored for up to 5 years.

> Indication of speed on 7 segment display.

Indication of operating mode on leds. Sidetone and relay output for all types of transmitter.

> **Full QWERTY** keyboard with real keys.

Metal cased for RF immunity.



For Full Details Send S.A.E. To:

Dewsbury Electronics, 176 Lower High Street, Stourbridge, West Midlands. Telephone: Stourbridge (0384) 390063/371228 Telex: 336712 SHELTN G. Ref. D2850

Instant finance available subject to status. Written details on request.



BARCLAYCARD VISA

RST MAIL ORDER CO LANGREX SUPPLIES LTD, 1 MAYO ROAD, CROYDON, SURREY CR0 2QP. SPECIAL EXPRESS

MAIL ORDER SERVICE

Fax: 01-684 3056

	€p							1	
AZ31	2.75	EM81	2.50	PL519	6.00	6AK5	5.99	6KD6	9.00
CL33	4.00	EM87	2.50	PL802	6.00	6AL5	1.50	6L6G	5.00
DY86/7	1.50	EN91	6.50	PY33	2.50	6AM6	6.02	6L6GC	7.50
DY802	1.50	EY51	2.75	PY81	1.50	6AN5	4.75	6L7	2.50
E88CC	10.33	EY86	1.75	PY82	1.50	6AN8A	3.50	6LQ6	7.50
E180F	12.05	EY88	1.75			6AQ5	3.25	6Q7	3.75
E810F	35.48	EY500A	3.00	PY83	1.25	6AR5	25.00	6RHH8/6K	N8
EABC80	1.25	EZ80	1.50	PY88	2.00	6AS6	8.66		10.00
EB91	1.50	EZ81	1.50	PY500A	4.00	6AS7G	8.75	6SA7	3.00
EBF80	1.50	GY501	300	PY800	1.50	6AT6	1.25	6SC7	2.75
EBF89	1.50	GZ32	4.00	PY801	1.50	6AU5GT	5.00	6SG7M	2.50
EC91	8.00	GZ33	4.75	QQV02-6	38.00	6AU6	2.50	6SJ7	3.25
ECC33	4.50	GZ34	5.00	QQV03-10		6AW8A	3.75	6SK7	3.50
ECC35	4.50	GZ37	4.75	QQV03-20		687	3.25	6SL7GT	3.00
ECC91	1.75	KT61	5.00	44.00.20	48.38	6B8	3.25	6SN7GT	3.00
ECC81 ECC82	1.75	KT66	15.00	QQV06-40		6BA6	1.50	6SS7	2.75
ECC83	1.75	KT77 Gold		44100 40	46.00	6BA7	5.00	6U8A	2.25
ECC85	1.75	KIN GON	12.00	QV03-12	6.80	6BE6	1.50	6V6GT	4.25
ECC88	3.50	KT88	15.00	R18	3.00	6BH6	2.50	6X4	3.00
ECC91	8.93	N78	15.00	R19	9.24	6BJ6	2.25	6X5GT	1.75
ECF80	1.50	OA2	3.25	SP41	6.00	6BN6	2.00	12AX7	1.75
	3.00	OB2	4.35	SP61	4.00	6BQ7A	3.50	12BA6	2.50
ECH35	3.50	OC3	2.50	U19	13.75	6BR7	6.00	12BE6	2.50
ECH42	3.50	OD3	2.50	U25	2.50	6BR8A	3.50	12BY7A	3.00
ECH81	3.00					6BS7	6.00	12E1	20.00
ECL80	1.50	PC86	2.50	U26 U37	2.50	6BW6	6.00	12HG7	4.50
ECL82	1.50	PC88	2.50		1.25	6BW7	1.50	30FL1/2	1.38
ECL83	3.00	PC92	1.75	UABC80			2.75	30PL 1/2	2.50
ECL86	1.75	PC97	1.75	UBF89	1.50	6BZ6		30P4 30P19	2.50
EF37A	5.00	PC900	1.75	UCH42	2.50	6C4	1.25	30P19 30PL13	1.80
EF39	2.75	PCF80	2.00	UCH81	2.50 1.75	6C6 6CB6A	2.50	30PL13	1.80
EF41	3.50	PCF82	1.50	UCL82		6CD6GA	5.00	572B	65.00
EF42	4.50	PCF86	2.50	UCL83 UF89	2.75	6CL6	3.75	805	45.00
EF50	2.50	PCF801	2.50	UL41	5.00	6CH6	13.00	807	3.75
EF54	5.00	PCF802			1.75	6CW4	8.00	811A	18.33
EF55	3.50	PCF805	1.70	UL84		6D6	3.50	811A	52.50
EF80	1.75	PCF808	1.70	UY41	4.00		7.50		65.00
EF86	5.00	PCH200	3.00	UY85	2.25	6DQ5 6DQ6B	4.75	813 866A	35.00
EF91	2.95	PCL82	2.00	VR105/30					20.00
EF92	6.37	PCL83	3.00	VR150/30	2.50	6EA8	3.00	872A 931A	18.50
EF183	2.00	PCL84	2.00	Z759	25.00	6EH5 6F6	1.85	2050	7.50
EF184	2.00	PCL85	2.50	Z803U	25.00	616	2.75		
EH90	1.75	PCL86	2.50	2D21	3.25	6Gk6		5763	6.80
EL32	2.50	PCL805	2.50	3B28	50.00	6H6	3.00	5814A	4.00
EL33	5.00	PD500	6.00	4CX250B	58.00	6HS6	3.77	5842	12.00
EL34	5.00	PFL200	2.50	5R4GY	5.50	6J5	4.50	6080	14.00
EL36	2.50	PL36	2.50	5U4G	3.00	6.16	8.93	6146A	12.00
ELL80	25.00	PL81	1.75	5V4G	2.50	6J7	4.75	6146B	12.00
EL81	5.25	PL82	1.50	5Y3GT	2.50	6JB6A	6.50	6550	12.50
EL84	2.25	PL83	2.50	523	4.00	6JE6C	7.50	6883B	12.50
EL86	2.75	PL84	2.00	5Z4GT	2.50	6JS6C	7.50	6973	7.50
EL91	7.39	PL504	2.50	6/30L2	1.75	6K6GT	2.75	7025	4.50
EL95	2.00	PL508	5.50	6AB7	3.00	6K7	3.00	7027A	9.00
EL360	18.50	PL509	6.00	6AH6	5.00	6K8	3.00	7360	22.50
THE RESERVE OF THE PARTY OF THE		_					AND DESCRIPTION OF	7586	15 00

COMMUNICATION CENTRE OF THE NORTH

The largest range of communications equipment available in the North. Full range of receivers, transceivers, antennas, power supplies, meters. Ali tubing - wall brackets - rotators - insulators.

ANTENNA RANGE

BUTTERNUT		WELZ	
HF2V 40-80m vertical		DCP5 5 band vertical with	
20 MRK 20m add on kit		radial kit.	£195.00
HF6VX 6 band vertical	£159.00	DCP4 40-20-15-10 vertical with	
TBR160S 160m Add on kit		radial kit	£147.00
HF4B Triband Mini Beam	£235.00	JAYBEAM	
CUSHCRAFT		VR33 band vertical	
A3 3 element Tribander	£262.00	TB1 Rotary Dipole	
A4 4 element Tribander	£350.00	Minmax Triband Mini Beam	
10-3CD 3 element 10m	£115.00	TB22 element Tribander	£202.00
15-3CD 3 element 15m		TB33 element Tribander	£316.00
20-3C23 element 20m		SWR/POWER METERS	
AP8 8 band 25ft vertical	£164.00	MFJ 815 HF 2kw SWR/PWR	£57.32
AV5 5 band 25ft vertical		SWR Twin Meter 1.8-50MHz	£25.00
18 element 2m Boomer		DIAWA CN410M 35-150MHz	
15 element 2m Boomer	£85.00	DIAWA CN460M 140-450MHz	£65.40
ANTENNA TUNERS		NS660P 1.8-150MHz + PEP	£115.00
Kenwood AT230	£208.00	Welz SP10X	£37.00
CAPCO SPC 300D	£225.00	Welz SP220	
CAPCO SPC 3000D	£325.00	Welz SP420	£59.95
MFJ 962B 1.5k Tuner	£241.00	DUMMY LOADS	
MFJ 949C 300W Versatuner	£157.00	DL60 60 watt	£10.96
MFJ 941D watt Basic	£105.00	DL600 600 watt	£62.75
MFJ 1601 Random Wire Tuner	£42.02	CTS30 500 watt	
Kenwood AT250 Automatic	£366.00	MFJ2600 300 watt	£28.35

ull size £16.50, half size £14.50 Full range of Antenna – A UHF – HF mobile Antennas

ull range of RSGB and ARRL publications in stock Part Exchanges welcome. Second hand lists daily Send S.A.E. for details of any equipment. HP terms. Access/Barclaycard facilities. Open 6 days a week. 24 Hour Mail Order Service.

TH2 MK3 2 ele Tribander 18 AVT 5 band trapped vertical £146.00 EXP14 4 element 20-15-10 m £449.00

HYGAIN

Goods normally despatched by return of post. Phone 0942-676790.

STEPHENS JAMES LTD. 47 WARRINGTON ROAD,

LEIGH, LANCS. WN7 3EA

666
Open daily to callers: Mon-Fri 9 a.m.-5p.m.
Valves, Tubes and Transistors – Closed Saturday
Terms C.W.O. only, allow 7 days for delivery.
ng Quotations for any types not listed S.A.E.
Post and packing £1.00 per order

VAT add 15%

1600–1800Z. Contacts on s.s.b. were made with AXONE (Macquarie Is), CP5HK, DL3LAB/TF, CU3AA, EJ1000, F05EC, HI8EMD, HK0EFU, HV1CN, IK7JWX/IJ7, JW6WDA, K7ZM, KB0NL (N. Dakota), KH6EV, KH6FKG, NL7V, OD5KV, OE1RUA/YK, RA4HT/UM, RZ10WA (Franz Josef Land), S0RASD, T5GG, T12VVR, TN4NW, TR8SA, UA0KB, UL7FG, V21WW, VR6YL, VU2RX, VKs, XE1EEF, ZB2GR, ZK1DD, ZL40D at 2234Z, 4J1FS, 4K0D, 5T5NU, 5V7TM, 5Z4BP, 6Y5IC and 8Q7MT.

G4KKI and his revamped version of the HW7 were able to work VI88NSW, N3RD, KR2Q, SV2AAG, KI1B, K2TQC, WA2IUO, UL8GW, KA2SZA, VK5NM, SP5YQ/QRP, UA3ARE/A, RA6LOK, while UAOSCJ came back but was lost twice.

The 21Mz Band

Conditions, says G3NOF, have been down, though the Pacific short path has been open between 0800-1000Z, with the same route taking in JA, and YB/YC between 1200-1500 and occasionally as late as 1800. The only VK heard was noted at 2200Z on short path. The few N. American openings seem to have been around the same time too. Africans have been heard at various times of the day. QSOs using s.s.b. were completed with AL7JG/3D2, CE3BRA, CE4ETZ, CM6CG, DL3LAB/TF, DX1CW, FH8CB. HB9ANQ/HC5, HC2DZ, JAs, KA2DD/JD1 (Minami Tori Shima), SP5DRH/JW, T30BC, T46CL (=CO land), TN4NW, UAOWZ, UWOLAP, WY5L/KH3, YCs, ZK3RVC, 3C1JPF, 4J1FS, 4M5T, 4U1VIC, 5T5NU, 9Q5MC and 9V1WP.

G4KKI's rebuild was tried out on 21MHz c.w. and it made contacts with LZ2KHN, DH1IAL, UB4MXR, UB5FDO, RA6LOK, UA6BPM and K1VGW with about one watt of r.f. output. Bill says there was lots more on the band, but for some reason he didn't spend much time working them!

Turning to GOHGA we find Angle in the IARU contest with QRP to a 20m wire or a vertical: on July 10 she managed NR5M, SMOJSN, SMODPZ, HA5KF/1, HA1XY, W1AW through a pile-up, Y42SA/P and

YU3DXK who came back to a CQ.

Now GOISN who is a s.s.b. addict; the G5RV and Yaesu FT-767 resulted in bookings with VE1ATP, KI4WU, OX3SG, W1CWV, W200XX, W3ARK, W2BYK, VE3ODC, VE3NDO, NC7K, UZ9UWZ, 5B4WB, EA6MQ, ZC4EE and 5H3ZO (Packet).

An all c.w. month on all bands for G2HKU, who mentions his 21MHz contacts with W6ALO, XE1ISE and WB6QPG/HR2.

The 28MHz Band

Here of course, the rise of the sunspot count and the seasonal doldrums have reduced activity. Don G3NOF says he found little DX on the band, skip was short most of the time, with plenty of strong European signals about. He made his mark with TN4NW and TR8CA for his only log entries on the band.

Turning to GOISN, he stuck to s.s.b., and managed contacts with EA6BE, OZ7JV, SMOOWX, HB9BRU, EA5FYH and 4X4JU.

GOHGA had a little play in the IARU Contest of July 9, using QRP only on this band, including HG60HQ, SP5KUW, OK2KDS, IO8RFD, DL7RAG, Y32CN, HA5KBM, SK6AW, Y35L, OK7AA, HA8KV, Y37ZE, OK1BZJ, IK8EJN, DL3LU, HA0MM, SP8NR, Y31EM, HA5HH, OK2KR, HA5KBM, Y43CO, OK1FFU, Y27FN, OK10FM, PT2KT (2-way QRP), I2CZQ, IK2GSN, LZ7A, DL1GHX, OH7AA, HA8KVK, HA5KKZ, DJ0MB, DL2OBF, HB9BYZ, DK2OY/TF (2-way QRP), OK2KR, Y38I, HA1SE, OK2PDT, OK1DZJ, Y61HQ, HA8KZL, HA5DA, I6IBE and UQ1GWW, with PS7BX and CE2LZR as gotaways. The latter disappeared back into the noise while Angie was standing by to call him. So—who says QRP can't raise 'em?

WARC Bands

A couple of reports this time. First, GOHGA who says her five watts of QRP c.w. wasn't good enough to raise

LU5DJO, who was in any case in heavy QSB at the time.

G2HKU found VK3BXN, ZL2AGY, N4PHH/9, VK2HW, VK3NC, N1FQB and VE3AJD on c.w. of course.

Antennas

A discussion of antennas among the locals arose from a Sunday-morning natter on 3.5MHz. Just about everyone has either Best Bent Wire jobs, or the G5RV/trap dipole where centre-feed is used. One station changed from trap dipole to G5RV, and it raised interesting thoughts: his signal was far improved on the G5RV, BUT, 1. He had slightly changed the orientation of it, and 2. Everyone on the net was reporting quite heavy QSB. QSB is pretty normal on this "local" net, as there are mountains in every direction, and one relies on the high-angle skywave. So ... was the change of antennas, or of orientation, or both, an improvement?

That, I hope, supplies a clue towards the answer for an s.w.l. who wrote asking why one so often hears the statement that "a new antenna should be used for a long period before a decision is made to keep it or scrap it".

Mailing Address

Some readers may have heard I've taken over the amateur bands column in Short Wave Magazine. Justin Cooper kindly "gave" me his PO Box number so, the address for your letters is now: E. P. Essery GW3KFE, PO Box 4, NEWTOWN, Powys SY16 1AR. Post them to arrive by the deadline date at the head of this piece. Meantime, all the best, and keep those letters rolling in with your DX.

The next three deadlines are: Sept 21, Oct 26 and Nov 24

VHF Up

The main headlines this month are of a major 144MHz Sporadic-E opening on July 10, a new record "first" QSO on 144MHz between GI and EA8, another first on 50MHz between GM and PJO and, sadly, of the death of Serge Canivenc F8SH

Vale Serge Canivenc F8SH

There can be few v.h.f. enthusiasts, who are interested in propagation studies, who will not be familiar with the work of Serge Canivenc F8SH. For many years Serge was the IARU Region 1 Coordinator for the study of Sporadic-E.

He accumulated a vast amount of data on this subject compiled from the thousands of reports from v.h.f. operators and had embarked upon a comprehensive computer data base program to record it

His reports also covered field aligned irregularity mode and he gave a lecture at the VHF Convention on this topic in 1983. Much of his work was filed with the CCIR and it has always seemed a great pity to me that it never got the exposure it deserved in National Society journals.

Serge lived in Perros-Guirec in Brittany and died in Grasse on the Côte d'Azur on July 5 whilst on holiday. It will be a very difficult task to find someone who will carry on his work with such dedication and enthusiasm. He really was a true radio amateur who spent thousands of hours on voluntary research, motivated by curiosity, that we might better understand this intriguing mode of propagation.

Award News

Congratulations to **Keith Hewitt G6DER** (YSS) who was elected to membership of the 430MHz QTH Squares
Century Club on July 26 with exactly 100
confirmed. One QSO was via Auroral
mode, the rest being on tropo. It has taken
since 1982 to accumulate the cards, ten
more being awaited from countries EI, F,
D, GM, OK and SM.

His station comprises a transceiver driving a transverter with a 2C39BA amplifier. He has a 3SK97 pre-amp and the antenna is a 21-ele Yagi. His certificate is number eight and he is also a member of the 144MHz QTHCC since August 1984.

Irwin Brown GI1JUS (ATM), member No. 81 of the 144MHz QTHCC, was awarded his "125" sticker on July 27. Thirteen QSOs were on tropo, 7 via Es, 4 on m.s. and 1 by Ar propagation.

40 Eskdale Gardens, Purley, Surrey CR2 1EZ

Reports to Norman Fitch G3FPK

His list includes SM6AFH/MM (AO), GM4DMA/A on tropo in July 1987, YT3ET (GF) and YT3AU (HG) via Es on 20 July 1987 and IKOFEC (GD) at 1858km on June 4 this year.

For G3FPK, July 19 was a good day when my 200th card arrived for 144MHz QTHCC No. 1. It took from November 1984 to get these last 25 QSLs, not that I QSL all that aggressively.

Any reader wishing to claim either the QTHCC, which is available for all v.h.f./u.h.f./s.h.f. bands, or the VHFCC for working 100 different stations on all bands except 144MHz, should send an s.a.e. to the Poole address requesting a copy of the rules and an application form.

Beacon Notes

G6DER writes, "We now have the licence for GB3BSY on 2320.88MHz to be co-sited with GB3SY. It will be on the air as

Practical Wireless, October 1988

soon as I can sort out an Alford slot." GB3SY is the Barnsley u.h.f. repeater and Keith promises more beacon details later.

From South Africa, I see from ZS6WB's VHF News No. 88-11 that ZS1STB (KF05) is now on 50.904MHz running 25W to a 4-ele Yagi pointed to Pretoria. ZS5SIX (KG50) is in continuous operation from the QTH of ZS5BN on 50.075MHz and runs 10W to a halo antenna. ZS2SIX on 50.005MHz (KF25) runs 25W to a dipole firing north/south but was temporarily off the air at July 3.

Contest Details

The sixth and final leg of this year's 10GHz Cumulatives is on Sept 11, 0900–2100UTC. There are three contests: narrowband, wideband and fast scan TV. Submit your logs for all sessions in which you took part and send them, postmarked no later than Sept 26, to G4FRE at 15 Ferry Lane, Cavendish Park, Felixstowe, Suffolk IP11 8UR.

For 70MHz fans, Sept 18 is the day of the Trophy and s.w.l. contest from 0900–1600UTC. Three sections: F for single-op fixed stations, O for all others and L for the listeners. Usual radial ring scoring but with county and country multipliers. Entries to G4NBS at 10 Quince Road, The Limes, Hardwick, Cambridge CB3 7XJ.

The weekend Oct 1/2 sees the RSGB and IARU u.h.f./s.h.f. contest covering all bands from 432MHz to 47GHz, starting at 1400 for 24 hours. Single-op and multi-op sections for the RSGB version plus a listeners' one with scoring at one point per kilometre. Entries go to G4WAD at Tanglewood, Bridge Street, Lower Moor, Pershore, Worcs.

The first two of the five sessions of the 432MHz Cumulatives are on Oct 6 and 22, 1930–2200UTC and are two section events, F for single-op fixed and O for all other stations.

The 50MHz Trophy Contest is on Oct 23, 1000–1700UTC with F and O sections. Radial ring scoring up to 650km, thereafter 25 points per QSO. County and country multipliers.

OSCAR-13

OSCAR-13 was successfully launched on June 15 and is now in its desired orbit. Full information was found last month in Pat Gowan's G3IOR Amateur Satellite feature. The reason for mentioning this in VHF Up is that adverse comments have been made about the use of part of the 144MHz s.s.b. segment for uplink transmission.

The situation is that because eastern bloc countries do not have an amateur allocation at 1269MHz, the uplink region for Mode L, 50kHz of parallel Mode L operation has been provided in the 144MHz band. This is termed Mode JL and the uplink is 144.425–144.475MHz. This was explained on page 61 of the July

In both cases, the downlink is in the 435MHz region of the 70cm allocation. Because the translator on 0-13 inverts the signals, the 2m uplink is on lower sideband.

In April 1987 there was a Region 1 IARU Conference and its Committee B dealt with v.h.f. band planning amongst other topics. I can find no reference to the proposal that the 144MHz band plan be amended to accommodate any satellite uplink, other than in the top 200kHz of the band.

Even so, there is no reason why anyone should object to s.s.b. signals directed to

satellites using this part of 144MHz, any more than there is when m.s. operators use it for pre-arranged schedules.

However, what cannot be tolerated is stations with very wide signals swishing their v.f.o.s around in an attempt to find their signals on the downlink and in the process interfering with other QSOs.

To comply with Clause 4(1) of the amateur licence you must listen first before transmitting to ensure you are not interfering "... with any wireless telegraphy." From what I have observed so far, this is not being done and certain operators are "W-h-a-a-a-l-l-o-w-i-n-g" for ages so ruining other QSOs.

The 145.8–146.0MHz part of the band has long since been an exclusive satellite band under the worldwide IARU band plan. But 144.425–144.475 MHz has not suddenly become an exclusive satellite subband, a point some OSCAR users seem to have conveniently overlooked.

My own feeling is that in countries where amateurs do have access to the 1269MHz part of the 23cm band, they should stick to Mode L and refrain from using Mode JL. I would like to hear from any readers who are suffering from unnecessary, or even deliberate, interference from 0-13 users.

A New Tropo Record?

Weather map watchers on July 15 will recall that there was a long, thin wedge of high pressure stretching from off the west African coast, northeastwards right up the Irish sea. Either side of it were active depressions and some humid air for good measure.

This resulted in a "first" for Brian Sheepwash GI4KIS (IO86VR) when he worked EA8BEX (IL27GX) at 2305UTC. My computer reckons the QRB as 3064km-true ellipsoidal-and a new European and probably IARU Region 1 tropo record for 144MHz.

Signals of S5 to S9 were exchanged on c.w. and s.s.b. Brian tried to alert other GIs by telephone with little success, one being GI1JUS who never heard it ring. One can imagine why Irwin felt as sick as the proverbial parrot when he heard the news

At 2335 Brian worked EA8BML also in IL27GX who had been working various Els. This QSO went on till 0055, signals ranging from S3 to 10dB over S9. EA8BML was using a Yaesu FT-480R, 60W amplifier, GaAsf.e.t. pre-amp and 17-ele Tonna Yagi 9m a.g.l. Gl4KIS was using an FT-290R, 100W amplifier, 3SK124 masthead pre-amp and four 9-ele Tonna Yagis at 18m a.g.l. Congratulations to all concerned.

The 50MHz Band

Clive Penna GM3POI operated -/A from Deerness (IO88OW) at the beginning of July. At 2144 on the 9th he worked the Saba Island DXpedition PJOM for an undoubted 'first'. The operator was WB2CZB from New Jersey whom Clive had worked before. The locator was not mentioned but I make the QRB around 6660km.

At 2150 **Mike Devereux G3SED** (HPH) worked PJO and his letter to Clive WB2CZB said he also worked G4GLT in this brief, five minutes opening. These were the only two-way 50MHz QSOs made into Europe and would seem to be via multi-hop E-layer.

However, G3SED had been monitoring 28MHz some half hour earlier and heard

QTH Locator Squares Table

		Band (M	Hz)	
Station	1296	430	144	Total
G8GXP G3XDY G4FRE G3JXN G1LSB	45 81 63 87	151 137 136 133 126	331 185 84 175 125	527 403 283 395 251
G3UVR G3IMV GJ4ICD G0DAZ G4KUX	75 42 59	125 122 119 114 112	224 406 253 249 367	424 570 431 363 479
G6DER G4RGK G4TIF G4XEN G8HHI	78 38 — — 31	110 107 107 106 106	183 262 193 264 148	371 407 300 370 285
G3COJ G4NBS G6HKM G8PNN G1EZF	44 59 31 63 32	103 103 101 98 93	186 102 190 128 249	333 264 322 289 374
G1KDF G8ATK G4MUT G6MGL G6DZH	35 45 28 59	93 91 90 89 87	163 143 149 141 149	291 279 267 289 236
G4SSO G1EGC HB9AOF G3NAO G0EHV	11 55 —	83 80 80 80 75	219 192 141 160 137	302 283 276 240 212
G8LHT G1GEY G6STI G6XVV GMOBPY	4 21 25	71 68 66 64 57	133 158 127 211 129	208 226 214 300 186
G6AJE G4CQM G8MKD EI5FK G4FVK	5 — — — 20	57 52 49 47 46	95 100 142 168 75	157 152 191 215 141
G4AGQ GJ6TMM G4DEZ G6MXL G4MJC	1 44 10	41 39 36 36 33	104 133 246 81 184	146 172 326 127 217
GM4CXP G4ZTR G0FEH G1VTR GM0GDL	29 — —	31 29 24 23 19	184 37 88 32 66	215 95 112 55 85
PA3EUS G1IMM GW6VZW G8PYP G2DHV	_ _ _ _	18 13 6 6	57 98 106 61 31	75 111 112 67 39
G4DHF G4SWX I4YNO G3FPK G4IGO		1111	307 293 270 232 223	307 293 270 232 223
G4SFY G4MEJ G8LFB G4YCD GW4FRX	11111		222 213 205 197 191	222 213 205 197 191
G4DOL G11JUS ON1CAK G4TGK G8XTJ		11111	183 174 172 118 108	183 174 172 118 108
G7ANV G1SMD GI4OWA GMOHBK GOHEE			103 93 91 75 73	103 93 91 75 73
GU4HUY G1CRH G0HDZ G1NVB G7AHQ			67 62 61 49 34	67 62 61 49 34
GM0J0L GM1ZVJ	_	=	29 21	29 21

Starting date January 1 1975. No satellite or repeater QSOs.

weak signals from W4, TI2, HP and 6Y5 from the same area. Mike writes, "I believe the 28/50MHz openings in this case were using the same propagation mechanism and occurred at the 'grey line' peak, probably by enhanced F2 layer as a result of high solar flux and a low A index."

On July 10, following a major Es opening on 144MHz, Mike worked/heard twelve stations for the W2, 3 and 4 call areas around the same time. He also reports openings to North America on June 6, 25, July 4, 5 and 9. He worked LA6HL/TF (HP94BD) on June 26 at 0745 with fully quieting f.m. signals. He learned that TF3JP has applied for a 50MHz permit.

Bob Nixon G1KDF (LNH) lists several Fs worked on July 6, 9 and 10 and it now seems that a number of them have their permits. Other QSOs were with CT4KQ/M, LA and OH. He lists DL8LAQ (EN) on the 24th but since there is no likelihood of any German 50MHz licences for a long time, such QSOs cannot be accepted for table scores.

Ian Galpin G1SMD (DOR) has filled many pages in his log book with 50MHz QSOs recently. He mentions OG2C, a Finnish special event station, and the good signal that GM1SMI/P (YT) was putting in in the mid-July period.

lan checked the band at 0122 on the 22nd and worked LA1K (JP53EK) who faded out till 0134 when signals were much stronger. LA6QBA/P was contacted at 0226 (JP61BJ) and again at 0310, the second QSO lasting till 0536. There was a huge Ar at the time in Norway and 'QBA's signal had a very distinct echo. G1SMD uses an FT-690 at 2.5W or 10W with an amplifier and a dipole antenna.

John Palfrey G4XEN (NHM) worked OG2C (KP20) on July 21 and OH2HK. GM3JIJ (IO68) in WIL was a new county via Es on the 24th. Welcome to Vic Van Den Bergh G6DIF (LDN) who is a keen c.w. operator. He contacted YU3ES on June 25 and G4XEN on July 10 and will doubtless add more in the coming months.

Ela Martyr G6HKM (ESX) now has 39 squares on the band. July QSOs included F6DRO (JNO3) and GI8YDZ (IO65). She heard N2CEI and W2CAP/1 on the 10th, GM1SMI/P (OKE) on the 21st and LA3TQ (JP99) on the 23rd.

Colin Redwood G6MXL (DOR) worked some GMs on the evening of July 10. Gerard Elliott GI4OWA (LDR) worked several Fs on July 6 and on the 10th EA1MO (IN71PP) who, I am told, insists he has a 50MHz permit. He also worked LA3TQ on the 23rd and 9H1EL (JM75FU) the next day, all being Es QSOs.

John Hilton GM1ZVJ (LTH) has been on the band since June 21 using an FT-690R Mk 2 at 2.5W to its quarter wave whip antenna. Best DX were FC1GXV (IN94) on June 28 and FC1FNH (IN96) on July 20 and he is suprised at such results considering his modest station so far.

Dave Lewis GW4HBK (GWT) added SV1DO and LA6HL/TF for a couple of new countries via Es on June 28. Finally, a reminder that the t.e.p. season is now underway, the peak month being October. So listen to the south for African stations for there are many in ZS in particular anxious to work into the British Isles.

The 70MHz Band

The second issue of Roger Banks's G4WND Four Metres Newsletter QSB has arrived and features a report from John Wilkinson G4HGT on the highly successful Squarebashers Contest Group's trip to

Annual v.h.f./u.h.f. table January to December 1988

Station	501 Courties	MHz Countries	701 Counties	MHz Countries	144 Counties	MHz	430 Counties	MHz	1296 Counties	MHz Countries	Total Points
G1KDF G1SWH G6HKM G4XEN G8LHT	38 38 24 40 8	16 17 12 14 6	_ _ _ 6	=======================================	83 88 71 63 58	18 17 26 28 27	57 48 44 46 39	11 7 11 9 11	25 20 5	6 6 - 2	254 215 214 200 163
GOIMG G1IMM GMOEWX GW6VZW G1EZF	28 26 53 35	11 8 12 10	25 — — — 18	3 _ _ 2	40 52 49 62 67	10 11 13 11 23	24 31 —	3 2 —	=======================================	=======================================	144 130 127 118 110
G4DEZ G4VOZ G4YCD G6MXL G0EHV	26 18 — 15 —	5 11 - 8	46 10 35	- 6 - 3 5	24 83 35 45	8 23 13 19	24 21 — 14	5 7 — 3	12 - 3	5 _ 1	109 109 106 105 104
GW4FRX GM0HBK G6MGL G3FPK G7ANV	26 19 —	- 8 10 -	=	=	69 46 49 74 66	28 15 10 20 21			_ _ _	_ _ _	97 95 94 94 87
G4ARI G8PYP G1SMD GI40WA GW4HBK	13 21 14 22	9 17 16 18	16 2 — 36	2 1 — 5	58 38 25 38	9 12 18 13	- 6 - -	_ _ _ _			85 83 81 81 81
G4ZEC G1DOX G1CEI G4AGQ G8XTJ	16 — —		19 13		56 22 59 35 53	23 5 12 7 11	- 5 12	- 2 - 2	_ _ _	- - -	79 76 71 70 64
G2DHV ON1CDO ON1CAK GJ6TMM G3EKP	5 - 8 12	1 - 9 3	12 - - 16	1 - - 4	28 46 44 27 7	6 15 13 9 4	7 - 2 5	- - 1	11111	=======================================	61 61 57 56 52
G4WHZ GMOJOL G4ZVS G0HGA G0HDZ	3 - - -	<u>2</u> 	=======================================	=======================================	31 30 34 30 30	12 10 5 5 5	11111	=	===	=======================================	48 40 39 35 35
GU4HUY GM1ZVJ G8PNN	_ 		_ 20	<u>-</u>	23 13 —	10 6 —	-	=		-	33 25 23

Gibraltar. They completed 168 contacts with 104 different stations in EI, G, GJ, GU and GW, best DX being GOEHV (TWR) at 2103km.

Other topics covered in *QSB* are a d.i.y. 6-ele 70MHz Yagi and a review of an R.N. Electronics transverter. There is a list of European stations QRV for cross-band working. The next issue is due in early October so why not drop Roger a line at Rivendell, Kiln Way, Polesworth, Tamworth B78 1JF for more details?

Eddie Ashburner's GOEHV (TWR) new interest is 70MHz and he uses a Kenwood TS-830, Spectrum transverter and QQV07-50 p.a. The antenna is a 4-ele Yagi and his QTH is 150m a.s.l. As previously reported, he was the best DX from ZB2IQ and vice versa. He reckons GM and GI activity to be very low, best chance to work these in contests.

John Jennings G4VOZ (LEC) has been in Scotland with portable gear and now appreciates why so little is heard from GM. He had great difficulty working from hill-tops and reckons some enhancement is necessary to get signals to middle England.

As for NFD, he felt activity was down on 1987 and that there were several poor quality stations around. Six countries were workable and he mentions GD3FLH/P (IOM). Another noteworthy station was EJ1000 on Dalkey Island (IO63XG), the Dublin Millenium station, operated by EI9FK. John worked it on July 23.

G6MXL confirms John's sentiments about NFD. Ron Reynolds G6WEM (ESX) gave away points in NFD and gained a couple of new countries. On July 12 in activity night he called CQ for 100 minutes with no takers and suggests Tuesday

nights should be called hibernation nights! GW4HBK worked a few new stations in July and also EJ1000. Dave has been doing a lot of cross-band to CT, D and OK.

The 144MHz Band

Most readers have suggested that the Es event on July 10 was the best of the year. It lasted around three hours and stations all over the British Isles were able to make QSOs. Countries "on offer" included HG, I, IT9, OE, OK, YU, YO and UB5.

Dave Thickett GOFEH (DYS) worked 19 stations, in HG, OE, YO and YU, in six new squares. Andrew Salt GOHEE (YSS) discovered the event at 1446 and with QRP on c.w. he worked YU7VA and YU7AS (KF) and HG5AB/3 (IG).

G1KDFs tally was nine is, three OEs, two YOs and 35 YUs between 1424 and 1629 in twelve new squares. G1SMD got nine new squares and three new countries in the opening. Ian worked one each OE, OK, YO5 and UT5 plus several HGs and YUs between 1400 and 1610.

Peter Atkins G4DOL (DOR) caught the brief morning event and between 1024 and 1037 worked Italians in GB, HA, HB and IY squares and IT9SBZ (HY). He did not get on till 1543 for the main Es when new squares were OK3YDZ (JI), YO5DJM (LH), UB5DAA, UT5DL and RB5DC (LI) and OK3AU (KI).

G4XEN was on from 1410 to 1622 and John completed 48 QSOs; 19 YUs, 15 HGs, four Is and five each OEs and YOs. New squares were I2EA/7 (JN81), YO7DL (KN14), IV3GBO (JN66), YO5BP/P (KN16), YO5DJM (KN17) and UO5OB (KN45CW) at 2203km for a new country.



AMATEUR **R**ADIO **C**OMMUNICATIONS **L**TD.

EX NORTHERN BRANCH OF A.R.E. COMMUNICATIONS LTD.

"As from May 1st we parted from our Parent Company in London and we are now completely independent but still good friends. The only change is the name, there are the same Smiling faces and the same Excellent service. Peter (G4KKN)



STANDARD C500 Phone for Special Deal

Phone us NOW for Special Deals On the following: STANDARD C-500 KENWOOD TS-680s ICOM IC-32E YAESU FT-767GX

ICOM IC-32E Phone for Special Deal

THE LATEST TNC PACKET TERMINAL **PK-88 AVAILABLE EX STOCK** £109.95

Come and visit the largest Emporium in the North of England with All brands of equipment on display for you to try in a relaxed friendly atmosphere together with a **NEW BRAND OF COFFEE!!**

Always a large selection of clean Second Hand equipment and commission sales available.





38 Bridge Street, Earlestown, Newton-le-Willows, Merseyside WA12 9BA. Only 1 mile from Junction 23 – M6 Telephone: N-le-W (09252) 29881/2 OPEN TUES-SAT 10 a.m. - 5 p.m.



MICROWAVE MODULES · TONNA · JAYBEAM · SANDPIPER · BNOS · AKD · CAPCO · REVEX

STANDARD

MILTON KEYNES & DISTRICT AMATEUR RADIO SOCIETY

Present their 2nd AMATEUR RADIO and General

CAR BOOT SALE

CRANFIELD AIRFIELD, BEDFORDSHIRE

SUNDAY, 25th SEPTEMBER, 1988 Admission 25p

Advance Bookings: Mike GOFMC (0908) 566796, Tony G6WXM (0908) 316435 TALK-IN S19

COMM RXs. Racal RA 17 MkII general coverage HF Rx 500Kc to 30 Mc/s in 30 bands as film scale tuning approx 45ft variable selectivity 6 pos 100/cs to 8Kc, BFQ, N Lim, AVC or manual control, int spk. tuning meter etc. Supplied checked and aligned with handbook & connec £188 SIG GENS. Marconi TF995/A2 1.5 to 220 Mc/s AM/FM var deviation & AM Mod, metered 0/P fitted fine & coarse atten to 1 Uv at 50 or 75 ohm in table case size 17×12×9" mains operated with book tested. £115 Army No. 2 Osc 20/80 Mc/s in two bands AM/FM var 0/P & deviation mains or 12v DC tested with connec. £45. CRYSTAL CAL, standard 100Kc unit with close tol oven incorporates 1° CRT unit to enable phase checks to made with 100Kc amp unit, provides 100Kc 0/P at low level, mains operated tested with connec. £28. ARMY TEST KIT for use with A 14 set as mains operated bench p.u, 3×12v Dc metered with set of connectors etc in 19° table case. £65. RF ASS spare front end units for R210 Rx tunes 2/16 Mc/s in 7 bands with 3 valves as If 0-P in range 450/470Kc with circ. £17.50. VIDEO RECORDERS Sony portable for use on 12v DC reel to reel 5° spools inc sound approx size 10×12×6° tested with cric. £55 mains nu charger £15. ARMY HAND GENY nom 0/P 12/44 DC 1 amp with elec regulator. £24.50. ARMY MONOC SIGHTS 5×27 5mm var focus. £9. ARMY AE KITS 30f in 10×3ft 1° screw sections with guys, stakes, base insul etc in carry bag new cond. £36. METAL DETECTORS ex Army described as bomb locators made by Forster in West Germany suitable for Ferros metal only range 3 to 5 metres, comprises search probe 24° long 2° dia (can be used in water) control unit with 4 ranges of sensitivity 30/90.30/90.900 gammas, meter unit center reading, electronic unit transis reps & DC 1:e 4× HP 2 batteries, provision for spk earphone supplied in fitted wood cheat size 34×15×7° with inst book & circ tested for operation. £115. ARADIOSONDE UNITS crystal controlled version of M 50 dil transis as sensors for temp, provision for spk earphone supplied in fitted wood cheat size 34×15×7° with inst bo

A.H. SUPPLIES
Unit 12, Bankside Works, Darnall Rd, Sheffield S9 5HA. Ph. 444278 (0742)

SPECIAL NOTICE TO READERS

Although the proprietors and staff of PRACTICAL WIRELESS take reasonable precautions to protect the interests of readers by ensuring as far as practicable that advertisements in PRACTICAL WIRELESS are bona fide, the magazine and its Publishers cannot give any undertakings in respect of claims made by advertisers, whether these advertisements are printed as part of the magazine, or are in the form of inserts.

While the Publishers will give whatever assistance they can to readers having complaints, under no circumstances will the magazine accept liability for non-receipt of goods ordered, or for late delivery, or for faults in manufacture. Legal remedies are available in respect of some of these circumstances, and readers who have complaints should address them to the advertiser or should consult a local Tradings Standards Office, or a Citizen's Advice Bureau, or their own solicitor.

PRACTICAL WIRELESS

July 88 19.70
Feb 88 73.00
Jan 88 41.30
Nov 87 24.90
Sept 87 25.60
June 87 19.70
May 87 49.00
April 87 72.50
Feb 87 39.30
Jan 87 16.50
Dec 86 25.30
Nov 86 14.20
Oct 86 17.80
Oct 86 18.20 Simple 50MHz Converter Sept 86
Arun Parametric Fitter May 86
Meon 2. 50MHz Transverter (144MHz IF) April 86
Meon 2. 70MHz Transverter (144MHz IF) April 86 Sept 86 21.50 May 86 49.30 April 86 41.00 April 86 41.00 April 86 44.00 Jan 86 31.85 Dec 85 25.30 Oct 85 41.00 Oct 85 41.00 Oct 85 19.90 Oct 85 12.30 Stell Johns, Teceive of Blenheim v. h. I. to h. I. receive of Downton Freq to Voltage Com AXE Signal Tracer Itchen LCR Bridge Woodstock, Short Wave Conver Masthead Preamp For 144MMz Westbury Basic Wobbulator Helph Ingreduces, Morfel Voltmein Rtty/Morse Modem (exc. case) Meon 144MHz Transverter (28MHz IF)
Meon 144MHz Transverter (28MHz IF) Fet Dip Oscillator Capacitance Meter High Impedance Mosfet Voltmeter Taw. VLF Converter Add On BFO Aug 85 Morse Sending Trainer Auto Notch Filter Active Antenna Automatic Nicad Charger

PRICES DO NOT INCLUDE YAT, WHICH SHOULD BE ADDED TO THE TOTAL ORDER VALUE AND PAP CHARGES. PAP = 70p UNLESS SPECIFIED. ARTICLE REPRINTS 50p (IF REQUIRED). ALL KITS ARE COMPLETE (LESS BATTERIES) UNLESS SPECIFIED INCLUDING POB. CASE ALL COMPONENTS, CONNECTORS AND HARDWARE. ALL COMPONENTS ARE NEW AND TO FULL SPECIFICATION. CHEQUE, P.O., OR ACCESS TO:

CPL ELECTRONICS, 8 Southdean Close, Hemlington, Middlesbrough, TS8 9HE TEL: 0642 591157. Other kits are available plus a wide range of components etc.

ACCESS, MAIL OR TELEPHONE ORDERS WELCOMED. FREE PRICE LIST ON REQUEST.



He found the main reflecting area brought in the HG, OE and YUs at QTE 104–111* but that two smaller patches provided propagation for short periods to Italy and Moldavia.

G6HKM did not get on till 1522 and worked 17 stations, the last QSO being at 1548. A CQ call at 1540 brought three HGs and two each from OE, OK and YO. New squares for Ela were JN87, JN96 and KN06.

Howard Staddon G6STI (LDN) was busy with the 432MHz WAB contest so only made one QSO to UT5DL at 1623. G6WEM was on between 1412 and 1552 and Ron lists a dozen QSOs with HG, I, OE, OK, YO and YU stations.

Stephen O'Malley G7ANV (NLD) has written for the first time to show that some G7s read this piece. Up to mid-July he had worked 103 squares and in the July 10 Es event he lists YU3C (JN76), OE8HIK (JN76) and YU1ADN (KN03).

lan Harwood G8LHT (YSS) worked many stations between 1432 and 1621, mainly YUs but "... nothing exotic was heard ..." lan was called by YO2BBT but the QSO was not completed; it would have been his first YO.

Frank Holland GIOAIQ made four Italian QSOs between 1440 and 1500 in FE, FF and IB squares from Armagh using 80W to two 9-ele Tonna Yagis.

GI1JUS lists 31 stations worked between 1414 and 1636. Irwin's best DX was YU1GT (KNO4LP) at 2216km. New squares were YT2GL (JF), I2AE/7 (IB), I4BXN (FE), IK2DDR (FF), YU1LR (JE), YU2EZA (IG), OE6AHD (HH) and HG1WD (IH). The last contact was YO2IS for a new country.

GI4OWA lists six Is and two YUs in this event and Gerard's new squares were I3LDS (FF), IK4GBZ (FE), IK4GNG (GE) and YU1EN (JE). Unfortunately rain static gave reception problems.

GM1ZVJ, using just 2.5W to a 10-ele Jaybeam Yagi, worked YU3C and YU3OU in HG between 1525 and 1540. John heard many YUs from South Queensferry.

Roger Sarre GU4HUY (GUR) operated between 1435 and 1552 working 38 stations in HG, OE, OK and SP, the only contributor to mention a Polish QSO. His best DX was UT5DL. Roger runs 40W of s.s.b. to a 10-ele Yagi.

Mervyn Rodgers GMOGDL (CTR) telephoned a report and worked YUs in HF, HG, JE and KD squares. For once G3FPK was around at the right time and five new squares were worked. It certainly was an exciting event and in the London area every couple of kilohertz was occupied by very loud local or DX signals.

Sheldon Hands GW8ELR (DFD) used his lcom IC-202 at 3W and worked 22 stations in HG, IV3, OE, YO and YU. It must be wonderful not to have many very QRO stations on your doorstep in these events.

There was an afternoon opening via Es to southern Spain on July 8. G4DOL worked EB7NK and EA7s CVC, CVD and GNO all in new square YW between 1630 and 1646. G6HKM had three QSOs, one to YX and two to YW, both new squares.

G6WEM's timing was 1704 when he worked EA7BHO (IM87EE) but he also heard EA7FTH at 1740 and EA7AJ at 1755. G4XEN mentions a five minutes Es opening at 1325 on July 20 when he worked YZ5XMA and YU5QG (KN02) a new square. John heard an LZ who quickly disappeared.

On the tropo scene there was a major, widespread opening on July 18/19. Peter

Hirons G1CEI (HPH) is a new contributor presently running a Yaesu FT-726R, 80W amplifier and 14-ele M.E.T. Yagi at 11m. The lift provided him with six new squares in the southern part of France.

G1KDF worked two GUs and three FS, one in JN04 for a new square. That was F1JGY/P also worked by G1SMD. On c.w. G4AGQ worked F6EPO (ZH), FD1GTR (ZG), F6DRO (AD), F5DE (AF), FE1JNA (AE) and F6GOY (BH).

G6HKM worked F6HLW/P (AE) and Ela hopes he will QSL. G6STI heard mostly squares already confirmed but Howard did find FC1JUC/P (DF) at 2151 and FC1BPK (AD) at 0007 for two new ones.

G8LHT reckons the real DX went over his head in this lift; it certainly did in London, lan, where he heard GMs working to the south of France exchanging S9-plus reports.

GIOAIQ worked FC1FMU (ZI), F1FHI and F6ETZ (ZH) plus GU and GJ stations. GI1JUS found a couple of new ones, FC1FVV (ZE) and FC1BPK (ZD). GI4OWA lists nine distant QSOs the longest to F6GPT and FC1ADT in ZE square which was new for Gerard, as was FC1DXP (AF).

GMOGDL worked F5IL (AJ) in this event. My take-off to the south is not too brilliant so I concentrated more to the west as there were lots of Irish stations QRV. I had a struggle with EI5FK at 1443 and appreciated help from Martin Lowe G4YCD (AVN) in getting some table figures from Charles. Conditions were much better late at night and I worked EI4AQB (VN) in Galway and EI4DQ and EI7BA in County Cork.

Some late news. On July 31, Band II was full of f.m. broadcast stations from Europe via Es. At around 1835 EA8BEX (IL27GX) was heard and worked by stations in the west and northwest parts of England at least

John Nelson GW4FRX (PWS) heard virtually nothing from EA8 but Colin Mister GODAZ (HRW) did work him as did G4KUX (DHM), G4PBP (WMD), G6HCV (SFD) and G8XVJ (CHS). He is sure a GM1 in YP square also worked EA8BEX.

I understand there was some very short skip Es propagation with GWs in the west and north working HB9. Apparently it was over by 1900, so your reports on this event are awaited with great interest for next month.

The 430MHz Band

G1KDF worked GM1SMI/P (OKE) on July 17 and now only needs Shetland for all 78 counties starting with the G prefix. In the tropo lift on the 18th Bob worked GU1HTY (GUR), GJ6BUK, F1FHI and F1DED (BI).

Pat Billingham G4AGQ (SRY) worked F6APE (ZH) on July 18. Swiss beacon HB9F was S9 with Pat the next morning but no other signals were heard. G4XEN wrote the 432MHz was hardly worth reporting but John did add G0BLB (AVN) and GW8KQW/P (CWD) for new table counties.

G6DIF is QRV on the band but is disappointed at the lack of c.w. activity. G6HKM still finds the band very quiet but did work GM8TFI/P (DGL) on July 2 in NFD. Ela did not work any GMs in the 1987 event. On the 18th she worked FC1ADT. GMOGDL found F1FHI the same day.

G8LHT worked GJ for the first time in the southerly lift on July 18/19.

The Microwaves

Precious little to report here, I regret. GOFEH is building a transverter for 1.3GHz

Annual c.w. ladder

Station	50	70	144	430	Points
G4ZEC -	_	_	474	_	474
G40UT	-	_	191	-	191
GOHGA	_	_	176		176
GOHLT	13	-	161	-	174
G4AG0	_	35	83	8	126
G4V0Z	24	79	-	17	120
G4WHZ	6	-	106	-	112
GOHEE	-	-	95		95
G4ARI	_	10	80	1	90
G4ZVS	-	-	80	10-	80
GODJA	11	-	64	-	75
G2DHV	10	33	24	_	67
G3FPK		_	63	ī —	63
GOGKN	-	-	52	-	52
GW4HBK	21	30	-	-	51
G1SMD	21	-	15	_	36
G6DIF	2	1-	30	·	32
GU4HUY		-	22	:	22
G1D0X	3	5	_	-	8

Number of different stations worked since January 1.

and has got the RX and TX converters working. However the oscillator drifts so Dave has now got an oven for the crystal.

On 1.3GHz G1KDF added new station G8ESB (YSN) on July 10. On the 17th Bob worked EI4CI/P (Meath). He advises that Pierce and EI9ED should be QRV on the band from their home QTHs soon. On the 18th, G8KBQ (SOM) was his 46th county.

G6HKM worked eleven stations on NFD on 1.3GHz which provided four more 1988 counties and GM for a new country. It took Ela nine minutes to exchange the information with GMOFRE/P (DGL) but perseverance finally paid off.

Liechtenstein Operation

Reg Woolley GW8VHI, currently in Germany as DA4RG, says he and some German friends will be operating from the Principality of Liechtenstein during the major IARU contest on Oct 1/2. He will be signing HBO/DA4RG.

Operation will take place on 144/432/1296 and 2320MHz and on 10GHz. Afterwards they will be concentrating on 144MHz m.s. giving priority for skeds to those who have been on DXpeditions themselves. Nice thought that. I assume they will be on the 14.345MHz European v.h.f. net for arranging "instant" skeds.

Giant Antenna Masts

Julie Yates G8MKD (WMD) sent me a clipping from a local newspaper following the successful planning application for a 10m tower. There are references to "...a giant aerial mast ..." and "the monster aerial ... which will stretch to a height of 33 feet when in use."

She wonders what the reporter would have written had they got permission for a 60 foot tower. As she says, this kind of reporting does little to further the radio amateur's cause.

Worked All Britain

From G8XTJ, the Publicity Officer for WAB, comes the August press release. On v.h.f., G0JHC has received the first Class II Counties Award for working 55 counties on 50MHz s.s.b. For WAB details send an s.a.e. to G4KSQ who is QTHR.

Keying Problems

Angela Sitton GOHGA is a dedicated c.w. operator but had been getting many

reports of faulty keying. It seemed satisfactory from her sidetone oscillator but the signal as received by another station was corrupted.

She eventually traced the problem to too much r.f. in the shack, some of it getting into the keyer which tended to do its own thing. It has to be appreciated that high impedance c.m.o.s. circuits are very susceptible to minute whiffs of stray r.f. so you need to ensure everything is properly shielded and grounded.

This example highlights the need to be able to monitor your transmitted signal otherwise how can you be certain your c.w. or speech is not distorted?

A Bit of a Spoof?

Under stations worked via Es, one reader has listed at 1327 on June 19 SPOOF in JO92EA. As far as I was aware, there was no Es propagation towards Poland that day and no other reader mentioned any. Furthermore, I have never heard an SPO

and, according to the Operating Manual, the Polish call areas are numbered one to nine for normal amateur calls.

This rather reminds me of a classic spoof in the late 1940s when a station signed as GO2HEL with the QSL address given as Obois, Ubinad, Lafter, Orkneys. Anyone remember that?

The next three deadlines are: Sept 21, Oct 26 and Nov 24

RTTY

Reports to Mike Richards G4WNC 200 Christchurch Road, Ringwood, Hants BH24 3AS

The "New" Licence

With all the fuss being made about this licence, I thought I would take a look at it from the data operator's point of view. This first thing I noticed was that although mailbox operation is now allowed (provided authority is obtained from the RSGB), unattended operation of mailboxes is still not allowed. I think it's a shame that this issue hasn't been resolved, as a properly regulated mailbox network would be a great asset for the dissemination of news and a whole assortment of other information. As it is, I expect the networks will continue to operate outside the licence.

One commendable aspect of the new licence is that they have used common names for the data modes, i.e. RTTY, AMTOR, etc. This helps to make the conditions much easier to understand.

Another important point is that data is accepted as a separate mode and is defined as "digital codes representing numbers, text, speech, images, measurements, computer programs or other information authorised by the licence". This is a nice open definition and leaves plenty of scope for future experimentation, which after all is what amateur radio is all about. We have even gained an extra segment of the band, 1.810–2MHz is now available for data modes. I await details of your first contacts on this segment!

My final point on the licence concerns the various classes of emission for the data modes. These have been a source of confusion for some time and it's good to see someone has actually put pen to paper to set the record straight. I know they were published in the supplement last month, but they bear repeating here:

RTTY/AMTOR

Direct frequency shift keying of the carrier F1B

Frequency shift keyed audio tone (f.m. transmitter) F2B

Frequency shift keyed audio tone (s.s.b. transmitter) **J2B**

Packet/Data

Direct frequency shift keying of the carrier F1D

Frequency shift keyed audio tone (f.m. transmitter) F2D

Frequency shift keyed audio tone (s.s.b. transmitter) J2D

Facsimile

Frequency shift keyed audio tone (s.s.b. transmitter) **J2C**

Band Plans

Brian Waddell GM4XQJ has written complaining about the poor operational standards of data enthusiasts, particularly h.f. mailboxes. Brian's main complaint,

145 - Color 15 - Color

An example of a chart using the J&P program, received by a reader

being a keen QRP operator, is with the use of 7.030MHz which is the c.w. QRP calling frequency.

Unfortunately, this frequency has been commandeered by several AMTOR mailboxes, which has got the QRP community up in arms on several counts. First, the very nature of the mailbox means that it doesn't listen before transmitting, it only responds to calls from other users. Consequently the poor QRP operator frequently gets flattened by 100W of AMTOR! To compound the problem, many of the QRPers are using very simple, home-brew, crystal-controlled equipment so they can't even QSY.

Fortunately, I do have some good news, the G3PLX mailbox has now moved to 7.036MHz and is issuing a message to all users mentioning the problem. I would reinforce Brian's plea for a frequency change and if by chance you find a mailbox operating on this frequency, please leave a message for the Sysop explain the situation. Regular readers will no doubt have noticed that I published this frequency as a mailbox frequency when I listed all the current mailboxes recently—apologies to the QRP world.

FAX

Whilst at the RSGB Exhibition in Birmingham, I managed to find time to look around at the various FAX software packages. Two very different options caught my eye, for reasons you will soon see.

At one end of the scale is the J&P Electronics FAX program which runs on the Spectrum. The program only handles "standard" transmissions using an i.o.c.

(index of co-operation) 576 and a speed of 120 r.p.m. But this is adequate for the majority of weather FAX and will also handle amateur transmissions with some distortion. One of the main attractions of this program is the price, which at £9 represents a cheap way of trying out FAX reception. There's always a snag and in this case you'll need a drum speed generator in addition to the program, which will cost £24. You need this because the computer's internal clock is not accurate enough to ensure properly aligned pictures.

At the other end of the scale is the Amiga-FAX from ICS Electronics2. This program is a full-blown FAX transmit/receive package which runs on the Commodore Amiga computer. This program makes full use of the high resolution screen of the Amiga to give 640 x 400 (250 000) dots with 16 grey levels. As you can imagine, this is a bit different to most of the programs available to the amateur today. Other features are that you can use the paintbrush files on the Amiga to draw your FAX pictures to be transmitted, images can be manipulated before or after reception and you can use a mouse to control the program. If you're interested in weather maps, charts with up to 3840 dots per line can be saved in memory and then printed in strips. With 500MByte memory expansion, maps with 4 million dots may be captured, and that's a lot of dots!

As you have probably guessed, this program is a little more expensive than the previous one I mentioned! The cost is £99.95 including VAT, but of course you need to have an Amiga first. I'm not actually sure how much they cost, or how many amateurs have access to them. Still if anyone does run this program perhaps they'll let me know how they get on. You never know if it catches on there might actually be some FAX activity around.

Readers' Letters

First letter this month deals with a plea for help. Terence Craig VK6PQ has written asking for information about AMTOR software for the Amstrad 464. Unfortunately, I don't know of any available, so I'm hoping that another reader will be able to help. If you can, drop me a line and I'll pass the information on to Terence.

Next, I heard from Raymond Hounslow who blames me (doesn't everyone) for reviving an old interest in RTTY. At first glance, his station would seem to be a non-starter, that's until you look into the subject. He has a 15-year vintage BARTG ST5 transistor terminal unit and a Toshiba HX10 MSX computer.

The terminal unit was originally designed to drive a ''real'' teleprinter (a clanking and whirring machine that usually smelt awful), so this will obviously need modifying as these machines used to work on $\pm 80 \text{V}$. I don't think that today's computers would think much of that. There are two options here, you can either contact BARTG³, who I'm sure could help or alternatively you could work out the modifications for yourself. The object is to end up with an output signal that swings between zero and $\pm 5 \text{V}$ maximum as opposed to the $\pm 80 \text{V}$.

As for software, I know of two possible sources. J&P Electronics¹ are one as they have Morse and RTTY programs for MSX (1) and the other possible source the MSX Software Shack⁴. An s.a.e. to either source is worth while to check that you're both talking about the same machine.

"Where's all the RTTY activity on 144.6MHz," asks Jason G4KVT. From this QTH, the only time I really hear very much on that frequency is during a v.h.f. RTTY contest, where everyone goes between contests is a mystery. Jason has been busy though listening around on h.f. In about an hour one evening he logged the prefixes YU, SP, IK, DF, UT, OE, W4, YO and DJ—all on 14MHz. His last comment was about software for Packet and AMTOR for the Spectrum. My suggestion was to contact SARUG (Sinclair Amateur Radio Users Group), but if any readers have details of this kind of software for the Spectrum I'd like to hear from them.

I received a very interesting letter from Michael Greig GM1YSI about the Maplin TU1000 and MBA-TOR program from

The next three deadlines are: Sept 21, Oct 26 and Nov 24

AEA. Michael is very active on v.h.f. where he uses a Trio 9130 transceiver and an eight element Yagi antenna. The computer in use is the Commodore C64 with a disk drive and a printer to complete the set-up. My first thought when I read his letter was, at last someone using RTTY on v.h.f.! It would seem that there is a quite a lot of v.h.f. activity in the Kirkcaldy area as you can apparently find RTTY or Cambridge Packet stations most evenings. If you live within r.f. contact of the area you may like to join in. The normal scenario is to all meet up on 145.525MHz (S21) for a chat and then to move down to either 145.275MHz or 145.325MHz for operation on RTTY or Cambridge Packet. Although Michael doesn't make it clear in his letter I would assume that, in that segment of the band, the modulation type would be audio frequency shift keying (F2B or F2D if you want to be clever).

Michael finds the TU1000 to be very good for his v.h.f. working. He bought it as a kit and built it himself without any real problems. The TU1000 has three preset shifts on it, 170, 425 and 850Hz, and the variable resistors needed to be set using a

frequency counter. After that he had to set up the internal clock to drive the two filters, then the tones were set up. Michael says, "this sounds all very simple, but it took me the best part of the week to get it up and running, but all the work was worth it."

It's always good to hear from readers who are getting on really well with their terminals or programs. So, if you think others would be interested in your set-up, drop me a line.

I haven't had a great deal of time for getting on the band this last month, it's the dreaded decorating season. Still I did hear/work one or two interesting stations. Top of the list came CE3FHR, that was Elias in Santiago in Chile. I managed a short chat on AMTOR with him whilst testing a rig out. Other interesting callsigns were (on AMTOR) K9MFI, VE2FK and WA1FBI, on RTTY there were only two of note, the EA7BTQ mailbox and KP4KC. All stations were worked/heard around 7 or 8pm towards the end of July.

Don't forget to send in your reports, no matter how mundane they seem to you.

(1) J&P Electronics. Unit 45, Meadowmill Estate, Dixon Street, Kidderminster DY10 1HH.

(2) ICS Electronics Ltd. PO Box 2, Arundel, West Sussex BN18 ONX. Tel: 0243 65655.

(3) BARTG. Pat & John Beedie, "Ffynnonlas", Salem, Llandeilo, Wales SA19 7NP.
(4) MSX Software Shack. 2011 Kensington Flats, Morningside, Durban 4001, Natal, South Africa.

Amateur Satellites

Reports to Pat Gowen G31OR 17 Heath Crescent, Hellesdon, Norwich, Norfolk NR6 6XD

AMSAT-OSCAR-13

As many readers will already have noted, our brand new, and first near-Molniya orbit, satellite is now in orbit for the next millenia. The last pictures from AMSAT-DL of the satellite on earth appears first as Fig. 1. It shows Dick Daniels and Werner Muller looking like real spacemen in the suits that protect them from the toxic, highly explosive, fuel and oxidant, filling the kick-motor tank with fuel. Next comes Fig. 2, the completed spacecraft with the entire AMSAT crew in their "clean-room" suits at the ESA launch site in Kourou, French Guiana. From left to right we see (standing) W. Gladisch, H. Wagner, W. Hass, D. Sunderland, G. Metz, D. Daniels, then (sitting) W. Muller, K. Muller, K. Meinzer, J. King, and O. Belser. The Ariane IV launch vehicle, with all satellites aboard and under countdown is shown the night before lift-off in Fig. 3, and Fig. 4 shows the lift-off of rocket itself at countdown plus 5 seconds, on its first step into space.

Tracking

Since the second kick motor firing, which burned off all the remaining fuel and even imparted a little additional velocity by exhausting the helium pressurising gas through the hot exhaust nozzle, the close to optimum orbit has been achieved. The latest set of RADAR derived Keplerian elements to hand follow, which can be used to give reasonable accuracy of passes with your computer program. Readers may wish to predict the shape and duration of passes for three and a half years' time, when the apogee point becomes that of the inclination, e.g. 57.654 degrees, to explore what an amazing cov-

erage then evolves for the northern hemisphere stations.

Epoch Year: 88 Epoch Day: 193.0

Inclination: 57.6540 degrees
Right Ascension: 247.5380
Eccentricity: 0.6538919
Arg. of Perigee: 187.2210
Mean Anomaly: 357.2170

Mean Motion: 2.09697960 orbits

Decay: 0
Orbit No/Rev: 57

Orbit No/Rev: 57 Semi-major Axis: 25783.070

Period: 25/83.070 Period: 686.701959 minutes Apogee: 36264.507 km

Perigee: 2544.826 km

Our Fig. 5 list of passes for the UK given for September 7 to 21 inclusive are based on this set of Keplerian elements, and evolve from the AMS-81 program. They show, reading left to right, the date, the time(s) of acquisition of signal, the time of loss of signal and the time of maximum DX range, all in UTC/GMT time. Under DX is given that mutual ground distance across the footprint, whilst under AZ comes the direction in which your beam should be pointing at this time.

The fifteen minute interval step-by-step tracking for the UK from acquisition of signal on Sunday 18 September 1988 is shown in Fig. 6 (a), (b), (c) and (d). It reads those cities in mutual communications range marked by an asterisk, at the time, phase (mean anomaly) and satellite range given, then the time, the probable mode, and indicating arrow showing if OSCAR-13 is going up or coming down from Apogee, followed by the azimuth and

elevation at those times. The then mode of operation, e.g. "B", "L", "JL", "S" or beacon telemetry cannot be confirmed, as it may well be moved slightly by the command team at AMSAT-DL to allow for eclipses and sun-angle before this set of passes comes into being.

Frequencies

On the first day of operation, your scribe worked JR3RRF on c.w. for a solid QSO on Mode "B". It was then discovered that the passband relationship, as expected, had suffered a change of some ten kilohertz since being measured and metered prior to downlink Mode "B" transponding at zero Doppler shift is as follows:

Uplink	Downlink	
435.576	145.823	This section of the
435.569	145.830	band will normally
435.559	145.840	be used for A1 c.w.
435.549	145.850	
435.539	145.860	
435.529	145.870	
435.509	145.880	This centre part will
435.499	145.900	normally be em-
435.489	145.910	ployed for mixed- modes, RTTY, SSTV, Packet, etc.
435.479	145.920	This section will
435.469	145.930	normally be utilised
435.459	145.940	by A3J s.s.b.
435.449	145.950	QSOs.
435.439	145.960	and so on to the band end.

Note, that the low-end c.w. mid-section mixed and upper section s.s.b. is recom-



OSING DX?

ANTENNA TUNER for outside or INDOOR antennas, end-fed LONG WIRES or dipoles, BOOST DX and reduce interference 100KHz-30MHz in 6 overlapping ranges, IDEAL for FRG7700 etc or 10W tx, ALSO connect voltmeter for FREE WAVEMETER, only £31.30, hear WEAK DX.

RARE DX UNDER QRM? DIG it OUT with a TUNABLE AUDIO NOTCH FILTER, between your receiver and extension speaker phones, BOOST your DX/QRM ratio, 40dB notch, only £22.20, hear FAINT DX.

Each fun-to-build kit (ready-made to order) includes all parts, case, pre-wound coils, instructions, by-return postage etc. and list of other kits.

CAMBRIDGE KITS

45 (PK) Old School Lane, Milton, Cambridge.

S.E.M.

UNIT P. UNION MILLS, ISLE OF MAN Telephone: (0624) 851277

Some comments on our QRM Eliminator in the last few days. "It works like magic". "Locals thought I was exaggerating until they heard it". "I'm phoning from Florida to say it's reduced my power line noise to zero. I can talk to my English friends again"

S.E.M. QRM ELIMINATOR. Unique design gets rid of any local interference. Connect in your aerial lead and removes QRM before it gets to your receiver (you can transmit through it). Any sort of interference, it can be next to your rx (your computer) or several miles away, e.g. power lines. £69.50 ex stock. As the P.W. review says "Does it work? Yes it does

S.E.M. TRANZMATCH MKIII. The only Aerial Matcher with UNBALANCED and TRUE BALANCED OUTPUTS. 1 kW 1.8-30 MHz, £135 Built-in EZITUNE (see below), £39.50. Built-in Dummy Load, £9.90. Ex stock.

EZITUNE. Allows you to TUNE UP on receive instead of transmit. FANTASTIC CONVE-NIENCE. Boxed unit, £45.00. P.C.B. and fitting intsructions to fit in any ATU, £39.50.

FREQUENCY CONVERTERS. V.H.F. to H.F. gives you 118 to 146 MHz on your H.F.

receiver, Tune Rx. 2-30MHz, £59.50 ex stock.
H.F. to V.H.F. gives you 100 kHz to 60 MHz on your V.H.F. scanner, £49.50 ex stock. Plug in aerial lead of any receiver. Tuning from 100MHz up.

2 or 6-METRE TRANSMATCH, 1kW, will match anything, G2DYM or G5RV? £35.00 ex

DUMMY LOAD. 100 W. THROUGH/LOAD switch, £24.00 ex stock.

VERY WIDE BAND PRE-AMPLIFIERS. 3-500 MHz. Excellent performance. 1.5 dB Noise figure. £32.00 or straight through when OFF, £37.00 ex stock.

R.F. NOISE BRIDGE. 1-170 MHz. Very useful for aerial work. £45.00 ex stock

IAMBIC MORSE KEYER, 8-50 w.p.m. auto squeeze keyer, Ex stock, Ours is the easiest to use. £45.00. First class twin paddle key. £20.00 ex stock.

TWO-METRE LINEAR/PRE-AMP. Sentinel 40: 14× power gain, e.g. 3 W - 40 W (ideal FT290 and Handhelds), £85.00. Sentinel 60: 6× power, e.g. 10 W in, 60 W out, £95.00. Sentinel 100: 10 W in, 100 W out, £135.00. All ex stock.

H.F. ABSORPTION WAVEMETER. 1.5-30 MHz, £39.50 ex stock

MULTIFILTER. The most versatile audio filter. BANDPASS HI Pass, Lo Pass and two notches. Frequency and Bandwidth adjustable 2.5 kHz-20 Hz, £75.00 ex stock

HIGH PASS FILTER/BRAID BREAKER. Cures T.V.I., £7.50 ex stock.

CO-AX SWITCH. Three-way + earth position. D.C.-150 MHz. 1kW, £25.00 ex stock

12 MONTHS COMPLETE GUARANTEE INCLUDING TRANSISTORS

Prices include VAT and delivery. C.W.O. or phone your CREDITCARD NO. Ring or write for further data or catalogue. Orders or information requests can be put on our Ansaphone at cheap rate times. Remember we are as near as your 'phone or post box.



electronics



SITUATED AT SOUTHERN END OF M23 — EASY ACCESS TO M25 AND SOUTH LONDON

HF REC	CEIVERS	£	(c&p)	2.M. TF	RANSCEIVERS	£	(c&p)	STATIO	ON ACCESSORIES	£	(c&p
Icom Kenwood Kenwood Kenwood Yaesu Yaesu Lowe	VC10 V.H.F. Converter	825.00 595.00 161.94 875.00 639.00 100.00 375.00	() () (2.00) () () (2.00) ()	Kenwood Kenwood Kenwood Kenwood Kenwood	TH215E Handheld TW41000E 2m/70cm FM Mobil TM221ES 45W Mobile	317.00		MC 50 MC 60A MC 55 MC 35S MC 43S MD1B8	Desk Microphone Desk Microphone with Pre-amp Mobile Microphone with Control Box Hand Microphone 4 pin Up/down Hand Microphone 8 pin Base Microphone	52.67 21.72 22.22 79.00	(2.00) (2.00) (1.00) (1.00) (1.00) (2.00)
HF TRA Kenwood Kenwood Kenwood Yaesu Yaesu Yaesu Yaesu Icom	TS930S TS440S	1995.00 1695.00 1138.81 862.00 1785.00 969.00 1550.00 659.00 949.00		Yaesu Yaesu Yaesu Icom Icom Icom Icom Icom	TH25E Handheld. FT290I Portable multimode FT23R + FNB10 Handheld FT736R Multimode VHF/UHF i with 2m, 70cm and duplex IC2E Handheld IC02E Handheld IC28E 25W mobile IC275E base station inc PSU IC3200E 2m/70cm FM mobile IC Micro II Handheld IC Micro II Handheld	1450.00 225.00 299.00 359.00 1039.00	(_) (_) (_) nplete (_) (_) (_) (_) (_)	LF 30A SP 40 HS 7 YH 77 HS 5 CS 100 VS 1 VS 2 GC5 CD600 KPC2	Kantronics Packet Communicator	21.06 15.80 19.99 37.54 13.50 32.26 32.26 43.00 215.14 159.00	(2.50)
Icom	IC751A SCANNING RECEIVE ICR7000 FRG9600M 60-950MHz AR2002	1465.00	(-)	Kenwood Kenwood Kenwood	TRANSCEIVERS TH41E Handheld TS811E base station TH405E Handheld TH415E Handheld	218.00 998.00 273.18 298.85	(—) (—) (—)	ANTEN HI-Q Bricomm	Morse Key Kits Twin-Paddle Morse Key Kits INA BITS Balun 1:1 5kW P.E.P. Balun 4:1 1kW		(2.50) (2.50) (1.50) (1.50)

lcom	ICR7000	957.00	(-)
Yaesu	FRG9600M 60-950MHz	509.00	()
A.O.R.	AR2002	487.30	()
Signal	R535 "Airband"	249.00	()
Sonv	Air 7 handheld	249.00	()
Sony	PRO 80 New Sony Receiver	349.00	(-)
WIN 108	Airband Receiver	175.00	(2.00)

V.H.F.	SCANNER ACCESSORIE	S	
A.K.D.	HFC1 HF Converter	49.00	(1.00)
Revcone	Discone Antenna 30-500MHz	32.16	(3.00)
Icom	AH7000 Antenna 25-1300MHz	82.00	(3.00)

ANTEN	NA TUNER UNITS		
Yaesu Yaesu Kenwood	FRT7700 Short wave listening	59.00	(2.00)
Yaesu	FC757AT	349.00	(-)
Kenwood	AT230	208.67	(2.50)
Kenwood	AT250 auto	366.00	(-)

Kenwood TH415E Handheld Kenwood TM421ES 35W Mobile Yaesu FT73R + FNB10 Handheld Icom IC4GE Handheld Icom IC4E Handheld Icom IC451E base station inc PSU Ic Micro 4 Handheld 352.84 274.50

STOP PRESS! SPECIAL OFFER EXTENDED UNTIL THE END OF SEPTEMBER While stocks last ICR7000 Scanner

plus AH7000 Antenna. £957 inc VAT.

HI-Q	Balun 1:1 5kW P.E.P.	13.95	(1.50)
Bricomm	Balun 4:1 1kW	13.80	(1.50)
Bricomm	7.1MHz Epoxy Traps (pair)	10.95	(1.50)
	gamating Tape 10m × 25mm	4.25	(0.75)
	Dlyprop Dipole centre	1.60	(0.25)
	amic egg insulators	0.65	(0.20)
	amic egg insulators	0.85	(0.20)

URM67	low loss coax 50 ohm	per metre	0.75	(0.25)
UR76	50 ohm coax dia, 5mm	per metre	0.30	(0.10)
UR70	70 ohm coax	per metre	0.35	(0.10)
UR95	50 ohm coax dia. 2.3mm	per metre	0.40	(0.10)
4mm	Polyester Guy Rope (400kg)	per metre	0.25	(0.10)
50mtrs.	16 swg hard drawn copper	wire	6.95	(2.00)
75ohm	Twin feeder light duty	per metre	0.20	(0.10)
300ohm	Slotted ribbon cable	per metre	0.32	(0.10)

GOODS NORMALLY DESPATCHED WITHIN 24 HRS - PRICES CORRECT AT TIME OF GOING TO PRESS - E&OE - MAIL ORDER AND RETAIL

HIGH ST, HANDCROSS, W. SX. RH17 6BW BREDHURST ELECTRONICS LTD (0444) 400786




Fig. 1




Fig. 2

ACCESS SKED FROM: 08SEP88 000000
075EP 1643 0150 2015 16027 238 085EP 1027 1237 1027 17716* 052 085EP 1533 0041 1909 15304 222 095EP 1009 1125 1009 17298* 038 095EP 1428 232 1802 14772 202 105EP 0943 1001 0943 16609* 019 105EP 1235 2222 1655 14567 180 115EP 1248 2112 1549 14752 159 125EP 0757 0822 0757 15725* 349 125EP 1211 2002 1442 15270 139 135EP 0635 0733 0635 16290* 346 135EP 1141 1852 1336 15984 122 145EP 0111 1852 1336 15984 122 145EP 0111 1742 1229 16769 107 155EP 0343 0532 0343 17117* 329 155EP 0150 0427 0150 17612* 313 165EP 0103 41522 1034 18118* 083
175EP 1017 1412 1017 18066* 073 175EP 1719 0213 2036 16804 263 185EP 1000 1301 1000 17941* 063 185EP 1554 0104 1929 16009 239 195EP 0941 1151 0941 17718* 052 195EP 1444 2355 1823 15278 222 205EP 0917 1038 0917 17369* 038

Fig. 3

	ATA	UTC	M	AZ EP88	EL
		>10:30	B↓	058	01 4
> LONDON	*	10:45	B↓	058 057	Ø3
NEW YORK		11:15	B÷	056	88
RIO CAPETOUN		11:45	B↓	052 048	11
SINGAPORE HONG KONG		12:15	B	044	12
TOKYO	*	12:45	-4	029	06
DARWIN	*	16:00	B↑	190	03 (
PERTH	*	16:15	B†	191	07 11
WELLINGTO	N	16:45	B↑ B↑	196	14
FAIRBANKS	*	17:15 17:30	B† B↑	202	19
PHS 152 RNG 36184	Kifu	17:45	Bt	208	55

Fig. 6(a)

TRACKING DAT		UTC	М	AZ	EL
PHASE 3C ON) 10:30	185I B↓	EP88 058	01
DX AT 10:30	9	10:45	B↓	058	03
> LONDON	*	11:00		057	06
NEW YORK		11:15		056	08
5 FRANCISCO	0	11:30		054	09
RIO		11:45	B+	052	11
CAPETOWN		12:00	B+	048	12
SINGAPORE	*	12:15	B+	044	12
HONG KONG	*	12:30	-#	037	10
TOKYO	*	12:45		029	06
DARWIN	*	16:00	B↑	190	03
PERTH	*	16:15	BT	191	07
SYDNEY	*	16:30	BT	193	11
WELLINGTON		16:45	B↑	196	14
HAWAII		17:00	B↑	199	16
FAIRBANKS	*	17:15	BT	505	19
		17:30	Bt	205	21
PHS 152		17:45	BT	208	55
RNG 36184 FD		18:00	BT	212	24

Fig. 6(b)




Fig. 4

185	AZ EP88	EL
	119370448260370448148222222222222222222222222222222222	20000000000000000000000000000000000000
	L+ B+ B+ B+ B+ B+	L+ 253 B+ 257 B+ 260 B+ 264 B+ 268 B+ 274 B+ 278

Fig. 6(c)

TRACKING DATA	UTC M AZ	
PHASE 3C ON:	5U 185EP8 23:00 B↓ 28	
DX AT 23:00	23:15 B+ 28	
> LONDON +	23:30 B+ 29	
NEW YORK *	23:45 B↓ 29	
5 FRANCISCO+	MO 195EP8	
RIO *	00:00 -+ 29	
CAPETOWN	00:15 -↓ 30	
SINGAPORE	00:30 -+ 30	
HONG KONG	00:45 -↓ 10	
TOKYO	01:00 -↓ 12	
DARWIN	10:15 B↓ Ø4	
	10:30 B↓ 04	
SYDNEY	10:45 B↓ 04	
WELLINGTON	11:00 B↓ 03	
HAWAII *	11:15 B↓ Ø3	
FAIRBANKS *	11:30 -+ 02	
	14:45 Bt 17	
PHS 206	15:00 Bt 17	5 06
	15:15 BA 17	

Fig. 6(d)



Fig. 8

Fig.	7 '	▼ Fig. 5			Fig. 6	(b)			Fig. 8		
Value of "n"	Cha	emetry Function annel ix Desig)	Equation	Value Obtained	Units	Value of "n"	Char		Equation	Value Obtained	Units
245	00	Solar panel out and BCR input voltage	(n-10) • 167	39245	mV	7	1F	Solar panel #6 current	(n-15)+4.854	0	mA
7	01	70 cm xmtr average power output	(261-n) ² /724	0	W	206	20	2m xmtr average power output	(287·n) ² /1796	3.653	W
147	02	70 cm rcvr temperature	(n-120)/1.71	15.8	C	136	21	He tank temperature	(n-120)/1.71	9.4	C
132	03	(Reserved)	The comment of the co	-	4	134	22	Solar panel #1 temperature	(n-120)/1.71	8.2	C
192	04	BCR output and main battery voltage	(n-10) • 79.5	14469	mV	7	23	Solar panel #5 current	(n-15) • 4.854	0	mA
7	05	(Special Purpose)	******	4		69	24	70 cm rcvr AGC	(n-71)3/2465	0	dB
138	06	2 m xmtr power amplifier temperature	(n-120)/1.71	10.5	C	131	25	70 cm xmtr PA temperature	(n-120)/1.71	6.4	C
48	07	+ 14 volt rail current to xponder	(n-15) • 24.27	800.9	mA	138	26	Solar panel #3 temperature	(n-120)/1.71	10.5	C
200	08	+ 10 volt regulator voltage	(n-10) • 53.2	10108	mV	35	27	Solar panel #4 current	(n-15) • 4.854	97.08	mA
126	09	Helium tank high pressure	(n-14) • 6.56	734.7	Bar	107	28	Special purpose	xxxxxxxx	-	
137	OA.		(n-120)/1.71	9.9	C	140	29	24 cm rcvr temperature	(n-120)/1.71	11.7	C
7	OB			0	4	138	2A	Solar panel #5 temperature	(n-120)/1.71	10.5	C
	00	and antenna relay	(n-15) - 4.854	100	mA	7	2B	Solar panel #3 current	(n-15)-4.854	0	mA
96	OC		0 = Off; N > 10 = On	On	4	226	2C	+ 14 volt regulator voltage	(n-10)+66.8	14429	mV
134	OD		(n-15) • .117	13.923	Bar	137	2D	RUDAK temperature	(n-120)/1.71	9.9	C
143	0E		(n-120)/1.71	13.4	C	129	2E	Top (+Z) skin temperature of arm #1	(n-120)/1.71	5.3	C
47	OF	+ 10 volt regulator current	(n-15) • 4.854	155.33	mA	7	2F	Solar panel #2 current	(n-15) • 4.854	0	mA
7	10	BCR oscillator #2 status	0 = Off: N > 10 = On	Off		178	30	Mode B transponder + 9 V supply voltage	(n-10)+54	9072	mV
143	11	N2O2 tank pressure	(n-106)+0.733	27.12	Bar	134	31	Wall temperature in arm #2	(n-120)/1.71	8.2	C
138	12	SEU temperature	(n-120)/1.71	10.5	C	122	32	Bottom (-Z) skin temperature of arm #1	(n-120)/1.71	1.2	C
7	13	Battery charge current	(n-15) • 12.135	0	mA	7	33	Solar panel #1 current	(n-15) • 4.854	0	mA
14	14	Top (+Z) photocell sun sensor	(n-10) • 8.53	34.12	mV	111	34	Special purpose	xxxxxxxx	14	4
99	15	Motor valve status	102 = Closed, 118 = C			133	35	Wall temperature in arm #1	(n-120)/1.71	7.6	C
136	16	Auxillary battery #1 temperature	(n-120)/1.71	9.4	C	137	36	N2O4 tank temperature	(n-120)/1.71	9.9	C
56	17	Active BCR outut current	(n-15) • 24.27	995.07	mA	137	37	Reserved	The control of the control	4	*
7	18	Bottom (-Z) photocell sensor	(n-10)-8.53	0	mA	15	38	Auxillary battery voltage	(n-10)-78.5	392.5	mV
2	19	XXXXXXXXXXXX	1	0		122	39	Mode S transponder temperature	(n-120)/1.71	1.2	C
135	1A		(n-120)/1.71	8.8	C	129	3A	+ Z platform temperature (SERI exp)	(n-120)/1.71	5.3	C
7	1B		(n-15)+12.135	0	mA		3B	Reserved	Control of the Contro		
116	1C		r = (131·n)·0.85 + 20	32.75	rpm	206	3C	Mode L transponder + 9 V supply voltage	(n-10)-45.4	8898	mV
110	10	or if n > = 139	r = 479/(n-109)-2		rpm	-	3D	AZ-50 tank temperature	(n-120)/1.71		C
7	10		(n-75) ² /-1125	0	dB	4	3E	Nutation damper temperature	(n-120)/1.71		C
137	1E		(n-120)/1.71	9.9	C		3F	Reserved		12	4
13/	16	main pattery temperature	(iii izo) iii i		~	M. 16	71	MARKET CONTROL			

mended, as in the normal IARU band-plan recommendations. It is not absolute, as many countries are plagued by amateur f.m., RADAR, military use, etc., that make specific sections of the downlink bands unusable. It is then logical for the operator so hit to use those frequencies that he can sucessfully transpond to. No priority frequencies for news broadcasts have been set, but these are expected to be used later close to the top edge of the downlink. Although unmeasured, the Mode "L" transponding relationship appears to be as earlier published. Mode "J" has been measured, and found to be very close to nominal. No frequency equivalents have yet been reported for Mode "S"

Operation

OSCAR-13 is in excellent health, with all systems working, and is now giving excellent communications to the world amateur radio satellite community. Transponded signals on Mode "B", "J" and "L" are adequate, and despite a little signal strength variation that limits really perfect QSOs, all seems well. The improvement of the 435MHz downlink compared to OSCAR-10 is quite dramatic, with substantial signals from quite modest uplinks resulting from both Mode "J" and "L". Mode "S" is reported to sound like a broadcasting stations to those equipped to receive the s.h.f. signal downlink, with a fade-free smooth fully quieting signal resulting.

Dr. Karl Meinzer DJ4ZC, at the July 5/6 AMSAT-UK colloquium at the University of Surrey reported that all bar a few minor annoyances, OSCAR-13 is performing to AMSAT's satisfaction. He explained that the "spin modulation" noticeable is not due to the same reasons as OSCAR-10. It's caused by the u.h.f. antenna offset swinging through the field producing a reradiation pattern, as it, as well as the whole body of the spacecraft, is resonant at 145MHz. Werner Haas DJ5KQ, explained in a long conversation that a few problems have been encountered with the function of the "RUDAK", but that he hoped all would be well following further testing and commanding.

Telemetry

The c.w. telemetry at the hour and half hour is keeping up with the input of information to provide updates for listeners, as is the RTTY at the quarter and three-quarter hours transmissions. For this u.s.b. is needed for the correct space and mark tones. An early copy of the BPSK telemetry taken at 0147 on July 11 by Vern Riportella WA2LQQ, AMSAT's president, is shown in Fig.7. With the exception of Channel 01 and 1C all is well, but channel 01 probably should be (261-n)/1724 instead of the /724 given. Channel 1C, the spin rate, is at odds with that detemined by QSB rotation measurement on earth, and new software is being developed.

Copious amounts of information is coming in about the new satellite, but we need to keep a little space for the other satellites too, so a wider profile of who is on, when, and working who, should evolve next month. Just let it be said that we have a wide new set of DX bands now available, to "A" and "B" licensees alike, who should not miss the opportunity presented by OSCAR-13.

RS Satellites

RS-1 is still being heard, after ten years in space. In a letter to Don Shirreff G3BGM, the operator of the RS command station, Andy Mironovy RS3A, said that they had been trying to command on the transponders of RS-5 and 7, but with only a modicum of success. Whilst RS-7 remained deaf to all instructions fom the reconstituted command assembly, RS-5 did respond, and stayed on for a full orbit on July 9, upon which RS3A made QSOs with F2JA and F9EA. Unfortunately, the satellite has failed to execute all attempts to command since that date, or, to quote . . . I believe that these were the last QSOs over RS-5. I will try to switch it on again - let us hope!.

RS-10/11 remains well populated, with every pass providing lots of QSOs for all. Mode "T" has been very quiet, but it is hoped that a schedule of use can be provided to perform the multi-satellite hop proposed by G4CUO when a common overlap window transpires.

During an all-too-short three day stay at the G3IOR QTH, **Leonid Labutin UA3GR** explained the future plans of the RS satellite building group. "Next year," said Leo, "We shall launch RS-12, which will be a very similar transponder, orbit and system as RS-10/11. It will only differ in the telemetry, which will be simplified with common prefixes and a following identifying letter to indicate the channels monitored, an increase in the memory capacity, and in having up to 8 watts of downlink power.

After this, in about three years time, we hope to have a Mode 'B' RS-13 in a 1000km polar orbit."

"The third plan," explained Leo, "is to build a joint satellite, with a Czechoslovak made command system, the power assembly from Bulgaria, the internal house-keeping unit from Hungary, Packet radio from the German Democratic Republic, and the actual satellite, transponders and solar cell assembly from the USSR group: It will be a Mode "J" and "L" linear and digital transponder, with some 40 watts of power available, in a Molniya type orbit"

FO-12

Mr.Shozo Hara JA1AN, President of the JARL, writes to assure us that we shall have no problems with the concern earlier expressed due to the potential use in Japan of f.m. in the satellite sections of the bands. He explains that the reaction evolved from a discussion paper produced to the deciding committee, which has since not only rejected the proposition, but extended the section of the bands for satellite uplinks and downlinks.

Yoshio Arisaka JA1HQG, also a Director of JARL, attended the University of Surrey AMSAT-UK colloquium, and explained to G3IOR some of the problems associated with maintaining a regular operating schedule with FUJI-OSCAR-12. Despite the difficulties involved with limited solar-cell power production on such a small satellite, they will try to get to us a long-term provisional plan when the satellite will be active on particular modes, in time for publication. The JARL and JAM-SAT will soon now begin work on JAS-1B, which will have a tight power budget, and better antenna directivity in order to accomplish a flatter pattern and smoother operation. Our Fig. 8 photograph from JA1AN shows the command station for FO-12, with operations in progress.

We will try to catch up on station news and the other information in next months pages, plus the latest OSCAR-13 news.

Reports to Ros Hom


The next three deadlines are: Sept 21, Oct 26 and Nov 24

Propagation


By the beginning of 1970, it was obvious that my simple radio telescope was working well and more than able to provide the information about the "active" sun that I wanted. From the start I kept a daily log of the solar events that occurred during my observational time and, from these archives, I prepared a bar-chart, Fig. 1, showing the total number of days each year when some form of solar noise was recorded.

In addition to a variety of individual bursts which manifested throughout 1970, noise storms were recorded from January 3-6 and 11-13, February 19-21, June 15-17, July 21-25, August 16-21, September 5-8 and 23-27, October 20-23 and 27-31, November 11-22 and December 17-23.

The sun was active every day from October 9 to November 5 and then went



quiet until the 11th, when a few tiny isolated bursts appeared on the chart. Next day, the receiver noise base-line increased and decreased as the sun passed through the antenna beamwidth. By switch-on time on the 13th a noise storm was in progress and the base-line was half way across the chart. This line was higher and the noise more intense on



Faraday, Greytriars, Storrington, West Sussex R20 4HF

the 14th and 15th and peaked on the 16th and 17th when the pen spent most of the observation against the upper stops, Fig. 2 and only declined a little on the 18th. Although still strong the base-level was about midway on the 19th and 20th and then gradually returned to normal, with slight noise and a few small bursts, on the 21st and 22nd.

This solar activity was responsible for many fadeouts on the h.f. bands and after sunset on the 16th, the background noise on these bands was exceptionally high. It sounded as though the whole atmosphere was still charged after its excessive bombardment from the sun. Perhaps the ionosphere, or even the earth's surface was re-radiating the solar noise I thought, however, a fellow radio-astronomer suggested that it was the moon deflecting the solar noise towards earth after sunset. Another good possibility because the sun was still pumping the stuff out and I don't think the earth's ionosphere was in any state to stop the noise getting through.

Whatever the cause it was a fantastic natural event from which I learnt a lot and then realised that this must have happened a million times before in the earth's history, but without radio, there was no means of detecting and/or knowing about it.

During this storm, the media was carrying the story of the flood disaster in East Pakistan. On the 17th I noted a piece in the Daily Telegraph newspaper which began, "Pakistan's tidal wave disaster was caused by the influence of sunspots, Prof. Raffaele Benandi, director of the Faenza Geophysical Observatory in Italy, suggested vesterday."

ed yesterday."
"Why not," thought I, there may still be unknown particles coming from the sun, which, as yet, man has not found an instrument to detect. After all the sun has been transmitting radio waves for millions of years, but science knew nothing of this until the invention and development of the short wave radio receiver earlier in this century. The Telegraph's report continued, "Prof. Benandi said that four separate groups of sunspots were moving across the Sun's face, the largest of them containing about 20 spots. The biggest group passed through the central meridian yesterday. (Remember that peak of noise on the 16th.) It will disappear over the Sun's western horizon on Nov. 22.

Over the years I found that noise storms always produced something of great interest for instance; my home is situated on the northern slope of the South Downs which rise sharply by approximately 120m, about 400m to the south of my garden. This has some advantages but during the mid-winter months the sun, being low in the sky, sets quite sharply behind the hill in a similar way to the sunset shown in Fig. 3. Now to the point of this example: The sun was radiating a high level of radio-noise on 9 January 1971 and as it set behind the downs and the source of radio noise was gradually cut off from the telescope's antenna, a rough profile of the hill was drawn on my recording chart. Next month I plan to look at the records for 1972, but now back to a very active period in 1988

Solar

Between June 6 and July 9, Patrick Moore (Selsey) found gaps in the often cloudy sky on 24 days to check for sunspots and the drawings he made showing their positions, at 0930 on June 19, 0830 on the 29th, 1900 on July 1 and 0545 on the 9th, are illustrated in Figs. 4, 5, 6 and 7.

"The sun became particularly active towards the end of the month when some massive sunspot groups developed to appear in the centre of the disc at the beginning of July," wrote Ron Livesey from his observatory in Edinburgh. Here, he uses a 2.5in refractor for his astronomi-



Fig. 3

cal studies. Ron makes measurements on a scale personal to his telescope and noted the presence of 3 sunspot groups on June 18, 20, 23, 24, 25 and 26; 4 groups on July 2 and 5 groups on July 8.

In Bristol, **Ted Waring** counted 63 sunspots on July 1, 20 on the 6th, 34 on the 13th and 32 on the 18th.

For the safety of your eyes, NEVER LOOK DIRECTLY AT THE SUN THROUGH ANY TYPE OF OPTICAL EQUIPMENT. Get advice from or join your local astronomical group, or the British Astronomical Association before making any solar observations.

Cmdr Henry Hatfield (Sevenoaks), using a spectrohelioscope, logged 1 large spot, 1 chain of 7 spots, 1 medium sized spot, 1 large group of about 20-30 spots over 23 degrees long with a very active plage, 10 filaments and a small flare in the large group around 0915 on June 30. At 1500 on July 1, he noted that the large group was crossing the central meridian and observed a small flare in its north-west corner. His entry for 1445 on the 7th read, The large group is going round the westlimb. To my surprise there are no prominences over it. In addition there are 2 spot groups, 2 single spots and 9 filaments. He also logged 1 group of 7 spots, 1 double spot and 8 filaments at 0955 on the 9th; 2 groups both with many small




Fig. 4



Fig. 6

spots, 1 single spot, 16 filaments and a large active plage at 1350 on the 18th; 20 filaments and a very large active plage on the 19th; 1 large group with active plage, 1 double and 1 single spot, 15 filaments and 1 small flare at 1137 on the 21st; and 2 double spots, 15 filaments and a large "loop prominence" on the north-west limb at 1050 on the 24th. "As you can see the sun has woken up with a vengeance! The very large group of June 30 (Figs. 5 and 6) was coming round the north-east limb again on July 24. I think it may have declined," said Henry.

I was not surprised when he recorded "violent" and "very large" bursts of solar radio noise at 136MHz on June 30, followed by a continuous noise storm, with much bursting, from July 1 to 5 inclusive. He also recorded "intermittent noise with isolated bursts on days 7, and 8, large bursts on 11, 12 and 23 and noise storms on 16, 17, 18 (violent), 19 and 21.

"The mean sunspot number for June was 101.8, the first mean monthly figure above 100 this cycle with a low of 66 on the 14th and a high of 217 on the 8th," wrote Neil Clarke GOCAS (Knottingley). He reported that the solar flux for June began at 150 s.f.u., reached 165 on the 9th and fell back to 108 by the 14th. It then rose to 119 on the 22nd and sharply on to its peak of 184 on the 30th. Neil's computer print out of the daily figures for solar and magnetic activity and the m.u.f., can be seen in Fig. 8.

Dave Coggins (Knutsford) heard solar radio noise while monitoring the 50MHz band, with his 2-element quad facing south-east, from 0814 to 0850 on July 2. "Noise levels were up and down with many "peaks and dips"," said Dave. He reports that the "hiss" rose to S6 at 0826. He was beaming east around 0600 on July 9 and heard small individual bursts on the 28MHz band. (Dave's beam was pointing toward the rising sun).




Fig. 5




Fig. 7



SPECTRUM COMMUNICATIONS

MANUFACTURERS OF RADIO EQUIPMENT AND KITS

CONVERTERS & TRANSVERTERS

RECEIVE CONVERTERS 4 or 6m antenna input, 10 or 2m .i., venichle cain 3.266. n.f. lose than 3.5dB. Buffered local oscillator output, types RC4-10, RC4-2, RC6-10 and RC6-2, PCB kit £17.25, PCB built and tested £41.00.

TRANSCEIVE CONVERTERS Single board version of receive converter and 500mW transmit converter, 10m drive 25mW to 500mW, Types TRC4-10 and TRC6-10, PCB kit £39.00, PCB built and tested £54.00, boxed kit £54.00, boxed, built and tested £83.25.

TRANSCEIVE CONVERTERS Separate receive converter and 2.5W transmit converter in a single boxed unit, 2m or 10m drive 10mW to 100mW only, requires £1 sensing switch and attenuator for use with 2.5W 2m rigs. Types TRX4-10H, TRX4-2H, TRX6-10H and TRX6-2H. Boxed kit £60.00, boxed and built £99.50.

TRANSCEIVE CONVERTERS As above but including an interface providing RF sensing attenuation and PTT switching. ½W-5W 2M drive. Types TRX4-21 and TRX6-21, Boxed kit £68.00, boxed and built £115.00.

RECEIVE PREAMPS

2, 4, 6, or 10 metres RF switched and DC sensing, 100W transmit handling power, gain 0-20dB adjustable by panel control, NF 1dB on 2M, 2dB on 4 & 6M, 3.5dB on 10M, 13.5V negative ground operation. Excellent performance at a reasonable price, Well made attractive boxed unit 77×70×39mm, an asset to any Ham shack, Types RP2S, RP4S, RP6S, & RP10S, PCB KIT £14.75, PCB BUILT £22.25, BOXED KIT £25.00, BOXED BUILT & TESTED £35.50.





VAT & P&P INC PRICES

FM CONVERSIONS

FOR YAESU & KENWOOD TRANSCEIVERS

FD311X & FM2000 for FT101, 101B, 101E, 101Z, 101ZD, 901, 902, 107, 107M, 77S, 77, 707, 200, 250, 7B, all £71.

FD311X & FM3000 for TS120V, 120S, 130V, 130S, 520, 520SE, 530, 830, 930, all £81.

State rig type when ordering.

CB to 10m

CB TO 10 FM CONVERSION BOARDS – THE FIRST COMMERCIALLY AVAILABLE, suits all UK FM CB rigs to give 29.31 to 29.70MHz. Size only 63 \times 40 \times 13mm. Built and aligned board SC29 £18.50. Or send your rig and we'll fit it. £31.50 inc. return P&P for mobiles. £35 inc. for base rigs

MULTIMODE CB CONVERSIONS, send your 120 channel rig and we'll convert MULTIMODE CB CONVERSIONS, send your 120 chainleing and we'll convert it to give 28.01 to 29.70MHz in straight sequences without gaps. Colt 1200DX, Cobra 148. Hy Gain 5, Multimode 2, Major M360, Tristar 747 & 777, Super Star 360, Concorde, etc., £62 inc. return P&P. Jumbo or Colt Excalibur 1200, £65. 80 Channel rigs such as Stalker 9 or Major M588 are modified to give 28.31 to 29.70MHz in straight sequence without gaps, £55.00 inc. return P&P. Channel in 4 bands of 50 are converted to give 28.00 to 30.00MHz or 28.00 to 29.70MHz as required. Super Hy Gain 5, Lafayette 1800, Super Star 2000. £45.00 inc. return P&P. Nato 2000 £52.50, Super Star 2000-5 × 40CH £70. Colt 1600. 4 × 40CH. £65.50





Delivery within 14 days if available. 24 hr answering.

SHOP TIMES: 9am-1pm & 2pm-5pm TUES-FRI 9am-1pm & 2pm-4pm SAT CLOSED SUNDAY & MONDAY

UNIT B6 MARABOUT INDUSTRIAL ESTATE, DORCHESTER, DORSET. TEL: 0305 62250

SOUTH MIDLANDS COMMUNICATIONS



The Communicators

BEWARE

NOT ALL YAESU RADIOS CURRENTLY BEING OFFERED FOR SALE BY SOME DEALERS HAVE THE BACK UP OF YAESU'S DISTRIBUTION NETWORK. SETS WITH JAPANESE MANUALS AND WARRANTY CARDS SHOULD BE AVOIDED! YAESU'S FAC-TORY BACK UP AND SPARES SERVICE IS NOT AVAILABLE IN THE U.K. FOR THESE SETS.

- "REMEMBER, A FEW POUNDS SAVED NOW COULD COST YOU DEARLY IF YOUR SET SHOULD EVER GO WRONG" -

DETAILS OF AUTHORISED DEALERS AVAILABLE ON REQUEST

YAESU UK SOLE DISTRIBUTOR

SOUTH MIDLANDS COMMUNICATIONS LIMITED

HEAD OFFICE: S M HOUSE, SCHOOL CLOSE, CHANDLERS FORD INDUSTRIAL ESTATE, EASTLEIGH, HANTS

TEL: (0703) 255111 TLX: 477351 SMCOMM G

FAX: (0703) 263507

R.A.S. (Nottingham)

G6XBH G1RAS **G8UUS**

Radio Amateur Supplies Tel: 0602 280267



Visit your Local Emporium

Large selection of New/Used Equipment on Show

AGENTS FOR: F.D.K. AZDEN ICOM YAESU ALINCO **KEMPRO**

ACCESSORIES: Welz Range Microwave Modules Adonis Mics
Adonis Mics
Mutek Pre-Amps
Barenco Mast Supports
DRAE Products
BNOS Linears & P.S.U.'s

AGENTS FOR CELLNET AND VODAFONE RADIOS AERIALS, Tonna, Halbar, New Diamond Range of Mobile Whips, Jaybeam BRING YOUR S/H EQUIPMENT IN FOR SALE

JUST GIVE US A RING
Monday: CLOSED Tuesday Saturday: 10.00am to 5.00pm

3 Farndon Green, Wollaton Park, Nottingham NG8 10U Off Ring Rd., between A52 (Derby Road) & A609 (Ilkeston Road)

MAKE YOUR INTERESTS PAY!

More than 8 million students throughout the world have found it worth their while! An ICS home-study course can help you get a better job, make more money and have more fun out of life! ICS has over 90 years experience in home-study courses and is the largest correspondence school in the world. You learn at your own pace, when and where you want under the guidance of expert personal tutors. Find out how we can help YoU. Post or phone today for your FREE INFORMATION PACK on the course of your choice.

Electronics		Radio, Audio and TV Servicing				
Basic Electronic Engineering (City & Guilds)		Radio Amateur Licence Exam (City & Guilds)				
Electrical Engineering		Car Mechanics				
Electrical Contracting/ Installation		Computer Programming				
GCE over 40 'O' and 'A' level subjects						

	Name			P	Code	9.	
LLD	International	Correspondence 1PR. Tel. 01-643			High	St.	Sutton,

Magnetic

Neil Clarke tells me that during the 3 minor magnetic storms recorded on days 14, 25 and 29/30, the Ap index was 37, 48 and 45-49 respectively. He said that most days in June were unsettled and that the only quiet day was the 5th when the Ap index was 9. The magnetometer used by Karl Lewis in Saltash was very unsettled for periods on June 20, 22, 27, 28 and 30 and recording storm levels on days 18, 19, 24, 25, 26, 29 and 30.

Aurora

Ron Livesey, the auroral co-ordinator for the British Astronomical Association, points out that the summer twilight prevents the observation of aurorae in the UK and it may be some weeks before overseas observations reach him. Overcast skies are also a problem to visual observers therefore it is important that radio enthusiasts send a report to Ron, the RSGB, or myself each time tone-A signals are heard. If nature prevents our seeing the auroral display then we can at least know of its existence by the effect it has on radio signals

Sporadic-E

During an intense Sporadic-E opening at 1730 on June 27, I counted over 40 very strong f.m. signals from East European broadcast stations who normally operate between 66 and 73MHz. At the same time received pictures and sound on Ch. R3 77 25MHz and 83.75MHz respectively. Later, between 1900 and 2000, Ken Lancaster (Rotherham) logged Italian and Spanish stations in Band II and while a similar event was in progress at 2130 on July 6 John Parry G4AKX (Northwich) heard a number of Spanish broadcast stations within the band. Around 0930 on July 12 at least 10 Italian stations were audible from 87 to 102MHz. Some 24 East Europeans were again very strong between 66 and 73MHz around 0900 on July 20 and over 35 at 1845 on the 23rd.

The 50MHz Band

Signals from Portugal, Finland, the USA and France were received by Dave Coggins on June 19, 24, 25 and 27 respectively as well as both France and Finland on July 9. While Sporadic-E was present during the evenings of the 20th and 23rd, I tuned between picture pulses on Chs. E2 and E3 (48.25-55.25MHz) and heard amateur stations, in the 50MHz band, from Norway and Finland respectively on s.s.b. Both were very active and I think that the latter was OG2C, a special event station in Helsinki.

The 28MHz Band

Dave Coggins logged short skip signals from Europe, the Middle East and Scandinavia on June 25, 26, 27, 28, July 2, 3, 4, 6, 9, 10, 11, 12, 13, 14 and 15 and DX from South America on July 2, 4, 5 and 9. Apart from a station in Sweden, Dave found the band "almost dead" on June 29 which is not surprising after looking at the sunspots and the solar flux level for that day, (Figs. 5 and 8).

John Levesley GOHJL (Bransgore) received signals from Europe and Scandinavia on June 25, July 9 and 23. He worked two Germans in the Lower Saxony Contest on June 25 and stations in Argentina, Czechoslovakia, Hungary, Portugal and Spain on July 9. John also heard f.m. signals from Denmark and Sweden on the

	MEER			FEMALE MAX
860601 860603 8806045 8806045 8806045 880606 8806606 8806610 8806611 8806613 8806613	110 113 113 113 113 113 113 113 113 113	150 144 144 144 156 166 165 143 122 108	014 013 0113 0199 0155 0156 0160 0137	093 054 055 093 069
380615 380616 380617 380618	089 121 113 095	111 116 121 122	018 014 021 021	081 075 071
GENER A	NSEER	FLUX	1014	FEMAZ
380619 880620 3806221 3806222 3806224 3806224 3806225 8806227 3806229 380623	088 1119 1109 1135 1136 1156 1166 1191	116 1121 1125 1125 1155 1155 1156 1164	3556271891259 000000000000000000000000000000000000	9772155425162 977775542 9777757677

Fig. 8

16th and all of Scandinavia plus Holland and the Budapest repeater (HA5BE-29.680MHz) on the 23rd.

Propagation Beacons

As usual my thanks are due to Chris van den Berg (The Hague), Dave Coggins, John Coulter (Winchester) Henry Hatfield, Don Hodgkinson GOEZL (Hanworth), John Levesley, Greg Lovelock G3III (Shipston-on-Stour), Ted Owen (Maldon), Fred Pallant G3RNM (Storrington), Patrick Wagemakers (Schoten) and Ted Waring for their 28MHz logs and for their dedication to supplying information for our monthly beacon Chart, Fig. 9.

In addition to the beacons listed in Fig. 9, Don Hodgkinson heard 5Z4ERR (28.240MHz) and Ted Owen heard WA4DJS (28.295MHz) (Florida) on July 9. It was Don, plus John Coulter and Fred Pallant that enabled me to add PI7ETE (28.302MHz) to the chart.

Dave Coggins received signals from the 50MHz beacon in Portugal (CTOWW) on June 17, 19, 27, July 8 and 9. He described the signals from the beacon at

Potters Bar (GB3NHQ-50.050MHz) as "not unlike slightly auroral" at 1150 on July 5, "slightly rough note" at 1152 on the 6th and "rapid rhythmic" type QSB" at 1201 on the 8th. Dave added that signals from the Inverness beacon (GB3RMK-50.060MHz) had a "rough note with an odd meteor scatter burst," at 1152 on the 6th. He also kept an ear on the 24MHz band and logged the beacons in Brazil (PY2AMI-24.900MHz) and Italy (IK6BAK-24.915MHz) on July 9, 10, 14, 15, 17 and 18. Ted Owen also heard the Italian beacon at 549 around 0749 on June 30 and July 3 and again at 0929 on the 9th.

Tropospheric

The slightly rounded variations in atmospheric pressure, measured with my barograph in Sussex throughout this period, can be seen in Fig. 10. Ted Owen's barometer indicated highs of 1020mb (30.15in) on June 26 and July 12, 16 and 19 and a low of 992mb (29.3in) on July 3.

934MHz

"A fairly quiet month," wrote John Levesley UK627, for the period prior to July 24. However, he did make contact with GY-186 in Guernsey on July 5 and 9 and heard SB-91 from Andover, DB-19 from Gloucester and TG-15 from Swindon who were visiting his area. He also worked TR-26/P from Canford Cliffs; "Nothing remarkable in the 10 mile copy", said John, "except for the fact that he was using a hand-held with a rubber duck."

During the 934MHz National Field Day, the winners of the multi-operator section were UK-1268 for the longest QSO (170km) and UK-1999/2000 for maximum number of contacts (70) and highest points scored (206). In the single operator section UK-1132 was first in all 3 divisions with the longest contact of 182km and gained 183 points from 64 QSOs. Our congrats to the leaders and thanks to John Levesley, the NFD manager, for the information.




Fig. 9




Fig. 10

It has been pleasant recently to receive some correspondence from readers of this column, together with their monitoring observations. Mr R F Merrall of Dunstable wrote this month, telling of his return to short wave listening, and saying that he finds this feature "invaluable to the process of sorting out, "who is where and when'— in conjunction with the more detailed round-up in ... Short Wave Maga zine". I'm glad that we are of help, Mr Merrall.

Last month we reported on the agreement for relay exchanges between Radio Canada International and Radio Beijing. It seems that this will take the form of a daily two hour exchange, starting in April 1989. RCI is also moving in to the domestic Chinese market, by providing an English language teaching course which will be broadcast in Shanghai, Beijing and Guangzhou starting in September.

A new 100kW transmitter has been inaugurated by Kossuth Radio in Hungary on 6.025MHz. The service carried on this h.f. channel is designed for Hungarians abroad and was first heard in November 1985, but with a power thought to be 20kW.

Israel Radio has dropped its daytime foreign language programmes, with the exception of English and French. Easy Hebrew has been removed from Kol Israel's schedule, and replace by Yiddish broadcasts.

The Voice of America's audibility programme continues apace, with the announcement that Marconi Electronics Incorporated, a subsidiary of the British firm, has won the contract to build ten 500kW transmitters for the Morocco relay station. Altogether, VoA intends to have 108 500kW transmitters around the world in both new and existing relay sites. Additional Marconi transmitters could also be installed in VoA sites in Botswana, Thailand and Sri Lanka. The Voice of America relay station in Sri Lanka is under construction in Puttalam, and is expected to be completed in five years.

Also in Sri Lanka, the Deutsche Welle relay station in Trincomalee, which suffered seige conditions during the civil war in the country, is now back on the air with test transmissions using three 250kW short wave transmitters and a 600kW m.f. sender. Tests are between 1200 and 1400 on 1.548MHz, 1430-1650 on 1.548 and 6.17MHz with Urdu 1430, Hindi at 1520 and English at 1610. The relay on DW's Chinese programmes continue on Radio Veritas in the Philippines, broadcast between 1230-1350 on 9.69MHz. Deutsche Welle hopes eventually to improve its South East Asian coverage by hiring additional time on R

Meanwhile Swiss Radio International is now using transmitters at Radiobras for Central American coverage. SRI's Press Officer, Walter Fankhauser, explained that the relay started on July 1 and will probably continue until the end of the year. It will be extended afterwards if the results prove successful. The current tests are on the air 0130-0300 on 17.73MHz using a 450kW transmitter.

The new BBC relay site in the Seychelles, designed to improve reception in East Africa, will begin operations on September 25. Tests on the two 250kW senders will be made before the official

Any reports for Broadcast Round-up should be sent to the PW offices

opening, but QSL cards will only be sent for reports made from within the target area!

Radio Austria International was heard on the 21 metre band channel of 13.73MHz during July, apparently with tests of this hitherto unexplored band for the ORF. It remains to be seen whether the station will make permanent use of this short wave frequency.

The American AFRTS network is to end short wave transmissions at the end of September, we learn. Now is the time to verify the station, if you collect QSL cards. Here in Europe, 15.265 is well received during the morning and 15.43 during the evening period. AFRTS programmes for overseas commands are now carried on satellite, and the h.f. links were mainly used by ships, or as a backup in the event of a satellite failure. Now ships are equipped with satellite receiving equipment, the short wave transmissions can be dispensed with, much to the disappointment of others abroad who enjoy listening to news from ABC, NBC and so

The Irish Government has told pirate stations operating in the Republic to close by 31 December 1988, prior to the shake up of broadcasting in the country next year.

Europe

All times are UTC (=GMT)

In addition to the 13MHz tests mentioned earlier, Radio Austria International is currently evaluating a new modulation compressor. The new compressor is deployed between 0000-0500 on the North American service on 9.875MHz (s.s.b. to the West Coast from 0300), 0500-0700 on 15.45MHz to Australasia, and 0400-2300 to Europe on 6.155MHz.

Radio Caroline's 558kHz frequency now carries RN 0600-1800, with Caroline heard at other times. The new RN service will move to 819kHz during August.

Radio France International has retimed its Arabic service, now 1400-1500 on 21.49 and 11.845MHz. Radio Norway has made some frequency changes: 1300 uses new 21.70 from 17.80MHz, and at 1400 there is a new 15.19 from 21.705MHz. Despite a misleading printed schedule, the 1500 broadcast on Mondays on 1.314MHz medium wave carries the Sunday English language programme.

Vatican Radio's Overseas Service at 0700, which includes English from 0715, has moved to 17.73MHz in parallel with 15.19MHz.

A harmonic of the Soviet Baku station, whose nominal frequency is 6.11, is heard around 1500 on 18.33MHz.

Africa

The clandestine, Radio Bardai, hostile to the Chadian Government, has been unheard on its usual 6.009MHz channel for some weeks. Operation seems to be very erratic, perhaps because of the war situation in the region. Listen out at 1100 and 1800UTC to see if it comes back.

We mentioned the Voice of Ethiopia last month. This station continues to be heard at 1800 on 7.315MHz Friday to Sunday and on 9.66MHz Monday to Thursday. Programmes are reported to be beamed to East Europe 1800-1830 and to Western Europe 1830-1900.

Ray Merrall reports RTM Morocco with slow speed English between 1705 and 1720 on 17.815MHz with "English for International Co-operation" through until 1745. This is also carried on m.f.: 1.325, 1.197, 1.188, 1.026MHz and 828kHz.

Radio RSA in English at 1800 is now using 15.405 and 11.915MHz, replacing 15.365 and 11.875MHz.

Middle East

The Palestinian Al-Quds Radio now has a short wave channel of 7.46MHz between 0600-1100 and 1300-1600, and an untraced 4.32MHz between 1600 and 1800.

Iran's Flag of Freedom Radio, a clandestine hostile to the Khomeni regime, is now on 11.315MHz at 1630, possibly a test frequency.

Syrian radio transmissions from Damascus have moved to new 9.95MHz in parallel with 15.095MHz including English at 2100

Turkey's strange out-of-band channel of 14.88MHz, which was heard in parallel with 11.96 has now been replaced. Between 1000 and 1500, the new frequencies are 9.46 and 11.955MHz. English is reported by Mr Merral at 0305 on 9.445MHz.

Asia

Afghanistan has moved from longestablished 4.450MHz to new 4.760MHz, with domestic and external programmes relayed. Audible in Europe during the evening, together with 4.740MHz.

Ray Merrall has been listening to R. Australia's 2100 Chinese programme on 11.73MHz from the Darwin site, with "Oz by Radio", as he describes the station's English course, at 2110-2130.

Radio Bangladesh uses new 17.71 and 15.195MHz for the 0800 and 1230 transmissions. At 1815 English is heard on 7.505MHz.

Radio France International's relays from Japan which began on 1 August are as follows:

0930-1130 on 15.215MHz to North Asia 1000-1100 on 17.705MHz to South East Asia

2300-0030 on 17.710MHz to South East

Radio Nepal uses new 7.165MHz (ex 3.23) 0015-1715, in parallel with long running 5.005MHz.

With the Olympic Games scheduled for September, I thought it might be interesting to provide transmission details for both North and South Korea . . . KBS, Seoul 0145–0200 on 15.575 & 9.640MHz 0500–0600 on 9.57, 7.275 & 6.06MHz 0700–0800 on 13.67 & 7.55MHz 0815–0830 on 13.67 & 9.57MHz 1000–1100 on 15.575MHz 1015–1030 on 11.74 & 7.275MHz 1230–1245 on 11.74 & 7.275MHz 1300–1400 on 15.575, 9.75 & 9.57MHz 1445–1500 on 9.87, 9.515 & 7.275MHz 1500–1600 on 9.87 & 5.975MHz

1615-1630 on 9.87MHz

1700-1800 on 15.575MHz

2230-2330 on 15.575MHz

1930-2030 on 15.575, 7.55 & 6.48MHz

1945-2000 on 9.87 & 5.975MHz

2345-0000 on 15.575 & 7.275MHz

Radio Pyongyang 0000-0050 on 15.16 & 15.115MHz 0400-0450 on 15.18, 15.16 & 15.115MHz 0600-0650 on 15.18, 15.16, 15.115 & 13.65MHz 0700-0750 on 15.34 & 13.75MHz 0800-0850 on 15.18, 15.16, 11.83 & 9.54MHz 1100-1150 on 11.735, 9.60 & 6.576MHz 1300-1350 on 9.60, 9.345 & 9.325MHz 1500-1550 on 11.74, 9.977, 9.64 & 9.325MHz 1700-1750 on 11.74, 9.977, 9.64 & 9.325MHz 2000-2050 on 9.977, 9.64, 9.345 & 6.576MHz 2300-2350 on 13.65 & 11.735MHz

Radio New Zealand, according to Ray Merrall, is heard 1830–2115 on 12.045MHz, and 0145–0315 (seasonal for sports), 0330-0730, 1830–2115 and 2345–0145 on 15.15MHz, all for the Pacific; to Australia and Melanesia on 12.045 MHz between 0330-0730, and on 6.10 and 9.54MHz from 1000 to 1215. Ray reports a QSL in just 10 days in late June for 12.045MHz at 0330-0730.

Radio Pakistan's English service at 1700 on 15.27MHz gives a good signal here in the UK.

SLBC in Colombo is heard on 15.435MHz at 0100 with an English *Morning Show* with records and requests, through to 0200.

Any reports for Broadcast Round-up should be sent to the PW offices

The Americas

Radio for Peace in Costa Rica now uses 13.66MHz between 0415 and 0700. WRNO is on 13.76MHz 2300–2400 with announced 7.355MHz from 0000.

REVISED SERVICE! LOWER PRICES!

Practical Wireless © 0202 678558 \(\text{DOS} \)

Printed circuit boards for *Practical Wireless* constructional projects are available from the PW PCB SERVICE. The boards are made in 1.5mm glassfibre, and are fully drilled and tinned. All prices include postage, packing and VAT for UK orders. Please add £2.00 per order for despatch to overseas addresses.

Orders and remittances should be sent to: PW Publishing Limited, FREEPOST, Enefco House, The Quay, Poole, Dorset BH15 1PP, marking your envelope PCB SERVICE. Cheques should be crossed and made payable to PW Publishing Ltd.

When ordering, please state the Article Title and Issue Date as well as the Board Number. Please print your name and address clearly in block letters, and do not send any other correspondence with your order. You may telephone your order using Access or Visa. A telephone answering machine will accept your order outside office hours.

Please allow 28 days for delivery. Always check the latest issue of PW for the current details of price and availability. Please enquire for p.c.b.s not listed here.

Board	Title of Article	Issue	Price
Number		Dated	(£)
WR068	AF Speech Processor	Jan 80	5.20
WR095	Transceiver Power Supply	Sep 80	3.85
WR126	"Exe" 10GHz Transceiver	Aug 81	7.70
WR144	lambic Keyer	Mar 82	6.50
WR143	ATV Converter	Apr 82	7.10
WR156	Repeater Time-out Alarm	Nov 82	5.20
WR160 WR167 WR165 WR166 WR168 WR169 WR165 etc set WR161	LMS Regenerative Receiver RTTY Terminal Unit for ZX81 "Severn" (VF0) "Severn" (Ch.over/Sidetone) "Severn" (Transmitter) "Severn" "Marchwood"	Feb 83 June 83 June 83 Jun 83 Jul 83 Jul 83 — Jul 83	5.20 7.80 5.20 6.50 6.50 6.50 14.90 2.40
WR179 WR183 WR184 WR185 WR187 WR190 WR199/192 pr WR194 WR195 WR196 WAD246 WAO01	Transceiver VOX Unit Top-band DF Receiver Simple Top-band Receiver Auto-notch Filter Morse Sending Trainer Mod FRG-7 (Switching) Bug Key with 528-bit memory Mod FRG-7 (FM/squelch) Stable Toneburst "Teme" (Transmitter) "Dart" Follow-up "Teme" (VFO/Doubler)	Mar 84 Apr 84 Jun 84 Jun 84 Jul 84 Oct 84 Oct 84 Nov 84 Nov 84 Nov 84 Dec 84	6.50 6.50 6.50 4.50 4.50 8.50 4.50 2.60 3.70 4.00 2.80
WA002	"Teme" (Receiver) Triambic Keyer Mod FRG-7 (BFO) "Colne" (RF Amp)	Jan 85	4.30
WAD280**		Feb 85	7.10
WAD249		Feb 85	3.00
A004		Apr 85	3.10

Board Number	Title of Article	Issue Dated	Price (£)
A005	"Colne" (VFO)	Apr 85	3.10
WR198	"Colne" (Product Det/Audio)	May 85	3.90
WR197	"Colne" (Oscill/Converter)	Jun 85	3.90
WAD302	Battery Charger Controller	Jun 85	3.00
WR200	Low-cost Crystal Tester	Jul 85	2.50
WR201	Add-on BFO	Aug 85	2.50
WR202	Economy UHF Pre-scaler	Sep 85	3.70
WR199	"Meon" 50MHz Transverter	Oct 85	6.70
WR203	Simple Capacitance Meter	Oct 85	2.80
WR204	WQ Medium Wave Loop	Nov 85	3.00
WR205	RTTY/Morse Modem	Jan 86	5.40
WR206	RTTY/Morse Modem (plug-in)	Jan 86	2.80
WR207	Crystal Calibrator	Jan 86	2.10
WR208	RF Speech Processor	Mar 86	4.10
WR209	Simple Audio Oscillator	Mar 86	4.30
WR211	"Meon" Filter	Apr 86	3.10
WR210	"Arun" Parametric Filter	May 86	8.10
WR213	Mod FRG-7 (Carrier Osc)	Jun 86	2.70
WR215	Simple 50MHz Converter	Sep 86	3.60
WR217	Automatic NiCad Charger	Oct 86	2.40
WR220	Get Started Low-cost Converter	Oct 86	2.40
WR216	LF Bands Active Antenna	Nov 86	2.40
WR222	"Taw" VLF Converter	Nov 86	2.80
WR223	High-imp MOSFET Voltmeter	Dec 86	2.90
WR214	Mod SRX-30D (Audio)	Dec 86	3.00
WR224	"Westbury" Basic Wobbulator	Jan 87	3.50
WR218	Masthead Pre-amp for 144MHz	Feb 87	4.20
WR219	Masthead Pre-amp PSU	Feb 87	2.50
WR225	"Woodstock" SW Converter	Mar 87	4.10
WR298	"Itchen" LCR Bridge	Apr 87	3.40
WR226-8 set	"Blandford" Rcve Converter	Apr 87	9.70
WR230-2 set	"Axe" Signal Tracer	May 87	9.20
WR233	"Downton" F-V Converter	Jun 87	3.90
WR234	Side-tone Oscillator	Jun 87	2.70
WR235	Mains on/off for Batt Radios	Sep 87	3.00
WR236	"Blenheim" VHF Converter	Sep 87	4.50
KANGA	High Stability VFO (see issue)	Oct 87	4.50
WR237	RTTY Tuning Indicator	Nov 87	5.20
WR238	"Otter" 50MHz Receiver	Jan 88	7.10
WR239-241 set	"Orwell" Medium Wave Recyr	Mar 88	9.10
WR242	"Orwell" Varicap Tune Option	Mar 88	2.90
WR243	VHF Monitor Receiver (Audio)	Apr 88	2.30
WR245	Stopband filter for PW Blenheim	Jun 88	2.90
WR244	Practice Morse Key	Jul 88	2.96
WR246	"Portland" RF Voltmeter	Jul 88	3.59
WR247	Zener Diode Tester	Aug 88	3.56
WR248	"Badger" 144MHz Receiver	Oct 88	9.10

OICOM

Count on us!

VISA

IC-28E, 2m FM Mini-mobile.


This 2-metre band transceiver is just 140mm (W) x 50mm (H) x 133mm (D) and will fit nearly anywhere in your vehicle or shack. Power output is 25 watts or 5 watts low power and is supplied complete with an internal loud-speaker. The large front panel LCD readout is designed for wide angle viewing with an automatic dimmer circuit to control the back lighting of the display for day or night

operation. The front layout is very simple, all the controls are easy to select making mobile operation safe. The IC-28E contains 21 memory


channels with duplex and memory skip funcions. All memories and frequencies can be scanned by using the HM-15 microphone provided. Also available is the IC-28H with the same features but with a 45 watt output power. Options include IC-PS45 13.8v 8A power supply, SP8 and SP10 external speakers, HS 15 flexible mobile microphone and PTT switchbox.

Icom (UK) Ltd. Contact us for the location of your nearest ICOM dealer. Barclaycard and Access welcome. Dept. PW. FREEPOST, Herne Bay, Kent CT6 8BR. Tel: 0227 363859. Telex: 965179 ICOM G.





RADIO AMATEURS EXAM? Before you enrol check the benefits of RRC'S unique Home Tuition Service RRC has helped thousands of students to success in their examinations with this unique system of postal tuition, one which guides you, step-by-step, to qualify in the shortest possible time. Only The Rapid Results College offers you all these advantages: Free advice before you enrol A qualified personal tutor Study material prepared by Telephone Helpline specialists Free 'How to Study' Guide Completely self-contained Instalment Plan courses Handy pocket-sized booklets Free Postage on course material Personal study programme ── Worldwide Airmail Service Regular marked tests Courses regularly updated Extra tuition free if you 48 hour despatch don't pass first time POST COUPON TODAY FOR FREE RADIO AMATEURS PROSPECTUS Please send me my prospectus as quickly as possible. Mr/Mrs/Miss/Ms Address \mathbf{m} Postcode The Rapid Results College CACC Dept. JX28, Tution House, London SW19 4DS. FREE ADVICE: 01-947-7272 [9am-5pm] PROSPECTUS: 01-946-1102 (24 hour Recordacall Service quoting Dept. No. above).



USE THIS SMALL ADS

The prepaid rate for classified advertisements is 40 pence per word (minimum 12 words), box number 60p extra. Semi-display setting £13.24 per single column centimetre (minimum 2.5 cm). Please add 15% VAT to total. All cheques, postal orders etc., to be made payable to Practical Wireless. Treasury notes should always be sent registered post. Advertisements, together with remittance should be sent to the Classified Advertisement Dept., Practical Wireless, Enefco House, The Quay, Poole, Dorset BH15 1PP. Telephone (0202) 678558.

Whilst prices of goods shown in advertisements are correct at the time of closing for press, readers are advised to check with the advertiser both prices and availability of goods before ordering from non-current issues of the magazine.

Receivers and Components

QUARTZ CRYSTALS and FILTERS

arge numbers of standard frequencies in stock for amateur, CB, professional and industrial applications.

Stock crystals **£5.00** each (inc. VAT and UK post). Any frequency or type made-to-order from £6.50.

Phone or SAE for lists.

GOLLEDGE ELECTRONICS Merriott, Somerset, TA16 5NS. Tel: (0460) 73718.

SCANNER OWNERS. For those of you who wish to hear more, we offer extensive frequency listings and many scanner modifications. For full details send a large S.A.E. to S.S.C. PO Box 71, Bournemouth, Dorset BH9 1DL.

FREE SCANNER AERIAL with every Realistic PRO-2004 programmable scanner sold. 25-520MHz, 760-1300MHz, 300 memories, carriage free of charge, PRO-2004 £349.95 (Access and Visa). Link Electronics, 228 Lincoln Road, Peterborough. Tel. 0733 46770.

Educational

COURSE FOR CITY & GUILDS, Radio Amateurs Examination. Pass this important examination and obtain your licence, with an RRC Home Study Course. For details of this and other courses)GCE, GCSE, Career and professional examinations, etc.) write or phone: THE RAPID RESULTS COL-LEGE, Dept. JX26, Tuition House, London SW19 4DS. Tel. 01-947 7272 (9am-5pm) or use our 24hr Recordacall Service: 01-946 1102 quoting Dept. JX26.

Software

COMMODORE COMPUTERS (+4, C16, 64, 128). CROCOM" cw/rtty tx/rx with superb morse tutor. "TURBO LOG" ultimate high speed station log. "MICROCOM INTERFACE" ready built. S.A.E. to: Moray Micro Computing. Enzie Slackhead, Buckie, Moray, AB5 2BR. Tel. 0542 7384.

COMPUTERS AND RADIO

Improve computer decoding of RTTY, CW & SSTV signals with our audio filter

SSTV signals with our audio filter

RTY only (unboxed but fully built & RTTY upper This unit has an adjusttested!

£7.00 able constant level output. No need

We only (unboxed but fully built & for constant digustment of volume

tested!

£7.00 control

£7.00 c

When ordering above units, please state software supplier. This will enable us to supply correct filter!

This will enable us to supply correct filter!

SPECTRUM 128 + 2

CASSETTE PORT ADO 0N. This unit enables owners of the Spectrum 128 + 2 to run existing decoding programmes which fequive the audio signal being fed into the cassette port. The guarantee is not affected, as there is no need to open the computer, simply connect to the expansion portE19.50 For further details of these and our other products, send a SAE, or see earlier advertisements.



J.&.P. ELECTRONICS LTD.

5, Meadowhill Est., Dixon : Kidderminster DY10 1WW Tel: (0562) 753893

Clubs & Societies

TELEVISION YOUR INTEREST? You need the British Amateur Television Club, only £6 per year - super magazine. Send SAE to: 'Grenehurst', Pinewood Road, High Send SAE to: Wycombe, Bucks.

Service Sheets

ACCESS

MASTERCARD **EUROCARD**

TECHNICAL INFO SERVICES (PW)

76 Church St., Larkhall, Lanarkshire ML9 1HE
Callers during business hours to 2 John Street, Larkhall ML9 2ET
Phone 0698 884565 Mon-Fri 9-5, 0698 883334 any other time FOR FAST QUOTES
IMMEDIATE DESPATCH OF ALL Phone Orders by ACCESS, etc. or to Listed Customers
WORLD'S LARGEST COLLECTION OF SERVICE MANUALS ... from £3.50 to £50 ... Most unobtainable elsewhere
Every issued FULL SIZE SERVICE SHEET in stock; CTV's or Combinations £3.50 Singles £2.50; Plus LSAE
LSAE for any Quotation, plus FBFF large Catalogue STEFF Review Proceedings of the Stephen Catalogue STEFF Review Procedure of the Stephen Catalogue STEFF Review P

Any Colour/Mono TV, Amateur Radio, Military Surplus, Music System, Vintage Valve Wireless tet etc. £5.00 plus LSAE.

Any Video Recorder. £10.00 dec.

Any Video Recorder. £10.00 plus LSAE.

* FREE Catalogue Unique Repair and
Data Guides for LSAE

* MAURITRON (PW),

* S Cherry Tree Road,
Chinnor, Oxon, OX9 4QY.

Rallies

****** THE NATIONS MOST CENTRAL LOCATION

> M62 ■ M6 ■ M56 COMMUNI-CONSTRUCTOR

RADIO & ELECTRONICS FAIR

ELECTRONICS * VINTAGE * COMPONENTS

"Great Sankey Forum" Warrington, Cheshire Sunday 23rd October 1988 10.30 am - 4.00 pm

Stall and General Enquiries: Audrey and Bernard (A & B) 0772 435858 ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★

Kits

F.J.P. KITS & COMPONENTS

MICROTRANSMITTER, VHF/FM, tuneable 70-146MHz. complete kit with microphone £5, built £9.50. Telephone to recorder adaptor, built £5.95. Automatic version £14.95 complete. SAE list, A.C. ELECTRONICS, 99 Greenheath. Hednesford, Staffs.

RECEIVER PRE-AMP, 15dB gain, low noise, 10m and 2m versions, simply adjusted for any band. Kit £7.99. SAE list. A.C. ELECTRONICS, 99 Greenheath, Hednesford, Staffs.

CONVERT MULTICHANNEL C.B.'s to amateur band simply and cheaply. Instructions only £2.50. SAE list. A.C. ELECTRONICS 99 Greenheath Hednesford, Staffs.

ORDER FORM PLEASE WRITE Please insert the advertisement below in the n	ext available issue of Practical Wireless for
insertions. I enclose Cheque/P.O. for £	CAT neading
NAME ADDRESS	PRACTICAL WIRELESS Classified Advertisement Department, Enefco House, The Quay, Poole, Dorset BH15 1PP. Telephone (0202) 678558 Rate 40p per word, minimum 12 words. Box No. 60p extra. PLEASE ADD 15% VAT TO TOTAL
	Company registered in England. Registered No. 1980539. Registered Office: Towngate House, 2 Parkstone Road, Poole, Dorset, BH15 2PJ. 10/8

HAVING DIFFICULTY OBTAINING AN OBSOLETE VALVE/TRANSISTOR/I.C.?

WE ALSO STOCK ALL POPULAR TYPES - USUALLY THE LOWEST PRICES ANYWHERE (compare our prices listed below!) we'll nearly always beat any written quote. Large discounts for wholesale quantities -phone/faxtelex for an immediate quote. Free advice re equivalents etc. (we've specialised in values and transistors since 1982). New boxed guaranteed values. Good quality brands (Mul.Bri.STC etc.)

Phone/faxtelex for immediate quote on any type not listed - ask for Martin Billington.

Please add 15% VAT to all prices and £1.15 p&p per order. Telephone your order quoting VISA, BARCLAYCARD (not ACCESS - sorry), or send cheque for prompt despatch for 1st Class Post. All parcels insured (at our expense) against damage in transit.

6L6GT	2.20	EL84	.95	QQV06-40A	24.00
6V6G	1.20	GZ34	2.40	UCH42	2.00
E88CC	3.00	GZ37 Mul	3.40	UF41	1.10
E88CC Mul	4.50	KT66/7581A		UL41	7.00
E810F	24.00	RCA	9.00	UY41	3.00
ECC81	.80	KT88 USA	10.75	4CX250B	
ECC82	.80	M8136 Mul	6.00	Eimac	58.00
ECC83	.93	M8137 Mul	7.00	5B 254M	14.00
ECC85 Mul	1.00	M8162 Mul	5.00	5B 255M	19.00
EF86 EF91	2.10	0A2	1.40	6CH6 Brimar	5.90
	1.40	OB2	1.40	68A6	1.00
EF92 EF95	1.65	PCL82 PCL805	.60	6E33STC	9.00
EL34	2.80	PL509 19	4.45	12E1	17.00
EL41	2.70	QQV03-20A	23.00	5763	7.00

B BILLINGTON VALVES
GOOD QUALITY-LOW PRICE-RARITIES A SPECIALITY
39 Highlands Road, Horsham, Sussex RH13 51.5
(Callers welcome but by appointment only).
Phone 0403 210729 Fax 0403 40214 Telex 87271.
Office hours Mon · Fri 9 a.m. · 6.30 p.m.

Magnetrons, Klystrons, trav-wave tubes also stocked. (Answerphone, telex and fax left on overnight and weekends)

Q.S.L. Cards

QSL CARDS New 1988 Impact Designs, Single and multi-colours, personal designs and with American style raised print. For the best value around send s.a.e. to: CONTACT CARDS, 11 Winchcombe Road, Bispham, Blackpool FY5

For Sale

RCS VARIABLE VOLTAGE D.C. BENCH POWER SUPPLY £36 VAT *

RADIO COMPONENT SPECIALISTS

ACCESS 337 WHITEHORSE ROAD, CROYDON SURREY, U.K. Tel: 01-684 1665
List, Large S.A.E. Delivery 7 days Callers Welcome Closed Wednesday

SPECIALIST VHF/HF MONITORS. Hand compact 53-ToMHz & 200Ch. 10/11m. All signals, squelch & vfo functions.

Quality production, European origin. Only £29.50 inc. p&p.

TAYLOR D/T. 8 Emmerson St., Crook, Co. Durham, UK (sae details).

For Sale (Cont.)

"GRUNDIG" INFRA-RED REMOTE CONTROL "VIF-K1" "GRUNDIG" INFRA-RED REMOTE CONTROL. "VIE-RI-consists of Transmitter TPV355 & VIF-E1 brand new & boxed £4.99, P&P £2. Box of 10 VIF-E1 £9.99p P&P £3. VIDEO HEADS (GRUNDIG 2×4 Super) with head assembly £29 P&P £2. 2×4 SUPER panels – DTF, SERVO, VIDEO, CROMA, STEREO-TON, MOTOR-BOARD, MODULA-TOR & TUNER all £5.99 each P&P £1. VIDEO TAPES VCC360 £6.99, VCC480 £7.99 P&P £1. REMOTE CON-TROLS suitable for use with FERGUSON, JVC, PHILLPS, SONY, GRUNDIG, ITT brand new boxed £19.95, P&P £1. GRUNDIG 2×4 SUPER STEREO £79 & £89 (callers only). SURPLUS STOCK WANTED. STAN WILLETTS. (PW). 37 High St., West Bromwich, West Midlands B70 6PB, 021 553 0186.

G3LLL's SPECIALS Toshiba 2SC2290 (outputs for F1707, 107 & 77) £49,90 pair, Black Star 600MHz counters £139,99, also new 2GHZS version S.A.E. leaflet, FT101E/B/ZD Bits. FM units for FT101ZD Mk3 £45 p.p. AT LAST! C.W. Filters FT101ZD/707/E/B? Phone. Double balanced mixer FT101E/B Mk1 £19. WARC Kits (all 3 new bands) FT101 Mk1, Mk2 B E Forthe £19,50 (418) FOR F17 F18 Rep. 118 C 1018 C 1018 F19. B Mix £19. WARC KIIS (all 5 new bands) F1 101 MKI, MK2 B & E only £19.50, 6JS6C NEC pair £38 p.p. NEC 12BY7A each £17 p.p. 6146B G.E. pair £27 p.p. Hols, late Septearly Oct. phone. B/Card, Access. G3LLL HOLDINGS/AMATEUR ELECTRONICS, 45 Johnston Street, Blackburn, BB2 1EF. (0254) 59595

YAESU FT690 Mk2, 6020 lin. NiCads £370 ono. FRG9600 Mk5. Mint £575 ono. G1EZJ Chris 0782 46570

Miscellaneous

C145 00 aa

Hacal MA 211 Aerial Tuning	
Racal MS 61 Line Prog. Unit	
Vernier Dial 0:100 25mm with	
8R 50W. W/W. V/contol 1/4" [D.shaft £1.75 ea.
HIGH VOLTAGE ELECTR	OLYTICS
1/360V A.C. Wkg 35p.	15/160V D.C. Wkg 60p.
2/360V A.C. Wkg 40p.	47/160V D.C. Wkg £1.50
4.5/280V A.C. Wkg 40p.	4/440V D.C. Wkg £1.25
6/360V A.C. Wkg 75p.	
CO-AXIAL CABLES	
LDF 4/50A Heliax 1/2"	£3.75 per mtr.
LDF 4/50B Heliax 2"	£4.25 per mtr.
RG 218 Co-Axial	£2.50 per mtr.
RG 215/U Co-Axial	£1.75 per mtr.
RG 215 B/U Co-Axial	£1.65 per mtr.
RG 178 B/U Co-Axial	£0.35 per mtr.
CA 190 Co-Axial	£0.60 per mtr.
ALL PRICES INCL	USIVE VAT +P&P

ELECTRONIC EQUIPMENT CO (LONDON) LTD. SPRINGFIELD HOUSE, TYSSEN ST., LONDON E8 2ND. Telephone: 01-248 5217, Allow 10 days delivery

HEATHKIT U.K. Spares and Service Centre. CEDAR ELECTRONICS. Unit 12, Station Drive, Bredon, Tewkesbury, Glos. Tel. (0684) 73127.

GZVF LOOP ANTENNAS COMPLETE WITH ATU FOR HIGH FREQUENCY HAM BAND TRANSMISSION (SWR One to One 40, 15 and 10 and One Point Five to AND TRANSMISSION (SWR One to One 40, 15 and 10 and One Point Five to the 80 and 20) AND SWL's, AND LONG AND MEDIUM WAVE BANDS FOR BCL's. Loops 21 BCL's: Loops 21 inches square or trangle D11: projects No special skills required Circuits, Parts Lists with sources of supply and full assembly data HRIF FREQUENCY LOOP BO to 10 Metres £5. LONG AND MEDIUM WAVE LOOP for BCL's EX. LONG WAVE MEDIUM WAVE AND SNORT WAVE LOOP 1500 to 10 Metres FOR THE BCL AND SW. 25. SNORT WAVE ATU FOR USE WITH EITHER A LOOP OR LONG WIRE ANTERNA £4. FILED STRENGTH METER £2. D1.12, pre-amp LW, MW and SWave £2. SAE for details. Photo Copy HRO Manual £4. F. G. Rylands, 39 Parkside Avenue, Millbrook, Southampton S01 9AF Tel. (0703) 775064

WAVEGUIDE, FLANGES & DISHES. All standard sizes & alloys (new material only) from stock. Special sizes to order. Call: EARTH STATION 01-228 7876. 22 Howie Street. London SWI1 4AR.

MORSE CODE PREPARATION

Cassette A. 1-12 wpm for amateur.

Cassette B. 12-25 wpm for professional examination preparation.

Each cassette is type C90.

Price of each cassette (including booklets) £4.95.

Morse key with separate battery (PP3) — driven solid-state oscillator and sound transducer produces clear tone for sending practice. Price of key with electronic unit £8.95.

MH ELECTRONICS (Dept PW)
12 Longstone Way Millon Portsmouth PO4 BLS

RACAL RA 17L £175, Racal accessories, Sony ICF 2001D £300, Sony ICF-7600D £180, JRC NRD-525 general coverage receiver, new £795, JST-125D 100W transceiver, new £1290. All optional accessories & Sony spares. Please contact E&M DESIGN ASSOCIATES Ltd. Tel: 01-391 0545. Fax: 01-391

INDEX TO ADVERTISERS

Aerial Techniques	61	FJP Kits	70	Radio Component Specialists	71
AH Supplies	57			Radio Shack	72
AKD	3	Garex	41	Randam Electronics	49
Amateur Radio Communications	57	Golledge Electronics	70	Rapid Results	69
A.R.E. Communications Ltd	2		22	RAS Nottingham	65
		Howes, CM Communications	s 49	Raycom Communications Syst	ems31
BCD	49	Isom (LIK) Ltd. 4 F CO	Course	RST Valve	53
Bicc Vero	19		, Cover 3	Rylands FG	71
Billington Valves	71	ICS Intertext	65		****
Birkitt J	69	J & P Electronics Ltd	70	SEM	61
Bonex Ltd	41	J & 1 Electronics Eta	70	Short Wave Magazine	25
Bredhurst	61	Kent R.A. Ltd	35	South Midlands Communicatio	
VARIANT TO THE STATE OF THE STA			-	Cover 2	
Cambridge Kits	61	Lake Electronics	45	Spectrum Communications	65
Colomor	69	Name and the second	9200 00 6	Stephens James Ltd	53
CPL Electronics	57	Maplin	Cover 4	otophiono cambo 2ta	
Data	40	Mauritron	70	Tandy	11,23
Datong	10	Merlin Systems	41	Technical Info Services	70
Dewsbury Electronics	53	WITH LICOTOFIICS LIG	71	Technical Software	35
Dressler Communications Ltd	10	Milton Keynes ARS	57	Tennamast	45
Electronic Equipment Co. (Lendon)				Termamast	45
Electronic Equipment Co (Lond Ltd	71	Nevada Communications	35	Ward Pag & Co Ltd	45
		Quartelah	15	Ward Reg & Co Ltd	45
Elliot Electronics	49	Quartslab	45	Waters & Stanton	8,9

YOUR LOCAL DEALERS

TO FILL THIS **SPACE** CALL: 0202 676033 IRELAND

Radcom Electronics

Icom. Yaesu and most Amateur Radio Accessories ex stock **NEW PREMISES:-**Unit 4, Albert Quay, Cork City. Tel: 021-632725 and 088 553947 (Mon-Fri 9-5 and Sat 9-3.45)

LONDON

Henry's 27MHz/934MHz Rigs & accessories in stock Lists - S.A.E. (A4) - 26p Full catalogue (TG/P) large S.A.E. £1.00 404 Edgware Road, London W2 1ED Tel: 01-724 0323 (Open 6 days a week)

FSSFX

Selectronic

The UK's leading suppliers of 934MHz personal radio equipment

203 High Street, Canvey Island, Essex Tel: 0268 691481

(Open Mon-Sat 9-5.30) Amateur radio equipment also in stock

HERNE BAY

СОМ

ICOM (UK) LIMITED

The Official Icom Importer Unit 8, Sea Street Herne Bay, Kent CT6 8LD Tel: 0227 369464

Fax: 0227 360 155 Open Mon-Sat 9-5.30, (Lunch 1-2.00 pm)

SOUTHAMPTON

South Midlands Communications

Official Yaesu Importer

S.M. House, School Close, Chandlers Ford Industrial Estate, Eastleigh Hants SO5 3BY. Tel: 0703 255111

PORTSMOUTH

Nevada Communications

Importers of the Nevada range of 934MHz equipment

189, London Road, North End, Portsmouth, Hants, PO2 9AE Tel: 0705 662145

DEVON

Reg. Ward & Co. Ltd.

The South-West's largest amateur radio stockist. Approved dealer for Kenwood, Yaesu and Icom

1 Western Parade. West Street, Axminster, Devon, EX13 5NY Tel: 0297 34918

(Closed 1:00-2:00 and all day Monday)

BUCKINGHAMSHIRE

Photo-Acoustics Ltd.

Approved Kenwood, Yaesu and Icom dealer (part exchange always welcome)

58 High Street, Newport Pagnell, Buckinghamshire MK16 8AQ Tel: 0908 610625

(Tues-Fri 9:30-5:30, Sat 9:30-4:30) Closed Mondays

SOUTH WALES

ELECTRO DISPOSALS

2000 sq ft of surplus equipment and components

UNIT 31, LONLAS WORKSHOPS SKEWEN, NEATH. Tel: 0792 818451

LONDON

AMCOMM OF LONDON

Approved dealer for Yaesu and Icom

> 373 Uxbridge Road, London W3 9RN Tel: 01-992 5765

(Mail order a speciality)

PLEASE MENTION PRACTICAL WIRELESS WHEN REPLYING TO ADVERTISEMENTS

MERSEYSIDE

MGR SERVICES

Wirral based communications ICOM – YAESU – M.MODULES – HOWES – CIRKIT – WOOD & DOUGLAS – PART-EX – AERIALS – PMR – MARINE – MET ANTENNAS – ALINCO – HEATHERLITE – SPECTRUM COMMS

48, Shrewsbury Road, Oxton, Birkenhead, L43 2HZ. Tel: 051 653 3437 (Callers by appointment 9 am-9 pm, Mon-Sat) SOUTH WALES

1754

A.C.S. SYSTEMS

PACKET RADIO: ST-PC-AMIGA COMPUTERS AMATEUR SOFTWARE FOR MOST COMPUTERS SATELLITE TELEVISION SYSTEMS

ICS DEALER FOR DATA COMMUNICATIONS

19, CILHAUL TERRACE, MOUNTAIN ASH, MID GLAMO SOUTH WALES, CF45 3ND. TEL 0443 476040 CALLERS BY APPOINTMENT 9am-9pm Mon-Sat

CHESHIRE

FLIGHTDECK

THE AIRBAND SHOP Specialists in Airband and Shortwave

receivers Official agents for Sony, Signal, AOR, Revco, Lowe and Kenwood (rec's only)

FAIRBOTHAM & Co. Ltd. 58-62, Lower Hill Gate, Stockport, SK1 3AN. Tel: 061 480 8080

(closed 1.00-2.15 & all day Thursdays)

SUPER DEALS ON SCANNERS

WEST SUSSEX

 \overline{a}

BREDHURST ELECTRONICS LTD.

High St., Handcross, West Sussex Tel: (0444) 400786

> uated at the Southern end of M23 Easy access to M25 and South London.
>
> Open Mon-Fri 9am-5pm except Wed 9am-12:30pm.
> Sat 10am-4pm.

YAESU

СОМ

SUPER DEALS ON SCANNERS

THE FINEST EVER SCANNER PRO 2004



BUNDLED WITH OF EXTRAS **£329.95** FROM RADIO SHACK



BUNDLED WITH A LOT OF £119.95 EXTRAS £119.95 FROM RADIO SHACK

PRO 2021



SUPER DEALS ON SCANNERS

SUPER DEALS ON **EVERYTHING IN** COMMUNICATIONS



RADIO SHACK LTD

188 BROADHURST GARDENS, **LONDON NW6 3AY**

VISA

(Just around the corner from West Hampstead Station on the Jubilee Line) Giro Account No. 588 7151 Fax: 01-328 5066 Telephone: 01-624 7174



Published on the second Thursday of each month by PW Publishing Limited, Enefco House, The Quay, Poole, Dorset BH15 IPP, Printed in England by Benham & Co Limited, Colchester, Essex Distributed by COMAG, Tavistock Road, West Drayton, Middlesex UB7 70E, telephone West Drayton 444055, Telex 8813787. Sole Agents for Australia and New Zealand - Gordon and Gotch (Asia) Ltd.; South Africa - Central News Agency Ltd. Subscriptions INLAND £14 and OVERSLAS (by A.S.P.) £18.50, payable to PRACTICAL WIRELESS, Subscription Department, Competition House, Farndon Road, Market Harborough, Leicestershire LE16 9NR, PRACTICAL WIRELESS is sold subject to the following conditions, namely that it shall not, without the written consent of the Publishers first having been given, be lent, resold, hired out or otherwise disposed of hy way of Trade at more than the recommended selling price shown on the cover, and that it shall not be lent, resold, hired out or otherwise disposed of in a mutilated condition or in any unauthorised cover by way of Trade, or affixed to or as part of any publication or advertising, literary or pictorial matter whatsoever.

ICOM

Count on us!

IC-R7000, 25-2000 MHz Commercial quality scanning receiver



With 99 programmable memories the IC-R7000 covers aircraft, Marine, FM Broadcast, Amateur Radio, television and weather satellite bands. For simplified operation and quick tuning the IC-R7000 features direct keyboard entry. Precise frequencies can be selected by pushing the digit keys in sequence of the frequency or by turning the main tuning knob. FM wide/FM narrow/AM upper and lower SSB modes with six tuning speeds: 0.1, 1.0, 5, 10, 12.5, 25KHz.

The IC-R7000 has 99 memories available to store your favourite frequencies including the operating mode. Memory channels can be called up by pressing the memory switch then rotating the

memory channel knob, or by direct keyboard entry. A sophisiticated scanning system provides instant access to the most used frequencies. By depressing the Auto-M switch, the IC-R7000 automatically memorises frequencies that are in use whilst it is in the scan mode, this allows you to recall frequencies that were in use. The scanning speed is adjustable and the scanning system includes the memory selected frequency ranges or priority channels. All functions including the memory channel readout are clearly shown on a dual-colour fluorescent display. Other features include dial-lock, noise blanker, attentuator, display dimmer and S-meter and optional RC-12 infra-red remote controller, voice synthesizer and HP 1 headphones.

Icom (UK) Ltd.

Dept PW, Sea Street, Herne Bay, Kent CT6 8LD. Tel: 0227 363859. 24 Hour.

Helpline: Telephone us free-of-charge on 0800 521145. Mon-Fri 09.00-13.00 and 14.00-17.30. This service is strictly for obtaining information about or ordering Icom equipment. We regret this cannot be used by dealers or for repair enquiries and parts orders, thank you.

Datapost: Despatch on same day whenever possible.

Access & Barclaycard: Telephone orders taken by our mail order dept, instant credit & interest-free H.P.

SINGLE-ACTION WIRE-STRIPPERS

Extremely quick and easy to use. Just place wire in jaws and squeeze handles. Wire is neatly stripped in one simple action.
Also includes tension adjustment and cutter.

NEW LOW PRICE

YOU CAN'T BUY CHEAPER

SUPPLY THE TOOLS! SO YOU CAN FINISH THE JOB WITH EASE!

☎ SALES 0702 554161


HOBBY VICE

Lever operated suction grip base holds tightly to smooth non-porous surfaces. Ideal for holding small components and assemblies. Metal faced jaws 37 x 1 lmm, open to 35mm. Base 60 x 60mm. Height 68mm.



HELPING HANDS

Remarkably low price on this most useful piece of equipment. Two fully adjustable crocodile clips hold pcb's etc. firmly and glass magnifier allows close inspection.



SOLDER by IDEPTO

INCREDIBLE LOW-PRICE TRIAL OFFER TO LAUNCH OUR NEW BRAND

½kg reel 18 swg



PER REEL or in boxes of

20 reels (10kg) £499

(=£4.34+VAT) PER REEL (SC20W price £99.80). Top quality standard flux-cored solder designed for hand and machine soldering of electronic components. Manufactured to BS219 Grade KP, BS441 Grade 2 and BS5625 Class 5a. The solder is a 60% tin, 40% lead alloy containing a non-corrosive flux. Solder starts to melt at 183°C and is fully molten at 188°C. Available on ½kg reels in 0.7mm dia. (22 swg) and 1.2mm dia. (18 swg). Perfect for use with all hand soldering irons including Antex, Weller etc.

UNBEATABLE TRIAL OFFER PRICE ON ADEPTO FINE OUALITY SOLDERS.

½kg reel 22 SWG

ONLY

FYZON

(=£6.95+VAT) PER REEL or in boxes of 20 reels (10kg)

(=£4.99+VAT)

PER REEL (SC21X price £114.80).

"The finest soldering irons in the world." - Maplin recommend Antex.

Precision soldering irons that are a pleasure to use. Low leakage currents, ceramic element, shatterproof handle. It all adds up to the number one soldering equipment for the hobbyist. Use CS type for very



ALL ITEMS SUBJECT TO AVAILABILITY

DESOLDER PUMP Powerful pump action and plunger guard. INCREDIBLE LOW PRICE NOW ONLY \$\frac{95}{FR26D}\$

MANGE ELECTRONICS

P.O. Box 3, Rayleigh, Essex, SS6 8LR.

MANY MORE PRODUCTS INSIDE!

Pick up a copy of our giant 512 page catalogue from WH SMITH for just £1.60.

ADD 50p



Shops at: O Sutton New Road, Erdington, Birmingham. O 302 Gloucester Road, Bristol. O 159-161 King Street, Hammersmith, London, O 8 Oxford Road, Manchester. O 46-48 Bevois Valley Road, Southampton. O 282-284 London Road, Southend-on-Sea.