

---

## **LM2500PE SCOPE OF SUPPLY**

### **Gas Turbine**

General Electric LM2500 - PE-MG gas turbine, ISO rated at 31,235 HP for continuous duty, with a heat rate of 6772 Btu/HP-hr (LHV). Suitable for base load or peaking, designed for simple cycle, combined cycle or cogeneration service. Turbine is shock mounted and shipped in position, ready to run. Turbine is complete with "last chance" inlet screen and bellmouth seal for protection against foreign object damage.

### **Generator**

Air-cooled generator B.E.M. Model 167ESS (or equal) with brushless excitation, suitable for Class 1, Group D, Division 2 areas, rated at 35,412 KVA @ 0.85 pf, 59°F cooling air, 13,800 volts, 60 Hz. The generator can handle the full continuous power of the gas turbine at any ambient temperature throughout the operating range. Filtered air from the inlet air filter is used to cool the generator. A cooling water loop and its associated fans and pumps are not required. The generator is a utility grade, 2-pole, synchronous design and includes a brushless excitation system with permanent magnet generator. Neutral and lineside cubicles and voltage regulator are also included.

### **Coupling**

The LM2500 gas turbine drives the generator with a dry, flexible-diaphragm coupling that bolts directly to the forged generator hub and the turbine output hub. No gearbox is required. The coupling transmits the full turbine load torque at all operation conditions. The coupling spacer is removed for shipment and is reinstalled at the jobsite by ProEnergy.

### **Enclosure**

Both gas turbine and generator are fully covered by a weatherproof acoustic enclosure. The enclosure is completely assembled and mounted over the equipment prior to testing and shipment. Both turbine and generator compartments are fully ventilated with redundant fans. Explosion-proof AC lighting and DC emergency lighting are provided in both compartments. A bridge crane in the turbine enclosure simplifies engine removal and maintenance.

### **Baseplate**

Full length I-beams are used to support the gas turbine, generator, and air inlet system. This provides single lift capability for the total equipment package. Dowelling of

baseplate sections in the field is not required. Lifting spools are incorporated in the baseplate design. A spreader bar and rigging are provided at no charge if returned prepaid to Derwick within 8 weeks of shipment. The rigidity of the baseplate is suitable for UBC earthquake Zone 4 installations.

### **Inlet Air System**

furnishes a modular, multi-stage filtration system consisting of weatherhoods and inlet screens, a pre-filter and a final barrier filter. All air for ventilation systems is filtered to the same level as turbine combustion air. Optional anti-ice system, evaporative cooling system and combustion air heating or chilling system are available. Filtered air is silenced before entering the turbine plenum. This compact arrangement eliminates the need for customer-supplied inlet ducting when the standard design is utilized. Internal lighting of the filter house is provided for inspection and service. Internal and external ladders and platforms for servicing the filter are included.

### **Exhaust System**

The LM2500 package includes a thermally insulated exhaust collector to direct the turbine exhaust gases to an 80"h x 55"w rectangular flange in the side of the main enclosure. Customer furnished expansion joint, ducting; ducting supports and mounting hardware are required for heat recovery applications. For simple cycle, an exhaust silencer assembly may be ordered as an option. Right-hand exhaust, as viewed from the exciter end, is standard. Left-hand exhaust may be ordered as an option.

### **Piping System**

Stainless Steel throughout. Lube Oil, Water and Fuel piping and fittings are Type 304 Stainless Steel. Steam piping and fittings are Type 321 Stainless Steel, and all piping is fabricated in accordance with ANSI B31.1 Power Piping Code requirements. Pipe spools are hydrostatically tested at 1.5 times maximum working pressure. Fuel, steam and high pressure hydraulic piping welds are 100% x-ray inspected. Lube oil piping welds are randomly x-rayed. Turbine and Generator Lube Oil Reservoirs are Type 304 Stainless Steel. The pressure vessels on the turbine baseplate (Water Wash Tanks, Generator Lube Oil Rundown Tanks) are also Type 304 Stainless Steel and are ASME Code stamped.

### **Fuel System**

A natural gas fuel system using an electronically controlled fuel-metering valve is supplied in the basic package. For full-load operation, the gaseous fuel must be supplied to the baseplate at 375 psig  $\pm$  20 psig (lower starting pressures available Liquid fuel or

dual fuel systems are available as factory options. Fuel specifications are included in Section 12. All necessary shutoff valves, piping and instruments between the baseplate connection and the engine are included.

### **Lube Oil Systems**

Two systems - mineral oil for the generator, synthetic oil for the gas turbine. Each lube oil system includes duplex full-flow filters, stainless steel piping and reservoirs and stainless steel trimmed valves. The oil from both systems is cooled by dualcore fin-fan coolers mounted on the enclosure roof. All interconnecting piping is included. The coolers are 100% redundant and either can handle the cooling load. The full-flow oil filters can be serviced during operation. An optional water-cooled design is available utilizing duplex shell and tube coolers for customer installation on a separate foundation.

### **Electro-Hydraulic Starting Module**

Rotates turbine for starting and water washing. The starting system includes a 200 HP electric motor, hydraulic pump, filters, cooler and controls mounted on a separate baseplate. The pump powers a hydraulic starting motor mounted on the turbine auxiliary gearbox. Customer furnishes interconnecting hydraulic piping between hydraulic start module and rotating equipment module.

### **Digital Control System**

The Derwickcontrol system provides operating, safety and sequencing controls for the gas turbine and generator. The unit panel is suitable for mounting indoors in a non-hazardous, air-conditioned control room. The panel contains a Woodward programmable, microprocessor-based controller for fuel management and sequencing. Also included are a Bently-Nevada vibration monitor, a manual/auto voltage regulator, a color CRT, and meters and switches for starting, synchronizing, and loading. CRT annunciates alarms and shutdowns, status, analog valves (pressure, temp. etc.), with RS-232 interface to customer DCS. Baseplate mounted equipment includes pressure, level, flow, speed and temperature sensors, plus valves and actuators. 24V DC Nickel-Cadmium batteries and dual battery chargers for control system power are included.

## **Fire Protection System**

The fire and gas detection and extinguishing system includes optical flame detection, hydrocarbon sensing and thermal detectors; complete with factory installed piping and nozzles in both generator and engine compartments. The fire protection system includes cylinders of CO2 extinguishant mounted on the side of the generator set enclosure. Derwick furnishes a dedicated 24V DC battery and charger to power the fire protection system. Fire system alarms and shutdowns are annunciated at the turbine control panel. An alarm sounds at the turbine enclosure and unit control panel if the gas detectors sense high gas levels, or if the system is preparing to release the extinguishant. When activated, the primary extinguishant cylinders discharge into both the turbine and generator compartments via multiple nozzles, and ventilation dampers close automatically. After a time delay, the reserve supply of extinguishant is discharged, if required.

## **"On Line" Cleaning and Soak Wash System**

For baseload application, an "on-line" cleaning system is included which allow customers to clean the compressor section of the engine during full power operation. The same system reservoir and piping are utilized for off-line soak washing. Baseplate connections are provided for customer supplied purified water at 15-85 psig and air at 85-120 psig filtered to 20 microns.

## **Component Testing and Package Full Load Test**

The generator is tested to IEEE 115 or IEC 34.3 standards at its factory of manufacture. The gas turbine is performance tested at the G.E. Aircraft Division factory. The entire assembled generator set is then tested at ProEnergy's factory to verify performance guarantees. A full KW load string test of the turbine generator set is performed using the contract controls and auxiliary systems. Water and steam systems are functionally proven but normally not operated during the full load test.

## **Drawings, Documentation and Manuals**

The basic equipment package is supplied with a customer drawing package, which includes general arrangement drawings, flow and instrument diagrams, electrical one-line drawings and a conduit interconnection plan. Additional electrical interconnect and logic drawings are provided for record. Maintenance manuals are provided, printed in the English language, using standard English engineering units. The manuals cover operating concepts for power generating equipment, guides to troubleshooting, and basic information on components and equipment within the turbine generator set.